



WPA 競技規則及び規程 2026 (英語原文-日本語訳対比版)

World Para Athletics Rules and Regulations 2026

本競技規則の日本語訳は、日本パラ陸上競技連盟 競技運営委員会が翻訳したものです。
本訳文は、競技規則の理解を補助することを目的としたものです。
和訳の解釈に疑義が生じた場合、または英語原文との間に相違がある場合は、World Para Athletics が公表する英語原文を確認し、その内容を基準としてください。

発行：一般社団法人日本パラ陸上競技連盟

翻訳：一般社団法人日本パラ陸上競技連盟 競技運営委員会

PART A – GENERAL

- 1 Definitions
- 2 General Provisions
 - 2.1 Scope and application
 - 2.2 Interpretation
 - 2.3 Governance
 - 2.4 Printing of the Rules
 - 2.5 Amendments to the Rules

PART B – WORLD PARA ATHLETICS REGULATIONS

- 3 World Para Athletics Recognised Competitions
 - 3.1 Competition levels
 - 3.2 Competition cycle
 - 3.3 Competition management
 - 3.4 Competition entries
 - 3.5 Recognition of results
 - 3.6 Advertising and displays during Competitions
 - 3.7 Anti-gambling requirements
- 4 Eligibility & Classification
 - 4.1 Eligibility requirements – Paralympic Games
 - 4.2 Eligibility requirements – WPA Championships and World Para Athletics Sanctioned Competitions
 - 4.3 Eligibility requirements – World Para Athletics Approved Competitions
 - 4.4 Qualification requirements
 - 4.5 Gender
 - 4.6 Classification
- 5 Anti-Doping
 - 5.1 Anti-Doping Code
 - 5.2 World Record Recognition
- 6 Medical
 - 6.1 Medical requirements
 - 6.2 Medical responsibilities
 - 6.3 Medical withdrawal request
 - 6.4 Medical insurance
 - 6.5 Medical and safety services at the Paralympic Games, WPA Championships and World Para Athletics Sanctioned Competitions
 - 6.6 Harassment
 - 6.7 Autonomic dysreflexia
 - 6.8 Hypoxic or hyperoxic chambers or tents
 - 6.9 Heat
 - 6.10 Smoking Ban

- 7 Technology and Equipment
 - 7.1 Fundamental principles
 - 7.2 Monitoring of the use of technology and equipment
 - 7.3 Prohibited technology
- 8 Disciplinary rules
 - 8.1 The IPC Code of Ethics and the World Para Athletics Code of Conduct
- 9 Protests & Appeals
 - 9.1 Field of play
 - 9.2 Anti-doping
 - 9.3 Classification

PART C – WORLD PARA ATHLETICS COMPETITION RULES

SECTION I – INTERNATIONAL OFFICIALS

Rule 1: Appointment of Officials

Rule 2: Description of Officials and Their Duties

- 2.1 Technical Delegate
- 2.2 Medical Delegate
- 2.3 Doping Control Delegate
- 2.4 International Technical Officials (ITOs)
- 2.5 International Road Course Measurer
- 2.6 International Starter and International Photo Finish Judge
- 2.7 Jury of Appeal
- 2.8 Officials of the Competition
- 2.9 Competition Director
- 2.10 Meeting Manager
- 2.11 Technical Manager
- 2.12 Event Presentation Manager
- 2.13 Referees
- 2.14 Judges
- 2.15 Umpires (Running and Wheelchair Racing Events)
- 2.16 Timekeepers and Photo Finish and Transponder Timing Judges
- 2.17 Start Co-ordinator, Starter and Recalls
- 2.18 Starter's Assistants
- 2.19 Lap Scorers
- 2.20 Competition Secretary, Technical Information Centre (TIC)
- 2.21 Marshal
- 2.22 Wind Gauge Operator
- 2.23 Measurement Judge (Scientific)
- 2.24 Call Room Judges
- 2.25 Advertising Commissioner
- 2.26 Chief Classifier

2.27 International Classifiers

SECTION II – GENERAL COMPETITION RULES

Rule 3: The Athletics Facility

Rule 4: Age, Gender Categories and Mixed Competition

Rule 5: Entries

Rule 6: Clothing, Shoes, Athlete Bibs, Prosthetics and Orthotics, Eye mask, Tether, Noncompliance on Equipment and Helmets

Rule 7: Assistance to Athletes

Rule 8: Warnings and Disqualification

Rule 9: Competing Outside Sport Class – Eligibility

Rule 10: Surveying and Measurements

Rule 11: Validity of Performances

Rule 12: Video Recording

Rule 13: Scoring

Rule 14: Wheelchair and Frame Running Requirements

SECTION III – TRACK EVENTS

Rule 15: Track Measurements

Rule 16: Starting Blocks

Rule 17: The Start

Rule 18: The Race

Rule 19: The Finish

Rule 20: Timing

Rule 21: Seedings, Draws and Qualification in Track Events

Rule 22: Ties

Rule 23: Relay Races

SECTION IV - FIELD EVENTS

Rule 24: General Conditions

A. VERTICAL JUMP

Rule 25: General Conditions

Rule 26: High Jump

B. HORIZONTAL JUMPS

Rule 27: General Conditions

Rule 28: Long Jump

Rule 29: Triple Jump

C. THROWING EVENTS FOR AMBULANT ATHLETES

Rule 30: General Conditions

Rule 31: Shot Put

Rule 32: Discus Throw

Rule 33: Javelin Throw

D. THROWING EVENTS FOR SEATED ATHLETES

Rule 34: General Conditions

Rule 35: Seated Throwing Requirements

Rule 36: Seated Throwing Technique, Lifting and Failure

Rule 37: Club Throw

SECTION V – INDOOR COMPETITIONS

Rule 38: Applicability of Outdoor Rules to Indoor Competitions

Rule 39: The Indoor Stadium

Rule 40: The Straight Track

Rule 41: The Oval Track and Lanes

Rule 42: Start and Finish on the Oval Track

Rule 43: Seeding, Draws and Qualification in Track Event

Rule 44: Spike Length

Rule 45: Relay Races

Rule 46: High Jump

Rule 47: Horizontal Jumps

Rule 48: Shot Put

SECTION VI - ROAD RACES

Rule 49: Road Races

SECTION VII - PROTESTS AND APPEALS

Rule 50: Protests and Appeals

SECTION VIII - WORLD AND REGIONAL RECORDS

Rule 51: World and Regional Records

SECTION IX - AWARDING MEDALS AND DIPLOMAS

Rule 52: Awarding Medals and Diplomas

APPENDIX 1

World Para Athletics Implement Weights For Sports Class

APPENDIX 2

Figure 25

Classification Hierarchy Table 1 – Paralympic Games and World Championships

Classification Hierarchy Table 2 – Regional Championships and Regional Games

PART A – GENERAL 1 Definitions Adaptive Equipment: As defined in the World Para Athletics Classification Rules and Regulations. Athlete Support Person: As defined in the World Para Athletics Classification Rules and Regulations. Classification: As defined in the World Para Athletics Classification Rules and Regulations. Competition: a series of individual events conducted together under one ruling body. Competition Medical Director: the person appointed by the LOC for a WPA Championship and/or a World Para Athletics Sanctioned Competition who is responsible to implement the World Para Athletics ‘Scope of Event Medical Services’. Competition Rules: the World Para Athletics Competition Rules set out in Part C of these Rules. International Federation: a sport federation recognised by the IPC as the sole world-wide representative of a sport for athletes with an impairment that has been granted the status as a Para sport by the IPC. The IPC and IOSD act as an International Federation for certain Para sports. IOC: the International Olympic Committee. IPC: the International Paralympic Committee. WPA Championships: World Para Athletics Championships and World Para Athletics Regional Championships. IOSD: International Organisation of Sport for the Disabled, an independent organisation recognised by the IPC as the sole worldwide representative for a specific impairment group to the IPC. LOC: Local Organising Committee – an organisation appointed by World Para Athletics to organise a WPA Championship or World Para Athletics Sanctioned Competition. LOC Chief Medical Doctor: the medical doctor appointed by the LOC for a WPA Championship and/or World Para Athletics Sanctioned Competition. National Federation: the national member of an International Federation. NPC: National Paralympic Committee, the national member of the IPC who is the sole representative of athletes with an impairment in that country or territory. These are the national members of the IPC. Observation Assessment: As defined in the World Para Athletics Classification Rules and Regulations. Orthosis: an orthopaedic appliance or apparatus used to assist functioning in a limb that is	PART A 総則 1 定義 補助装具：世界パラ陸上競技クラス分け規則及び規定にて定義される 競技者サポート担当者：世界パラ陸上競技クラス分け規則及び規定にて定義される Classification(クラス分け)：世界パラ陸上競技クラス分け規則及び規定にて定義される Competition(競技会)：一つの団体の元で行われる一連の個別の種目 Competition Medical Director(競技会医事ディレクター)：LOC が WPA 競技会及び/または WPA 認定競技会のために任命した、WPA の「競技会医療サービス」の実施を担当する人物 Competition Rules(競技会規則)：これらの規則 PART-C に定められた WPA 競技会規則 International Federation(国際競技連盟)：IPC によってパラスポーツとしてのステータスが付与された障害のある競技者のためのスポーツの唯一の世界的な代表として IPC によって承認されたスポーツ連盟。IPC と IOSD は、特定のパラスポーツの国際連盟として機能する。 IOC：国際オリンピック委員会 IPC：国際パラリンピック委員会 WPA Championships(WPA 競技会)：世界パラ陸上競技選手権大会と WPA 地域競技者大会 IOSD：国際障害者スポーツ機構は、特定の障害グループの IPC への唯一の世界的な代表者として IPC によって承認された独立組織である。 LOC：組織委員会–WPA 競技会または WPA 認定競技会を開催するために WPA によって承認された組織 LOC Chief Medical Doctor(LOC 医師チーフ)：LOC が WPA 競技会及び/または WPA 認定競技会に指名した医師 National Federation(各国競技連盟)：国際競技連盟の各国メンバー NPC：国内パラリンピック委員会、その国または地域で障害のある競技者の唯一の代表者である IPC の各国メンバー。これらは IPC の各国メンバーである。 Observation Assessment（観察評価）：世界パラ陸上競技クラス分け規則及び規定にて定義される Orthosis(矯正装具)：解剖学的には損傷はないが、可動域にダメージがあったり、筋力や足の長さの	P A R T A 総 則 1 定 義
--	---	---

anatomically intact but which has impaired range of movement, muscle power or leg length difference. Paralympic Games: means the major international event owned and sanctioned by the IPC comprising summer and winter editions usually held in alternating biennial cycles where Para athletes compete in Para sports that are on the Paralympic games Sports Programme. Para athlete: means any athlete competing in a Para sports. Para sport: a sport governed by the IPC Athlete Classification Code and recognised as a Para sport by the IPC. Prosthesis: An artificial device that replaces a missing body part, which may be lost through trauma, disease, or congenital conditions. Raza Points System: the scoring system in Para athletics events used to compare performances in the same event by athletes in different Sports Classes, as published on the WPA website from time to time. Referee: the person appointed to adjudicate World Para Athletics Recognised Competitions. Regulations: the World Para Athletics Regulations set out in Part B of these Rules. Rules: the World Para Athletics Rules and Regulations comprised of the General Provisions, the World Para Athletics Regulations and the World Para Athletics Competition Rules. Sport Class: a category for Competition defined by World Para Athletics by reference to the extent to which an athlete can perform the specific tasks and activities required by a Para athletics. Sport Class Status: a designation applied to a Sport Class to indicate the extent to which an athlete may be required to undertake athlete evaluation and/or be subject to a classification protest. Further detail in relation to Sport Class Statuses can be found in the World Para Athletics Classification Rules and Regulations. WADC: the World Anti-Doping Code. WA: World Athletics World Athletics Rules: Competition and Technical Rules reacting to WA. WPA: World Para Athletics. World Para Athletics Approved Competitions: international, national, endorsed and World Athletics endorsed competitions for the sport of Para Athletics that have been approved by World Para Athletics. World Para Athletics Athlete License: a license issued by the IPC in accordance with the IPC Athlete Licensing Programme to enable athletes and guide-runners to compete in the Paralympic	違いを補う四肢の機能を補う器具 Paralympic Games: パラリンピック競技大会は、IPC が主催及び許可し、通常は 2 年ごとに開催される夏季大会と冬季大会からなり、パラリンピック・スポーツ・プログラムに沿って、パラアスリートがパラスポーツで競い合う主要な国際イベントを意味する。 Para athlete : パラスポーツに参加するあらゆるアスリート Para sport(パラスポーツ) : IPC 競技者クラス分け規程によって管理され、IPC によってパラスポーツとして認定されたスポーツ Prosthesis(義肢) : 外傷や病気などで、あるいは先天的に失われている体の一部を補うもの Raza Points System : WPA のウェブサイトですぐに公表されている採点システムである。パラ競技者の種目で使用され、違う競技クラスの競技者が同じ種目で技術を比べるために使用される。 Referee(審判長) : WPA 認定競技会を裁定するために任命された人物 Regulations(規程) : これらの規則 PART-B に定められた WPA 規程 Rules(規則) : 一般規定、WPA 規程及び WPA 競技会規則で構成される WPA 規則及び規程 Sport Class(競技クラス) : 競技者がパラ陸上に必要な特定のタスクやアクティビティを実行できる範囲を参照することにより、WPA によって定義された競技のカテゴリー Sport Class Status(競技クラスステータス) : 競技者が評価されること、及び/またはクラス分け抗議を必要とする範囲を示すために競技クラスに適用される指定。競技クラスステータスに関する詳細は、W P A のクラス分けルールと規約に記載されている。 WADC : 世界アンチドーピング規程 WA : World Athletics World Athletics Rules : WA に関連する競技や技術規則 WPA : 世界パラ陸上競技連盟 World Para Athletics Approved Competitions(WPA 承認競技会) : WPA によって承認されているパラ陸上競技のスポーツのための国際、国内、及び WPA が承認した大会。 World Para Athletics Athlete License(WPA 競技者ライセンス) : 競技者とガイドランナーがパラリンピック競技大会、WPA 競技会、WPA 認可競技会に参加できるようにするために、IPC 競技者ライセンスプログラムに従って IPC が発行するラ
---	--

Games, WPA Championships and World Para Athletics Sanctioned Competitions. World Para Athletics Recognised Competitions: Paralympic Games, WPA Championships, World Para Athletics Sanctioned Competitions and World Para Athletics Approved Competitions. World Para Athletics Sanctioned Competitions: World Para Athletics Grand Prix events, World Para Athletics World Cups and other World Para Athletics international competitions determined by World Para Athletics. World Para Athletics Technical Delegate: a person appointed by World Para Athletics to monitor and oversee a World Para Athletics Recognised Competition and to ensure all technical operations are conducted in accordance with these Rules. 2 General Provisions 2.1 Scope and application 2.1.1 These World Para Athletics Rules and Regulations comprise the World Para Athletics Regulations (Regulations) and the World Para Athletics Competition Rules (Competition Rules) (together referred to as ‘these Rules’). 2.1.2 These Rules are mandatory for all World Para Athletics Recognised Competitions. 2.1.3 All participants (including, but not limited to, athletes and support personnel, coaches, trainers, managers, interpreters, team staff, officials, medical or paramedical personnel) of any World Para Athletics Recognised Competitions agree to be bound by these Rules as a condition of such participation. 2.1.4 The World Para Athletics Classification Rules and Regulations are an integral part of these Rules and are located on the World Para Athletics website. 2.1.5 The IPC Handbook is an integral part of the governance of the sport of Para Athletics. 2.1.6 Any matter not addressed in these Rules shall be determined by WPA, in its sole discretion. 2.1.7 These Rules will be effective from 11 March 2024. 2.2 Interpretation 2.2.1 References to a ‘Regulation’ mean a Regulation referred to in Part B of these Rules, references to a ‘Rule’ mean a Rule referred to in Part C of these Rules, references to an ‘Appendix’ means an Appendix to these Rules, and capitalised terms used in these Rules have the meaning given to them in the Definitions section of these Rules. 2.2.2 Any comments annotating various provisions of these Rules shall be used to interpret these Rules. 2.2.3 Headings used in these Rules are used for convenience only and have no meaning that is separate from the Regulation(s) or Rule(s) to which they refer.	イセンス。 World Para Athletics Recognised Competitions(WPA 認可競技会) : パラリンピック競技大会、WPA 競技会、WPA 認定及び承認の競技会 World Para Athletics Sanctioned Competitions(WPA 認定競技会) : WPA グランプリのイベント、WPA ワールドカップ、及びその他の WPA の国際競技会 World Para Athletics Technical Delegate(WPA 技術代表) : WPA 認可競技会を監視及び監督し、すべての技術的運用がこれらの規則に従って実施されるようにするために、WPA によって任命された者 2 一般規定 2.1 範囲と適用 2.1.1 これらの WPA 規則及び規程は、WPA 規程及び WPA 競技規則（総称して「これらの規則」と呼ぶ）で構成される。 2.1.2 これらの規則は、すべての WPA 認可競技会に必須である。 2.1.3 WPA 認可競技会のすべての参加者（競技者及びサポート要員、コーチ、トレーナー、マネージャー、通訳、チームスタッフ、職員、医療または救急隊員を含むが、これらに限定されない。）は、参加の条件として、これらの規則に拘束されることに同意する。 2.1.4 WPA 陸上競技のクラス分け規則及び規程は、これらの規則の不可欠な部分であり、WPA のウェブサイトに掲載されている。 2.1.5 IPC ハンドブックは、パラ陸上競技のスポーツのガバナンスの不可欠な部分である。 2.1.6 これらの規則で扱われていない事項は、WPA の独自の裁量により決定されるものとする。 2.1.7 これらの規則は、2024 年 3 月 11 日から発効する。 2.2 解釈 2.2.1 「規程」とは、これらの規則 PART-B の規定を意味し、「規則」とは、これらの規則 PART-C の規定を意味し、「付録」は、これらの規則の付録を意味する。また、規則で使用される大文字の用語は、これらの規則の定義セクションでそれらに与えられた意味を持っている。 2.2.2 これらの規則のさまざまな規定を注釈するコメントは、これらの規則を解釈するために使用されるものとする。 2.2.3 これらの規則で使用される見出しは、便宜のためにのみ使用されており、それらが参照する規程または規則とは別の意味はない。	2 一般規定 2.1 範囲と適用
---	--	--

2.2.4 Unless otherwise expressly provided for in the Regulations, all references in the Regulations to “athletes” shall also include “guide-runner”. This does not apply to Part C of the Rules. 2.3 Governance 2.3.1 The IPC acts as the International Federation for and governs the sport of Para Athletics. It carries out these responsibilities under the name “World Para Athletics” and the term “World Para Athletics” must be read in these Rules as the IPC and vice versa. 2.4 Printing of the Rules 2.4.1 These Rules are the copyright property of WPA and have been published for the benefit of NPCs, athletes, officials and others who are engaged in an official capacity with World Para Athletics. These Rules may be reprinted or translated by any organisation with a legitimate need to do so, subject to WPA’s continuing ability to assert its copyright in the Rules, including the right to insist on a assignment to WPA of the copyright in any translated version of these Rules. Any other organisation must obtain the permission of WPA prior to reprinting, translating or publishing these Rules. 2.4.2 The English version of these Rules shall be accepted as the authoritative version for the purpose of interpretation. 2.5 Amendments to the Rules 2.5.1 After the conclusion of each Paralympic Games, WPA shall undertake a review of these Rules, in consultation with NPCs and any relevant IOSDs, in accordance with the IPC Handbook (located on the IPC website). All amendments shall be implemented prior to the start of the second season following the relevant Paralympic Games. 2.5.2 These Rules also may be amended at any time by WPA as a result, for example, of changes in Classification related matters, the World Athletics Rules, or where World Para Athletics otherwise considers it necessary to do so. PART B – WORLD PARA ATHLETICS REGULATIONS 3 World Para Athletics Recognised Competitions 3.1 Competition levels 3.1.1 World Para Athletics categorises Competitions based on their scale, size, and nature to determine the applicable requirements at each Competition. 3.1.2 World Para Athletics Recognised Competition levels are as follows: a) Paralympic Games b) WPA Championships • World Para Athletics Championships • World Para Athletics Regional Championships c) World Para Athletics Sanctioned Competitions • World Para Athletics Grand Prix events • World Para Athletics World Cups • Any other World Para Athletics international competitions determined by World Para Athletics d) World Para Athletics Approved Competitions • International competitions for the sport of Para Athletics	2.2.4 規程で別段の定めがない限り、規程における「競技者」には「ガイドランナー」も含まれるものとする。これは規則 PART-C には適用されない。 2.3 ガバナンス 2.3.1 IPC は、WPA のスポーツの国際連盟として機能し、これを管理する。それはこれらの責任を「WPA」という名称で実行し、「WPA」という用語はこれらの規則で IPC として読み取る必要があり、その逆も同様である。 2.4 ルールの印刷 2.4.1 これらの規則は WPA の著作権財産であり、NPC、競技者、役員、及び世界パラ陸上競技の公的能力に従事している他の人々の利益のために公開される。これらのルールは、WPA がルール内で著作権を主張する継続的な能力（これらのルールの翻訳版の著作権の WPA への割り当てを主張する権利を含む）を条件として、そうする必要がある正当な組織によって転載または翻訳される場合がある。他の組織は、これらの規則を転載、翻訳、または公開する前に、WPA の許可を得る必要がある。 2.4.2 これらの規則の英語版は、解釈の目的で正式版として受け入れられるものとする。 2.5 規則の修正 2.5.1 各パラリンピック競技大会の終了後、WPA は、IPC ハンドブック（IPC ウェブサイトにある）に従って、NPC 及び関連する IOSD と協議して、これらの規則の見直しを行うものとする。すべての修正は、関連するパラリンピック競技大会に続く第 2 シーズンの開始前に実施されるものとする。 2.5.2 これらの規則は、たとえば、クラス分けに関連する事項、世界陸連競技規則の変更、または WPA がそうする必要があるとその他の理由で変更した結果として、WPA によっていつでも修正できる。 PART B-WPA 規程 3 WPA 認可競技会 3.1 競技会レベル 3.1.1 WPA は、規模、サイズ、及び性質に基づいて競技会を分類し、各競技会で適用される要件を決定する。 3.1.2 WPA 認可競技会レベルは以下のとおり a) パラリンピック競技大会 b) WPA 競技会 • WPA 世界選手権大会 • WPA 地域選手権大会 c) WPA 認定競技会 • WPA グランプリ大会 • WPA ワールドカップ • WPA が開催を決定した WPA 国際競技会 d) WPA 承認競技会 • パラ陸上競技の国際競技会 • パラ陸上競技の国内競技会	P A R T B W P A 規 程 3. WPA 認可競技会
--	--	--

• National competitions for the sport of Para Athletics • World Athletics /NF endorsed competitions (as defined in the World Athletics Rules) • Any other competitions for the sport of Para Athletics determined by World Para Athletics 3.2 Competition cycle 3.2.1 Unless otherwise determined by the IPC, the cycle for Paralympic Games, WPA Championships and World Para Athletics Sanctioned Competitions is as follows: <table><tr><th>Cycle</th><th>Competition</th></tr><tr><td>Year 1</td><td>World Para Athletics Championships World Para Athletics Grand Prix events World Para Athletics World Cups</td></tr><tr><td>Year 2</td><td>World Para Athletics Regional Championships World Para Athletics Grand Prix events World Para Athletics World Cups</td></tr><tr><td>Year 3</td><td>World Para Athletics Championships World Para Athletics Grand Prix events World Para Athletics World Cups</td></tr><tr><td>Year 4</td><td>Paralympic Games World Para Athletics Regional Championships World Para Athletics Grand Prix events World Para Athletics World Cups</td></tr></table> 3.3 Competition management 3.3.1 The IPC shall manage the Paralympic Games. 3.3.2 World Para Athletics shall have the right to manage all WPA Championships and World Para Athletics Sanctioned Competitions. It also shall have the right to oversee all World Para Athletics Approved Competitions. The words World, Regional and World Para Athletics may not be used in connection with any Para Athletics event without the prior written consent of World Para Athletics. In addition, the IPC is the owner of all rights of whatever kind or nature in respect of the terms "Paralympics" and "Paralympic", the term "Para Athletics" when associated with sport or any IPC activities, the IPC motto, flag and anthem, the Paralympic Symbol (three Agitos design) and any other trademarks, logos and other indicia used or intended to be used in the context of the Paralympic Movement. 3.3.3 World Para Athletics shall enforce these Rules for all World Para Athletics Recognised Competitions. World Para Athletics shall have jurisdiction over all matters not assigned by the Rules to another person or entity (such as an official or LOC). 3.3.4 The events and competition format for all World Para Athletics Recognised Competitions are outlined in the Competition Rules. 3.4 Competition entries 3.4.1 All entries to participate in WPA Championships and World Para Athletics Sanctioned Competitions must be in accordance with these Rules and the entry criteria outlined on the World Para Athletics website. 3.4.2 The entry criteria and minimum qualifying standards for the Paralympic Games shall be defined in the qualification criteria outlined on the IPC website. 3.4.3 The entry criteria and minimum qualifying standards for each WPA Championship and World	Cycle	Competition	Year 1	World Para Athletics Championships World Para Athletics Grand Prix events World Para Athletics World Cups	Year 2	World Para Athletics Regional Championships World Para Athletics Grand Prix events World Para Athletics World Cups	Year 3	World Para Athletics Championships World Para Athletics Grand Prix events World Para Athletics World Cups	Year 4	Paralympic Games World Para Athletics Regional Championships World Para Athletics Grand Prix events World Para Athletics World Cups	• (WA 規則に定義される)WA/NF 公認競技会 • WPA が認めたその他のパラ陸上競技会 3.2 競技会サイクル 3.2.1 IPC によって別段の定めがない限り、パラリンピック、WPA 選手権、WPA 認定競技会のサイクルは次のとおりである。 3.3 競技会運営 3.3.1 IPC はすべてのパラリンピック競技大会を管理する。 3.3.2 WPA は、すべての WPA 競技会及び WPA 認定競技会を管理する権利を有する。また、すべての WPA 承認競技会を監督する権利を有する。「世界」、「地域」、及び「WPA」という言葉は、WPA の事前の書面による同意なしに、WPA の競技会で使用することはできない。さらに、IPC は、「Paralympics」及び「Paralympic」という用語や、スポーツまたはIPC アクティビティ、IPC のモットーに関連する「Para Athletics」という用語に関して、あらゆる種類または性質のすべての権利の所有者である。「Para Athletics」という用語は、スポーツや IPC 活動、IPC のモットー、旗、国歌、パラリンピックシンボル（3つのアギトスデザイン）、及びその他の商標、ロゴ、及びその他の商標、ロゴ、その他の関連で使用またはパラリンピック運動が意図されている場合に使用される。 3.3.3 WPA は、すべての WPA 認可競技会にこれらの規則を施行するものとする。WPA は、規則によって別の人物または団体（役員や LOC など）に割り当てられていないすべての事項を管轄するものとする。 3.3.4 すべての WPA 認可競技会の種目と競技形式は、競技規則に概説されている。 3.4 競技会エントリー 3.4.1 WPA 競技会及び WPA 認定大会に参加するためのすべてのエントリーは、これらの規則及び WPA のウェブサイト で概説されているエントリー基準に従っている必要がある。 3.4.2 パラリンピック競技大会のエントリー基準と最低資格基準は、IPC ウェブサイトで概説されている資格基準で定義されている。 3.4.3 各 WPA 競技会と WPA 認定競技会のエントリー基準と最低資格基準は、WPA のウェブサイト で	3.2 競技会サイクル 3.3 競技会運営 3.4 競技会エントリー
Cycle	Competition											
Year 1	World Para Athletics Championships World Para Athletics Grand Prix events World Para Athletics World Cups											
Year 2	World Para Athletics Regional Championships World Para Athletics Grand Prix events World Para Athletics World Cups											
Year 3	World Para Athletics Championships World Para Athletics Grand Prix events World Para Athletics World Cups											
Year 4	Paralympic Games World Para Athletics Regional Championships World Para Athletics Grand Prix events World Para Athletics World Cups											

Para Athletics Sanctioned Competition shall be defined in the qualification criteria outlined on the World Para Athletics website. 3.5 Recognition of results 3.5.1 World Para Athletics accepts results achieved at World Para Athletics Recognised Competitions by eligible athletes (in accordance with Regulation 4) solely for the following purposes: 3.5.1.1 World Para Athletics rankings; 3.5.1.2 World Para Athletics records; 3.5.1.3 allocation of NPC qualification slots for the Paralympic Games, WPA Championships and World Para Athletics Sanctioned Competitions; and/or 3.5.1.4 achieving qualification standards for entry into the Paralympic Games, WPA Championships and World Para Athletics Sanctioned Competitions. 3.6 Advertising and displays during Competitions 3.6.1 The IPC determines the advertising requirements at the Paralympic Games. 3.6.2 The World Para Athletics Uniform and Equipment Advertising Regulations (located on the World Para Athletics website) outline the advertising permitted by World Para Athletics at WPA Championships. During all other World Para Athletics Recognised Competitions (except the Paralympic Games), the relevant LOC, shall adopt the applicable advertising requirements. 3.7 Anti-gambling requirements 3.7.1 The IPC may adopt anti-gambling regulations, policies, codes and/or requirements from time to time, which will be binding on all participants of World Para Athletics Recognised Competitions. 4 Eligibility & Classification 4.1 Eligibility requirements – Paralympic Games 4.1.1 The IPC determines the eligibility requirements for the Paralympic Games. 4.2 Eligibility requirements – WPA Championships and World Para Athletics Sanctioned Competitions 4.2.1 To meet the eligibility requirements to participate in WPA Championships and World Para Athletics Sanctioned Competitions an athlete must: 4.2.1.1 hold a valid IPC Athlete Licence issued in accordance with the IPC Athlete Registration and Licensing Programme (located on the World Para Athletics website). 4.2.1.2 be internationally classified and have been assigned a Sport Class (other than Not Eligible (NE)) in accordance with the World Para Athletics Classification Rules and Regulations; 4.2.1.3 be entered by their NPC (or National Federation if such responsibility has been delegated by the NPC), in either case the NPC being a member in good standing of the IPC; 4.2.1.4 satisfy the nationality requirements of the IPC Athlete Nationality Policy (located on the IPC	概説されている資格基準で定義される。 3.5 結果の認定 3.5.1 WPA は、以下の目的のためにのみ、（規程 4 に従って）適格な競技者が WPA 認可競技会で達成した結果を受け入れる。 3.5.1.1 WPA ランキング 3.5.1.2 WPA 記録 3.5.1.3 パラリンピック競技大会、WPA 競技会、WPA 認定競技会への NPC 資格の割り当て 3.5.1.4 パラリンピック競技大会、WPA 競技会、WPA 認定競技会への参加資格基準の達成 3.6 競技中の広告と表示 3.6.1 IPC は、パラリンピック競技大会での広告要件を決定する。 3.6.2 WPA ユニフォーム及び機器広告規程（WPA ウェブサイトにある）は、WPA 競技会で WPA が許可する広告の概要を示している。他のすべての WPA 認可競技会（パラリンピック競技大会を除く）では、LOC が該当する広告要件が採用されなければならない。 3.7 ギャンブル対策の要件 3.7.1 IPC は、賭博防止規則、ポリシー、規則、及び/または要件を随時採用する場合があります、これは WPA 認可競技会のすべての参加者を拘束する。 4 資格とクラス分け 4.1 資格要件 - パラリンピック競技大会 4.1.1 IPC は、パラリンピック競技大会の資格要件を決定する。 4.2 資格要件 - WPA 競技会と WPA 認定競技会 4.2.1 WPA 競技会及び WPA 認定競技会に参加するための資格要件を満たすために、競技者は： 4.2.1.1 IPC 競技者登録及びライセンスプログラムに従って発行された有効な IPC 競技者ライセンスを保持する（WPA ウェブサイトにある）。 4.2.1.2 国際的にクラス分けされており、WPA クラス分け規則及び規則に従って競技クラス（対象外（NE）以外）が割り当てられている。 4.2.1.3 NPC（またはそのような責任が NPC によって委任されている場合は NF）から出場する。どちらの場合も、NPC は IPC の良好な状態のメンバーである。 4.2.1.4 （IPC ウェブサイトにある）IPC 競技者国籍ポリシーの国籍要件を満たす。	3.5 結果の認定 3.6 競技中の広告と表示 3.7 ギャンブル対策の要件 4 資格とクラス分け
--	---	---

website); 4.2.1.5 be 14 years of age (or older) on 31 December of the year during which the WPA Championship or World Para Athletics Sanctioned Competition takes place; and 4.2.1.6 not be disqualified, suspended or otherwise sanctioned. 4.2.2 In order to meet the eligibility requirements for WPA Championships and World Para Athletics Sanctioned Competitions a guide-runner must meet all of the above criteria except for criterion 4.2.1.2. 4.3 Eligibility requirements – World Para Athletics Approved Competitions 4.3.1 In order to compete in World Para Athletics Approved Competitions an athlete/guide-runner must meet the eligibility requirements determined by the relevant organising committee or governing body. 4.4 Qualification requirements 4.4.1 In addition to the eligibility requirements outlined above, in order to compete in World Para Athletics Recognised Competitions an athlete must also meet the qualification standards, qualification criteria and any sport entry rules applicable to the relevant World Para Athletics Recognised Competition. 4.5 Gender 4.5.1 Subject to Regulation 4.5.3, below, an athlete shall be eligible to compete in men's competition if they are: 4.5.1.1 recognised as male in law; and 4.5.1.2 eligible to compete under these Rules. 4.5.2 Subject to Regulation 4.5.3, below, an athlete shall be eligible to compete in women's competition if they are: 4.5.2.1 recognised as female in law; and 4.5.2.2 eligible to compete under these Rules. 4.5.3 World Para Athletics will deal with any cases involving transgender athletes in accordance with the IOC's transgender guidelines (as amended by the IOC from time to time) and any applicable World Para Athletics regulations. 4.5.4 The eligibility of persons recognised as third gender in law will be determined by the IPC on a case-by-case basis, in accordance with any applicable World Para Athletics regulations. 4.6 Classification 4.6.1 World Para Athletics shall determine the World Para Athletics Recognised Competitions where international Classification will be offered. At such Competitions, Classification will be conducted prior to the start of each Competition in accordance with the World Para Athletics Classification Rules and Regulations.	4.2.1.5 WPA 競技会または WPA 認定競技会が開催される年の 12 月 31 日に、14 歳（またはそれ以上）であること 4.2.1.6 失格、一時停止、またはその他の制裁措置を受けていないこと 4.2.2 WPA 競技会及び WPA 認定競技会の資格要件を満たすために、ガイドランナーは、基準 4.2.1.2 を除く上記の基準をすべて満たしている必要がある。 4.3 資格要件、WPA 承認競技会 4.3.1 WPA 承認競技会に出場するために、競技者／ガイドランナーは、関連する組織委員会または運営団体によって決定された資格要件を満たさなければならない。 4.4 参加資格要件 4.4.1 上記の資格要件に加えて、WPA 認可競技会に出場するためには、競技者は資格基準、資格基準、及び関連する WPA 認可競技会に適用されるスポーツエントリールールも満たさなければならない。 4.5 性別 4.5.1 以下の規定 4.5.3 に従い、競技者は以下を満たせば男性対象の競技会に出場する資格がある。 4.5.1.1 法律で男性として認められていること。また： 4.5.1.2 これら規則に基づいて競技する資格があること 4.5.2 以下の規定 4.5.3 に従い、競技者は以下を満たせば女性対象の競技会に出場する資格がある。 4.5.2.1 法律で女性として認められていること。そして： 4.5.2.2 これら規則に基づいて競技する資格があること 4.5.3 WPA は、IOC のトランスジェンダーガイドライン（IOC によって随時修正される）及び該当するすべての WPA 諸規程に従って、トランスジェンダーの競技者が関与するすべてのケースを取り扱う。 4.5.4 法律で第 3 の性として認定された人物の適格性は、該当する WPA 諸規程に従って、ケースバイケースで IPC によって決定される。 4.6 クラス分け 4.6.1 WPA は、どの WPA 認可競技会で、国際クラス分けを実施するかを決定する。 （実施する）競技会では、WPA クラス分け規則及び規程に従って、競技の開始前にクラス分けを行う。	4.3 資格要件 WPA 承認競技会 4.3 資格要件 WPA 承認競技会 4.4 参加資格要件 4.5 性別 4.6 クラス分け
---	--	---

4.6.2 An athlete who has not been assessed and allocated a Sport Class by a World Para Athletics Classification Panel will not meet the eligibility criteria (set out in this Regulation 4) to compete in the Paralympic Games, WPA Championships and, unless WPA determines otherwise, World Para Athletics Sanctioned Competitions. 5 Anti-Doping 5.1 Anti-Doping Code 5.1.1 The IPC Anti-Doping Code (located on the IPC website) applies to the Paralympic Games, WPA Championships and World Para Athletics Sanctioned Competitions. 5.1.2 World Para Athletics Approved Competitions must be conducted in accordance with the anti-doping rules of the relevant governing body and the WADC International Standards. 5.2 World Record Recognition 5.2.1 In order for a World Record to be recognised by World Para Athletics, doping control conducted in accordance with the WADA International Standard for Testing and Investigations must occur at the competition that the record is set. The testing must have been arranged in advance of the start of the first day of competition. It is not a requirement that an athlete that has broken a world record is selected for testing. 5.2.2 In the case where a record is broken at a competition that has not arranged for doping control in accordance with Regulation 5.2.1, the record shall not be recognised. 6 Medical 6.1 Medical requirements 6.1.1 The IPC Medical Code (located on the IPC website) applies to the Paralympic Games, WPA Championships and World Para Athletics Sanctioned Competitions. 6.1.2 The medical and safety rules of the relevant governing body apply to World Para Athletics Approved Competitions. 6.2 Medical responsibilities 6.2.1 In accordance with the IPC Medical Code, all athletes who compete in the Paralympic Games, WPA Championships and World Para Athletics Sanctioned Competitions are responsible for their own physical and mental health and for their own medical supervision. 6.2.2 By entering in the Paralympic Games, WPA Championship or a World Para Athletics Sanctioned Competition, an athlete releases the IPC and World Para Athletics from any liability to the extent permitted by law for any loss, injury or damage that they may suffer in relation to, or as a result of their participation in Classification, the relevant Competition. 6.2.3 Notwithstanding the above Regulations 6.2.1 and 6.2.2, NPCs shall use best efforts to ensure the physical and mental health of all athletes under their jurisdiction prior to their participation in the Paralympic Games, WPA Championships and World Para Athletics Sanctioned Competitions. 6.2.4 Every NPC is responsible to ensure that appropriate and continuous medical monitoring of	4.6.2 WPA クラス分けパネルによる評価が行われていない、または競技クラスが割り当てられていない競技者は、(本規程 4 における) パラリンピック競技協会、WPA 競技会、WPA が認めた場合を除いて WPA 認定競技会に参加する資格を有しない。 5 アンチドーピング 5.1 アンチドーピング要件 5.1.1 IPC アンチドーピング規程 (IPC ウェブサイトにある) は、パラリンピック競技大会、WPA 競技会及び WPA 認定競技会に適用される。 5.1.2 WPA 承認競技会は、関連する運営機関のアンチドーピング規則及び WADC 国際基準に従って実施されなければならない。 5.2.世界記録認定 5.2.1 WPA が世界記録を認めるには、その記録が出た競技会で WADA の国際基準に従ってドーピング検査が実施され、検査と調査が行われなければならない。また、ドーピング検査は競技会初日の競技開始までに手配されていなければならない。ただし、世界記録を出した競技者がドーピング検査を受ける必要はない。 5.2.2 もし、事前にドーピング検査が手配されていなければ、規定 5.2.1 に従ってその世界記録は認められない。 6 医療 6.1 医療要件 6.1.1 IPC 医療規約 (IPC ウェブサイトにある) は、すべてのパラリンピック競技大会、WPA 競技会、及び WPA 認定競技会に適用される。 6.1.2 関連する運営機関の医療及び安全規則は、WPA 承認競技会に適用される。 6.2 医療責任 6.2.1 IPC 医療規約に従って、パラリンピック競技大会、WPA 競技会、WPA 認定競技会に出場するすべての競技者は、自分の身体的及び精神的健康と自分の医療監督に責任を負う。 6.2.2 パラリンピック競技大会、WPA 競技会、または WPA 認定競技会に参加することにより、競技者は、IPC 及び WPA を、クラス分け、関連競技会への参加に関連して、またはその結果として、受けた損失、負傷、または損害について法律で認められている範囲で、責任から解放する。 6.2.3 上記の規程 6.2.1 及び 6.2.2 に関わらず、NPC は、パラリンピック競技大会、WPA 競技会、及び WPA 認定競技会に参加する前に、管轄下にあるすべての競技者の心身の健康を確保するために最善の努力を払うものとする。 6.2.4 すべての NPC は、その競技者の適切かつ継続的な医療モニタリングが確実に行われるようにする	5. アンチドーピング 5.1 アンチドーピング要件 6 医療 6.1 医療要件 6.2 医療責任
---	--	---

its' athletes is undertaken. It is further recommended that NPCs organise for a periodic health evaluation of each athlete that it enters in the Paralympic Games, WPA Championship or World Para Athletics Sanctioned Competition and that NPCs appoint a team physician to attend all such Competitions. 6.2.5 In accordance with the Rules, the Medical Delegate will be entitled to prevent any athlete from competing where in their opinion it would be dangerous for the athlete to compete, including where the safety of other athletes, officials, spectators and/or the Competition itself is put at risk. 6.2.6 At all times, the overriding priority must be to safeguard the health and safety of athletes, officials and spectators. The outcome of the relevant Competition must never influence such decisions. 6.3 Medical withdrawal request 6.3.1 At all Paralympic Games, WPA Championships and World Para Athletics Sanctioned Competitions the official World Para Athletics Medical Withdrawal Request Form (located on the World Para Athletics website) must be submitted to the World Para Athletics office in order to officially request the withdrawal of an athlete from the relevant Competition after submission of the final entry numbers or as otherwise determined in the Competition entry requirements. 6.3.2 The Medical Withdrawal Request Form must be signed by the athlete and one of the following three category of physicians: a) the team physician of the athlete; b) In the event there is no team physician, if the team has an agreement to use the physician of another team, that physician may sign the form; or c) the LOC Chief Medical Doctor. 6.3.3 All sections of the Medical Withdrawal Request Form must be completed. 6.3.4 All Medical Withdrawal Request Forms must be submitted at least twenty-four (24) hours prior to the relevant event of the Competition. If this is not possible (for example due to the onset of an acute injury or illness within the twenty-four (24) hours prior to the relevant event) an explanation must be provided in the Medical Withdrawal Request Form and comply with Regulation 6.3.2. 6.3.5 The Medical Delegate, or such other person determined by the IPC/World Para Athletics makes a decision and informs the Technical Delegate who shall communicate to the Athlete's relevant team whether a Medical Withdrawal Request is accepted. This decision is final with no opportunity to protest or appeal. 6.3.6 If circumstances permit, the Technical Delegate may direct that the athlete be removed from the start list and the start list may be re-drawn.	責任がある。さらに、NPC がパラリンピック、WPA 競技会、または WPA 認定競技会に参加する各競技者の定期的な健康評価のために組織し、NPC がそのようなすべての競技会に参加するチーム医師を任命することを推奨する。 6.2.5 規則に従い、医事代表は、他の競技者、競技役員、観客、及び競技会自体が危険にさらされるような場所も含め、競技者が競技するのが危険であると判断があれば、競技者が競技するのを制限する権利を有する。 6.2.6 最優先事項は、競技者、競技役員、観客の健康と安全を守ることである。関連する競技会の結果は、そのような決定に決して影響してはならない。 6.3 医事的理由による欠場リクエスト 6.3.1 すべてのパラリンピック競技会、WPA 競技会及び WPA 認定競技会では、公式の WPA 医事的理由による欠場リクエストフォーム（WPA ウェブサイトにある）を最終エントリー人数の提出後、またはその他の方法で競技会のエントリー要件で決定された、関連する競技会からの競技者の欠場を正式にリクエストするために、WPA に提出する必要がある。 6.3.2 医事的理由による欠場リクエストフォームには、競技者及び下記の 3 つのカテゴリーの医師のいずれかによって署名される必要である。 a) 競技者のチーム医師 b) チームの医師がいない場合、医事的理由による欠場リクエストフォームを提出するチームが別のチームの医師に依頼することに同意している場合は、その医師はフォームに署名することができる。または、 c) LOC の主任医師。 6.3.3 医事的理由による欠場リクエストフォームのすべてのセクションに記入する必要がある。 6.3.4 すべての医事的理由による欠場リクエストフォームは、関連する競技の開始少なくとも 24 時間前に提出する必要がある。これが不可能な場合（たとえば、関連する競技の 24 時間前に急性の怪我または病気が発生したため）、医事的理由による欠場リクエストフォームで説明を加える必要があり、規則 6.3.2 に従わなければならない。 6.3.5 医事代表、または IPC/WPA に任命された者は決断し、技術代表に報告し、競技者に関係するチームに医事的理由による欠場リクエストが受理できるか否かの決定を技術代表に進言する。この決断は最終であり、抗議や上訴はみとめられない。 6.3.6 技術代表は、状況に応じて競技者をスタートリストから除外し、リストの組み直しを指示することができる。	6.3 医事的理由による欠場リクエスト
--	--	-----------------------------------

6.4 Medical insurance 6.4.1 NPCs are responsible to ensure suitable medical provision and medical insurance coverage for their respective delegations for World Para Athletics Recognised Competitions and (subject to Regulation 6.4.2 below) for the full duration of the relevant Competition, including travel to and from such Competitions. NPCs must provide a copy of this insurance to World Para Athletics if requested. 6.4.2 It shall be the responsibility of the LOC in each case to ensure on-site medical, emergency ambulance, first aid services and medical insurance coverage is provided at all Paralympic Games, WPA Championships and World Para Athletics Sanctioned Competitions. The WPA Medical Committee shall issue and keep updated practical guidelines to assist LOCs in providing adequate medical services and taking appropriate safety measures at such Competitions. 6.5 Medical and safety services at the Paralympic Games, WPA Championships and World Para Athletics Sanctioned Competitions 6.5.1 The LOC shall be responsible for implementing the medical and safety services for the Paralympic Games in accordance with the relevant host agreement, as well as the WPA scope of event medical services. 6.5.2 LOCs shall be responsible for implementing the medical and safety services at WPA Championships and World Para Athletics Sanctioned Competitions in accordance with the Scope of Event Medical Services for IPC Athletes (that forms part of the host agreement between the WPA and the LOC). 6.5.3 A Competition Medical Director shall be appointed by the LOC for each WPA Championship and World Para Athletics Sanctioned Competition to prepare and co-ordinate the medical services and safety requirements during the relevant Competition. The IPC Medical and Scientific Director shall be the liaison person between World Para Athletics and the Competition Medical Director for all medical and safety-related matters. The IPC Medical and Scientific Director may delegate specific responsibilities to such person or persons at their discretion. 6.5.4 At all WPA Championships and any other Competitions determined by World Para Athletics, World Para Athletics shall be responsible to ensure a medical representative to monitor implementation of these and any other competition specific medical and safety rules. 6.6 Harassment The dignity of every individual must be respected. All forms of abuse and/or harassment are prohibited. The IPC Code of Ethics and the Policy on Nonaccidental Violence and Abuse (located on the IPC website) apply to all World Para Athletics Recognised Competitions. 6.7 Autonomic dysreflexia The IPC Policy on Autonomic Dysreflexia (located on the IPC website) applies to all World Para Athletics Recognised Competitions.	6.4 医療保険 6.4.1 NPCは、WPA認可競技会の各代表団及び（以下の規程 6.4.2 に従い）該当する競技会への旅行期間を含む、関連する競技会の全期間について、適切な医療措置と医療保険を確保する責任があります。NPC は、要求された場合、この保険のコピーを WPA に提供する必要がある。 6.4.2 すべてのパラリンピック競技大会、WPA 競技会、及び WPA 認定競技会で、オンサイト医療、緊急救急車、応急処置サービス、及び医療保険が提供されることを保証するのは、LOC の責任である。IPC 医事委員会は、LOC が適切な医療サービスを提供し、そのような競技会で適切な安全対策を講じるのを支援するために、最新の実用的なガイドラインを発行し、維持する 6.5 パラリンピック競技大会、WPA 競技会、WPA 認定競技会での医療及び安全サービス 6.5.1 LOC は、関連するホスト契約に従ってパラリンピック競技大会の医療及び安全サービスを WPA 基準の医療サービスを同様に実施する責任がある。 6.5.2 LOC は、IPC 競技者のためのイベント医療サービスの範囲（IPC と LOC の間のホスト契約の一部を形成する）に従って、WPA 競技会及び WPA 認定競技会で医療及び安全サービスを実施する責任がある。 6.5.3 競技会メディカルディレクターは、関連する競技中の医療サービスと安全要件を準備及び調整するために、LOC によって各 IPC 競技会及び WPA 認定競技会に指名される。IPC メディカル科学ディレクターは、すべての医事及び安全関連の問題について、WPA と競技会メディカルディレクターの間の連絡係となる。IPC メディカル科学ディレクターは、裁量により、そのような人物に特定の責任を委任することができる。 6.5.4 すべての IPC 競技会及び WPA によって決定されたその他の競技会では、WPA は、これら及びその他の競技会固有の医療及び安全規則の実施を監視する医療担当者を確保する責任がある。 6.6 ハラスメント すべての個人の尊厳を尊重しなければならない。あらゆる形の虐待や嫌がらせは禁止されている。IPC 倫理規定及び偶発的でない暴力と虐待に関するポリシー（IPC ウェブサイトにある）は、すべての WPA 認可競技会に適用される。 6.7 自律神経過反射 自律神経過反射に関する IPC ポリシー（IPC ウェブサイトにある）は、すべての WPA 認可競技会に適用される。	6.4 医療保険 6.5 パラリンピック競技大会 WPA 競技会 WPA 認定競技会での医療及び安全サービス 6.6 ハラスメント 6.7 自律神経過反射
--	---	---

6.8 Hypoxic or hyperoxic chambers or tents The use of hypoxic or hyperoxic chambers or tents is prohibited at all World Para Athletics Recognised Competitions. 6.9 Heat The WPA Heat Countermeasure Policy (located on the WPA website) applies to the Paralympic Games and WPA Championships. For all other WPA Sanctioned and Approved Competitions, WPA expects the LOC to implement reasonable measures that are aligned with this policy. 6.10 Smoking Ban Smoking is prohibited (including electronic vape devices) during competition at all venues of World Para Athletics Recognised Competitions. 7 Technology and Equipment 7.1 Fundamental principles 7.1.1 The IPC Policy on Sport Equipment (located on the IPC website) applies to all World Para Athletics Recognised Competitions. The principles outlined in this policy apply in particular (but not exclusively) in relation to the development of sports specific prosthetic devices. 7.2 Monitoring of the use of technology and equipment 7.2.1 World Para Athletics will monitor the use of technology and equipment used, or, intended to be used, at World Para Athletics Recognised Competitions to ensure that it conforms to the principles outlined in the IPC Policy on Sport Equipment. The following examples shall be considered contrary to that policy; technology and/or equipment that, in the opinion of the World Para Athletics: 7.2.1.1 provides an unrealistic enhancement of height of release in throwing events; 7.2.1.2 provides an unrealistic enhancement of stride length; 7.2.1.3 is not commercially available to all athletes, unless the athlete can establish that the: 7.2.1.3.1 technology and/or equipment is in final product form; 7.2.1.3.2 manufacturer has announced the market launch date of the technology and/or equipment and this date is within 9 months of the date of the athlete's request to use it; and 7.2.1.3.3 manufacturer has published information on the technology and/or equipment; and/or 7.2.1.4 contains materials or devices that store, generate or deliver energy designed to provide an athlete with an overall competitive advantage over an athlete not using such technology and/or equipment (unless, in relation to technology and equipment not yet commercially available or commercially available from February 2020, the athlete can establish on the balance of probabilities that the use of such technology and/or equipment would not provide them with an overall competitive advantage over an athlete not using such technology and/or equipment).	6.8 低酸素または高酸素チャンバーまたはテント 低酸素または高酸素チャンバーまたはテントの使用は、すべての WPA 認可競技会で禁止されている。 6.9 暑熱 WPA ヒートポリシー（WPA ウェブサイトにある）は、パラリンピック競技大会、および W P A 競技会に適用される。ほかのすべての W P A 認可競技会や承認大会では、組織委員会は、これらの対策に沿った合理的な措置を講ずることを期待する。 6.10 喫煙禁止 WPA 認可競技会の全会場での競技中の喫煙（電子たばこを含む）は禁止されている。 7 テクノロジーと用器具 7.1 基本原則 7.1.1 スポーツ用器具に関する IPC ポリシー（IPC ウェブサイトにある）は、すべての WPA 認可競技会に適用される。このポリシーで概説されている原則は、スポーツ専用の補綴装置の開発に関連して特に（ただし、これに限定されない）適用される。 7.2 技術及び用具の使用の監視 7.2.1 WPA は、WPA 認定競技会で使用される、あるいは、使用される予定の技術や用具が、IPC Policy on Sport Equipment で規定されている原則に適しているどうかを監視する。 WPA が認定した以下のような例は、IPC Policy、技術、用具として WPA の意に反していると考えられる。 7.2.1.1 投てき競技でのリリースの高さの非現実的な追加を提供すること 7.2.1.2 ストライドの長さの非現実的な追加を提供すること 7.2.1.3 すべての競技者が商業的に入手できないもの。ただし、競技者が以下のことを準備できる場合を除く。 7.2.1.3.1 その技術及び用具は最終製品であること 7.2.1.3.2 製造会社が販売日を公表しており、その日が競技者が「使用すると希望する日」から 9 か月以内であること 7.2.1.3.3 製造会社がその技術の情報を公表していること 7.2.1.4 同用具を使用していない競技者との比較で、力を蓄えたり生み出したりする機能を含む用具（ただし、2020 年 2 月以降、商業的にまだ購入可能になっていない技術や用具については、競技者が、同機能/用具を使用しない競技者と比較して優位になる機能/用具ではないことを説明できる場合は、その限りではない。）	6.8 低酸素または高酸素チャンバーまたはテント 6.9 暑熱 6.10 喫煙禁止 7. テクノロジーと用器具
---	--	---

7.2.2 World Para Athletics has adopted provisions to enable the use of certain technology and equipment designed to provide assistance to Para athletes. Such provisions are outlined in the Competition Rules. 7.3 Prohibited technology 7.3.1 Use of the following technology is prohibited at World Para Athletics Recognised Competitions: 7.3.1.1 equipment that breaches the fundamental principles outlined in the IPC Policy on Sport Equipment; 7.3.1.2 equipment that results in athletic performance being generated by machines, engines, electronics, motors, robotic mechanisms or the like; and 7.3.1.3 osteo-integrated prosthesis. 7.3.2 At any Paralympic Games, WPA Championship or World Para Athletics Sanctioned Competition the World Para Athletics Technical Delegate shall be entitled to prohibit the use of any equipment prohibited by these Regulations. In every case of a suspected breach the World Para Athletics Technical Delegate must report the matter to World Para Athletics. Upon receiving such a report World Para Athletics must refer the matter to the IPC Medical and Scientific Director. Any further investigation and/or action will be determined by the IPC on a case by case basis. 7.3.3 World Para Athletics shall be entitled to prohibit the use of equipment either permanently or on a temporary basis (to allow for further investigation) where it considers, acting reasonably, that any of the fundamental principles of equipment design and availability are breached. 8 Disciplinary rules 8.1 The IPC Code of Ethics and the World Para Athletics Code of Conduct 8.1.1 The IPC Code of Ethics and the World Para Athletics Code of Conduct (both located on the IPC website) shall apply to all participants of World Para Athletics Recognised Competitions. 8.1.2 Any breach of these Regulations shall be determined in accordance with the procedures outlined in the World Para Athletics Code of Conduct. 9 Protests & Appeals 9.1 Field of play 9.1.1 Protests and appeals relating to the field of play shall be determined in accordance with the Competition Rules. 9.2 Anti-doping 9.2.1 All anti-doping rule violations, including any appeals regarding such violations, shall be determined in accordance with the IPC Anti-Doping Code. 9.3 Classification 9.3.1 Protests and appeals relating to Classification shall be determined in accordance with the World Para Athletics Classification Rules and Regulations.	7.2.2 WPA は、パラ競技者を支援するために設計された特定の技術や用具の使用を可能にする規定を採用している。そのような規定は、競技規則に概説されている。 7.3 禁止されている技術 7.3.1 WPA 認可競技会では、次の技術の使用は禁止されている。 7.3.1.1 スポーツ用品に関する IPC ポリシーで概説されている基本原則に違反する用具 7.3.1.2 機械、エンジン、電子機器、モーター、ロボット機構などによって生成される運動パフォーマンスをもたらす用具 7.3.1.3 骨統合型義肢 7.3.2 パラリンピック、WPA 競技会、または WPA 認定競技会では、WPA 技術代表は、これらの規程で禁止されている機器の使用を禁止する権利を有する。違反が疑われるすべてのケースで、WPA 技術代表は、問題を WPA に報告する必要がある。そのようなレポートを受け取ったら、WPA はその問題を IPC の医事科学代表に照会する必要がある。それ以上の調査やアクションは、ケースバイケースで IPC によって決定される。 7.3.3 WPA は、用具の設計と可用性の基本原則のいずれかに違反していると合理的に判断する場合、永続的または一時的に（さらなる調査を可能にするため）用具の使用を禁止する権利を有する。 8 懲戒規則 8.1 IPC 倫理規約及び WPA 行動規範 8.1.1 IPC 倫理規約及び WPA 行動規範（どちらも IPC ウェブサイトにある）は、WPA 認可競技会のすべての参加者に適用される 8.1.2 これらの規程の違反は、WPA 行動規範に概説されている手順に従って決定される。 9 抗議と異議申し立て(上訴) 9.1 競技場内(FOP) 9.1.1 競技場内での抗議及び異議申し立て(上訴)は、競技会規則に従って決定される。 9.2 アンチドーピング 9.2.1 すべてのアンチドーピング規則違反は、そのような違反に関する異議申し立てを含め、IPC アンチドーピング規程に従って決定される。 9.3 クラス分け 9.3.1 クラス分けに関する抗議及び異議申し立ては、WPA クラス分け規則及び規程に従って決定される。	7.3 禁止されている技術 8 懲戒規則 8.1 IPC 倫理規約及び WPA 行動規範 9 抗議と異議申し立て 9.1 競技場内 9.2 アンチドーピング
---	---	--

PART C – WORLD PARA ATHLETICS COMPETITION RULES Interpretation – where a number appears in brackets next to the heading of any of the following Rules it shall generally refer to the corresponding World Athletics Rules. This is for guidance only and the World Athletics rules must not be used to determine any issue at an WPA Recognised Competition (see Part – B 3.1.2), except in the limited number of places where these Rules clearly specify that the World Athletics Rules shall apply. SECTION I – INTERNATIONAL OFFICIALS Rule 1: Appointment of Officials 1. At the Paralympic Games and WPA Championships the following international officials should be appointed by WPA: a) WPA Technical Delegate(s); b) WPA International Technical Officials; c) Medical Delegate; d) Doping Control Delegate; e) Chief Classifier; f) International Classifiers; g) International Starter h) International Photo Finish Judge; i) Jury of Appeal. Note: International Officials should wear distinctive attire or insignia. At the Paralympic Games and WPA Championships (see Part B - 3.1.2 (a) and (b)), the number of officials appointed in each category, how when and by whom they shall be appointed, shall be indicated in the respective WPA Technical Requirements. The travelling and accommodation expenses of each individual appointed by WPA under this Rule shall be paid to the individual by the LOC of the competition according to the relevant Regulations. 2. Appointment of Officials for WPA Sanctioned and Approved Competitions (see Part B -3.1.2 (c) and (d)): a) A WPA Technical Delegate(s) for International and National Competitions must be appointed by WPA. b) If WPA Classification is being conducted in conjunction with the respective competition, then the Chief Classifier and International Classifiers must be appointed by WPA. c) Such other officials as the STC and the TD shall (in consultation with the LOC) decide is necessary. Rule 2: Description of Officials and Their Duties 2.1 Technical Delegate The Technical Delegate(s), in conjunction with the LOC, which shall afford them all necessary help, are responsible for ensuring that all technical arrangements are in conformity with these Rules and the World Athletics Track and Field Facilities Manual. Technical Delegate(s) appointed for competitions other than one day meetings shall ensure: a) That the submission of the final timetable of events is concluded and published together with any entry standards for the competition;	PART C - WPA 競技会規則 解釈—以下に示す規則の見出しに続いて括弧内表記される条番号は、ほとんどの場合、当該規則に対応する世界陸上競技連盟（WA）規則を示している。これはあくまでも参考のために記載されるもので、例外的に WA 規則が適用されることが WPA の規則に明記されている場合を除き、WPA 認可競技会（PART-B 規則 3.1.2 参照）におけるいかなる問題についても WA 規則に基づいて判断してはならない。 第 1 部 国際競技役員 第 1 条 役員の任命 1 パラリンピック競技大会及び WPA 競技会では、WPA から任命された以下の国際競技役員をおくべきである。 a) WPA 技術代表 b) WPA 国際技術委員 c) 医事代表 d) ドーピングコントロール代表 e) クラシファイヤー主任 f) 国際クラシファイヤー g) 国際スターター h) 国際写真判定員 i) ジュリー 注意：国際競技役員は、明確に区別できる服装または腕章を着用すべきである。 パラリンピック競技大会及び WPA 競技会（PART-B 規則 3.1.2 参照）では、役職ごとの役員数、いつ、どのように、誰によって任命されるかは WPA 競技会開催規定に示されている。 この規則のもとで WPA から任命された各役員の旅費と宿泊費は、該当する競技会開催規程に従って、組織委員会から各役員に支払われる。 2 WPA 認定及び承認競技会（PART-B 規則 3.1.2 参照）の役員任命 a) 国際競技会や国内競技会の WPA 技術代表は、WPA が任命しなければならない。 b) 上記各競技会において WPA のクラス分けが行われる場合、WPA は、クラシファイヤー主任と国際クラシファイヤーも任命しなければならない。 c) その他の役員については、技術委員会（STC）及び技術代表（TD）が（大会組織委員会と協議の上）必要と判断する場合に任命する。 第 2 条 役員の詳細とその任務 2.1 技術代表 技術代表は組織委員会と連絡をとりつつ、必要とされるあらゆる支援を行うことが任務であり、競技運営に関するすべてについて、競技規則と WA 陸上競技施設マニュアルに完全に合致して行われるようにする責任がある。 1 日開催の競技会を除き、指名された技術代表は以下のことを行わなければならない。 a) 組織委員会(LOC)に対し競技日程と参加標準記録の提案書を確実に提出する。	PART C - WPA 競技会規則 第 1 部 国際競技役員 第 1 条 役員の任命 第 2 条 役員の詳細とその任務 2.1 技術代表
--	---	---

b) For Field events, to approve the list of implements to be used and whether athletes may use their own implements or those provided by a supplier; c) For Field Events, to determine the qualifying standards, and for Track Events the basis on which the rounds shall be arranged; d) That the applicable Technical Regulations are issued to all competing delegations in good time before the competition; e) All other technical preparations necessary for the holding of the athletics events; f) To reject entries for technical reasons; g) The seeding and draws for all events are made in accordance with the Rules and any applicable Technical Regulations and approve all start lists; h) Decide upon any matters which arise prior to the competition and for which provision has not been made in these Rules (or any applicable regulations) or the arrangements for the competitions, where appropriate in consultation with the LOC and/or conjunction with WPA at the Paralympic Games and WPA Championships (see Part B - 3.1.2 (a) and (b)). i) Decide (including where appropriate in conjunction when available with the relevant Referee(s) and the Competition Director) upon any matters which arise during the competition and for which provision has not been made in these Rules (or any applicable regulations) or the arrangements for the competitions or which might require a deviation from them in order for the competition to continue in whole or in part or in order to ensure fairness to those taking part. j) That if requested, to chair the Technical Meeting and brief the Technical Officials k) The submission of written reports in advance of the competition on its preparation and after its conclusion on the execution, including recommendations for future editions. Technical Delegates appointed for one day meetings shall provide all necessary support and advice to the LOC and ensure the submission of written reports on the execution of the competition. 2.2 Medical Delegate The Medical Delegate shall: a) Have ultimate authority on all medical matters. They shall be given full access to the available medical information and communicate with the LOC chief medical officer. b) Ensure that adequate facilities for medical examination, treatment and emergency care will be available at the venue(s) of the competition, training and Warm-up Areas and that medical attention can be provided where athletes are accommodated and for provision of and compliance with the requirements of Rule 7.1. c) Review medical certificates in accordance with Rule 5.4 and Regulation 6.3.	b) 使用できる投てき用具の一覧表及び競技者個人所有の投てき用具や供給業者提供の投てき用具の使用可否の承認を行う。 c) フィールド競技の予選通過標準記録とトラック競技における予選ラウンド設定の基準を決定しなければならない。 d) 参加加盟団体に対し、競技実施まで十分な余裕の期間において、適用する競技注意事項等を確実に提示する。 e) 競技を実施するにあたって必要となるすべての競技運営準備全般に責任を持つ。 f) 競技規則上の理由に従って参加を拒否する権限を持つ。 g) 競技規則や適用する競技注意事項等に従い、すべての種目で組み合わせ及び抽選を行い、スタートリストを承認する。 h) パラリンピック大会や WPA 世界選手権大会 (Part B - 3.1.2 (a) 及び (b)参照)では 競技前に発生した問題や、競技規則や競技注意事項等であらかじめ取決めがなされていなかったあらゆる問題に対して、組織委員会(LOC)と共に決定する。 i) 関係する審判長や競技会ディレクターとの協議も含め、競技規則や競技注意事項等であらかじめ取決めがなされていなかった、競技中に発生したあらゆる問題に対して、あらゆる事項に関する決定を行う。あるいは競技会全体あるいは一部を継続するために、参加している競技者の公平性を確保するために、競技規則や競技注意事項等に規定されていない運営が必要な場合の決定を行う。 j) 要請があった場合は監督会議の議長を務め、競技役員に必要な指示を与えなければならない。 k)競技会前には競技会準備状況報告書を、競技会後には今後への提言を含む競技会実施報告書を、書面で提出する。 1 日開催の競技会に指名された技術代表は、必要な支援やアドバイスを組織委員会(LOC)に行い、競技会実施報告書を書面で提出する。 技術代表に関する情報は WA のウェブサイトから入手可能な技術代表ガイドラインにより提供される。 2.2 医事代表 医事代表は以下のことを行う。 a) 全ての医事関連事項について、最終判断の権限を持つ。彼らは、組織委員会のメディカル主任と連携し可能な限りの医療情報を得ることができる。 b) 競技実施場所、練習場、ウォーミングアップエリアにおける医事関係の検査、治療、救急処置についての十分な設備の設置、また競技者が滞在している場所での規則 7.1 の要件を満たし遵守した医療関係サービスを確実に提供する。 c) 規則 5.4 及び規程 6.3 に従い、診療を行い、診断書を発行する。	2.2 医 事 代 表
---	---	---

d) Have the power to order an athlete to withdraw before, or to immediately retire from an event during, competition. Note (i): The powers under (c) and (d) above may be passed by the Medical Delegate to (or where no Medical Delegate is appointed or available be exercised by) the LOC Chief Medical Doctor or one or more medical doctors appointed and so designated by the LOC who should normally be identified by an armband, vest or similar distinctive apparel. Where the Medical Delegate or doctor is not immediately available to the athlete, they may provide instruction or direction to an official or other authorised person to act on their behalf. Note (ii): Prior to withdrawing an athlete before the commencement of an event under Rule 2.2(d), that athlete must be examined by one of the medical doctors appointed by the LOC. Any athlete withdrawn during an event under Rule 2.2(d) must, as soon as practically possible after the withdrawal, be examined by one of the medical doctors appointed by the LOC. Note (iii): Any athlete withdrawn or retired from a running event under Rule 2.2(d) shall be shown in the result as DNS and DNF respectively. Any athlete not complying with such an order shall be disqualified from that event. Note (iv): Any athlete withdrawn or retired from a Field Event under Rule 2.2(d) shall be shown in the result as DNS if they have not taken any trial. However, if they have taken any trials, the results of those trials shall stand and the athlete classified in the result accordingly. Any athlete not complying with such an order shall be disqualified from further participation in that event. COMMENT: The health and safety of all participants in the competition is a high priority consideration for WPA, other governing bodies and by the LOC of the competition. The availability of the expertise of a well-respected and qualified person in the role of Medical Delegate is essential to carry out these key tasks, especially as they (or those authorised by them or the LOC) amongst other duties has the responsibility to withdraw an athlete from competition if deemed necessary for medical reasons. It is important to note that the power of the Medical Delegate (or a medical doctor acting at their request or in their place) applies to all events. It is essential that there is a reliable communication system and procedures in place between the Medical Delegate (and those authorised to act in their place), the Technical Delegates and the Competition Director particularly in relation to the duties under (c) and (d) above as these have a direct impact on start lists, results and the management of the competition 2.3 Doping Control Delegate The Doping Control Delegate shall liaise with the LOC to ensure that suitable facilities are provided for the conduct of doping control. They shall be responsible for all matters relating to doping control. 2.4 International Technical Officials (ITOs) Where ITOs are appointed, the Technical	d) 競技者に対し、競技開始前に出場を止めさせたり、競技中でも競技を中止させる権限を持つ。 注意(i) 上記(c)(d)の権限は、医事代表（任命されていない場合や不在の場合も含む）から組織委員会の主任医師または組織委員会によって任命された1名ないし複数の医師に委譲することができる。そうした医師は腕章やベスト、周囲と区別できる服装を着用すべきである。 医事代表が任命された医師が直ちに競技者の診療ができない場合には、審判員や大会関係者に対して、自分に代わって行動するように指示を与えることができる。 注意(ii) 規則 2.2(d)により、種目開始前に競技者を欠場させる場合、事前に、その競技者は LOC によって任命された医師の 1 人によって検査されなければならない。規則 2.2(d)により、種目実施中に競技を中止させられた競技者は、棄権後できるだけ早く、LOC によって任命された医師の 1 人によって検査されなければならない。 注意(iii) 規則 2.2(d)により、出場を止められたり、競技を中止された競技者は、DNS か DNF として記録される。この指示に従わない競技者は失格となる。 注意(iv) 規則 2.2(d)によって出場を止めさせられたり、競技を中止させられたりしたフィールド競技の競技者が試技をしていなかった場合、リザルトでは DNS と表記される。しかし、試技を行った場合には試技の結果は成立し、競技者はその結果に従って扱われる。この指示に従わない競技者は失格となり、その種目においてそれ以後、競技する権利を失う。 コメント：競技会に参加するすべての参加者の健康と安全は、WPA、各加盟団体、競技会組織委員会(LOC)にとって最優先事項である。これらの重要な任務を果たすためには、高い評価を受け、資格を有する専門家の知見が不可欠である。特に、医事代表（あるいは医事代表または主催者によって承認された者）はその職務に加え、医学的理由から必要と判断した場合、競技者を競技会から撤退させる責任を負う。医事代表（または医事代表の要求に応じて行動する医師）の権限は、すべての競技に適用される事に注意することが重要である。医事代表（およびその代わりに行動する権限を与えられた者）、技術代表、および競技会ディレクターとの間には、信頼できる通信システムと手順が整備されていることが不可欠である。特に（c）および（d）に基づく職務に関しては、スタートリスト、競技結果そして競技運営に直接影響を及ぼすため、確実な連携が求められる。 2.3 ドーピングコントロール代表 ドーピングコントロール代表は組織委員会と連絡し、ドーピングテストを行う適切な施設を整えなければならない。同代表は、ドーピングコントロールに関する事項について責任を負う。 2.4 国際技術委員(ITOs) 技術代表は ITO が任命されている競技会で、事前に	2.3 ドーピングコントロール代表 2.4 国際技術委員 ITOs
--	---	--

Delegate shall appoint the Chief ITO among the appointed ITOs, if one was not appointed previously. Whenever possible, the Chief ITO, in conjunction with the Technical Delegates, shall assign at least one ITO for every event on the programme. The ITO shall be the Referee of each event to which they are assigned. COMMENT: From January 2016, the role of the International Technical Official (ITO) has changed significantly but this is a logical part of the evolution of the position. From this time the ITOs act as the Referee of the events to which they are appointed. Amongst the locally appointed Officials, the Chief Judge will now be the “senior” and lead role and if in the past there was some organisational or training aspect of the team that was undertaken by a locally appointed referee, these tasks will become the duty of the respective Chief Judges. It has been noticed that the ITOs are very helpful to the Technical Delegate(s) and the LOC. They must have a great knowledge of rules, officiate within their National Governing Bodies as Referee at major competitions in their country, and be responsible for developing or delivering officiating courses in their countries. They must also know the duties of the Meeting Manager and, in principle, they should be familiar with such duties and finally, it is necessary that they speak English. WPA has developed an education pathway for Technical Officials similar to the WARECS of the World Athletics. The pathway includes an online introductory training program, national technical officiating training and international technical officiating training. Those who pass the International Technical Officials course (which includes a requirement for spoken and written English) are eligible for the International Technical Officials panel which is established every four years. The first official panel selection was conducted in November 2017. It is also extremely important that ITOs understand well the duties of the Referees; as with the changes in 2016 ITOs act as the relevant Referee for events that they are assigned. 2.5 International Road Course Measurer An International Road Course Measurer may be appointed to verify the courses where road events are held entirely or partially outside the stadium. The appointed course measurer shall be a member of the World Athletics /AIMS Panel of International Road Course Measurers (Grade “A” or “B”). The course should be measured in good time before the competition. The measurer will check and certify the course if they find it conforms to the Rules for Road Race (See Rule 49.2 and Rule 49.3 and respective notes). They shall cooperate with the LOC in the course arrangements and witness the conduct of the race to ensure that the course run by athletes follows the same course that was measured and approved. They shall furnish an appropriate certificate to the Technical Delegate(s). COMMENT: It is important to note that WPA does not certify course measurers but uses those	ITO 主任が任命されていなければ、ITO の中から主任を任命しなければならない。ITO 主任は可能な限り実施される各種目にそれぞれ 1 人の ITO を任命しなければならない。ITO は担当する各種目の審判長を務める。 コメント：2016 年 1 月から、国際技術委員 (ITO) の役割は大幅に変更されたが、これは身分を発展的にとらえた必然的な部分である。この時から任命された ITO は指定された競技の審判長として行動する。現地で任命された役員の中で、主任審判員は「上級」で主導的な役割を果たし、過去に現地で任命された審判長によって行われたチームの組織的または訓練的側面があった場合、これらのタスクはそれぞれの主任審判員の責任になる。 ITO は技術代表と LOC に非常に役立つ。彼らはルールについての豊富な知識を持ち、自国の主要な大会で審判長として国の主催団体内で担当し、自国での審判育成の開発または実施に責任を負っている。彼らはまた、大会総務の義務を知っていて、原則として、彼らはそのような義務に精通して、最後に、彼らは英語を話せることが必要である。 WPA は、世界陸上競技連盟の TOECS と同様の技術役員向けの教育方法を開発した。この方法には、オンラインの入門トレーニングプログラム、国内の技術役員研修、及び国際的な技術役員研修が含まれる。国際的な技術役員研修コース（英語の口頭及び筆記の要件を含む）に合格すると、4 年ごとに設立される国際的な技術役員パネルの資格が得られる。最初の公式パネル選考は 2017 年 11 月に行われた。ITO が審判長の職務をよく理解していることも非常に重要である。2016 年の変更と同様に、ITO は割り当てられた種目の担当審判長として行動する。 2.5 国際道路コース計測員 全部あるいは部分的に競技場外で実施する道路競技種目のコースを確認するために、1 人の国際道路コース計測員を任命しなければならない。 任命される計測員は WA/AIMS 国際道路コース計測員（A または B 級）でなければならない。 コースは競技会が行われるより以前の適切な時期に計測されなければならない。計測員は、そのコースが道路競走に関する規則（規則 49.2、49.3 及び注意）に合致しているか確認し証明する。 また、計測員はコース設定に当たって組織委員会に協力するとともに、競技者が競技したコースが事前の計測によって承認したコースと同一であることを確認するために競技に立ち会わなければならない。さらに計測員は技術代表に適切な証明書を提供する。 コメント：WPA は、コース計測員の認証をしていないため、WA ロードレースから独立して実施されるレース
--	--

certified by World Athletics /AIMS for any of their events which run independently of World Athletics road races. 2.6 International Starter and International Photo Finish Judge At all Paralympic Games and WPA Championships (see Part B - 3.1.2 (a) and (b)) an International Starter and an International Photo Finish Judge shall be appointed by WPA. The International Starter shall start the races and undertake any other duties assigned to them by the Technical Delegate(s). The International Photo Finish Judge shall supervise all Photo Finish functions and shall be the Chief Photo Finish Judge. COMMENT: It is noted that whilst the International Photo Finish Judge acts as the Chief Photo Finish Judge at those competitions to which they are appointed and the ITOs act as Referees, there remains a clear division in responsibilities between the International Starter (IS) and the other members of the start team. Whilst the IS takes on all the powers and duties of the Starter when starting any race to which they are allocated, they do not either then or at any other time replace or have the power to override the Start Referee. 2.7 Jury of Appeal At all Paralympic Games and WPA Championships (see Part B - 3.1.2 (a) and (b)) a Jury of Appeal shall be appointed. The Jury should normally consist of three, five or seven persons. One of its members shall be the Chairman and another Secretary. If and when considered as appropriate, the Secretary may be a person not included in the Jury. Members of the Jury of Appeal shall not be present during any deliberations of the Jury concerning any Appeal that affects, directly or indirectly, an athlete affiliated to their own national governing body. The chair of the Jury shall ask any member implicated by this rule to withdraw, in the event the Jury member has not already done so. WPA or other organisation responsible for the competition shall appoint one or more alternative Jury members to substitute for any Jury member(s) who are not able to participate in an Appeal. Further more, a Jury of Appeal should likewise be appointed at other competitions where the LOC deem it desirable or necessary in the interest of the proper conduct of the competitions. The primary functions of the Jury of Appeal shall be to deal with all protest appeals, and any matters arising during the course of the competition that are referred to it for decision. COMMENT: It is particularly important to note that in certain circumstances now, where new conclusive evidence is available, that both the Referee (in the case of a protest) and the Jury (in the case of an appeal) can reconsider the decision if it was made in error – it is still applicable and practical to do so. Normally all of this is done prior to the Victory Ceremony for the event in question.	では、WA/AIMS 認証コースを利用することを理解することは重要である。 2.6 国際スターターと国際写真判定員 パラリンピック競技大会及び WPA 競技会(PART-B 規則 3.1.2 参照)に該当する競技場内での競技会では WPA が国際スターターと国際写真判定員を任命する。 国際スターターは技術代表によって割り当てられたレースをスタートさせるとともに、関連した任務も遂行する。国際写真判定員は写真判定員主任となり写真判定業務を監督する。 コメント：国際写真判定員は、ITO が任命され審判長を務める競技会において写真判定員主任を務める一方で、国際スターター（IS）と他のスタートチームメンバーとの間の責任は明確に区分されていることを留意しなくてはならない。IS は、自身が割り当てられたレースのスタートに関しては、スターターとしてのすべての権限と義務を負うが、スターターとしての任にある時だけでなく、それ以外のいかなる場面でも、スタート審判長の任を代行したり、その決定を覆したりする権限は持っていない。 2.7 ジュリー パラリンピック競技大会及び WPA 競技会(PART-B 規則 3.1.2(a)及び(b)参照)に該当する競技会ではジュリーを任命しなければならない。ジュリーは、通常 3 人か 5 人、または 7 人で構成される。このうち 1 人を主任とし、もう 1 人を秘書とする。必要であれば、秘書はジュリーとは別の人物でもよい。 ジュリーのメンバーは直接的・間接的にも自身が所属する加盟団体の競技者の上訴については、審議に加わることはない。 ジュリーの主任はこの規則に関連するメンバーに退席するよう要請しなければならない。 競技会運営に責任がある WPA あるいはその他の組織委員会(LOC)は審議に参加できないジュリーに欠員が生じた時のために 1 人もしくは 2 人の交代要員を指名しなくてはならない。 上記競技会以外でもさらに組織委員会がその競技会の遂行上好ましいと考える場合は同様なジュリーを設けるべきである。 ジュリーは上訴について裁定し、また競技会の進行中に生じた問題のうち、その決定を付託された事項について裁定することを基本的な任務とする。 コメント：新しい決定的な証拠が利用できるようになった特定の状況では、審判長（抗議の場合）とジュリー（上訴の場合）の両方が決定を再検討できることに注意することが特に重要である。間違いがあった場合でも、適用可能で実用的である。通常、これはすべて、問題の種目の表彰式の前に行われる。	2.6 国際スターターと国際写真判定員 2.7 ジュリー
--	--	--

2.8 Officials of the Competition The LOC of a competition and/or the relevant governing body shall appoint all other officials, subject to these Rules. The following list comprises the officials considered necessary and or desirable for major International Competitions. The LOC may, however, vary this according to local circumstances. MANAGEMENT OFFICIALS • One Competition Director • One Meeting Manager and an adequate number of assistants • One Technical Manager • One Event Presentation Manager COMPETITION OFFICIALS • One (or more) Referee(s) for the Call Room • One (or more) Referee(s) for Track Events • One (or more) Referee(s) for Field Events • One (or more) Referee(s) for events outside the Stadium • One (or more) Video Referee (s) • One Chief Judge and an adequate number of Judges for Track Events • One Chief Judge and an adequate number of Judges for each Field Event • One Chief Umpire and an adequate number of Umpires • One Chief Timekeeper and an adequate number of Timekeepers • One Chief Photo Finish Judge and an adequate number of assistants • One Chief Transponder Timing Judge and an adequate number of assistants • One Start co-ordinator and an adequate number of Starters and Recalls • One (or more) Starter's Assistant(s) • One Chief and an adequate number of Lap Scorers • One Competition Secretary and an adequate number of assistants • One Technical Information Centre (TIC) Manager and an adequate number of assistants • One Chief and an adequate number of Marshals • One (or more) Wind Gauge Operator(s) • One Chief Measurement Judge (Scientific) and an adequate number of assistants • One Chief and an adequate number of Call Room Judges ADDITIONAL OFFICIALS • One (or more) Announcer(s) • One (or more) Statistician(s) • One Advertising Commissioner • One Official Surveyor • One (or more) Doctor(s) • Stewards for Athletes, Officials and Press Referees and Chief Judges should wear a distinctive attire or insignia. Care should however be taken to limit the number of officials present within the field of play to that number necessary for the smooth running of the competition. Where women's events are held, a female doctor shall be appointed when possible. COMMENT: The number of officials appointed to a competition should be adequate to ensure the required duties are carried out both correctly and	2.8 競技会役員 競技会の組織委員会および競技会統括団体は、これら規則に基づき、上記以外にも必要とされるすべての役員を任命しなくてはならない。 下記に示されたリストは、必要と考えられ、かつ主要国際競技会で必須とされる役員である。しかしながら、組織委員会(LOC)の状況によってこれを変更してかまわない。 運営役員 ・競技会ディレクター(1 人) ・総務(1 人)及び補佐(適切な人数) ・技術総務 (1 人) ・イベント・プレゼンテーション・マネージャー(1 人) 競技役員 ・招集所審判長(1 人以上) ・トラック競技審判長(1 人以上) ・フィールド競技審判長(1 人以上) ・場外競技審判長(1 人以上) ・ビデオ監察審判長(1 人以上) ・決勝審判員主任(1 人)及び同審判員(適切な人数) ・フィールド競技審判員主任(1 人)及び同審判(適切な人数) ・監察員主任(1 名)及び監察員(適切な人数) ・計時員主任(1 名)及び計時員(適切な人数) ・写真判定員主任(1 名)及び補佐(適切な人数) ・トランスポンダー主任(1 名)及び補佐(適切な人数) ・スタートコーディネーター(1 名)及びスターター、リコーラー (適切な人数) ・出発係(1 名以上) ・周回記録員主任(1 名)及び周回記録員(適切な人数) ・記録・情報処理員(1 名)及び補佐(適切な人数) ・TIC マネージャー(1 名)及び補佐(適切な人数) ・マーシャル主任(1 名)及びマーシャル(適切な人数) ・風力計測員(1 名以上) ・計測員(科学)主任(1 名)及び補佐(適切な人数) ・競技者係主任(1 名)及び競技者係(適切な人数) 上記以外の役員 ・アナウンサー(1 名以上) ・記録統計担当者(1 名以上) ・広告コミッショナー(1 名) ・公式計測員(1 名) ・医師(1 名以上) ・競技者、役員、報道に関わる必要な役員 審判長及び審判員主任は、目立つ服装または腕章を着用するとよい。 競技区域には、必要最小限の役員のみがいるよう最大限の配慮がなされなくてはならない。 女子の競技が行われる時は、できる限り女性医師 1 名は任命されなくてはならない。 コメント：競技会に委嘱される競技役員の数、競技が 1 日または数日間連続して長時間にわたって行	2.8 競技会役員
--	--	-------------------------

efficiently and also to ensure sufficient rest if the competition is over a long period of time on a single day or on several consecutive days. But care must also be taken not to appoint too many so that the competition area becomes cluttered or obstructed by unnecessary personnel. In more and more competitions, some tasks undertaken by on-field officials are being “replaced” by technology and unless a back-up is logically required, this needs to be taken into account when officials are appointed.

A Note on Safety

Competition officials at athletics events have many important functions, but none is more important than their roles in ensuring the safety of all concerned. The athletics arena can be a dangerous place. Heavy and sharp implements are thrown and pose a hazard to anyone in their path. Athletes running on the track or on runways at high speeds can hurt themselves and anyone with whom they collide. Those competing in jumping events, often land in an unexpected or unintended manner. Weather and other conditions can make athletic competition unsafe either temporarily or for longer periods. There have been instances of athletes, officials, photographers and others who have been injured (sometimes fatally) in accidents in or near competition and training areas. Many of those injuries could have been prevented.

Officials must always be mindful of the dangers that are inherent in the sport. They must be alert at all times and must not allow themselves to be distracted. Regardless of their official position, all officials have the responsibility to do what they can to make the athletics arena a safer place. All officials should think about safety whenever and wherever they are in the competition area, and should intervene when necessary to prevent an accident, when they see conditions or a situation that could lead to one. Ensuring safety is of the utmost importance – even more so than strict compliance with the rules of competition. In the rare event when there is a conflict, the concern for safety must prevail.

2.9 Competition Director

The Competition Director shall, where applicable with the Technical, and other relevant, Delegate(s):

1. plan the technical organisation of a competition, including the integration of Event Presentation and Victory Ceremonies;
2. ensure that this plan is executed before and during the competition;
3. ensure that any technical problems are resolved or an alternate solution put in place;
4. direct the interaction between the participants in the competition; and
5. through the communication system, be in contact with all key officials and other relevant stakeholders involved in the delivery and broadcast of the competition;
6. engage fully with the Event Presentation Manager to ensure compliance with Rule 2.12;
7. ensure the accurate preparation and publication of the Call Room schedule in

われる場合、競技会が正確かつ効率的に実行されることを確実にするために十分なものでなければならない。しかし、競技区域が不必要な人員によって混みあったり、妨げられたりすることがないように、あまりにも多くの競技役員を委嘱しすぎないように注意しなければならない。競技会によっては、現場の競技役員による任務の一部は、技術力によって代替可能であるので、バックアップ要員が必要であるという相応の理由がない限りは、この点を考慮する必要がある。

安全に関する注意

陸上競技の競技役員には多くの重要な役割があるが、すべての関係者の安全確保が何より重要な任務である。陸上競技の実施場所は危険な場所になりうる。重くて鋭い器具が投げられることで、通りがかりの者に危険をもたらす。トラックや助走路を速いスピードで走っている競技者は、自分自身だけでなく、衝突した相手を傷つけてしまう可能性がある。跳躍競技を行っている競技者は、しばしば予期しないまたは意図しない形で着地することがある。天気やその他の条件によって、一時的に、または長期間、陸上競技会が危険にさらされることもある。

競技実施場所やトレーニングエリアやその近くで、競技者、競技役員、カメラマン、その他の関係者が怪我をするという（時には命に関わるほどの）事故が発生しているが、これらの怪我の多くは防ぐことができたと思われる。

競技役員は、スポーツに内在する危険性に常に注意する必要がある。競技役員は常に注意を払い、気を散らしてはならない。競技役員としての立場に関わらず、全員が陸上競技場をより安全な場所にするためにできることを行う責任がある。すべての競技役員は、競技実施場所にいる間はいつでもどこでも安全を考えるべきであり、何らかの事態が発生する可能性がある状況を目にしたなら、事故を防止するために、必要に応じて介入すべきである。競技規則を厳格に遵守するよりも安全性を確保することがより重要である。規則の遵守と安全確保において相反する状況が発生した場合、安全が優先されなければならない。

2.9 競技会ディレクター

競技会ディレクターは、技術代表およびその他の関係する代表とともに、以下の業務を行わなければならない。

- 2.9.1. イベントプレゼンテーションと表彰式を含めた、競技会の技術的な運営を計画する。
- 2.9.2. 立案した計画が競技前および競技中に確実に実行されるようにする。
- 2.9.3. 技術的な問題が解決されるか、代替する解決策を取り入れることを確認する。
- 2.9.4. 競技会参加者の相互の影響状況を監督し、各種指示を行う。
- 2.9.5. 情報伝達システムを通して、競技会映像の配信や放送に関係する全ての主要関係者およびその他の関係者と連絡を取り合う。
- 2.9.6. 規則 2.12 を確実に順守するために、イベントプレゼンテーションマネージャーと十分な連携を図る。
- 2.9.7. 規則 2.24.に従い、招集所のスケジュールを正確に作成し、公開する。

accordance with Rule 2.24; 8. communicate with the Start Coordinator to ensure the efficient operation of Rule 2.17.1(a); 9. be fully aware of the applicable regulations for the competition and the functioning of the planned technological and IT systems; and 10. manage any matters arising under Rule 8.5. Note: For Paralympic Games and WPA World Championships, the appointment of the Competition Director must be approved by WPA. COMMENT: During the competition, to ensure an efficient operation, the Competition Director should be located with an optimal view of the competition area, close to the Event Presentation team and with satisfactory and reliable availability of technological connections and supporting monitors. 2.10 Meeting Manager The Meeting Manager shall be responsible for the correct conduct of the Competition. They shall check that all officials have reported for duty, appoint substitutes when necessary and have authority to remove from duty any official who is not abiding by the Rules. In cooperation with the appointed Marshal, they shall arrange that only authorised persons are allowed in field of play areas. Note: For competitions of longer than four hours or over more than one day, it is recommended that the Meeting Manager has an adequate number of Assistant Meeting Managers. COMMENT: While WPA Rules are sometimes rather simple in wording they, in reality, hide very heavy responsibilities such as when we consider the duties of the competition director or Meeting Manager at any competition, but particularly those the size of the Paralympic Games, the World or Regional Championships. The Meeting Manager(s) must be responsible, under the authority of the Competition director, and in accordance with the Technical Delegates' guidance and decisions, for everything happening in the field of play. In the stadium, they must place themselves so as to be able to see everything that is happening and to give necessary orders. They must have in their possession the complete list of all appointed officials and be able to communicate efficiently with the other Managers, Referees and Chief Judges. In competitions that take place over multiple days in particular it is possible that some judges may not be able to officiate during the whole competition. The Meeting Manager shall have at their disposal a reserve of officials from which they can draw any replacement, if necessary. Even if all the officials for an event are present, the Meeting Manager should ensure that the officials fulfil their duties correctly and if they do not be ready to replace them. They shall ensure that the Judges (and those assisting them) leave	2.9.8. 規則 2.17.1(a)の効率的な運用を確保するために、スタートコーディネーターと連絡を取る。 2.9.9. 競技会に適用される競技注意事項と、導入される技術および IT システムの機能を十分に理解する。 2.9.10. 規則 8.5 に関して生じるあらゆる問題を管理する。 注意: パラリンピック大会及び WPA 世界選手権では、競技会ディレクターの任命は WPA の承認が得なければならない。 コメント: 競技会中、効率的な運営を確保するために、競技会ディレクターはイベントプレゼンテーション・マネージャーの近くで、技術的なサポートが受けられ、モニター画面が十分かつ信頼してみることができる状態で、競技会全体を視覚的に把握できる場所に位置する。 2.10 総務 総務は競技会を順調に進行させる責任を負う。また役員の任務遂行の状況を把握し、必要がある時にはその代わりの者を任命する。また競技規則に精通していない役員の任を解く権限を有する。マーシャルと協同して、許可された者以外は競技区域内に入れないようにする。 注意: 4 時間を超える、あるいは 2 日以上競技会に、総務は総務員を任命することが望ましい。 コメント: WPA 規則は、説明の表現がかなり単純な場合もあるが、実際には、どの競技会においても、競技会ディレクター及び総務の職務を検討するにあたり、非常に重要な責任を秘めている。特に、パラリンピック競技大会、世界選手権、地域選手権はそうである。 総務は、競技会ディレクターの権限の下で、また技術代表の指導及び決定に従って、競技実施場所で行っているすべてのことについて責任を負う必要がある。競技場で、総務は、起こっていることすべてを見ることができ、必要な命令を出すことができるような場所に位置しなくてはならない。総務は、任命されたすべての競技役員全員の名簿を所持し、他のマネージャー、審判長、及び審判員主任と効率的にコミュニケーションできる必要がある。 複数日に渡って開催される競技会では、審判員の一部は、競技会全体を通して任にあたることできない可能性がある。総務は、必要に応じて、交代要員を補充できるよう、予備の競技役員名簿を所持しておくべきである。競技に十分な数の競技役員がいても、総務は競技役員が任務を正しく遂行しているかどうかを確認し、もし不適当であるなら、その競技役員を交代させる準備をしなくてはならない。 総務は、審判員（及びその補助員）が、担当する競技が終了した時点でまたはその後の業務が完了した時点で、競技実施場所から速やかに離れることを	2.10 総務
---	---	-----------------------

the arena as soon as their event is finished or when their subsequent work is done. The Competition Director, Meeting Manager and Technical Delegate(s) all work together to ensure the best possible conditions for athletes to perform and for spectators to observe and celebrate the performances 2.11 Technical Manager The Technical Manager shall be responsible for: a) Ensuring that the track, runways, circles, arcs, sectors, landing areas for Field Events and all equipment and implements are in accordance with the Rules. b) The placement and removal of equipment and implements according to the technical organisational plan for the competition as approved by the Technical Delegates. c) Ensuring the technical presentation of the competition areas is in accordance with such plan. d) Checking and marking any personal implements permitted for the competition according to Rule 30.3. e) Ensuring that they have received or are aware of the existence of, the necessary certification under Rule 10.1 before the competition. COMMENT: The Technical Manager acts under the authority of the Competition Director or the Meeting Manager but of course an experienced Technical Manager will undertake much of their role without any direction or supervision. They must be contactable at any time. If a Referee or a Field Event Chief Judge notices that the site where an event is taking place (or will take place) needs to be modified or improved, they must refer it to the Meeting Manager who will ask the Technical Manager to take the necessary action. Also, when a Referee feels that there is a need for a change of place of a competition (Rule 24.20) they will act the same way towards the Meeting Manager who will instruct the Technical Manager to carry out, or have carried out, the wishes of the Referee. It must be remembered that neither the wind strength nor its change of direction is sufficient condition to change the place of the competition. Once the Competition director, or for international competitions the Technical Delegates, has approved the implements list to be used during the events, the Technical Manager shall prepare, order and receive the various implements. For the latter, their team must then carefully check their weight and dimensions, and any personal implements that are permitted and submitted, in order to comply with the Rules. They must also ensure that 51.20 (d) is followed in both a correct and efficient manner if a Record is set. In relation to throwing implements, the Technical Manager(s) should apply the range of implements for competition specified in these tables when	確実にしなければならない。 2.11 技術総務 技術総務は以下の点を確認する責任を負う。 a) トラック、助走路、サークル、円弧、角度、フィールド競技の着地場所及び用器具が競技規則に合致していること b) 技術代表によって承認された競技会の技術的・組織的計画に従って用器具を設置することと撤収すること c) 競技場所の設備や用器具等が前述の計画に従っていること d) 規則 30.3 に従って、競技会に許可された個人の投てき用具を点検し、マークを付けること e) 規則 10.1 に従って、競技会前に公式計測員から必要な証明書を受け取ること コメント：技術総務は競技会ディレクターまたは総務の権限の下で行動するが、もちろん経験豊富な技術総務は監督、指示がなくとも自らの役割の多くを遂行する。技術総務は、常に連絡が取れる状態でなければならない。審判長またはフィールド審判員主任が、種目を実施している（または実施することになる）場所を変更または改善する必要があることに気付いた場合は、総務に連絡し、総務は技術総務に必要な対応を依頼する。審判長が、競技実施場所の移動（規則 24.20）が必要であると感じた際にも、同様の対応を行い、総務から技術総務に対し、審判長の要請を実施する、または実施させるよう指示する。ただし、風の強さや風向きの変化のみをもって、競技実施場所を変更する十分な条件ではないことを留意しなければならない。 競技会ディレクターまたは技術代表が、競技中に使用する投てき用具を承認したなら、技術総務は、さまざまな物品を、準備し、注文し、受け取らなくてはならない。その後、技術総務またはそのチームは、これら公式投てき物の重量と寸法、提出された個人持ち込み投てき物が規則に合致するかを慎重にチェックしなければならない。また、記録が誕生した場合、規則 51.20(d)が正確かつ効率的に実施されることを保証しなければならない。 投てき用具に関連して、技術総務は、製造会社から新しい投てき物を受け入れる際に、このガイドラインを適用すべきであるが、この重さの範囲にないことを理由に、競技会に提出され使用される器具を拒否してはならない。この点で重要なのは最小重量である。	2.11 技術総務
--	--	-------------------------

accepting new equipment from suppliers but should not reject implements submitted for or used in competition because they do not comply with this range. It is the minimum weight that is critical in this regard. 2.12 Event Presentation Manager The Event Presentation Manager shall plan and implement, in conjunction with the Competition Director, the event presentation arrangements for the competition. They shall also direct the interaction between the members of the event presentation team, using the communication system to be in contact with each of them. They shall ensure that, through announcements and the available technology, the public is informed of information concerning the athletes taking part in each event, including the start lists, Classification, intermediate and final results. The official result (placings, times, heights, distances and points) of each event should be conveyed at the earliest practicable moment after receipt of the information. COMMENT: The Event Presentation Manager not only has the responsibility of planning, leading and coordinating a production in presentation terms of all the activities that take place on the infield but also integrating them into the show to be presented to the spectators within the venue. The final aim of their work is to create an informative, entertaining, lively and attractive production of the show that is to be offered to the spectators. To succeed in this, it is important to have a team and the necessary equipment to carry out the work. The Event Presentation Manager is the person in charge of coordinating the activities of the event presentation staff working on and off the field who are related to this role including but not limited to the Announcers, Scoreboard and videoboard Operators, Audio and video Technicians and victory Ceremony officials. For almost every competition, an announcer is essential. They must be placed so as to be able to follow the meeting properly and preferably near to or otherwise in immediate communication with the Competition Director or if appointed, the Event Presentation Manager. It is also critical that the Event Presentation Manager is aware of the events which require more quiet (such as T11/T12 Long Jump or Triple Jump events) so as to ensure the announcers and music/sound system respects the requirement for a quieter presentation of these events. 2.13 Referees 1. One (or more) Referee(s) shall be appointed respectively for the Call Room, for Track Events, for Field Events, and for Road Race Events outside the stadium. When appropriate, one (or more) Video Referee(s) shall be appointed. The Video Referee(s) shall operate from a Video Review Room, should consult and shall be in communication with the other Referees.	2.12 イベント・プレゼンテーション・マネージャー イベント・プレゼンテーション・マネージャーは競技会ディレクターと共に競技会の各種目やその他の演出準備を組織代表及び技術代表と協力して計画する。また、その計画が達成されるよう、競技会ディレクター及び関係する代表と協力して関連する諸問題を解決する。イベント・プレゼンテーション・チーム内の連携についても、情報伝達システムを利用して監督する。各競技のスタートリスト、クラス分け、途中経過、及び結果等の情報をアナウンスまたは他の方法で確実に提供させる。各種目の結果（順位、時間、高さ、距離、得点）は情報を受け取ったならば、できるだけ早く発表させる。 コメント：イベントプレゼンテーションマネージャー（EPM）は、インフィールドで行われるすべての活動のプレゼンテーションについてのプロダクションの企画、指導、調整を行うだけでなく、ショーに組み込んで会場内の観客に提示する責任も持っている。EPM 業務の最終的な目的は、観客に提供されるショーの有益で活気に満ちた、魅力的なプロダクションを作り出すことである。この成功のために、作業を実行するための EP チームと必要な機器を用意することが重要である。EPM は、アナウンサー、スコアボード及びビデオボードオペレーター、オーディオ及びビデオ技術者、表彰式スタッフやそれ以外でも、この役割に関連する現地内外で任務にあたるイベントプレゼンテーションスタッフの活動を調整する責任者である。ほとんどの競技会において、アナウンサーは不可欠である。アナウンサーは、できれば競技会ディレクターの近くで、またはそうでなければ競技会ディレクター及び任命されていればイベントプレゼンテーションマネージャーと速やかに交信することができるようにして、適切に競技会を進行できるような場所に位置すべきである。 また、アナウンサーと音楽/サウンドシステムがより静かなプレゼンテーションを尊重するように、イベントプレゼンテーションマネージャーはより静かにする必要があるイベント（T11/T12 走幅跳または三段跳など）を認識していることも重要である。 2.13 審判長 2.13.1. 招集所、トラック競技、フィールド競技、道路競技、ビデオ監察には必要に応じて 1 人以上の審判長を任命する。ビデオ監察審判長は、他の審判長と連絡をとりながら、ビデオ管理室で判定を行わなければならない。	2.12 イ ベ ン ト ・ プ レ ゼ ン テ ー シ ョ ン ・ マ ネ ー ジ ャ ー 2.13 審 判 長
--	---	---

COMMENT: At meetings where sufficient officials are available so that more than one Referee is appointed for the races, it is strongly recommended that one of them is appointed as the Start Referee. This Start Referee should be a specialist and experienced starter, thus basing their observations on a technically sound background. To be clear the Start Referee in such circumstances should exercise all the powers of the Referee in relation to the start and is not required to report to or act through any other track Referee when doing so. However, if only one Referee is appointed to oversee the races of a certain competition, and considering the powers they have, it is strongly recommended that the Referee be positioned in the start area, during each start (at least for those events using a crouch start) to witness any eventual problem that may occur and to take any decision needed to solve it. This will be easier when a World Athletics certified Start Information System is in use. If not, and if the Referee will not have time to place themselves in line with the finish line after the start procedure (as in 100m and 200m) and foreseeing the possible need for the Referee to decide placings, a good solution may be to have the Start Coordinator (who should have an extensive experience as a starter) being appointed to also act as Start Referee. 2. Referees shall ensure that these Rules (and applicable Technical Regulations) are observed and shall decide upon any matters which arise during the competition (including in the Warm-up Area, Call Room and, after the competition, up to and including the Victory Ceremony) and for which provision has not been made in these Rules (or any applicable Technical Regulations), where appropriate or necessary in conjunction with the Technical Delegate(s). The respective Referees for Track Events and for events outside the stadium shall have jurisdiction to decide placings in a race where the Judges of a disputed place(s) are unable to arrive at a decision. The Start Referee (or if one is not appointed, the relevant Track Referee) has the power to decide on any facts related to the starts if they do not agree with the decisions made by the start team, except in cases when it regards an apparent false start indicated by a World Athletics approved Start Information System, unless for any reason the Referee determines that the information provided by the system is obviously inaccurate. A Track Referee appointed to oversee the starts is designated the Start Referee. The Referee shall not act as a Judge or Umpire but may take any action or decision according to the Rules based on their own observations and may overrule a decision of a Judge. Note: For the purpose of this Rule and applicable Regulations, including the Advertising Regulations, the Victory Ceremony is concluded	コメント：レースのために複数の審判長が任命されるような、十分な競技役員がいる大会では、その 1 人がスタート審判長として任命されることが強く推奨される。このスタート審判長は、専門的で経験豊富なスターターであるべきであり、技術的に確かな背景に基づいて観察をおこなうべきである。明確な理解のために補足すると、このような状況では、スタート審判長は、スタートに関する審判長としてのすべての権限を行使しなければならず、その際、他のトラック審判長に報告したり、了解を得て行動したりする必要はない。 しかしながら、特定の競技のレースを監督するために審判長が 1 人だけしか任命されていない場合、審判長の権限を考慮すると、スタート時には（少なくともクラウチングスタートを行う種目では）、現場で発生する可能性があるあらゆる問題を間近で見て、それを解決するために必要な決定を下す目的で、スタート地点にすることが強く推奨される。これは、WA が承認したスタート・インフォメーション・システム（SIS）が使用されていれば、より容易になる。 SIS を使用していない場合、さらに、審判長が、スタート手続き（100m 及び 200m）の後に、フィニッシュを見る場所に移動する時間がなく、審判長が順位を決定しなくてはならない可能性がある場合の最良の解決策は、スタート審判長としての任も兼ねるようスタートコーディネーター（スターターとして豊富な経験を持つべきである）を任命することである。 2.13.2. 審判長は、競技規則と競技注意事項が遵守されているかどうかを監視する責任を負う。審判長は競技運営に関するいかなる抗議や不服申し立てを裁定しなければならず、ウォーミングアップ場・招集所から競技後の表彰式に至るまでを含めて競技中に起こった技術的問題、ならびに競技規則や競技注意事項等に明確に規定されていない事項についても決定する。 トラック競技審判長、場外競技審判長は、レースの順位決定について、審判員が順位に疑義があり、順位を決定できない場合に限り、決定する権限がある。スタート審判長（任命されていなければトラック審判長）は、もしスタートチームのスタート関連の判定に同意できなければ、当該スタートに関するどのような事実についても判断する権限を持つ。ただし、審判長が WA により承認されているスタート・インフォメーション・システム（SIS）による情報が明らかな不正であるとは判断する場合を除き、スタート・インフォメーション・システムによって示された明らかな不正スタートの場合には、その権限は及ばない。 トラック審判長がスタートを管理する場合は、スタート審判長を兼ねる。 審判長は審判員または監察員としての行動をしてはならないが、自己の観察に基づいて競技規則に従ったあらゆる行動や決定を行うことができ、審判員や監察員の決定・報告を覆すこともできる。 注意：本条や広告規程を含む他の諸規程は、表彰式に関連するすべての活動（写真撮影、ビクトリーラン、観客との対応を含む）が終わるまで適用する。
--	--

when all directly related activities (including photographs, victory laps, crowd interaction etc.) are completed. COMMENT: It should be carefully noted that it is not necessary for a Referee to have received a report from a Judge or Umpire in order to make a disqualification. They may act at all times by their own direct observation. The above Note should be interpreted to include all matters which are incidental to or relate to the Victory Ceremony and that the Referee for that event is responsible for them. When Victory Ceremonies are held at a different location or in a different session, common sense should be applied and if necessary, another Referee may have to be substituted if it is not practical for the original Referee to manage the situation. 3. The appropriate Referee shall check all final results, shall deal with any disputed points and, in conjunction with the Measurement Judge (Scientific) where appointed, shall supervise the measurements of Record performances. At the conclusion of each round of an event, the result card shall be completed immediately, signed (or otherwise approved) by the appropriate Referee or the Chief Photo Finish Judge and handed to the Competition Secretary. COMMENT: For Track Events once the Track Referee and Video Referee "clear" the event, the results are released by the Chief Photo Finish Judge and there is no need to physically sign the results sheet. 4. The appropriate Referee shall rule on any protest or objection regarding the conduct of the competition (including in the Warm-up Area, Call Room and, after the competition, up to and including the Victory Ceremony). COMMENT: In major competitions such as Paralympic Games, World and Regional Championships an ITO is assigned to observe the Victory Ceremony and report on any infractions as well as to issue yellow or red cards to athletes who act in an unsporting manner. 5. A Referee shall have authority to warn or exclude from competition, any athlete or relay team in accordance with Rule 8.1. 6. The Referee may reconsider a decision (whether made in the first instance or in considering a protest) on the basis of any available evidence, provided the new decision is still applicable. Normally, such re-consideration may be undertaken only prior to the Victory Ceremony for the relevant event or any applicable decision by the Jury of Appeal. COMMENT: This Rule clarifies that as with the Jury of Appeal (see Rule 50.9) a Referee can reconsider a decision and may do so equally whether this was a decision by themselves in the first instance or one made when considering a	コメント：審判長は、失格を決定するにあたり、審判員または監察員からの報告を必ず受け取らなくてはならないということではない点に注意する必要がある。審判長は、いつでも、自身による直接の監察によって行動してよい。上記の注意は、表彰式に付随するまたは関連するすべての事項を含むと解釈されるべきであり、その種目の審判長はそれらの責任も負うものとする。表彰式が別の場所や別のセッションで実施される場合は、常識の範囲内で対応することとし、元々担当していた審判長が状況を管理することが現実的でない場合は、必要に応じて代わりの審判長を任命する必要がある。 2.13.3. 当該審判長はすべての最終結果を照合し、問題点を処理しなければならない。計測員（科学）が任命されていれば、共同して、記録計測を監督しなければならない。各種目の予選・決勝の各ラウンドが終了したら、記録用紙に当該審判長または写真判定主任による署名または承認を行った後、記録・情報処理員に引き継ぎ、成績表として直ちに完成させなければならない。 コメント：トラック競技の場合、トラック審判長とビデオ審判長が種目を「クリア(完了と判断)」したなら、結果は写真判定員主任によって展開されることになるが、その際、結果表(リザルトシート)にサインは必要ない。 2.13.4. 当該審判長は競技会の（ウォームアップ場、招集所、競技後の表彰式で生じる問題も含めて）競技運営に関する異議もしくは抗議を裁定する。 コメント：パラリンピック、世界選手権大会及び地域選手権大会などの主要競技会では、ITO が表彰式にも(審判長として)割り当てられ、違反を報告するとともに、競技者にあるまじき行為をとる者に対してはイエローカードまたはレッドカードを出す役割を果たす。 2.13.5. 審判長は規則 8.1 に基づき、競技者やリレーチームに対して警告を与えたり、当該競技会から除外する権限を持つ。 2.13.6. 審判長はもし新たな決定を適用できる状況にあるなら、明らかな証拠に基づいて、先に出した決定（最初になされたものでも、抗議を検討してなされたものでも）を再考してもよい。通常そのような再考は当該種目の表彰式が実施される前、あるいはジュリーの裁定が下される前までにおこなわれる。 コメント：この規則は、ジュリー（規則 50.9 参照）と同様に、審判長は決定を再考することができ、これが最初の自らによる決定であろうと、審判長に対しなされた抗議の検討による決定であろうと、どちらのケースでも同様に再考してよいと解釈される。このオプショ
---	--

protest made to them. This option can be considered especially when new evidence of information comes to hand quickly as it could avoid the need for a more complicated or involved appeal to the Jury of Appeal. But note the practical time limitations on such a reconsideration. 7. If, in the opinion of the appropriate Referee, circumstances arise at any competition such that justice demands that any event or any part of an event should be contested again, they shall have authority to declare the event or any part of an event void and that it shall be held again, either on the same day or on some future occasion, as they shall decide. COMMENT: It should be carefully noted by Referees and Juries of Appeal that, except in very special circumstances, an athlete who does not finish a race, should not be advanced to a later round or included in a re-run of an event. 8. The Road Race Referee shall, wherever practicable give a warning prior to disqualification. 2.14 Judges General 1. The Chief Judge for Track Events and the Chief Judge for each Field Event shall co-ordinate the work of the judges in their respective events. If the duties of the Judges have not been allocated in advance, they shall allocate the duties. 2. The judges may reconsider any original decision made by them if it was made in error, provided the new decision is still applicable. Alternatively, or if a decision has subsequently been made by a Referee or the Jury of Appeal, they shall refer all available information to the Referee or to the Jury of Appeal. Track Events and Road Events 3. The track and road Judges should all operate from the same side of the track or course, and they shall decide the order in which the athletes have finished and, in any case where they cannot arrive at a decision, shall refer the matter to the Referee, who shall decide. Note: The Judges should be placed at least 5m from, and in line with, the finish and should be provided with an elevated platform. Field Events 4. The field event Judges shall judge and record each trial and measure each valid trial of athletes in all Field Events. In the High Jump precise measurements should be made when the bar is raised particularly if Records are being attempted. At least two Judges should keep a record of all trials, checking their recordings at the end of each round of trials. The appropriate Judge shall normally indicate the validity or non-validity of a trial by raising a white or red flag, as appropriate. Alternative visual	ンは、情報の新たな証拠が迅速に提出されたときに特に考慮することができる。 Juryにとつては、より複雑で難しい上訴となる必要性を避けることができるからである。しかし、そのような再考をするにあたっては、現実的な時間の制約に注意すべきである。 2.13.7. 審判長は、ある種目の全部または一部の競技をやり直すが公正と思われる事態が生じたと判断した場合、当該種目の全部または一部の競技の結果が無効であることを宣言し、競技のやり直しを命じる権限を有する。再競技は、審判長の決定に従い、同日または別の日に行う。 コメント：審判長と Jury は、非常に特殊な状況を除き、レースを完了しなかった競技者は、以降のラウンドに進出させたり、再レースに含んだり、すべきではないことに注意する必要がある。 2.13.8. 道路競技審判長は違反があった場合には、状況が許す限り、失格を告げる前に警告を与えなければならない。 2.14 審判員総則 2.14.1. 審判員主任はそれぞれの種目の審判の任務を調整する。各審判員の任務が事前に割り当てられていなければ、審判員主任は各審判員に任務を割り当てなければならない。 2.14.2. 審判員は一度下した判定に間違いがある場合には、再考して新たな判定を下すことができる。その後、審判員の判定に対して抗議や上訴により審判長や Jury が判断を下す場合には、審判員は全ての情報を提供しなければならない。 トラック競技と道路競技 2.14.3. 決勝審判員はトラックまたは道路コースの同一サイドから競技者のフィニッシュ順を判定する。その判定について、審判員で決められない時には、これを審判長の決定にゆだねる。 注意：決勝審判員はフィニッシュラインの延長線においてフィニッシュラインから少なくとも 5 m 離れた場所に位置すべきであり、階段式スタンドが用意されるべきである。 フィールド競技 2.14.4. フィールド競技審判員は、すべてのフィールド競技において、競技者の試技を判定し記録するとともに、その試技が有効であれば計測して記録する。走高跳ではバーの高さを上げる時、特に新記録に挑戦する時は確実に計測を行う。少なくとも 2 人の審判員が試技の記録を管理し、各ラウンドの終了ごとにその記録を確認しなければならない。当該審判員は、通常、有効試技は白旗、無効試技は赤旗を挙げて示す。旗以外の視覚的な表示物を使用することも認められる。	2.14 審判員
---	---	------------------------

indication may also be approved by WPA. COMMENT: Unless a Judge is sure that an infringement of the Rules has occurred they will normally give the benefit of any doubt to the athlete, determine that the trial is valid and raise a white flag. However, when a video Referee is appointed and with access to footage for the Field Events, there is an option in the case of some doubt for the Judge in conjunction with the on-field Referee to delay the raising of either flag until they have sought the advice of the video Referee – always ensuring either that the landing mark is preserved or the trial is measured in case it is valid. Alternatively, the Judge if in real doubt could raise the red flag, ensure the mark is preserved or that the trial is measured and then seek advice from the video Referee. It is recommended that for each Field Event only one set of white and red flags are used in order to reduce the possibility of any confusion about the validity of trials. It is considered that it is never necessary to use more than one set of flags in a Jumping Event. Where a specific scoreboard is not available to indicate the wind reading in Horizontal Jumps, some form of indication other than a red flag should be used to indicate an excessive reading. In the case of Throwing Events, with respect to: Indications by other circle judges to the judge with the flags that a failure has been made, it is recommended that an alternate form of indication to flags is used such as a small red card held in that judge's hand, or some form of hand signals; The landing of an implement on or outside the sector line, it is recommended that an alternate form of indication to a flag is used - such as a judge's outstretched arm parallel to the ground; A judgment in the Javelin Throw that the metal head has not touched the ground before any other part of the javelin; it is recommended that an alternate form of indication to a flag is used - such as the pushing of the open hand of the judge towards the ground. 2.15 Umpires (Running and Wheelchair Racing Events) 1. Umpires are assistants to the Referee, without authority to make final decisions. 2. The Umpires shall be placed by the Referee in such a position that they may observe the competition closely and, in the case of a failure or violation of the Rules by an athlete or other person, make an immediate written report of the incident to the Referee. 3. Any such breach of the Rules should be communicated to the relevant Referee by the raising of a yellow flag or any other reliable means approved by the Technical Delegate(s).	コメント：審判員は規則違反が発生したと確信しない限り、通常、いかなる疑念にも競技者にとって有利になるように解釈し、試技が有効であると判断して白旗を挙げる。しかし、ビデオ審判長が任命され、フィールド種目の映像にアクセスできる場合、フィールド審判員が着地場所の特定に疑念がある場合には、現場担当のフィールド審判長と協力して、ビデオ審判長からの助言を待つ間（白でも赤でも）旗上げを遅らせるという選択肢がある。その際には、落下域の痕跡を保存するか、有効であった時に備えて計測しておくかのいずれかを徹底する必要がある。別の方法として、審判員が判断に迷う場合には赤旗を上げた上で痕跡を保存するか、計測したことを確認したうえで、ビデオ審判員に助言を求めることもできる。 試技の有効性に疑念を抱かせ混乱させてしまう可能性を減らすためにフィールド種目毎に白と赤の旗は 1 セットだけ使用することを推奨する。跳躍種目で複数の旗のセットを使用する必要はないと考えられる。長さの跳躍で、風速を示す仕様のボードが用意できないとき、赤旗以外の何らかの方法を用いて風速が高いことを示す必要がある。 投てき種目の場合： サークル担当の審判員が旗上げ担当審判員への無効試技を知らせる場合、旗による合図に代えて、手に持った小さな赤カードによる表示など、何らかの形の手信号などで表示することが推奨される。 角度線の上または外への投てき物の着地。旗による合図に代えて、審判員が地面に平行に腕を伸ばすような動作が推奨される。 メタルヘッドより先に他の部分が地面に着地した際のやり投げの判定。旗による合図に代えて、審判員が手で地面を押すような動作が推奨される。 2.15 監察員（競走、車いすレース種目） 2.15.1. 監察員は審判長の補佐で、最終の判定をする権限を持たない。 2.15.2. 監察員の任務は、審判長が指示した地点に位置して競技を厳正に監察し、競技者あるいは他の人によって競技規則の不履行や違反が起こった時には、ただちに審判長にその出来事を書面で報告しなければならない。 2.15.3. いかなる規則違反も黄旗を挙げるか、あるいは技術代表が許可した信頼性のある方法で、当該審判長に伝達する。	2.15 監察員（競走車いすレース種目）
---	--	------------------------------------

4. A sufficient number of Umpires shall also be appointed to supervise the take-over zones in relay races. Note (i): When an Umpire observes that an athlete has run in a different lane from their own, or that a relay take-over has taken place outside the take-over zone, they should immediately mark on the track with suitable material the place where the infringement took place or make a similar notation on paper or by electronic means. Note (ii): The Umpire(s) shall report to the Referee any breach of the Rules, even if the athlete (or team, for relay races) does not finish the race. COMMENT: The Chief Umpire (see Rule 2.8) is the assistant of the Track Referee and indicates the placement of and co-ordinates the work and reports of each Umpire. It is up to the Meeting Manager in consultation with the Track Referee to select the appropriate number of Umpires according to the level of the meeting, the number of entries and the number of available officials. Indication of an infringement When the events take place on a synthetic track, it has been the practice to provide the Umpires with adhesive tape so that they can mark the track where an infringement has taken place – although the Rules (see note (i) above) now acknowledge that this may be and is often done in other ways. Note that the failure to report an infringement in a particular way (or at all) does not prevent a valid disqualification being made. It is important that Umpires “report” all instances where they believe the Rules have been infringed, even when the athlete or team does not finish the race. 2.16 Timekeepers and Photo Finish and Transponder Timing Judges 1. In the case of hand timing, a sufficient number of timekeepers for the number of athletes entered shall be appointed. One of them shall be designated the Chief Timekeeper. They shall allocate duties to the Timekeepers. These Timekeepers shall act as back-up Timekeepers when Fully Automatic Photo Finish System or Transponder Timing System are in use. 2. Timekeeper, Photo Finish and Transponder Timing Judges shall act in accordance with Rule 20. 3. When Fully Automatic Timing and Photo Finish System is used, a Chief Photo Finish Judge and an adequate number of assistants shall be appointed. 4. When a Transponder Timing System is used, a Chief transponder Timing Judge and an adequate number of assistants shall be appointed. 2.17 Start Co-ordinator, Starter and Recalls 1. The Start Co-ordinator shall:	2.15.4. リレー競技においてはテイクオーバーゾーンを監察するために十分な人数の監察員を任命する。 注意(i)：監察員は競技者が自分のレーン以外を走ったり、リレー競走のテイクオーバーゾーン外での受け渡しを監察した時は、ただちにその違反が行われた場所に適当なものでマークし、書面または電子媒体で同様の記録をしなければならない。 注意(ii)：監察員はたとえ競技者（あるいはリレーにおけるチーム）がそのレースでフィニッシュしなかった場合でも、いかなる規則違反も審判長に報告しなければならない。 コメント：監察員主任（規則 2.8 参照）は、トラック審判長の補佐役であり、各監察員の配置を指示し、各監察員の任務と報告の調整を行う。何名の監察員を選抜するかは、競技会のレベル、エントリー数、委嘱可能な競技役員の数に応じて、トラック審判長と協議のうえ総務が決定する。 違反の表示 競技が全天候舗装のトラックで実施されているとき、違反行為が発生したトラックにマークを付けることができるように監察員に粘着テープを提供することが実践されている。ただし、規則（上記の注意(i)を参照）は、これは他の方法で行うことができ、しばしば行われている。 違反を特定の方法で（またはまったく）報告できなかったとしても、失格を有効とすることを妨げるものではないことに注意が必要である。 競技者またはチームがレースでフィニッシュしなかった場合でも、規則違反があったと監察員が思う、あらゆるすべての事案を報告することが重要である。 2.16 計時員、写真判定員とトランスポンダー主任 2.16.1. 手動計時の場合、参加人数に十分な計時員を任命し、その中の 1 人を計時員主任に任命する。主任は、計時員の役割を決める。写真判定システムあるいはトランスポンダー計時システムを使用する時、計時員は予備計時員として行動しなければならない。 2.16.2. 計時員、写真判定員及びトランスポンダー主任は規則 20 によって行動しなければならない。 2.16.3. 写真判定システムを使用する場合は写真判定員主任と適切な人数の写真判定員が任命されなければならない。 2.16.4. トランスポンダー計時システムを使用するときはトランスポンダー係が任命され、その中からトランスポンダー主任と適切な人数のトランスポンダー主任補佐が任命されなければならない。 2.17 スタートコーディネーターとスターター及びリコーダー 2.17.1. スタートコーディネーターは次の任務を担当	2.16 計時員 写真判定員とトランスポンダー主任
---	---	---

a) Allocate the duties of the start team However, in the case of the Paralympic Games and WPA Championships (see Part B - 3.1.2 (a) and (b)), the determination of which events will be assigned to the International Starter will be the responsibility of the Technical Delegates; b) Supervise the duties to be fulfilled by each member of the team; c) Inform the Starter, after receiving the relevant order from the Competition Director, that everything is in order to initiate the start procedure (e.g., that the Timekeepers, the Judges and, when applicable, the Chief Photo Finish Judge, Chief Transponder Timing Judge and the Wind Gauge Operator are ready); d) Act as an interlocutor between the technical staff of the timing equipment company and the Judges; e) Keep all papers produced during the start procedure including all documents showing the reaction times and/or false start waveform images if available; COMMENT: All members of the start team must be well informed about the Rules and how they should be interpreted. The team must also be clear on what procedures it will follow when implementing the Rules, so that the events can continue without delay. They must understand well the respective duties and roles of each member of the team, especially the Starter and the Start Referee. 2. The Starter, whose primary responsibility is to ensure a fair and equitable start for all competitors, shall have entire control of the athletes on their marks. When a Start Information System is used, the Starter and/or an assigned Recaller shall wear headphones in order to hear clearly any acoustic signal emitted when the System indicates a possible false start. 3. The Starter shall position themselves so that they have full visual control over all athletes during the start procedure. It is recommended, especially for staggered starts, that loudspeakers in the individual lanes be used for relaying the commands of the start and any recall signals to all athletes at the same time. Note: The Starter shall place themselves so that the whole field of athletes falls into a narrow visual angle. For races using crouch starts it is necessary that they are placed so that they can ascertain that all athletes are currently steady in their set positions before the gun is fired or the approved starting apparatus is activated. (All such starting apparatus is termed "gun" for the purpose of these Rules.) Where loudspeakers are not used in races with a staggered start, the Starter shall place themselves so that the	する。 a) スタートチームのメンバーにそれぞれの任務を割り当てる。しかしパラリンピック競技大会及び WPA 競技会 (PART-B 規則 3.1.2(a)及び(b)において、どの種目を国際スターターが撃つかの割り当ての決定は技術代表の責務である。 b) スタートチームのメンバーが割り当てられた任務を実行しているかどうかを監督する。 c) 競技会ディレクターからの関連指示を受けた後、スタートの手続きを始めるためにすべての準備 (計時員、決勝審判員、写真判定員主任、トランスポンダー主任、風力計測員) が整っていることをスターターに連絡する。 d) 審判員と計時装置技術スタッフとの間の仲立ちをする。 e) スタート手順の中で生じたすべての書類、もし存在するのなら、反応時間と不正スタートの波形図の両方またはいずれかを含むすべてを保存する。 コメント：スタートチームのすべてのメンバーは、規則及び規則をいかに解釈すべきかについて十分に理解している必要がある。チームは、競技が遅滞なく継続できるよう、規則を適用する際、どのような手順に従うか明確にしておく必要がある。チームのメンバーは、各々の、特にスターターとスタート審判長の任務と役割を十分に理解していなければならない。 2.17.2. スターターは全ての競技者に対して公平で公正なスタートを保証することに責任を持ち、スタート地点における競技者を完全に統括する。スタートインフォメーションシステムが使用される場合には、スターター及び/またはリコーラーは不正スタートの可能性が検出されたとき信号を明瞭に聞き取ることができるようヘッドフォンを着用しなくてはならない。 2.17.3. スターターはスタート動作の間、全走者を視野に収められるような位置に立たなければならない。階段式スタートの場合、特に各レーンにスピーカーを置き競技者にスターターの指示、スタート信号及びリコール信号が同時に伝えられるようにすることが望ましい。 注意：スターターは全走者を狭い視野に収められるような位置に立たなければならない。クラウチングスタートを用いるレースでは、全走者が信号器を作動させる前の「用意」の状態に静止しているのが確認できるところに立つことが必要である。階段式スタートを用いるレースでスピーカーが使用できない場合、スターターは、スターターと各競技者の距離がほぼ同じになる位置に立たなければならない。しかし、スターターがそのような位置に立たない場合は電気で作動する補助スタート信号器を置く。	2.17 スター トコー ディネ ーター とスター ター及 びリコー ラー
--	--	--

distance between them and each of the athletes is approximately the same. Where, however, the Starter cannot place themselves in such a position, the gun shall be placed there and discharged by electric contact. COMMENT: The Starter's commands have to be clear and heard by all athletes but, unless they are a long way from the athletes and without a speaker system, they should avoid shouting whilst giving the commands. 4. One or more Recallers shall be assigned to assist the Starter. Note: For races of 200m, 400m, 4x100m, 4x200m, 4x400m Relays, and the 4x100m universal Relay, there shall be at least two Recallers which is mandatory for WPA Recognised Competitions (see Part B-3.1.2. (a), (b) and (c) only). 5. Each Recaller shall place themselves so that they can see each athlete assigned to them. 6. Each Recaller is obliged to recall the race if any infringement of the Rules is observed. After a recalled or aborted start the Recaller shall report their observations to the Starter who decides whether and to whom a warning or disqualification shall be issued (See also Rule 17.7 and Rule 17.10). For disciplinary infringements, the decision is made by the Referee (See also Rule 17.2) 7. Disqualification under Rule 17.8 may be decided only by the Starter. COMMENT: It is important that the contents of this rule be read in conjunction with Rule 2.13 (Referee) as in effect both the starter and Referee (Start Referee when appointed) are responsible for starts and who can determine whether a start is fair. On the other hand, a Recaller has no such power and whilst they may recall a start, they cannot act unilaterally thereafter and must simply report their observations to the starter about why they recalled the race. 8. To assist in races using crouch starts, a World Athletics approved Start Information System shall be used (See also Rule 16.3). 2.18 Starter's Assistants 1. The Starter's Assistants shall check that the athletes are competing in the correct heat or race and that their number bibs are worn correctly and, where applicable, other equipment is worn and used correctly. 2. They must place each athlete in their correct lane or station, assembling the athletes approximately 3m behind the start line (in the case of races started in echelon, similarly behind each start line). When this has been completed, they shall signal to the Starter that all is ready. When a new start is ordered, the Starter's	コメント：スターターの合図は、すべての競技者に明瞭に聞き取れる必要があるが、競技者から遠く離れ、スピーカーシステムがない状況を除けば、スタート合図を叫んで行うことは避けるべきである。 2.17.4. スタートにおいて、スターターを支援するために 1 人あるいは 2 人以上のリコーラーを配置する。 注意：200m, 400m, 4×100m, 4×200m, 4×400mリレーおよび 4x400m ユニバーサルリレー は、少なくとも 2 人のリコーラーをおくことが望ましく、WPA 認可競技会で必須である。(Part B-3.1.2. (a), (b), (c) 参照)。 2.17.5. リコーラーは自分が受け持つ全競技者を平等に見ることができるように位置しなければならない。 2.17.6. リコーラーはどのような不正でも確認したならば、信号器を発射し競技者を戻さなければならない。リコーラーは競技者を戻した後、どの競技者に警告もしくは失格を与えるべきかの情報をスターターに伝えなければならない。スターターは、どの競技者に警告もしくは失格を与えるべきかを判断する。(規則 17.7 及び 17.10 参照) スタート時における不適切行為の判断は、審判長が行う。(規則 17.2 参照) 2.17.7. 規則 17.8 に規定されている警告や失格の決定についてはスターターのみが行うことができる。 コメント：この規則の内容は、スターターと審判長（スタート審判長が任命された場合）の双方がスタートに責任を持ち、スタートが公正であるかどうかを判断することができることから、規則 2.13（審判長）と併せて読むことが重要である。一方、リコーラーにはそのような権限はなく、リコーラーはスタートを呼び戻すことはできても、その後は権限を持って行動することはできず、自身の観察内容をスターターに報告することだけが求められる。 2.17.8. クラウチングスタートを用いるレースを補助するために、スタートインフォメーションシステムを使用すべきである。(規則 16.3 参照) 2.18 出発係 2.18.1. 出発係は競技者が所定の組またはレースに参加しているか、ビブスを正しくつけているか、または該当する場合は、ほかの機材が正しく使われているかを点検する。 2.18.2. 出発係は各競技者をスタートラインの後方約 3m のところ（段階的にスタートする競走では各スタートラインの後方）に集めて、競技者を正しいレーンまたは定められた位置に並べなければならない。この作業を終えたなら、スターターに準備完了を合図する。スタートのやり直しが命じられた時には出発係は再び競技者をスタートラインの後方約 3 m のところに集	2.18 出発係
--	--	------------------------

Assistants shall assemble the athletes again. 3. The Starter's Assistants shall be responsible for the readiness of batons for the first athletes in a relay race. 4. When the Starter has ordered the athletes to their marks, the Starter's Assistants must ensure that Rule 17.4 and Rule 17.5 are observed. 5. In case of a false start, the Starter's Assistants shall proceed in accordance with Rule 17.9. 6. The Starter's Assistants shall assist athletes to set their starting block in accordance with Rule 7.13. COMMENT: The importance of the Starter's assistants cannot be underestimated. They set the mood for the competitors by ensuring that they are in the correct heat and lanes as assigned. They help to control the start of races by ensuring the athletes are ready for introductions and the instructions of the Starter. In addition, they are responsible for ensuring that batons are available for those relay races where batons are used and to collect them at the conclusion of the race. 2.19 Lap Scorers 1. Lap Scorers shall keep a record of the laps completed by all athletes in races longer than 1500m. For races of 5000m and longer, a number of Lap Scorers under the direction of the Referee shall be appointed and provided with lap scoring cards on which they shall record the times over each lap (as given to them by an official Timekeeper) of the athletes for whom they are responsible. When such a system is used, no Lap Scorer should record more than four athletes. Instead of manual lap scoring, a computerised system, which may involve a transponder carried or worn by each athlete, may be used. 2. One Lap Scorer shall be responsible for maintaining, at the finish line, a display of the laps remaining. The display shall be changed each lap when the leader enters the finish straight. In addition, manual indication shall be given, when appropriate, to athletes who have been, or are about to be, lapped. The final lap shall be signalled to each athlete, usually by ringing a bell. 2.20 Competition Secretary, Technical Information Centre (TIC) 1. The Competition Secretary shall collect the full results of each event, details of which shall be provided by the Referee, the Chief Timekeeper, Chief Photo Finish Judge, or Chief Transponder Judge and the Wind-Gauge Operator. They shall immediately relay these details to the Announcer, record the results and convey the result card to the Competition Director. Where a computerised results system is used the computer recorder at each Field Event site shall ensure that the full results of each event are entered into the	める。 2.18.3. 出発係はリレーの第 1 走者に対してバトンを用意する責任がある。 2.18.4. スターターが競技者にスタート位置につくように命じた時には出発係は規則 17.4 と 17.5 が守られていることを確認しなければならない。 2.18.5. 不正スタート時において、出発係は規則 17.9 に定められた手続きを行う。 2.18.6. 出発係は、規則 7.13 に従い、競技者がスターティングブロックを設置する手助けをする。 コメント：出発係の重要性を過小評価することはできない。彼らは、割り当てられたとおりの正しい組とレーンにいることを確認することにより、競技者の準備を完了させる。彼らは、競技者紹介とスターターの指示の準備ができていることを確認することにより、レースの開始をコントロールする。さらに、バトンが使用されているリレーレースでバトンが利用可能であることを確認し、レースの終了時にバトンを収集する責任がある。 2.19 周回記録員 2.19.1. 1500m を超える競走で、複数の周回記録員は、各競技者の走り終わった回数を記録しなくてはならない。特に 5000m 以上の競走では、審判長の指示のもと複数の周回記録員が任命され、割り当てられた競技者の各周回の時間を記録する（時間は計時員が周回記録員に知らせる）。この方法をとる場合、1 人の周回記録員は 4 人を超える競技者の時間を記録することはできない。手動による記録に代わって、競技者が装着したトランスポンダーを含むコンピューター化されたシステムを使用してもよい。 2.19.2. 1 人の周回記録員はフィニッシュライン付近の内側で、各競技者に残っている周回の数知らせる。周回の表示は先頭の競技者がフィニッシュラインのある直走路に入った時に変える。さらに（周回遅れが）生じた時には周回遅れになったか、なりそうな競技者にマニュアル表示（手持ちカード）で残りの回数を知らせる。最終周回は、通常鐘を鳴らして各競技者に合図する。 2.20 記録・情報処理員、テクニカル・インフォメーション・センター(TIC) 2.20.1. 記録・情報処理員は、各審判長、計時員主任、写真判定員主任またはトランスポンダー主任及び風力計測員から提供される各種目の詳細な結果を集めなければならない。記録・情報処理員は、これら詳細をただちにアナウンサーに伝えとともに、結果を記録し、成績表を競技会ディレクターに渡さなくてはならない。コンピューターによる競技会運営システムを採用する場合、各フィールド種目の記録・情報処理員は、競技場所で各種目の結果をコンピューターシステムに確実に入力しなければならない。トラック競技の結果は写真判定員主任の指示のもとで入力しな	2.19 周回記録員 2.20 記録・情報処理員 テクニカル・インフォメーション・センター (TIC)
--	---	---

computer system. The track results shall be input under the direction of the Chief Photo Finish Judge. The Announcer and the Competition Director shall have access to the results via a computer. 2. In events in which athletes are competing with different specifications (such as implement weight), the relevant differences should be clearly indicated in the results or a separate result shown for each category. 3. The following standard abbreviations should be used in the preparation of start lists and results where applicable: Did not start – DNS Did not finish – DNF No valid trial recorded – NM Disqualified – DQ Valid trial in High Jump – “O” Failed trial in Field Events – “X” Passed trial in Field Events – “–” Retired from competition in Field Event – r Qualified by place in Track Events – Q Qualified by time in Track Events – q Qualified by standard in Field Events– Q Qualified without standard in Field Events – q Advanced to next round by Referee – qR Advanced to next round by Jury of Appeal – qJ Advanced to next round by draw qD Yellow Card – YC Second Yellow Card – YRC Red Card – RC Lane infringement (Rules 18.5(c) and 18.5(d)) – L Competing under protest – P Reserve athletes for vacant positions-Res COMMENT: An athlete shall be regarded as DNS if: (a) after their name having been included on the start list for any event, except where they are on the start list as ‘Res’, they do not report to the Call Room for that event; (b) having passed through the Call Room they do not make any attempt in a Field Event or do not attempt to make a start in a running event. If an athlete is disqualified in an event for an infringement of any Rule, reference shall be made in the official results to the Rule which has been infringed. If an athlete is disqualified from an event for acting in an unsporting or improper manner, reference shall be made in the official results giving reasons for such disqualification. COMMENT: Rules 2.20.2 and Rule 2.20.3 acknowledge the not uncommon situation in many competitions below the top level (and even in some high level competitions) where athletes of different age and categories who are competing in the same competitions. This Rule confirms that this is acceptable - including as a means of meeting minimum competitor number requirements, even for the purposes of Rule 51.1 and Rule 51.2 as well as setting out how the	ればならない。アナウンサーと競技会ディレクターはこれらの結果を見るためにコンピューターにアクセスする権限を有する。 2.20.2. 投てき物の重さなど、異なった仕様で行う競技については、競技結果にその仕様を明示するか、カテゴリー別に明示すべきである。 2.20.3. スタートリスト及び結果には以下の略号を用いる。 欠場 - 「DNS」 途中棄権 - 「DNF」 記録なし - 「NM」 失格 - 「DQ」 成功・有効試技（走高跳） - 「○」 失敗・無効試技（フィールド競技） - 「×」 パス（フィールド競技） - 「–」 試合放棄（離脱） - 「r」 トラック種目における順位による通過者とフィールド種目における標準記録突破による通過者 - 「Q」 トラック種目における記録による通過者とフィールド種目における記録による通過者 - 「q」 救済及び審判長等の決定による通過者 - 「qR」 Juryの決定による通過者 - 「qJ」 警告 - 「YC」 抽選による次ラウンドへの進出 - 「qD」 イエローカード - 「YC」 2 回目の警告（による除外） - 「YRC」 （レッドカードによる）失格（除外） - 「RC」 レーン侵害（規則 18.5.(c), 18.5(d)） - 「L」 抗議中の競技 - 「P」 空きレーン用のリザーブ競技者 - 「Res」 コメント：以下の行為を行った競技者は、DNS とする。 (a) 当該競技者の名前がスタートリストに記載されているにもかかわらず、当該競技に関して招集所に何の連絡もない。ただしスタートリストに‘Res’と記載されている場合を除く。 (b) 招集所でチェックをうけていながら、フィールド競技では一回も試技をしない、競走競技でスタートの位置につかない。 競技者が規則違反で失格になった場合には、公式記録にはどの規則に違反したかを明記する。 競技者が競技者にあるまじき行為や不適切な行為で失格になった場合には、失格の理由について公式記録に明記する。 コメント：規則 2.20.2 と 2.20.3 は、異なる年齢と競技種目の競技者が同じ競技会で競技している最上位レベル（さらにはいくつかの高レベル）以下の多くの競技会で、珍しくない状況を反映したものである。この規則は、規則 51.1 及び 51.2 に定められている最小の競技者数の要件を満たす手段として、及び結果の表示方法も含め、これが容認できることを確認している。競技規則違反からの理由と懲戒的理由の両方で失格が生じる可能性があることを考えると、失格の理由が常に結果に示されていることが非常に重要となる。これは、DQ の略称の隣にどの規則により競技
--	---

results should be presented. Given that disqualifications can be made for both technical and disciplinary reasons, it is very important that the reason for a disqualification is always indicated in the results. This is achieved by always stating the Rule under which the athlete was disqualified next to the symbol DQ. 4. A Technical Information Centre (TIC) will be established for WPA Recognised Competitions (see Part B - 3.1.2) and is recommended for other competitions held over more than one day. It may be a virtual or physical operation, or a combination of both. The main function of the TIC is to ensure smooth communication between each team delegation, the LOC, the Technical Delegates and the competition administration regarding technical and other matters relating to the competition. COMMENT: An effectively managed Technical Information Centre will significantly assist in the delivery of a high quality competition organisation. The TIC Manager should have excellent knowledge of the Rules and equally importantly of the specific Regulations for the particular competition. The hours of operation of the TIC should reflect the hours of the competition plus some periods of time before and after when there will need to be interaction between the various parties, particularly between the team delegations and the LOC. It is common, although not essential, for larger events to have "branches" of the TIC (sometimes called Sport Information desks) in the main athlete accommodation locations. If this is the case, there must be excellent communication between the SID(s) and the TIC. Because the hours of operation of the TIC and SID(s) may be long, it will be necessary for the TIC Manager to have several assistants and for them to work in shifts. Where a virtual TIC is fully or partially in operation, the hours of operation may more easily be extended, but it is important to make clear the hours during which the virtual operation will be monitored. Whilst some duties of the TIC are covered in the Rules (see for example Rules 2.20, 50.3 and Rule 50.7), others will be set out in the Regulations for each competition and in competition documents such as team handbooks etc. 2.21 Marshal The Marshal shall have control of the field of play and shall not allow any persons other than the officials and athletes assembled to compete or other authorised persons with valid accreditation to enter and remain therein. COMMENT: The Marshal's role is to regulate entry to the field of play during preparations immediately beforehand and while the event is in progress. They operate generally in accordance with the plan established by the Competition Director and in relation to more immediate matters receives their orders directly from the Meeting Manager. Accordingly, they will:	者が失格となったのかを常に明記することによって達成される。 2.20.4. WPA 認可競技会(PART-B 規則 3.1.2 参照)では、テクニカルインフォメーションセンター (TIC) を設置する。またそれ以外の競技会でも開催期間が 1 日を超える場合は TIC を設置することが望ましい。TIC はバーチャルに運営するか (Web 方式)、実際に設置して運営するか、両方を組み合わせて運営することができる。TIC は各チーム代表、組織委員会(LOC)、技術代表及び競技運営の間で、競技会の技術面等に関する事項について円滑なコミュニケーションを図ることを主要業務とする。 コメント：効果的に管理されたテクニカル・インフォメーション・センター(TIC)は、質の高い競技会組織の提供に大きく貢献する。TIC マネージャーは、規則だけでなく同様に重要なのは特定の競技会のために用意された特別な規程について優れた知識を有するべきである。TIC の開設時間は、競技会の時間と、様々な関係者、特にチーム選手団と組織委員会(LOC)との間のやり取りが必要となる競技会前後の時間帯を含んでいなくてはならない。大規模な競技会では、主要な選手宿泊施設に、TIC の出張所 (時にはスポーツインフォメーションデスク SID と呼ばれる) を持つことが、必須ではないものの、一般的である。このような場合は、SID と TIC との間の十分なコミュニケーションが必要となる。TIC 及び SID の開設時間は長くなる可能性があるため、TIC マネージャーには複数の補佐役が必要であり、シフト制で任務につく必要がある。バーチャル TIC を完全または部分的に運営させる場合、より簡単に稼働時間の延長はできるが、バーチャル TIC の運営状況を監視する時間を明確にすることが重要である。TIC のいくつかの任務は競技規則 (例えば規則 2.20、50.3 及び 50.7 参照) に記載されているほか、競技会規程やチームハンドブックなどの競技会関係書類にも網羅される。 2.21 マーシャル マーシャルは競技場内の完全な統制権を持つ。競技を運営する役員とその競技に出場する競技者あるいは入場が正式に許可されている者の他は、だれも競技区域に出入りすることを許可してはならない。 コメント：マーシャルの任務は、競技開始直前の事前準備中、及び競技開催中の間、競技実施場所 (FOP)への立ち入りを規制することである。マーシャルは、概して、競技会ディレクターが定める計画に従って任務につくが、より直接的な事項に関しては総務から直接指示を受ける。従ってマーシャルは： 競技者、競技役員、競技担当ボランティア(補助員)、(計測機器会社などの)サービススタッフ、認可さ	2.21 マー シャル
--	---	----------------------------

manage the control for the entrances into the arena of the athletes, the officials and on-field volunteers, service staff, accredited press photographers and the TV crews. At each competition, the number of such in-field accreditations is agreed beforehand and all these persons must wear a special bib; manage the control at the point where the athletes leave the arena (usually for larger events into the Mixed Zone and/or the Post Event Control Area) when they have finished their event; ensure that, at all times, the sight lines to the competition sites are as clear as possible for the spectators' benefit as well as for television. They are directly answerable to the Meeting Manager who must be able to contact them at any time if the need arises. To assist the Marshal and their team in their work it is usual that those persons permitted to enter the arena, other than the athletes, are clearly distinguishable by means of the special bib or accreditation card or distinctive uniform. 2.22 Wind Gauge Operator The Wind Gauge Operator shall ascertain the velocity of the wind in the running direction in events to which they are appointed and shall then record and sign the results obtained and communicate them to the Competition Secretary. COMMENT: Whilst in practice it may be that the Wind Gauge Operator, the Technical Manager or a Photo Finish Judge actually puts the gauge in the correct place ultimately it is the responsibility of the relevant Referee to check that this is done and in accordance with the Rules (see Rules 18.13 and Rule 27.12) It is noted that particularly for the Track Events the wind gauge can be operated remotely. In such cases it is almost always connected to the photo finish and results "system", so that a Wind Gauge Operator will not be required and their duties are filled, for example, by someone in the Photo Finish team. 2.23 Measurement Judge (Scientific) One Chief Measurement Judge and one or more assistants shall be appointed when Electronic or Video Distance Measurement or other scientific measurement device is to be used. Before the start of the competition, they will meet the technical staff involved and familiarise themselves with the equipment. Before each event they will supervise the positioning of the measuring instruments, taking account of the technical requirements given by the manufacturer and the instrument calibrating laboratory. To ensure that the equipment is operating correctly, they shall, before the event, supervise a set of measurements in conjunction with the Judges and under the supervision of the Referee,	れた取材カメラマン、テレビクルーの競技場内への入場コントロールを管理する。各競技会では、そのようなフィールド内で撮影のための認可数は事前に合意されており、これらは全員、特別なビブスを着用しなければならない。 競技を終了したときに、競技者が競技場内から離れる地点（通常は大規模な競技会では、ミックスゾーン及びポスト・イベント・コントロール・エリア）でのコントロールを管理する。 テレビ中継のためと同様に、観客の利益のため、可能な限り、常に競技実施場所をクリア(余計な人物が立ち入らないよう)にする。 マーシャルは、総務に直接状況報告をする。そのために総務は必要に応じていつでもマーシャルと連絡を取ることができなければならない。 マーシャルの任務遂行の助けとするために、競技者以外に競技場内に入ることを許可された者は、特別なビブスや AD カード、独特のユニフォームによって明確に区別されるのが通常である。 2.22 風力計測員 風力計測員は担当する種目において、走る方向に対する風速を測定し、それを記録する。その結果に署名したのち記録・情報処理員に報告する。 コメント：実際には、風力計測員、技術総務、または写真判定員が、風向風速計を正しい場所に置くことになるが、最終的には、これが正しく行われ、規則(規則 18.13 及び 27.12 参照)に合致していることを確認するのは審判長の責任である。 特に、トラック種目の場合、風向風速計は、遠隔操作可能であることに留意すべきである。そのような場合、写真判定及びリザルトシステムに直結しているのが通例であり、従って、風速計測員は必要なく、その任務は、例えば、写真判定チームによって代行される。 2.23 計測員（科学） 電気もしくはビデオ距離計測装置を使用する場合は計測主任（科学）1 人及び 1 人以上の計測員（科学）を任命しなければならない。 計測員（科学）は競技会開始前に関係技術者と打ち合わせ、その装置を熟知しておかなければならない。 各種目の競技開始に先立ち、計測員（科学）は製造会社及び計測器精度検査機関から提示された技術的要件を考慮して、計測器の位置決めを監視する。 計測員（科学）は計測装置が正しく作動することを確認するために、その競技種目の開始前に、審判長の監督の下で複数の審判員による検査済の鋼鉄製巻尺の測定結果と一致するよう一連の計測を管理する。確認作業に関わった全員の署名を付した適合確	2.22 風力計測員 2.23 計測員（科学）
---	--	---

to confirm agreement with results achieved using a calibrated certified steel tape. A form of conformity shall be issued and signed by all those involved in the test and attached to the results card. During the competition they shall remain in overall charge of the operation. They will report to the Referee to certify that the equipment is accurate. Note: Whilst it is not mandatory, it is recommended that the Measurement Judge should carry out a set of measurements during the event to verify the measurements taken before the event. COMMENT: When electronic or video distance measuring equipment is used a Chief Judge is placed as the official in charge in a similar way as is the case with photo finish or transponder timing. In the case of video measurement, the Chief Measurement Judge will be expected to take a more active and hands-on role during the events, than would be the case with fully on-field electronic distance measurement. In particular this should involve ensuring that an appropriate communication system is in place between the on-Field Judges and the Judges undertaking the video reading to ensure that each measurement is correctly made and that in the case of the Horizontal Jumps, the landing mark is not raked out until an image has been confirmed. Whether it is the Chief Measurement or another Judge who is responsible for ensuring the video reading is correct, they must be especially careful to ensure that the current, and not a previous, trial is the one that is measured. 2.24 Call Room Judges The Call Room Chief Judge shall supervise the transit between the Warm-up Area and the competition area to ensure that the athletes after being checked in the Call Room, be present and ready at the competition site for the scheduled start of their event. The Call Room Judges shall ensure that athletes are wearing the national or Club uniform clothing officially approved by their national governing body, that the bibs are worn correctly and correspond with start lists; that shoes, number and dimension of spikes, eye masks, tethers, racing chairs, running frames, throwing frames, Maximum Allowable Standing Height (see Rule 6.12.2), prosthetic device(s) and advertising on clothing and athletes' bags comply with the Rules and Regulations; and that unauthorised material is not taken into the field of play. The Judges shall refer any unresolved issues or matters arising to the Call Room Referee. COMMENT: A well planned, and efficiently managed Call Room is fundamental to the success of a competition. Planning to ensure sufficient space at the point when the Call Room will be at its fullest capacity, how many Call Rooms (and sections within each) are required and a reliable communication system with the	認書を作成し、成績表に添付する。 競技中は操作の総括責任を負い、終了後は、装置が正確に作動したことを確認し、審判長に報告する。 注意：義務ではないものの、競技開始前に確認した計測機器が正常に作動しているかを確認するために、競技中、事前に定めた地点を使つての計測確認を実施すべきである。 コメント：光波またはビデオ距離計測装置を使用する場合は、写真判定員やトランスポンダー主任の場合と同様に、責任者である競技役員として、主任が任命される。ビデオ距離計測の場合、距離計測主任は、競技実施場所に設置する光波距離計測の場合よりも、競技中には、より積極的かつ実践的な役割を果たすことが期待される。 特に、これは、競技場所にいる審判員とビデオ画像読み取りを担当する審判員との間に適切な通信システムが用意され、各計測が正しく行われていること、及び、距離の跳躍の場合には 画像が確認されるまで痕跡を消さないよう注意が必要である。主任であろうと読み取りを確実にする責任ある他の審判員であろうと、計測された痕跡が、それ以前のものでなく、間違いなく現在の試技のものであることに特に注意する必要がある。 2.24 競技者係 競技者係主任は招集所においてチェックを済ませた競技者が、出場種目の予定されたスタート時刻に確実に競技場所において競技開始できるようにウォームアップ場と競技場内への移動を監督する。 競技者係は、競技者の国・加盟団体が公式に承認した国代表のまたはクラブのユニフォームを着用しているか、ナンバーカードがスタートリストと合っているか、また正しくつけているかを確認する。またシューズ、スパイクの寸法と数、アイマスク、テザー、レース用車いすや投てき台の検査、MASH(最大許可身長)の計測(規則 6.12.2 参照)、義肢や衣類やバッグの広告が規則や規程に適合しているか、承認されていないものを競技場内に持ち込もうとしていないかどうかを確認しなければならない。 審判員は未解決の問題または発生している問題を招集所審判長にゆだねる。 コメント：綿密に計画され効率的に管理された招集所は、競技会成功の基本である。招集所が最大限の能力を発揮できるように十分なスペースを確保するための計画、招集所として必要とされる数（及びびーすを作るのに必要な仕切りの数）、他の競技役員とのやり取り、及び競技者がウォームアップエリアで招集を受ける際の告知のための信頼性の高い通信システ	2.24 競技者係
---	--	-------------------------

other Officials and to notify the athletes when to report from the Warm-up Area are constants. It is important that in the planning process it is determined which checks will be made and preferably these should be communicated to the athletes and teams in advance to avoid stress or confusion immediately before competition. Most important of all is that the Call Room Judges ensure the athletes are in the correct heat, race or group and that they leave for the competition area in a timely manner in accordance with the Call Room schedule. Ideally the Call Room schedule, indicating such key times as entry to and departure from the Call Room and arrival at the event site, as well as the start time of the event will be published in advance of the competition and an accurate clock showing the correct time will be situated outside the Call Room. Call Room Judges play another extremely important role which relates to the inspection of the equipment being used by some athletes such as tethers, eye patches, eye masks, wheelchairs and throwing frames. They are also responsible for ensuring athletes in Sport Classes T/F61-62 do not exceed their Maximum Allowable Standing Height (see Rule 6.12.2). For events which require guide-runners or assistants, the Call Room Judges are responsible for ensuring that both the athlete and their guide-runner or assistant are both checked; just like they would for an individual athlete. It is important to note that in Throwing Events for Sport Classes F11-12, F31-33 and F51-54 one (1) assistant, per athlete, per event, is permitted in accordance with Rule 7.14 and Rule 7.16. The same applies for T12 athletes in Jumping Events, see Rule 7.20. However, for T11 athletes in Jumping Events, up to two (2) assistants are permitted, per athlete, per event in accordance with Rule 7.18. It should be noted that T11 athletes must have one (1) guide-runner and may have two guide-runners for 5000m or longer races, whereas a T12 athlete may have one (1) guide-runner or two (2) guide-runners for races of 5000m or longer. If a T11 or T12 athlete intends to run with two guide-runners, in races of 5000m or longer, the intention to interchange guide-runners, as well as the specifics of which lap in track events and at which distance in road events the guide-runner exchange will occur, must be notified in advance to the Referee and Technical Delegate in accordance with the regulations of the respective competition. It is also important that the Call Room Judges do not allow someone onto the field of play who is not a competing athlete or who has not been correctly accredited and is entitled to be there for the specific event. This is more important for relay races than many other events which are easier to determine with the start lists.	ムの確保は常に重要である。計画の過程では、どのチェックが行われるかが決定され、競技直前の競技者の緊張や混乱を避けるために、チェック項目は、事前に競技者やチームに伝えられることが好ましい。競技者係は、競技者が正しい組、レース、またはグループにいるか、また招集スケジュールに従って時間通りに競技エリアに向かっているかを確実にしなければならない。理想的には、招集所の締切時刻、出発時刻、競技場所到着時刻、競技開始時刻などの主要な招集場スケジュールを競技会開催前に発表され、開示し、招集所の外に正しい時間を示す時計を設置する。 招集所審判員は、テザー、アイパッチ、アイマスク、車椅子、投てきフレームなど、一部の競技者が使用している器具の検査に関連する別の非常に重要な役割を果たす。また、競技者係は、競技クラス T/F61-62 競技者が最大身長を超えていないか、確認する責任がある。(規則 6.12.2.参照) ガイドランナーまたはアシスタントを必要とする種目の場合、招集所審判員は、競技者とそのガイドランナーまたはアシスタントの両方が個々の競技者と同じようにチェックされていることを確認する責任がある。 競技クラス F11-12、F31-33、F51-54 の投てき種目では、競技者 1 種目 1 人につき、規則 7.14 及び規則 7.16 に従って 1 人のアシスタントが許可されることに注意することが重要である。跳躍競技の T12 競技者にも同じことが適用される。規則 7.20 を参照。ただし跳躍競技の T11 競技者の場合、規則 7.18 に従い競技者ごと種目ごとに最大 2 人のアシスタントが許可される。 T11 競技者は 1 人のガイドランナーが必要で、5000m 以上のレースでは 2 人のガイドランナーがいる可能性があるが、T12 競技者は 5000m 以上の場合は 1 人または 2 人のガイドランナーがいる可能性がある。5000m 以上のレースに T11 または T12 競技者が 2 人のガイドランナーと走る場合は、ガイドランナーが交代すること、トラック競技の場合、どの周回でガイドランナーが交代するか、道路競技の場合は、どの距離で交代するのかを事前に各競技の規則に従って審判長と技術代表に通知する必要がある。 また、招集所審判員は、競技者ではない、または正しく認定されておらず、特定の種目に参加する資格が無い人物を競技場に入れることを許可しないことも重要である。これは、スタートリストで判断しやすい他の多くの種目よりもリレー競走にとって重要である。
--	--

2.25 Advertising Commissioner The Advertising Commissioner (when appointed) will supervise and apply the current Advertising Rules and Regulations and shall determine any unresolved advertising issues or matters arising in the Call Room in conjunction with the Call Room Referee. 2.26 Chief Classifier Where international classification is staged, a Chief Classifier shall be appointed by WPA. The Chief Classifier shall liaise with the LOC and the appointed Technical Delegate to ensure that suitable facilities and logistics are provided for the conduct of classification. They shall supervise and ensure the appointed International Classifiers deliver classification in full compliance with the WPA Classification Rules and Regulations. The Chief Classifier shall be responsible for all matters relating to classification. COMMENT: The Chief Classifier, the Technical Delegate(s) and the Competition Director must liaise together should an athlete's Sport Class change during the Classification Evaluation Period and/or the Classification Competition Period. Re-entry may be considered and is subject to the Technical Delegate's approval (see Rule 5.3). 2.27 International Classifiers International Classifiers shall be appointed by WPA to work in their duties as members of classification panels. They shall evaluate and observe athletes in terms of their respective impairment pre and/or during competition and allocate sport class and class status in accordance with WPA Classification Rules and Regulations. SECTION II – GENERAL COMPETITION RULES Rule 3: The Athletics Facility Any firm, uniform surface that conforms to the specifications in the World Athletics Track and Field Facilities Manual, may be used for WPA Recognised Competitions. Paralympic Games and World Championships must be held only on synthetic surfaced facilities that hold a current valid World Athletics Class 1 or Class 2 Athletics Facility Certificate. In any case, a current national track certificate from an accredited surveyor shall be required for all facilities intended for use for Regional Championships, Regional Games, Sanctioned and Approved Competitions. Note (i): The World Athletics Track and Field Facilities Manual, which may be downloaded from the World Athletics website, contains more detailed and defined specifications for the planning and construction of track and field facilities including further diagrams for track measurement and marking. Note (ii): The current standard forms required to be used for the certification application and measurement report as well as the Certification System Procedures may be downloaded from the	2.25 広告コミッショナー 広告コミッショナーが任命された際には、最新の広告規則及び規程を管理し適用すると共に、招集所における未解決の問題または発生している問題を招集所審判長と一緒に解決する。 2.26 クラシファイヤー主任 国際クラス分けが実施される場合、WPA によりクラシファイヤー主任が任命されるものとする。クラシファイヤー主任は、大会組織委員会及び技術代表と連絡を取り合って、クラス分けのための適切な施設と設備が提供されるよう取り計らうものとする。クラシファイヤー主任は、国際クラシファイヤーによって、WPA クラス分け規則及び規程に従ったクラス分けが確実に実施されるよう監督するものとする。クラシファイヤー主任は、クラス分けに関するすべての事柄に責任を持つものとする。 コメント：クラス分け評価期間及び/またはクラス分け競技期間中に競技者の競技クラスが変更された場合は、クラシファイヤー主任、技術代表、及び競技会ディレクターが連絡を取り合う必要がある。再エントリーを検討することができるが、技術代表の承認が必要である（規則 5.3 参照）。 2.27 国際クラシファイヤー 国際クラシファイヤーは WPA によって任命され、クラス分けパネルのメンバーとしての任務を遂行するものとする。国際クラシファイヤーは、競技会前及び競技会中における各競技者の障害状況を評価観察し、WPA クラス分け規則及び規程に従って、競技クラスとクラスステータスを割り当てるものとする。 第 2 部 競技会一般規則 第 3 条 陸上競技場 WPA 認可競技会では、WA 施設マニュアルで定めた基準に合致した堅固で均一なトラック表面でなくてはならない。パラリンピック及び世界選手権は、陸上競技場のトラックや助走路の表面は、WA クラス 1 またはクラス 2 の認定証を保持している全天候舗装の施設のみで行われる。 地域選手権、地域競技大会、認定及び承認競技会は、資格ある計測員によって検定され有効な国内公認を保持する施設であることが必須となる。 注意(i) WA 陸上競技施設マニュアルには、トラックの計測やマーキングに関する詳細な図を含め、トラックとフィールド施設の規格と建造に関する詳細かつ明確な仕様があり、WA のウェブサイトからダウンロードできる。 注意(ii) 認証システムの手続きと同様に使用に際して認可申請及び検査報告が求められる現行の標準書式は、WA のウェブサイトからダウンロードできる。	2.25 広告コミッショナー 2.26 クラシファイヤー主任 2.27 国際クラシファイヤー 第 2 部 競技会一般規則 第 3 条 陸上競技場
---	---	--

World Athletics website. Rule 4: Age, Gender Categories and Mixed Competition Age Categories 1. The following age groups are recognised by WPA: a) Master Men and Women: Any athlete who has reached their 35th birthday b) Under-20 (U20) Men and Women: Any athlete of 17, 18 or 19 years on 31 December in the year of the competition; c) Under-17 (U17) Men and Women: Any athlete of 14, 15 or 16 years on 31 December in the year of the competition. Note (i): An athlete must be 14 by 31 December in the year of competition to compete in an open event. Note (ii): Eligibility, including minimum age for participation in the Paralympic Games and WPA Championships (see Part B – 3.1.2 (a) and (b)) shall be subject to specific competition regulations. 2. An athlete shall be eligible to compete in an age group competition under these Rules if they are within the age range specified in the relevant age group classification. An athlete must be able to provide proof of their age through presentation of a valid passport or other form of evidence as permitted by the Regulations for the competition. An athlete who fails or refuses to provide such proof shall not be eligible to compete. COMMENT: While this rule defines the age groups in a particular way, it is often the Technical Regulations for a specific competition which determines whether younger athletes can participate as envisaged by note (ii). If they are accepted into the competition they are required to compete with the same conditions and implements as their competitors in the age grouping. Gender Categories 3. Competition under these rules is divided into men's, women's and universal categories. When a Mixed Competition is conducted outside the stadium or in one of the limited cases set out in Rule 4.7 and Rule 4.8, separate men's and women's categories results should still be declared or otherwise indicated. When a universal event or competition is conducted a single category result only shall be declared. 4. An athlete shall be eligible to compete in men's (or universal) competition if they are recognised as a male in accordance with Part B – 4.5 of these Rules. 5. An athlete shall be eligible to compete in women's (or universal) competition if they are	第 4 条 年齢、性別区分及び男女混合競技年齢区分 4.1. WPA は、以下に示す年齢区分を定める。 a) マスター男子・女子：35 歳以上の男子・女子 b) アンダー20（U20）男子・女子：競技会が行われる年の 12 月 31 日現在で 17 歳、18 歳あるいは 19 歳の競技者 c) アンダー17（U17）男子・女子：競技会が行われる年の 12 月 31 日現在で 14 歳、15 歳あるいは 16 歳の競技者 注意(i) 競技者は、競技会が行われる年の 12 月 31 日現在で 14 歳以上でなくてはならない。 注意(ii) パラリンピック競技会及び WPA 競技会 (PART-B 規則 3.1.2(a)及び(b)参照)における最低年齢を含む参加資格は、各競技会規程に従わなければならない。 4.2. もし競技者が当該年齢区分に分類されるのであれば本規則により当該年齢区分対象の競技会に出場する資格を持つ。競技者は有効なパスポートやその他競技会の規程によって承認された証拠書式を提示することで年齢の証明をしなければならない。そのような証拠を提出できなかったり、拒否したりした競技者は競技に参加することは許されない。 コメント：この規則は特定の方法で年齢グループを定義しているが、どの年齢グループが適用されるのか、注 (ii) によって想定される出場できる競技者の年齢の下限を定めるのは各競技会の規程である。彼らが競技会に受け入れられた場合、彼らはその年齢層での競技者と同じ条件と器具で競技する必要がある。 性別 4.3. この競技規則によって行われる競技会は、男子・女子・ユニバーサル（男女混合）に分類される。男女混合競技が競技場外で行われた場合、あるいは規則 4.7 または規則 4.8 に定めるものを例外として競技場内で行われた場合、競技結果を発表またはその他の方法で男女別に示すべきである。ユニバーサル種目や競技会の結果は、一つの種目分類として取り扱う。 4.4. PART-B 規則 4.5 により、男性として認められている者は、男性（またはユニバーサル）の競技に出場する資格がある。 4.5. PART-B 規則 4.5 により、女性として認められている者は、女性（またはユニバーサル）の競技に出	第 4 条 年齢 性別区分及び男女混合競技 年齢区分 性別
--	---	---

recognised as a female in accordance with Part B – 4.5. 6. An athlete who fails or refuses to comply with the applicable Regulations shall not be eligible to compete. COMMENT: Universal competition covers events in which men and women participate together without separate category of results as well as relay or team events in which both men and women are included in the same teams. Mixed Competition 7. Universal competitions such as relays or other team events in which men and women compete together or events in which men and women compete for a single category are permitted in accordance with the applicable regulations of the relevant body. 8. Other than under Rule 4.7, for all other competitions held completely in the stadium, mixed events between male and female participants shall not normally be permitted. However, the following may be permitted in all competitions except held under Part B - 3.1.2 (a) and (b): a) Mixed stadium competition in races of 5000m or longer but it is permitted only when there are insufficient athletes of one or both genders competing to justify the conduct of separate races. The gender of each athlete shall be shown in the result. Such races shall not, in any case, be conducted so as to allow athletes of one gender to be paced / drafted or assisted by athletes of another gender. b) Field Events for men and women may be conducted simultaneously at one or more event sites. Separate result cards shall be used and results declared for each gender. Each round of trials of such events may be conducted either by calling all athletes of one gender followed by the other or by alternating them. For the purposes of Rule 24.17, all athletes shall be regarded as if they were of the same gender. Where Vertical Jumps are conducted on a single event site, Rule 25 and Rule 26 must be strictly applied including that the bar must continue to be raised in accordance with a single set of previously announced increments for the entire competition. COMMENT: The intent of Rule 4.8 is to facilitate the conduct of Field Events and in races of 5000m or longer, when small numbers of athletes of one or both genders are entered in the case of longer events, where timetabling constraints make it difficult to program separate races. The intent of the Rule is not to provide opportunity for women to compete in races against men to achieve potentially better performance conditions. To be clear, mixed competition in Field Events and in races of 5000m or longer is:	場する資格がある。 4.6. 現行の規程に合致しない、あるいは拒否した競技者は競技に参加する資格を有しない。 コメント：ユニバーサル競技会とは、男性と女性と同じチームに含まれているリレーやチームのイベントだけでなく、リザルトを男女別の分類することなしに男女が一緒に参加する競技も定義に含まれる。 男女混合競技 4.7. 加盟団体の規則が適用されていれば、男女が一緒に競うリレーや男女混合チームで行う競技、男女が一つのカテゴリーで行う種目などの男女混合競技会を行うことができる。 4.8. 規則 4.7 以外のその他の競技会で競技場内のみで行う競技では、男女混合の種目は通常では認めない。しかしながら、PART-B 規則 3.1.2(a)及び(b)以外の競技会においては、以下の混合競技を認めることがある。 a) 競技場内で行う 5000m以上の競技で、男女のいずれかまたは男女ともに男女別に競技を実施するのに十分な人数がそろわず、男女別々での実施が非効率的である場合。競技結果には男女の別を表示しなければならない。こうした競技では、いかなる場合でも、他の性別の競技者がペースメイクをしたり、助力をしたりするような行為は許されない。 b) フィールド競技では、男女が同時に同じ場所で同じ種目を行うことができる。その際には、記録用紙は男女別々に作成しなければならない。男女混合で同一種目を行う場合、各ラウンドは一つの性別の競技者全員を先に行ないその後別の性別の競技者全員が行うことも、それぞれの性別の競技者が交互に行うこともできる。規則 24.17（試技時間）の目的から、男子・女子に分けてではなく、全競技者の人数で試技時間を考えなければならない。高さを競う跳躍競技が男女混合として一か所で行われる場合には、事前に公表されている当該競技全体に適用されるバーの上げ幅も含めて、規則 25 及び 26 は厳格に適用されなければならない。 コメント：規則 4.8 の目的は、フィールド競技の実施を促進することであり、より長い種目の場合に 1 人または 2 人のごく少数の性別しかエントリーしておらず、タイムテーブルの制約により、男女別々のレースをプログラムすることが困難な場合に 5000m 以上のレースで行われる。 この規則の目的は、女性競技者が、男性競技者と競技する機会を提供することにより、潜在的により良い記録が出せる環境を作り出すことではない。 誤解を防ぐために補足すると、フィールド種目及び 5000m 以上のレースでの男女混合競技会は、	男女混合競技
---	--	----------------------

a) permitted in WPA Approved Competitions, subject only to the rules of the applicable governing body. [No additional permission from WPA is required]; b) permitted in WPA Sanctioned Competitions under Part B - 3.1.2 (c) if specifically permitted by WPA; c) not permitted at the Paralympic Games and WPA Championships under Part B - 3.1.2 (a) and (b). In the case of mixed competitions in Vertical Jumps, Rule 25 must be strictly applied -including that the bar must continue to be raised in accordance with a single set of agreed increments for the entire competition. There are also restrictions on the recognition of World Records in mixed competitions – see Rules 51.2 (with reference to track races of 5000m and longer) and Rule 51.22 (with reference to women’s road races). Rule 51.22 Note (i) provides guidance on how a women’s only race can be achieved (enabling a women’s only record to be set) in a situation where both men and women are or might be competing. (See also Rule 2.20.2 and Rule 2.20.3). Rule 5: Entries 1. Competitions under the Rules are restricted to eligible athletes. Simultaneous Entries 2. If an athlete is entered in both a Track Event and a Field Event, or in more than one Field Event taking place simultaneously, the appropriate Referee may, for one round of trials at a time, or for each trial in the High Jump, allow an athlete to take their trial in an order different from the start list (or as determined in accordance with Rule 24.6(a)). However, if an athlete subsequently is not present for that particular trial, it shall be deemed that they are passing once the period allowed for the trial has elapsed. As this possibility exists only for that particular round / trial allowed by the Referee, if the athlete is then not present for a subsequent round / trial, when their competing order will be again according to the start list (or as determined in accordance with Rule 24.6(a)), it will be counted as a failure once the period allowed for the trial has elapsed. Note: In Field Events, the Referee shall not allow an athlete to take a trial in a different order in the final round of trials, but the Referee may allow an athlete to do so during any earlier round of trials. COMMENT: The Note clarifies that allowing an athlete to take a trial in a different order in the final round of trials (irrespective of the number of rounds of trials) because of a clash with another event is not permitted. If an athlete is not present in the final round and has not previously indicated that they will pass, then the time	(a) WPA 承認競技会で認められ、適用可能な連盟の規則のみに従う。[WPA からの追加の許可は必要ない。] (b) PART-B 規則 3.1.2(a)及び(b)に基づいて開催される認定競技会において、WPA によって特別に許可されている場合に認められる。 (c) PART-B 規則 3.1.2(a)及び(b)に基づいて開催される競技では認められない。 高さの跳躍の男女混合競技会の場合、規則 25 を厳格に適用する必要がある。すなわち、競技会全体を通して合意されたひとつの上げ方に従ってバーを上げなければならないことが含まれる。 男女混合競技会での世界記録の公認には制限がある-規則 51.2 (5000m 以上のトラックレース) と規則 51.22 (女性の道路競走) を参照 規則 51.22 注意(i)は、男性と女性の両方が参加する状況において、女性の唯一の競走としてどのように認められるか（女性単独での記録の樹立）についての指針を提供する。(規則 2.20.2 及び 2.20.3 も参照) 第 5 条 申し込み 5.1.本規則によって行われる競技会では有資格競技者に限定される。 同時申し込み 5.2. 競技者が、同時にトラック競技とフィールド競技あるいは 2 種目以上のフィールド競技に参加する時には、審判長は 1 ラウンドに一度、走高跳で各試技に一度、競技会に先立って決めたスタートリスト記載の順序によらないで、あるいは 規則 24.6.(a) に従って決定される順序によらないで、その試技を許すことができる。もし、競技者がその後の特定の試技に不在の時、その試技時間が過ぎれば、パス扱いとなる。このことは審判長が許可した特定のラウンドや試技のみであり、競技者がその後のラウンドや試技を行わなければ、競技順序は再びスタートリスト記載の、あるいは規則 24.6.(a)に従って決定される順序によって行われ、試技を行うべき順序の際に競技者が不在の場合は、その試技時間が過ぎれば無効試技とする。 注意：審判長は、フィールド競技の最終ラウンドで異なる順序で試技を行うことを認めてはならないが、それ以前のラウンドでは認めることができる。 コメント：注意は、別の種目との重複出場のために、試技の最終ラウンド（試技のラウンド回数に関係なく）で競技者が違う順序で試行することを許可してはならないと解釈される。競技者が最終ラウンドの場におらず、それ以前にパスすることを表明していない場合、その競技者の試技に許される制限時間がカウントダウンされ、時間が経過する前に戻らなければ、無効	第 5 条 申し込み 同時申し込み
--	--	---

allowed for their trial will run and if they do not return before it expires, then they will be recorded as a failure. (See also Rule 24.18 where a change of order will normally not be made when a substitute trial is awarded - in any round of trials).

Re-entry after Changes in Sport Class

3. At all Paralympic Games and WPA Championships(see Part B - 3.1.2 (a) and (b)) should an athlete's Sport Class change during the Classification Evaluation Period and/or the Classification Competition Period re-entry may be considered and are subject to the approval of Technical Delegate(s).

If an athlete's Sport Class changes during the Classification Evaluation Period the athlete, someone acting on their behalf or an official representative of a team is required to notify of their intention for the athlete's re-entry immediately after publication of the classification outcomes.

Athletes who are subject to re-entry may only be permitted to re-enter in the same event(s) that they had been previously entered **in their new Sport Class**. If an athlete cannot be entered into an event due to lack of availability in their new Sport Class, they may request to enter an alternative available event of their **new Sport Class**.

During the competition period, the Sport Class of an athlete may change after Observation in Competition or classification protests and may affect an athlete's Sports Class, result(s), placing and record(s) at that competition in accordance with Rule 52.4 of these Rules. If the athlete is entered in other events of their previous Sport Class at the same competition, they may be re-entered in those events of their revised Sport Class subject to the approval of the Technical Delegate(s).

If at any stage of the athlete's evaluation WPA or a Classification Panel is unable to allocate a Sport Class to the athlete, the athlete may be designated with Classification Not Completed (CNC) in accordance with Article 10 of the WPA Classification Rules and Regulations. Any athlete who has been designated as CNC following Observation in Competition shall be shown in the official results as **DQ** and any performances achieved by the athlete in that Competition shall be void.

COMMENT: The following criteria should be considered when determining re-entry after changes in Sport Class:
The Minimum Entry Standard for the newly allocated sport class;
The event(s) is/are offered in the newly allocated sport class;
The maximum entries per team have not been reached;
The competition of the concerned event(s) has not started;
The competition schedule is not affected.

試技として記録される。(規則 24.18 参照。どのラウンドであっても、代替試技が与えられた場合には、通常では試技順の変更は行われない。

競技クラス変更後の再エントリー

5.3. すべてのパラリンピック競技大会及び WPA 競技会 (PART-B 規則 3.1.2(a)及び(b)を参照) においては、クラス分け評価期間及び/またはクラス分け競技会期間中、競技者の競技クラス変更は可能であるが、技術代表の承認を条件とする。

クラス分け評価期間中に競技者の競技クラスが変更された場合、競技者、代理人もしくはチームの代表者は、クラス分け結果の発表直後に、競技者の再エントリーの意思を通知する必要がある。

再エントリーの対象となっている競技者は、**新しい**クラスで事前にエントリーしていたのと同じ種目にのみ再エントリーすることが認められる。**新しい**クラスの種目に、空きがないためにエントリーが不可能な場合、競技者は、**新しい**クラスでの代替種目へのエントリーを要求することができる。

競技会期間中、競技観察またはクラス分けに関する抗議により、競技者の競技クラスの変更されることがあり、本規則の規則 52.4 により、競技者の競技クラス、結果、順位及び記録に影響を及ぼすことがある。もし、競技者が同じ競技会で変更前のクラスで他の種目にもエントリーしている場合、技術代表の承認を得て、変更後の競技クラスで、その種目に再エントリーすることができる。

競技者のクラス分け評価のどの段階においても、WPA あるいはクラス分けパネルが競技者に競技クラスを与えることができない場合、WPA クラス分けチーフ、あるいはクラス分け主任は、WPA クラス分け規則に則り、競技者を「Classification Not Completed (CNC)」と指定する。「CNC」となった競技者は、リザルトには **DQ** と記録され、その競技会で達成された記録は無効となる。

コメント：競技クラスの変更後に再エントリーを決定するときは、次の基準を考慮する必要がある。
新しく割り当てられた競技クラスの最低エントリー基準が満たされている。
種目は、新しく割り当てられた競技クラスで実施される。
チームあたりの最大エントリー数に達していない。
関係する種目の競技は始まっていない。
競技スケジュールは影響を受けない。

Failure to Participate 4. At the Paralympic Games and WPA Championships (see Part B - 3.1.2 (a) and (b)), an athlete shall be excluded from participation in all further events (including other events in which they are simultaneously participating) in the competition, including relays, in cases where: a) A final confirmation was given that the athlete would start in an event but then failed to participate; Note: A fixed time for the final confirmation of participation shall be published in advance. b) An athlete qualified in a Qualification Round of an event for further participation in that event but then failed to participate further; c) An athlete and/or the accompanying guide-runner failed to compete honestly with bona fide effort. The relevant Referee will decide on this and the corresponding reference must be made in the official results. However a medical certificate, provided by and based on an examination of the athlete by the Medical Delegate appointed under Rule 2.2 or if no Medical Delegate has been so appointed, by the Medical Officer of the LOC, may be accepted as sufficient evidence that the athlete and/or the accompanying guide-runner became unable to compete due to illness or injury, even if they are able to compete in further events on a subsequent day of the competition. Other justifiable reasons (e.g., factors independent of the athlete's own actions, such as problems with the official transport system) may also be accepted by the Technical Delegate(s). d) An athlete fails to report to the Call Room(s) for an event in contravention of Rule 5.5. COMMENT: If the relevant Referee, is satisfied that an athlete who abandoned a race was not competing with a bona fide effort, they must make a reference to this in the relevant results as "DNF Rule 5.4(c)". Either in the process of the Technical Delegate(s) making such a decision or the Jury of the Appeal considering any protest arising from it, reasons for the withdrawal or nonparticipation proposed by or on behalf of the athlete can be considered. The Rule sets out the process that should explicitly be followed in the case of a medical reason. If the appropriate Referee is in any doubt that an athlete and/or guide-runner has made a bona fide effort in a specific event, available video evidence shall be considered. If the available video evidence is conclusive, then the athlete shall be disqualified in accordance with Rule 8.1 and will not be permitted to take part in any further events in that Competition. Failure to Report to the Call Room(s) 5.5.1 It is each athlete's responsibility to ensure that they are present in the Call Room(s) on time. Except as provided in this Rule, an athlete shall be excluded from participation in any event	参加の拒否 5.4. パラリンピック競技大会及び WPA 競技会 (PART-B 規則 3.1.2(a)及び(b)参照)において、次の競技者はリレーも含む当該競技会で実施される全種目（当該競技者が同時にエントリーし参加している他の種目も含む）に以後参加することが認められない。 a) その種目に出場するという最終確認がなされていたにもかかわらず、出場しなかった競技者 注意：出場者を最終確認するために限定した時間が、あらかじめ発表されているべきである。 b) その種目における以後の出場者を決める予選や準決勝等において資格を得たにもかかわらず、その後の競技をしなかった競技者 c) 誠実に全力を尽くして競技しなかった競技者及び／またはガイドランナー。その判断は審判長が行い、公式記録で本件の記載がなされなければならない。 しかしながら、規則 2.2 に基づいて任命された医事代表によって、あるいは、医事代表が任命されていない場合は組織委員会によって任命された医師によって診察され、診断書が提示された場合、その診断書は、（出場の最終確認後または予選ラウンドで競技した後に）病気や怪我で競技できなくなった競技者及び／またはガイドランナーが翌日以降行われる種目で競技できると認める十分な理由とすることができる。 他の正当な理由（例えば競技者自身の行動と無関係の諸条件、具体的には公的交通手段のトラブルなど）は、技術代表によって同様に是認されることがある。 d) 規則 5.5 に違反する種目について招集所に報告しなかった競技者 コメント：関連する審判長が、そのような状況に気づき、レースを放棄した競技者が、誠意を尽くして競技していないと確信を持った場合には、この競技者について、該当するリザルト上で「DNF 規則 5.4(c)」とする必要がある。技術代表がそのような決定を下す過程、またはそれに起因する抗議を考慮したジュリーの検討の過程において、競技者や競技者に代わってチームから示された棄権や出場しなかった理由が考慮され得る。この規則は、医学的理由の場合に明確に従わなければならない過程を規定している。 適切な審判長が、競技者及び／またはガイドランナーが特定の競技において誠実を尽くしていたことに疑いがある場合、入手可能なビデオ証拠が考慮されるものとする。利用可能なビデオ証拠が決定的である場合、当該競技者は、規則 8.1 に従って失格となり、それ以降の種目に出場することを認めない。 招集所での参加の除外 5.5.1. 招集所に時間通りに現れるのは競技者の責任である。この規則に記載されている場合を除き、招集所のスケジュールに公表されている該当時間に招集所に現れない競技者は、該当種目に出場することは認められない。	参加の拒否
---	---	---------------------

in which they are not present in the Call Room(s) at the relevant time as published in the Call Room schedule. 5.5.2 The relevant Referee shall determine if the athlete was present in the Call Room(s) on time, and if not, whether there was a justifiable reason for the athlete not being present on time. For this purpose, the following justifiable reasons may be considered by the Referee if the athlete can provide evidence that this led to them not being present on time: 1. Problems with the official transport system; 2. Error(s) in the published Call Room Schedule; 3. Illness or injury, for which a medical certificate must be provided as evidence and signed by the Medical Delegate. 5.5.3 The relevant Referee may, at their discretion, allow the athlete to compete in the event under protest if a decision cannot be made immediately in respect of 5.5.2. 5.5.4 If the Referee determines that the athlete was present in the Call Room(s) on time or had a justifiable reason for not being present on time, they shall be permitted to compete in the event. 5.5.5 If the Referee determines that the athlete was not present in the Call Room(s) on time and had no justifiable reason for not being present on time, the athlete shall be listed as "DNS", and a corresponding reference shall be made in the official results. Note: If an athlete on the Start list is as 'Res' and does not show to the Call Room there will be no penalty. 5.5.6 At Paralympic Games, WPA Championships and WPA Sanctioned Competitions, if the athlete is listed as "DNS" as a result of this Rule, they shall also be excluded from all further events in which they are entered at that Competition. COMMENT: As the rule states, the athlete must be present in the Call Room(s) at the appropriate time, as determined by the relevant Referee. Being present in the Call Room does not mean standing outside the Call Room. The technical regulations for the Competition may outline any Call Room procedures which must be followed. For the avoidance of doubt, a "DNS" designation as a result of this Rule shall not affect any results obtained by the athlete at the same Competition in events prior to the event in which they received the "DNS" designation. Rule 6: Clothing, Shoes, Athlete Bibs, Prosthetics and Orthotics, Eye mask, Tether, Non-compliance on Equipment and Helmets 6.1 Clothing 6.1.1 In all events, athletes and guides must wear clothing that is clean, designed and worn so as not to be objectionable. The clothing must be made of a material which is non-transparent	5.5.2 関連する審判長は、当該競技者が招集所に時間通りに現れたか判断し、現れていなかった場合は、当該競技者が時間通りに現れなかった事に正当な理由があったかどうかを検討するものとする。この意図は、競技者が時間通りに招集所に現れなかった証拠を提出した場合、以下の正当な理由が考えられる場合、審判長が検討する必要がある。 1.公式交通機関のトラブル 2.公開された招集所のスケジュールのエラー 3.病気や怪我、証拠として医師の診断書が提出され医事代表の署名が必要である。 5.5.3. 規則 5.5.2 に関して直ちに決定を下すことが難しい場合、関連する審判長は自らの裁量で「抗議中」として競技に出場することを許可することができる。 5.5.4. もし審判長が、当該競技者が招集所に時間通りに現れたと判断したり、時間通りに現れることができなかったことへの正当な理由がある場合は、当該種目に出場することが認められる。 5.5.5. もし審判長が、当該競技者が招集所に時間通りに現れていない、または正当な理由がないと判断した場合は、当該競技者は、リザルトに「DNS」と記録される。公式結果に対応する言及が行われるものとする。 注意： スタートリストに'Res'と記載された競技者が招集所に現れなかった場合はペナルティーを課さない。 5.5.6. パラリンピック競技会、WPA 世界選手権大会および WPA 認定競技会では、競技者がこの規則に従って「DNS」とリザルトに記録されたら、当該競技者は、その競技会でエントリーしている他の種目もすべて競技会から除外される。 コメント：規則に記載されているように、関連する審判長が決定した適切な時間に競技者は、招集所にいる必要がある。招集所に現れる、とは、招集所の周辺にいないことを意味するものではない。競技会の規則は、従わなければならない招集所の手順を概説する必要がある。 疑義を避けるために付記すると、この規則による「DNS」判定は、「DNS」判定を受けた種目以前の同じ競技会の種目で出した記録には影響を与えないものとする。 第 6 条 服装、競技用靴、アスリートビブス、義肢・矯正装具、アイマスク、ヘルメット 6.1 服装 6.1.1 いずれの種目でも、競技者及びガイドは清潔で、不快に思われないようにデザインされ仕立てられた服装を着用しなければならない。その布地は濡れてもすきとおらないものでなければならない。また、審判員	招集所での参加の除外
---	--	--------------------------

even if wet. Athletes must not wear clothing that could impede the view of the Judges. 6.1.2 Any athlete who removes an article of clothing inappropriately, such as taking off their top throughout a field event or at the end of a race to expose their torso, shall, for a first offence in that Competition, be warned by the Referee in accordance with Rule 8.1. For a second offence in that Competition, the Referee shall disqualify the athlete in accordance with Rule 8.1. 6.1.3 Where appropriate, athletes shall participate in the uniform clothing approved by their national governing body. The Victory Ceremony and any lap of honour are considered part of the competition for this purpose. Note (i): In Seated Throwing Events clothing must be close fitting, and not loose, so that the view of the judges is not impeded. COMMENT: Prior to entering the field of play Officials in the Call Room may require an athlete to change their clothing if it is deemed to be inappropriate or objectionable. If an athlete refuses to follow the requirements of the Call Room Judges, the relevant Referee shall warn the athlete and issue a yellow or red card as deemed appropriate. Athletes may be asked by Officials to adjust their clothing to make it easier for the Officials to observe their form, such as in a Seated Throwing Event. 6.2 Shoes - General 6.2.1 Athletes may compete barefoot or with footwear on one or both feet. The primary purpose of shoes for competition is to give protection and stability to the feet and a firm grip on the ground. They must not give athletes any unfair assistance or advantage. 6.2.2 Any shoe which appears on the World Athletics list of approved competition shoes, updated and published from time to time by World Athletics, may also be used in corresponding events in WPA Competitions. Any shoe not on such list must comply with all other terms of Rules 6.2 - 6.7 of these rules in order to be used in WPA Competition. COMMENT: For example, if a shoe is listed on the World Athletics list of approved competition shoes in the category "track from 800m", athletes may also use this shoe for World Para Athletics track events of 800m or longer. 6.2.3 Any type of shoe used must be reasonably available to all in the spirit of the universality of athletics. A shoe that meets the criteria set out in this Rule 6.2 may be customised to suit the characteristics of a particular athlete's foot. However, one-off shoes made to order (i.e., that are only ones of their kind) are not permitted.	の判定を妨げるような服装を着用してはならない。 6.1.2 競技者がフィールド種目の競技中またはレース終了後に衣類を脱いで体を露出させるなど、不適切に衣類を脱いだ場合、その競技会での最初の違反について、規則 8.1 に従って審判長によって警告されなければならない。その競技会での 2 回目の違反については、審判長によって規則 8.1 に従い競技者を失格とする。 6.1.3 各国を代表する場合は、競技者はその国・地域の加盟団体によって定められたユニフォームを着て参加しなければならない。この規定は、表彰式及び競技場内ビクトリーランも競技会の一部とみなす。 注意(i)：座位の投てき種目においては、審判員の視認を妨げることのないよう、服装は身体に密着してはならず、ダブダブであってはならない。 コメント：競技場に入る前に、不適切または不快であると思われる場合、競技者に衣服の交換を要求する場合がある。競技者が競技者係の要件に従うことを拒否した場合、当該審判長は競技者に警告し、適切にイエローまたはレッドのカードを発行する。 競技者は、座位の投てき種目などで、競技役員が競技者のフォームを観察しやすいように服装を調整するように求められる場合がある。 6.2 競技用靴 – 一般 6.2.1 競技者は、裸足でも、また片足あるいは両足に靴を履いて競技をしてもよい。競技の時靴を履く目的は、足の保護安定とグラウンドをしっかり踏みつけるためである。競技用靴は、競技者に不正な付加的助力や優位性を与えるものであってはならない。 6.2.2 WA で承認された競技靴リストに掲載されている靴は、随時更新、公開され、WPA 競技会の該当する種目においても使用できる。このリストにない靴を WPA の競技会で使用するためには、規則 6.2-6.7 のすべての条件に準拠する必要がある。 コメント：例えば、800m 以上のトラック種目で承認された競技用靴で WA のリストに記載されている場合、競技者は 800m 以上の WPA のトラック種目においても使用できる。 6.2.3 使用されるどのような靴でも、陸上競技の普遍性の精神に基づき、すべての人が合理的に入手できるものでなければならない。規則 6.2 に定められた基準を満たす靴は、競技者の足の特性に合うようカスタマイズすることができる。ただし、オーダーメイドの靴（その種類の靴のみ）は許可されない。	第 6 条 服装 競技用靴 アスリートビブス 義肢 6.2 競技用靴 – 一般
---	---	---

6.2.4 Where WPA has reason to believe that a type of shoe or specific shoe technology may not comply with the letter or the spirit of Rules 6.2 – 6.6, it may refer the shoe or shoe technology for detailed examination and it may prohibit the use of such shoes or technology in competition pending examination. 6.3 Shoes - Number of Spikes The sole of the shoes and/or prosthetic(s) (including the part beneath the shoe) may be so constructed as to provide for the use of up to 11 spikes. Any number of spikes up to 11 may be used but the number of spike positions shall not exceed 11. 6.4 Shoes - Dimensions of Spikes That part of each spike which projects from the sole or the heel shall not exceed 9mm except in the High Jump and Javelin Throw, where it shall not exceed 12mm. The spike must be so constructed that it will, at least for the half of its length closest to the tip, fit through a square sided 4mm gauge. If the track manufacturer or the stadium operator mandates a lesser maximum, or prohibits the use of certain shaped spikes, this shall be applied and the athletes notified accordingly. Note: The surface must be suitable for accepting the spikes permitted under this rule. COMMENT: The revised spike length requirement would normally be outlined in the Team Manual or technical requirements for the competition and athletes should be aware that due to modern track construction, the maximum spike length is likely to be shorter than the maximum permitted by these rules. 6.5 Technical Requirements for Shoes - The Sole 6.5.1 The sole of the shoe (including the part beneath the heel of the shoe) may have grooves, ridges, indentations or protuberances, provided these features are constructed of the same or similar material to the basic sole itself. The maximum thickness of the sole of the shoe is set out at Rule 6.6. 6.5.2 The thickness of the sole shall be measured at the centre of the forefoot and the centre heel of the shoe as the distance between the inside top side and the plane of the outside under side at the centre of the forefoot and heel respectively. This measurement includes the above-mentioned features. See Figure (1) below:	6.2.4 WPA が、ある種類の靴または特定の靴の技術が規則 6.2-6.6 の精神に準拠していない可能性があると考えられる理由がある場合、靴またはその技術は詳細な調査対象となることがあり、調査結果次第で、WPA はそのような靴または技術の使用を禁止することができる。 6.3 競技用靴-スパイクの数 競技用靴、及び義足の靴底（踵の下 of 靴底を含む）は、11 本以内のスパイクを取りつけられる構造とする。11 個までの任意の数のスパイクを使用することができるが、スパイク取付け位置は 11 か所を超えてはならない。 6.4 競技用靴-スパイクの寸法 競技用靴の靴底または踵から突出した部分のスパイクの長さは 9mm を超えてはならない。また走高跳及びやり投の場合は、12mm を超えてはならない。スパイクは先端近くで、少なくとも長さの半分は 4mm 四方の定規に適合するように作られていなければならない。トラック製造業者もしくは競技場管理者が、より小さい寸法の上限を設けている場合や、特定の形状のスパイクの使用を認めていない場合は、これが適用され、そのことが競技者に対して適切に通知されなければならない。 注意: トラックの表面は、本条で認められるスパイクの使用が可能なものではない。 コメント: スパイクの長さの要件が異なる場合は、通常、チームマニュアルまたは競技注意事項に記載される。また競技者は、最新のトラック構造より、スパイクの最大長がこれらのルールで許可される最大長より短く規定されている場合があるので注意すべきである。 6.5 競技用靴-靴底 6.5.1 靴底（踵の下 of 靴底を含む）には、うね、ぎざぎざ、突起物などがあってもよいが、これらは靴底本体と同一もしくは類似の材料で作られていること。靴底の最大厚は、規則 6.6 に定められている。 6.5.2. 靴底の厚さは、靴を履いていないとき、靴の前足の中心と踵の中心で、それぞれ靴の内部にある靴底の最上部と靴の外部下側の平面部分との間の距離として計測する。この測定に際しては、本規程で記述しているもの、及びインナーソール、その他の挿入物も含めて計測する。図（1）参照。	6.3 競技用靴 - スパイクの数 6.4 競技用靴 - スパイクの寸法 6.5 競技用靴 - 靴底
---	---	--




Figure 1 – Measuring the thickness of the sole

6.5.3 The centre of the forefoot of the shoe is the centre point of the shoe at 75% of its internal length. The centre of the heel of the shoe is the centre point of the shoe at 12% of its internal length. See Figure (2), below. For a standard sample unisex size 42 (EUR), the centre of the forefoot of the shoe will be the centre point of the shoe approximately 203mm from the inside back of the shoe, and the centre of the heel of the shoe will be the centre point of the shoe approximately 32mm from the inside back of the shoe. The thickness of the sole outside of these points is not relevant for the purposes of meeting the requirements of these Rules.




Figure 2 – Location for measurement of the centre of the forefoot and heel

6.5.4 WPA acknowledges that a shoe above that standard sample size might contain a marginally thicker sole than that of a standard sample size shoe of the same make and model, which marginal increase in sole thickness is only attributable to the larger size of the shoe. Such marginal increases will be disregarded for the purposes of confirming compliance with these Rules.

6.6 Until further notice, unless in exceptional circumstances and specifically agreed by WPA in writing, any shoe used in competition:

a) (except where Rule 6.6(c) applies) must not contain more than one rigid structure (e.g. plate, blade etc.) whether that structure runs the full length of the shoe or only part of the length of the shoe;

6.5.3 足の中心は、靴の内部の長さの 75%にある靴の中心点とする。踵の中心は、靴の内部の長さの 12%にある靴の中心点とする。図(2)参照。標準的な事例としてユニセックスサイズ 42 (EUR) (= 26.5~27.0cm) の場合、前足の中心は靴の内側の背面から約 203mm の位置であり、踵の中心は靴の内側の背面から約 32mm の位置である。

6.5.4 WPA は、標準的なサイズを超える競技用靴には、同じメーカーと同じモデルの靴であっても、標準サンプルサイズの靴よりもわずかに靴底が厚いものが含まれる可能性があること、それは靴のサイズに起因することを認識している。このようなわずかな厚みの差は、本規程が遵守されているかを確認する目的においては問題としない。

6.6 例外的な状況で WPA が書面により明確に合意した場合を除き、競技会で使用される競技用靴は次のとおりとする。

a) (規則 6.6(C)が適用される場合を除き) 靴の全長または靴の長さの一部かどうかにかかわらず、2 つ以上の剛性構造プレート、ブレード等、あるいは同様の効果をもたらすものを含んではならない。

- b) the one rigid structure referred to in Rule 6.6(a) may be in more than one part, but those parts must be located in one plane (i.e. must not be tacked above each other, must not overlap);
- c) may contain one additional rigid structure or other mechanism (e.g. plate, blade etc.) only where used solely to attach spikes to the outer underside of the shoe. For the avoidance of doubt, the additional rigid structure to attach spikes cannot be a continuation of the rigid structure referred to in Rule 6.6(a);
- d) must not contain any embedded ‘sensing or intelligent’ technology whatsoever. This does not prevent heart rate or speed distance monitors or stride sensors carried or worn personally by an athlete pursuant to Rule 7.4(d);
- e) must have a sole with a maximum thickness as set out in the table below.

New Sole Thickness Table – in force from 1 November 2024

Event	Maximum thickness of the sole (as per Rule 6.6)	Further Requirement/Note
Track Events	20mm spike shoe or non-spike shoe	For relays, the rule applies to the distance of the leg being run by each athlete.
Field Events	20mm spike shoe or non-spike shoe	For all Jumping Events, the sole at the centre of the athlete's forefoot must not be higher than the sole at centre of the athlete's heel referred to at Rules 6.5.2 and 6.5.3 (i.e., at centre point of the shoe at 12% and 75% of the shoes internal length).
Road Events	40mm	

6.7 Shoes - Inserts and Additions to the Shoe
Athletes may not use any appliance, either inside or outside the shoe, which will have the effect of increasing the thickness of the sole above the permitted maximum, or which can give the wearer any advantage which they would not obtain from the type of shoe described in the previous paragraphs.

COMMENT: Please refer to the further rules on shoes set out at Rules 6.9 (Non-Compliance) and Rule 6.6 above.

6.8 Athlete Bibs

6.8.1 Every athlete shall be provided with two bibs, which during the competition, shall be worn visibly on the breast, back and/or on their competition equipment (i.e., racing chairs, Running frames and throwing frames), as set out in the table below. Either the athletes' names or other suitable identification will be allowed instead of numbers on any or all of the bibs. If numerals are used, they shall correspond

- b) 規則 6.10(a)の 1 つの剛性構造は複数のパーツで構成されている場合があるが、それらのパーツは同一平面上に配置されなければならない（互いに積み重ねたり、重なり合ったりしてはならない）。
- c) 靴の外側下面にスパイクをとりつけるためだけにしようされる場合に限り、追加の合成構造または他の機構（例：プレート、ブレードなど）を 1 つ含めることができる。誤解を避けるために付記するが、スパイクを取り付けるための追加の剛性構造は、規則 6.6（a）で言及されている剛性構造の継続であってはならない。
- d) いかなる「センシングまたはインテリジェント」テクノロジーも組み込まれてはならない。これは規則 7.4(d)に従い、競技者が個人的に携帯または着用する心拍計や速度距離モニター、またストライドセンサーを妨げるものではない。
- e) 下記表の通り、設定された最大ソールの厚さが必要である。

2024 年 11 月 1 日から適用される靴底の最大の厚さ

6.7 競技用靴-競技用靴への仕掛け

競技者は、靴の内側、外側を問わず、靴底の規定の厚さを増やすような効果があったり、前項で述べたタイプの靴からは得られない利益を与えたりするような仕掛けをしてはならない。

コメント：以下の規則 6.9（ノン・コンプライアンス）及び上記規則 6.6 参照。

6.8 アスリートビブス

6.8.1 競技者は、競技中、以下に示すように胸と背及び／あるいは競技用具（競技用車いす、ランニングフレーム、投てき用台）にはっきり見えるように 2 枚のビブスをつけなければならない。跳躍競技の競技者は、背または胸につけるだけでもよい。競技の際にトレーニングシャツを着る時は、同じ方法でその上につけなければならない。ビブスの一部または全部に、数字の代わりに競技者の名前またはその他の適切な識別記号を記載することが認められる。番号を記載する場合は、スタートリスト

with the number allocated to the athlete on the start list or in the programme. If track suits are worn during the competition, bibs shall be worn on the track suit in a similar manner.
Bib Allocation Table

Bib Allocation Table

	Track Events	Throwing Events	Jumping Events
Ambulant Athletes	1 bib on back <u>and</u> 1 bib on breast	1 bib on back <u>and</u> 1 bib on breast	1 bib on breast <u>or</u> back
Seated Throws		1 bib on back of throwing frame <u>and</u> 1 bib on breast	
Wheelchair Racing	1 bib on back of the racing chair <u>Optional:</u> 1 helmet number <u>and/or</u> 1 bib on side of the frame		
Frame Running	1 bib on back of the athlete <u>Optional:</u> 1 helmet number <u>and/or</u> 1 bib on side of the frame		

6.8.2 The bibs shall be visibly displayed in accordance with the bib allocation table above.

6.8.3 Athletes must not wear any bibs on their leg instead of on their breast or back.

6.8.4 These bibs must be worn as issued and may not be cut, folded or obscured in any way. **It is prohibited to modify the bibs in any form, including by writing or adding on anything to the bibs.** In long distance events, the bibs may be perforated to assist the circulation of air, but the perforation must not be made on any of the lettering or numerals that appear on them.

6.8.5 Where a Photo Finish System is in operation, the LOC may require athletes to wear additional number identification of an adhesive type on the side of their shorts or lower body as determined by Call Room or other Technical Officials.
For athletes competing in all individual and team track and road wheelchair and Frame Running races, these additional number identifications shall be worn on the helmet.

6.8.6 No athlete shall be allowed to take part in any competition without displaying the appropriate bib(s) and/or identification.

6.8.7 The bib(s) shall be worn until the athletes have passed through the mixed zone or left the field of play where no mixed zone exists.

6.9 Non-Compliance in relation to clothing, shoes and bibs

If an athlete does not follow any part of any of the Rules 6.1 – 6.8 to and:

a) refuses the direction of the relevant Referee or other official to comply; or

もしくはプログラム上で各競技者に割り振られた番号を記載する。競技中にトラックスーツを着用する場合も、同様にビブスはスーツの上につけなければならない。

6.8.2 ビブスは、上記表に基づきはっきり見えるようにつけなければならない。

6.8.3 競技者は胸や背の代わりに脚部にビブスをつけてはならない。

6.8.4 ビブスは配布された形で着用しなければならず、切ったり折り畳んだりあるいはいかなる方法でも見えなくしてはならない。**ビブスに何かを書き込んだり追加したりするなど、いかなる形であれビブスを変更することは認められない。**
長距離種目においては、風通しをよくするためにビブスに穴をあけてもよいが、文字や数字の部分に穴があってはならない。

6.8.5 写真判定装置を使用する競技会において、主催者は、招集所審判あるいは他の競技役員の指示で、競技者のショーツまたは下半身の横に粘着性の腰ナンバー標識をつけさせることができる。
車いす及びフレームランニングによる個人種目、リレー及び道路競技に出場する競技者は、腰ナンバーに代えて、ヘルメットにナンバーを貼らなくてはならない。

6.8.6 いかなる競技会であろうと、競技者が自分のビブスその他の標識を着用せずに参加することは一切認められない。

6.8.7 ビブスは競技者がミックスゾーンを通過するまでまたはミックスゾーンを設けていない場合は競技区域から出るまで装着していなければならない。

6.9 衣類、靴及びビブスに関する不適合

競技者が本条の規則 6.1-6.8 に従わず、

a) 審判長が従うよう命じてもその命令を拒否した場合、または

b) participates in the competition, they shall be disqualified. COMMENT: This Rule 6.9 prescribes the sanction if any aspect of any of the Rules 6.1 – 6.8 is not followed. It is expected however that where possible the relevant officials should request and encourage the athlete to comply and to advise them of the consequence if he they do not. But where an athlete does not follow an aspect of the Rule during competition, and it is not practical for an official to request compliance athletes should note that disqualification may follow. It is a responsibility of the Starters Assistants and Umpires (for Track and Out of Stadium Events) and the Judges (for Field Events) to be vigilant on these matters and report any apparent breaches to the relevant Referee. 6.10 Referee directions as to shoes 6.10.1 If the Referee has a reasonable suspicion that a shoe worn by an athlete in a competition might not comply with the letter or spirit of the Rules, the Referee (or other official as directed by the Referee) may request and the athlete must immediately hand over the shoe to the Referee or such other official at the conclusion of the event for further investigation by WPA. However, where it has already been declared that a shoe does not comply with the spirit of the Rules, the relevant Referee shall immediately act in accordance with Rule 6.9. 6.10.2 When shoes have been handed over by the athlete under this Rule and the athlete intends to subsequently compete in later rounds of the same event or in other events during the same competition, the Referee or other official shall ensure the shoes are available to the athlete to use in each such subsequent event. How, when and on what conditions the shoe is made available to the athlete during the competition is at the Referee's discretion. 6.11 Exceptions to Rules 6.2, 6.5, 6.7 or 6.6 6.11.1 If an athlete presents with an anatomical limitation (for example leg length difference or foot deformity) that prevents adherence to the requirements of Rule 6.2, 6.5, 6.7 or 6.6, then an assessment shall be made by WPA in advance of the event and an exception may be granted. 6.11.2 The shoe worn by the athlete on the other non-impaired foot and/or leg must comply with the requirements of Rules 6.2, 6.5, 6.7 and 6.6. 6.11.3 WPA may establish a process for applications under this Rule to be considered. 6.12 Prostheses 6.12.1 Athletes in Sport Classes T/F61-64, with lower limb deficiency and leg length difference must wear lower limb prosthetic device(s) in order to ensure both legs are balanced and to allow for symmetric movement during Competition. Such prosthetic device(s) shall not provide any other assistance to the athlete or breach any of the fundamental principles outlined	b) そのまま競技に参加した場合、当該競技者は失格とする。 コメント：規則 6.9 は、規則 6.1-6.8 の条項が遵守されない場合の制裁措置を規定している。関連する競技役員は、可能な限り競技者がこれらの規則を遵守するよう注意するとともに、従わなかった場合、どのような結果を招くかを競技者に説明することが期待される。但し、競技者が競技会中に規則のいずれかの条項に従わず、競技役員が競技者に規則遵守を要求することが現実的でないのなら、失格となる可能性があること五競技者は留意しなければならない。出発係と(トラック種目と場外競技担当の)監察員及び(フィールド種目担当の)審判員はこうした問題を警戒し、明らかな違反があった場合には審判長に報告する責任がある。 6.10 靴に関する審判長の指示 6.10.1 競技用靴に関し、審判長が本規程に定められている精神に照らし何らか合理的な疑義を持った場合、審判長（または、審判長から指示された競技役員）は競技者に対し、WPA による更なる調査を求めることがあり、その場合、競技者は当該競技終了後直ちに当該競技用靴を審判長あるいは当該競技役員に引渡さなければならない。ただし、当該競技用靴が本規程に定められている精神に合致していないことが既に明らかになっている場合、審判長は本規程 6.9 に従い速やかに行動する。 6.10.2 競技者が当該競技用靴を手渡した後、当該競技者が同じ種目の後のラウンドや、同じ競技会の他の種目で競技を行う予定がある場合、審判長または競技役員は、後から行われる競技でも当該競技用靴を確実に着用できるようにしなければならない。以後の競技中にどのように、いつ、どのような条件で競技者が当該競技用靴を着用できるようにするかは、審判長の裁量に委ねられる。 6.11 競技規則 6.2, 6.5, 6.7 または 6.6 の例外 6.11.1 競技者が、規則 6.2、6.5、6.7 または 6.6 の要件の順守を妨げる制限（例えば、脚の長さの違いや足の変形）を示した場合、競技の前に WPA によって評価が行われなければならないが、例外が認められる場合もある。 6.11.2 競技者が障害のない足及び脚に着用する靴は、規則 6.2、6.5、6.6 及び 6.10 の要件に準拠していなければならない。 6.11.3 WPA は、この規則に基づく申請方法を検討することがある。 6.12 義肢 6.12.1 下肢欠損及び脚長差（WPA クラス分け規則及び規程の付録 1 の最低障害基準 2.1.4.1 及び 2.1.7 を満たす）に該当する競技クラス T/F61-64 の競技者は、競技中、両脚または両腕の長さを等しくしてバランスよく走れるようにするために義肢を装着しなければならない。かかる義肢はバランスを補正する以外の助力を競技者に与えるものであってはならず、PART-B 規則 7.1 に概説されている基本原則に違反してはならない。	6.10 靴に関する審判長の指示 6.11 競技規則 6.2 6.5 6.7 または 6.6 の例外 6.12 義肢
---	--	--

in Part B – 7.1. a) In Track and Road Events, athletes in Sports Classes T61-64 shall compete with lower limb prosthetic device(s) and shall complete the race with such device(s). Prostheses are considered an extension of the athlete's body. If the athlete reaches the nearer edge of the finish line without the attached prosthetic device(s), the athlete shall be disqualified. b) In Field Events, athletes in Sports Classes T/F61-64, shall compete with lower limb prosthetic device(s). They shall complete all trials from start to finish with such device(s). If the athlete does not, such trial(s) shall be considered a failure. 6.12.2 For Sport Classes T/F61-62 the actual height of an athlete in their Competition leg prostheses shall not exceed their Maximum Allowable Standing Height (MASH) in accordance with Appendix 3 of these Rules. The height of athletes shall be measured at the Call Room by Call Room Judges. If an athlete exceeds their MASH then the athlete will not be permitted to start the event and shall be shown in the results as "DNS" in accordance with Rule 6.16. COMMENT: World and Regional Records - For the purpose of record ratification, all World and Regional Records achieved by athletes in Sport Classes T/F61-62 must comply with Rule 51.10 Note (i). 6.12.3 For athletes in Sport Classes T45-47 and F45-46 with upper limb deficiency meeting the requirements as per the WPA Classification Rules and Regulations), the use of upper limb prosthetic device(s) is optional. a) In Track and Road Events, athletes in Sport Classes T45-47, that choose to compete with the upper limb prosthetic device(s), shall complete the race with such device(s). Since the use is optional, the athlete may decide whether or not to use the upper limb prosthetic device(s) in the next round (e.g., in the semi-final or final in 100m). Prostheses are considered an extension of the athlete's body. Once the race starts, athletes running with upper limb prosthetic device(s) must reach the nearer edge of the finish line with such device(s). If the athlete reaches the nearer edge of the finish line without the attached prosthetic device(s), the athlete shall be disqualified. b) In Field Events, athletes in Sport Classes T45-47 and F45-46, the use of upper limb prosthetic device(s) is optional. Prior to the start of each round of the Event, the athlete shall notify the relevant Official of their intention. If an athlete decides to compete with the prosthetic device(s), they shall complete all trials from start to finish with such device(s). If the athlete does not, such trial(s) shall be considered a failure.	a) トラック種目と道路種目においては、競技クラス T61-64 の競技者は、下肢用義肢を装着して競技し、それら義肢を装着した状態で競技を終えなくてはならない。義肢は競技者の身体の延長とみなす。競技者がスタートラインに最も近いフィニッシュラインの端に到着するまで義肢を装着していなければその競技者は失格となる。 b) フィールド種目においては、競技クラス T61-64 の競技者は、下肢用義肢を装着して競技を行わなければならない。その競技者は競技開始から終了まですべての試技で義肢を装着して競技しなくてはならない。装着せずに試技した場合、無効試技とみなされる。 6.12.2 競技クラス T/F61-62 については、競技用義足装着時の競技者の身長が、Appendix 3 に記載されている規則に定める最大許可身長 (MASH) を超えてはならない。競技者の身長は、招集所で招集所審判(競技者係)が測定するものとする。競技者が MASH を超えた場合、その競技者は競技を開始することができず規則 6.16 に従い、リザルトに DNS と記録される。 コメント：世界記録とエリア記録 世界及び地域の記録の承認を目的として、競技クラス T/F61-62 の競技者が達成したすべての世界及び地域の記録は、規則 51.10 の注記(i)に準拠している必要がある。 6.12.3 上肢欠損の競技クラス T45-47 及び F45-46 の競技者は WPA クラス分け規則及び規程に合致していることを条件として上肢用義肢の使用は任意である。 a) トラック及び道路競技において、上肢用義肢を着用して競技することを選択した競技クラス 45-47 の競技者は、その義肢を着用した状態でレースを完了しなければならない。着用は任意のため、競技者は次のラウンド（例えば、100m の準決勝や決勝進出の場合）でも使用するかどうかを選択できる。義肢は競技者の身体の延長とみなす。一旦競技が開始されたら、その競技者はその義肢と共にスタートラインに最も近いフィニッシュラインの端に到達しなければならない。競技者がスタートラインに最も近いフィニッシュラインの端に到着するまで義肢を装着していなければその競技者は失格となる。 b) フィールド種目において、競技クラス T45-47 及び F45-46 の競技者の上肢用義肢の使用は任意である。各種目のラウンドの競技開始前に、競技者は担当競技役員に使用の意思を通知しなければならない。上肢用義肢を着用して競技することを競技者が決断した場合、その競技者は、その義肢を着用した状態で試技の最初から最後まで完了しなければならない。競技者がそのようにしなかった場合、その試技は無効試技とみなされる。	
---	---	--

COMMENT: In the case that the athlete decides to use the prosthetic device(s) (e.g., in High Jump or Long Jump), the relevant Official shall ensure that Rule 25.7 and Rule 27.14 are observed. The phrase "round of trials" instead of "rounds" is designed to ensure a clear difference between a "round of trials" within a Field Event competition and a "round of the competition" (i.e., a Qualification Round or a final). 6.13 Orthoses 6.13.1 For athletes in Sports Classes T32-34/F31-34, T/F35-38, T/F42-44 and T51-54/F51-57 with Lower Limb Impairment with two anatomical limbs, the use of orthotic device(s) is optional. 6.13.2 In Sport Classes T32-34/F31-34, T/F35-38, T45-47/ F45-46 and T51-54/F51-57, athletes with Upper Limb Impairment, the use of orthotic device(s) is optional. 6.13.3 For athletes with lower and/or upper limb impairment the use of assistive devices other than those permitted in Rule 6.12 or this Rule 6.13 to facilitate running is not allowed. COMMENT: Up until 01 January 2018, Sport Classes T/F42-44 included both athletes who competed with a prosthetic device(s) and athletes who did not. Recent findings indicate that the use of prosthetic device(s) may provide a performance advantage in Track Events. 6.14 Eye mask 6.14.1 Athletes in Sport Classes T/F11 must have their eyes/eye cavities completely covered by gauze patches or an equivalent material and must wear approved opaque glasses or an appropriate substitute during all track and/or field events. These opaque glasses or their substitute must completely cover the eyes of the competitor and must be checked and approved by the responsible technical official and must in their opinion be effective in blocking out all light. These opaque glasses or their substitute may be inspected again at any time, including immediately before the start and/or after finish. 6.14.2 It is the responsibility of the athlete to provide the eye patches, eye masks / opaque glasses and to ensure that these eye patches, eye masks and opaque glasses or appropriate substitute meet the requirements set out in 6.14.1. If an athlete arrives at the call room and a) does not have eye patches, and/or an eye mask/opaque glasses/appropriate substitute, or b) the eye patches, an eye mask/opaque glasses/appropriate substitute fails to comply with this Rule 6.14, Rule 6.16 shall apply. 6.14.3 Eye patches and eye masks / opaque glasses or appropriate substitute must be worn from the time the athlete leaves the Call Room	コメント：競技者が競技中に義肢装具を使用することを決定した場合（つまり、走高跳または走幅跳で）、関係役員は、その特定の試技で規則 25.7 及び規則 27.14 が遵守されていることを確認する。 "ラウンド"ではなく、"試技のラウンド"の表現はフィールドのラウンドと競技会のラウンド（例えば決勝ラウンドや決勝）の違いを明確にするためである。 6.13 矯正装具 6.13.1 下肢に機能障がいに伴う競技クラス T32-34/F31-34、T/F35-38、T/F42-44、T51-54/F51-57 の競技者において、（下肢）矯正装具の使用は任意である。 6.13.2 競技クラス T32-34/F31-34、T/F35-38、T45-47、F45-46 及び T51-54/F51-57、では、上肢障害を有する競技者は、矯正装具の使用は任意である。 6.13.3 下肢及び/または上肢の障害を有する競技者については、走行を容易にするために規則 6.12 及び規則 6.13 で許可されている以外の補助装置の使用は認められない。 コメント：2018 年 1 月 1 日まで、競技クラス T/F42-44 には、義肢装具を付けて競技した競技者とそうでなかった競技者の両方が含まれていた。最近の調査結果では、義肢装具を使用すると、トラック競技でパフォーマンスが向上する可能性があることが示されている。 6.14 アイマスク 6.14.1 競技クラス T/F11 の競技者は、すべてのトラック種目とフィールド種目の競技中、アイパッチまたは同等の物で完全に目を覆ったうえで、承認を受けた不透明で前の見えない眼鏡または適切な代用品を装着しなければならない。不透明眼鏡またはその代用品は完全に目を覆うもので、担当競技役員のチェックと承認を受けなければならない。競技役員の判断において、完全に光を遮断する効果があるものでなければならない。担当の技術役員は、競技開始直前や競技終了直後を含めいつでも、不透明眼鏡またはその代用品の再検査を行うことができる。 6.14.2 アイパッチ、アイマスク、不透明眼鏡は競技者の責任で用意されなければならない。アイパッチ、アイマスク、不透明眼鏡またはその代用品が規則 6.14.1.の基準を満たすことは競技者の責任である。競技者が招集所に a)アイパッチ、アイマスク、不透明眼鏡またはその代用品を持参していない、 b)アイパッチ、アイマスク、不透明眼鏡またはその代用品が規則 6.14 に準じていない場合は、規則 6.16 が適用される。 6.14.3 競技者が招集所を離れる時から競技終了までの間（トラック競技ではフィニッシュラインの基準線を越えるまで、フィールド競技では最終試技終了まで	6.13 矯正装具 6.14 アイマスク
---	--	--

until the end of the event (after the athlete has crossed the leading-edge of the finish line in track events or after the end of the athlete's final trial in field events) or after an athlete has retired from an event. Save for where Rule 6.14.4 applies, any athlete who removes their eye patches and/or eye mask/opaque glasses before the end of the event or before retiring from an event shall, for a first offence, be warned by the Referee in accordance with Rule 8.1. For a second offence in that Competition, the Referee shall disqualify the athlete in accordance with Rule 8.1. 6.14.4 In field events an athlete may temporarily remove the eye mask / opaque glasses (but not eye patches) between trials in the event. 6.14.5 It is not required for athletes to wear eye patches and masks during road races. COMMENT: It is important for ITOs to remember that as Referees they must ensure that inspection of eye patches and eye masks must be conducted in the Call Room (see Rule 2.24) and that athletes wear proper eye patches and masks during the events for which they are intended to be worn. Where an athlete wishes to remove the eye patches or eye mask, they must ask for permission to do so. This shall not be unreasonably withheld by the Referee or Chief Judge of the event. While in a Track Event the eye patches and eye masks are normally in place at the starting line and remain for the duration of the event; however, in some Field Events an athlete may remove their eye mask/opaque glasses between attempts. If they do so, the Judges and Referee need to observe that they are replaced by the athlete or their assistant prior to their next attempt. Failure to wear the eye patches and eye masks correctly will result in disqualification of the athlete. This may include where the eye patch or eye mask falls off during a Track Event. 6.15 Tether 6.15.1 When competing with a guide-runner, athletes in Sport Class T11 and T12 shall be guided through a tether which shall be supplied by the athlete and shall comply with Rule 6.15.4. If such an athlete arrives at the call room and a) does not have a tether, or b) the tether is not in compliance with Rule 6.15.4, Rule 6.16 shall apply. 6.15.2 Only one tether shall be used between an athlete and their guide-runner(s) during a race. 6.15.3 If during a race their tether breaks then the athlete shall be disqualified. COMMENT: It is the responsibility of the athlete to ensure that their tether is durable and serviceable and that, in the event that the tether	の間、) 、または、競技者が途中で棄権するまで、アイパッチ、アイマスク、及び不透明で前の見えない眼鏡または適切な代用品を装着しなければならない。規則 6.14.4 の場合を除き、競技終了前、または競技を棄権する前にアイパッチ、アイマスク、及び不透明で前の見えない眼鏡を外した場合、規則 8.1 に則り審判長から警告を受ける。同じ競技会で 2 度目の警告を受けた場合、規則 8.1.に則り、その競技者は失格となる。 6.14.4 フィールド競技の場合、種目の試技の間にアイマスク、及び不透明で前の見えない眼鏡（アイパッチは除く）を外してもよい。 6.14.5 ロードレースでは、競技者はアイパッチ及びアイマスクを着用する必要はない。 コメント：ITO は審判長として、招集所でアイパッチとアイマスクの検査が行われていることを確認する必要がある（規則 2.24 参照）、競技者が着用する必要のある種目では、競技者が競技中に適切なアイパッチとマスクを着用する必要があることを覚えておくことが重要である。競技者がアイパッチまたはアイマスクを外したい場合は、外す許可を求める必要がある。これは、審判長または審判員主任によって不当に拒否されてはならない。 トラック種目では、アイパッチとアイマスクは通常スタート地点にいますとき装着されており、競技中もそのまま着用される。ただし、一部のフィールド種目では、各試技の間にアイマスク、不透明な眼鏡を外すことができる。その場合、審判員と審判長は、次の試技の前に、競技者またはアシスタントによってそれらが着用されることを確認する必要がある。 アイパッチとアイマスクを正しく着用していない場合、その競技者は失格となる。これは、トラック種目の最中にアイパッチまたはアイマスクが落ちることも含まれることがある。 6.15 テザー 6.15.1 ガイドランナーの伴走がある場合、競技クラス T11 と T12 の競技者は、テザーによってガイドランナーとつながっていかなくてはならず、それは競技者が用意し規則 6.15.4 に適合していなければならない。競技者が招集所に、a)テザーを持参していない、b)テザーが規則 6.15.4.に適合していない場合、規則 6.16 が適用される。 6.15.2 競技中、競技者とガイドランナーの間では 1 本のテザーのみ使用が許される。 6.15.3 競技中にテザーがこわれた場合は失格となる。 コメント：テザーが競技中に耐えうるものであるかどうかの責任は競技者にあり、規則 7.9 に従い、競技中にこわれた場合は失格となる。	6.15 テザー
--	---	----------------------------

breaks during a race, they will be disqualified under Rule 7.9.

6.15.4 The tether shall be made from non-elastic material and shall not store energy and/or offer a performance gain to an athlete. It shall consist of two closed holding loops and a middle section with a fixed stopper of 1cm length at each end.

a) For track events, the maximum length between the two furthest points of the holding loop at the full extension of the tether shall not exceed 30cm. For road events, the maximum length between the two furthest points of the holding loop at the full extension of the tether shall not exceed 50cm. Each tether shall be measured in the Call Room at its full extension when the tether is not being worn.

b) The holding loops shall not incorporate any mechanism that allows the loops to open. The holding loops may incorporate a locking mechanism, which can be easily operated by the athlete and that allows the size of the loops to be adjusted and locked. This adjustable locking mechanism shall not in any way be extended beyond the two fixed spherical stoppers and shall not shorten the middle section. The middle section shall be a minimum of 10cm in length and shall be measured at its full extension from the closest points of the two spherical stoppers. The middle section shall be of a distinctive colour and be distinguishable from a distance to the rest of the tether. The stoppers shall be sphere-shaped (or spherical) and a minimum of 1cm in diameter.




Figure 3 – Tether features

COMMENT: The above Figure 3 shows the minimum and maximum length that must be observed and respected at all times during the races for Track and Road Events. The Call Room Judges will conduct the appropriate inspection and will ensure that the length of the tether complies with the above Rule 6.15.1 and Rule 6.15.4.

6.16 Non-compliance on equipment

6.16.1 An athlete (and in the case of a relay, their team) may be excluded from participation in any event in which their competition equipment (i.e., racing chairs, Running frames, throwing frames, prosthetic device(s), helmets, tethers and eye masks) is not compliant with the rules. In such circumstances, the Call Room Referee (or other appropriate referee) must issue the athlete

6.15.4 テザーは、伸縮性のない材質で作られ、何らかの力を蓄えたり競技者が利益を得るようなものであってはならない。テザーは、2つの握り用の輪と、各端部に2つの固定された1cm幅のストッパーを有する中間部分とからなる。

a) トラック種目では、テザーを最も伸ばした状態における握り用の輪の両端の間の最大長は30cm以下とする。道路競技では、テザーを最も伸ばした状態における握り用の輪の両端の間の最大長は50cm以下とする。テザーは、装着されていないときに、最も伸ばした状態で招集所にて測定されなければならない。

b) 握り用の輪は、輪を解くことができるような構造を組み込んではならない。握り用の輪には、競技者が簡単な操作で、輪のサイズを調節して固定することができる構造を組み込むことができる。この調節可能なロック構造は、2つの固定された球状ストッパーを超えて拡張されてはならず、中間部分を短くしてはならない。中間部の長さは10cm以上とし、完全に伸ばした状態で、2つの球状ストッパーの最も近い点の間で測定しなければならない。中間部分は、際立った色とし、テザーの残り部分の距離が明確に判別できるようにする。ストッパーは、球状（または球形）で直径1cm以上でなければならない。

コメント：上の図3は、トラック及び道路競技のレース中に常に遵守されなければならない最小と最大の長さを示している。招集所の審判員は適切な検査を行い、テザーの長さが上記規則6.15.1及び規則6.15.4に準拠していることを確認する。

6.16 器具の不適合

6.16.1 競技器具（レース用車いす、ランニングフレーム、投てき台、義手/義足、テザー、アイマスク等）が規則に適合していない場合、その競技者（リレーの場合はそのチーム）はその競技会のどの種目からも除外されることがある。その場合、招集所審判長（または担当審判長）はイエローカードで警告する。

6.16 器具の不適合

with a yellow card. 6.16.2 If the athlete is able to make the necessary adjustments to ensure compliance with the rules or is able to obtain the missing equipment (e.g. borrowing a tether from the LOC), prior to the scheduled exit from the Call Room, they shall be permitted to compete, but the yellow card awarded will stand. No event shall be delayed while an athlete makes adjustments to their equipment. 6.16.3 If an athlete fails to comply with this Rule, then the athlete (and in the case of a relay, their team) will not be permitted to start the event and they (and in the case of a relay, their team) shall be shown in the results as "DNS". A reference shall be made in the official results to the Rule that has been infringed (for example, DNS + YC 6.12.2). In such circumstances, the athlete shall not be excluded from participation in further events of the competition under Rule 5.5. 6.16.4 If the athlete's equipment is non-compliant for any subsequent event, then they shall also be excluded from that event. In such circumstances, the Call Room Referee (or other appropriate referee) shall show the athlete a second yellow card followed immediately by a red card and in such circumstances the athlete shall be excluded from participation in further events of the competition. 6.16.5 The provisions of this Rule 6.16 relating to the issuing of a yellow card and/or red card by the appropriate Referee will also apply in circumstances where an athlete, having started or completed an event, is subsequently disqualified from that event for having competed using non-compliant equipment. COMMENT: Under such circumstances where the athlete's equipment is non-compliant with the rules and in order to be consistent with the application of the rules, it is recommended that the Call Room Referee keep a written record of the yellow and red cards that have been issued. 6.17 Helmets Helmets for Sport Classes T31-34, T51-54 and T71-72. 6.17.1 The wearing of helmets is compulsory in all track and road Wheelchair races and Frame Running races. The helmet shall be a hard-protective shell that has a recognised international safety standard e.g.: Snell b-84/90/95, BSI 6863, EN 1078. 6.17.2 If an athlete arrives at the Call Room and a) does not have a helmet, or b) the helmet is not in compliance with Rule 6.17.1, Rule 6.16 shall apply. 6.17.3 The helmet must be worn from the time the athlete leaves the Call Room until the end of the race. Any athlete who removes their helmet during this time, shall, for a first offence in that Competition, be warned by the Referee in	6.16.2 規則に適合させるため、競技者が招集所出発時間までに競技器具に必要な変更を加える、あるいは必要な器具を準備できた場合（例えば、LOCからテザーを借りる等）、その競技者は競技に参加できるが、イエローカードが提示される。ただし、その調整のために競技を遅らせてはならない。 6.16.3 本規則に違反した場合、その競技者（リレーの場合はそのチーム）は競技を開始することはできず、リザルトに DNS と記録され、備考として該当する規則を明記する（例：DNS + YC 6.12.2.）。その場合でも、その競技者は、規則 5.5.に則りその競技会の以降の競技から除外されることはない。 6.16.4 競技者の競技器具がその後の競技でも違反している場合は、その競技者はその種目から除外される。その場合、招集所審判長（または担当審判長）は 2 枚目のイエローカードを提示、その後、直ちにレッドカードを提示し、競技者はその競技会ではそれ以降の種目も出場できない。 6.16.5 規則 6.16 における、審判長によるイエローカード/レッドカードは、仮に競技が開始または終了した場合にも適用され、用具が適合していなかったとして失格となる。 コメント：競技者の器具が規則に適合していなかった場合、規則の一貫性を持たせるため、招集所審判長はイエローカードとレッドカードの記録をとることが推奨される。 6.17 ヘルメット 競技クラス T31-34、T51-54 及び T71-72 の競技者によるヘルメット 6.17.1 すべての車いすのトラック競技及び道路競技、またフレームランニングでは、ヘルメットの着用が義務付けられている。ヘルメットは外殻が固く、保護性に優れ、国際安全基準（スネル規格 b-84/90/95、BSI6863、EN1078 等）を満たしていなければならない。 6.17.2 競技者が招集所に、a)ヘルメットを持参していない、b)ヘルメットが規則 6.17.1 に準じていない場合は、規則 6.16 が適用される。 6.17.3 競技者は、招集所を離れる時からレース終了までヘルメットを装着していなければならない。競技中にヘルメットを外した場合、1 度目は規則 8.1.に基づき警告が与えられ、同じ競技会で 2 度目は規則 8.1.に基づき失格となる。	6.17 ヘルメット
---	---	------------------------------

accordance with Rule 8.1. For a second offence in that Competition, the Referee shall disqualify the athlete in accordance with Rule 8.1. 6.17.4 The purpose of this Rule 6.17 is to ensure the safety of all athletes while on the track and is not intended to punish the temporary removal of a helmet for genuine reasons. For example, should an athlete need to briefly adjust their helmet while stationary, this shall not require disciplinary action. COMMENT: For safety reasons, athletes covered by this Rule are advised to wear a helmet on the track at all times (i.e. including after the race.) 6.18 Urine Storage Devices Athletes must ensure that urine is not allowed to drain from storage devices such as leg bags onto the competition or warm-up areas. Failure to do so may result in disqualification Rule 7: Assistance to Athletes Medical Examinations and Assistance 1.a) Medical examination / treatment and/or physiotherapy may be provided either on the competition area itself by the official medical staff appointed by the LOC and identified by armbands, vests or similar distinctive apparel or in designated medical treatment areas outside the competition area by accredited team medical personnel specifically approved by the Medical or Technical Delegate for the purpose. In neither case shall the intervention delay the conduct of the competition or an athlete's trial in the designated order. b) Attendance or assistance by any other person, whether immediately before competition, once athletes have left the Call Room, or during competition, is assistance. c) An athlete shall retire at once from an event if ordered to do so by the Medical Delegate, the LOC Chief Medical Doctor or a medical doctor who is a member of the official medical staff, identified by armbands, vests or similar distinctive apparel. Note: The competition area, which normally also has a physical barrier, is defined for this purpose as the area where the competition is being staged and which has an access restricted to the competing athletes and to personnel authorised in accordance with the relevant Rules and Regulations. 2. Any athlete giving or receiving assistance (including under Rules 18.17, 18.18(b), and 49.8(h)) shall be warned by the Referee and advised that, if there is any repetition, they will be disqualified from that event. If an athlete is subsequently disqualified from the event, any performance accomplished up to that time in the same round of that event shall not be considered valid. However, performances accomplished in a previous round of that event shall be considered valid.	6.17.4 規則 6.17 の目的は、トラック上で競技者の安全を確保することであり、正当な理由で一時的に外すことを罰するものではない。例えば、競技者が静止している時にヘルメットを調整しても罰せられない。 コメント：安全のため、本規則が適用される競技者はトラック上では常に（レースのあとも）ヘルメットを装着していることが推奨される。 6.18 尿貯蔵装置 競技者は競技区域やウォームアップエリアで尿脚バッグ等の貯尿器から尿が漏れ出さないようにしなければならない。これを怠った場合、失格になる。 第 7 条 競技者に対する助力 医療処置と助力 7.1. a) 診察、治療、理学治療は、大会組織委員会に任命され、腕章、ベスト、その他の識別可能な服装を着用した公式の医療スタッフが競技区域内で、または、この目的のために医事代表もしくは技術代表の承認を得たチーム付き医療スタッフが競技区域外の所定の治療エリアで、行うことができる。いずれの場合においても、競技の進行や競技者の試技の順序は遅らせないものとする。 b) 他者による介助や手助けは、競技者がひとたび招集所を出た後は、競技開始前であろうと競技中であろうと、助力である。 c) 医事代表、組織委員会の主任医師または公式医療スタッフのメンバーで腕章、ベスト、その他の識別可能な服装を着用した医師によって競技の中止を命じられた競技者は、直ちに競技を中止しなければならない。 注意：競技区域は、通常、柵等で仕切られているが、上記規定の解釈上、競技が行われ、競技参加者と規則及び規程で認められた人員のみが立ち入ることのできる区域のことと定義される。 7.2. 助力を与えたり受けたりしている（規則 18.17, 18.18.(b)および 49.8(h)に従って）競技者は、審判長によって警告され、さらに助力を繰り返すとその競技者は失格になるということを勧告される。競技者がその種目から失格させられる場合、その種目のそのラウンドの記録は無効とするが、前のラウンドの記録は有効とする。	6.18 尿貯蔵装置 第 7 条 競技者に対する助力 医療処置と助力
--	--	--

Note: in cases under Rules 7.3 (a) or 7.3(f) disqualification may be made without warning. 3. For the purpose of this Rule the following examples shall be considered assistance, and are therefore not allowed: a) Save as otherwise permitted below, pacing in races by persons not participating in the same race, by athletes lapped or about to be lapped or by any kind of technical device (other than those permitted under Rule 7.4 (d)); b) Possession or use of video recorders, radios, CD, radio transmitters, mobile phones or similar devices in the competition area which have the capacity to communicate; Note: Possession or use of items specified within Rule 7.3 b) also applies to athlete's assistants and guide-runners. c) Except for devices complying with Rule 6.12, the use of any technology or appliance that provides the user with an advantage which they would not have obtained using the equipment specified in these Rules. d) Provision of advice or other support by any official of the competition not related to or required by their specific role in the competition at the time (e.g. coaching advice, the take off point in a Jumping Event except to indicate a failure in horizontal jumps, time or distance gaps in a race etc.). COMMENT: Rule 7.3(d) however makes it clear that the officials should not assist any athlete beyond what is required of their role – and specifically states as an example that officials should not provide details of the take-off position in jumping events, other than for the purpose of indicating the point of “impact” in a foul jump in Horizontal Jumps. e) Ambulant athletes who are competing from a standing position using a wheelchair to access the field of play. f) Receiving physical support from another athlete (other than helping to recover to a standing position) that assists in making forward progression in a race. COMMENT: Any physical or technological action or activity that provides an athlete with an unfair advantage is not permitted on the field of play. Any device that has the capacity to be used for communicating is prohibited from the field of play. Speedometers attached to wheelchairs that have a GPS component, may be allowed as long as communication function is not included (see Rule 7.3(b)). Call Room Judges will inspect the racing wheelchair frame as well as the helmet and athlete's ears to ensure the athlete is not in possession of any device that has the capacity to	注意：規則 7.3(a)または 7.3(f)に該当する場合は、警告なしで失格とすることができる 7.3. この規則の目的から下記については、助力とみなされ許可しない。 a) 同一レースに参加していない者によってペースを得ること、周回遅れか、周回遅れになりそうな競技者がペースメーカーとして競技すること、あるいは（規則 7.4(d)で許されたものを除いて）あらゆる種類の技術的な装置によってペースを得ること。 b) ビデオ装置、レコーダー、ラジオ、CD、トランシーバーや携帯電話もしくは類似の機器を競技区域内で所持または使用すること。 注意：規則 7.3(b)で示された物品の所持は、アシスタント及び伴走者にも適用される。 c) 規則 6.12 で認められた装具等を除き、規則で規定された用具では達成できない有利さを使用者に提供する装置の使用。 d) 当該競技に関係するしないにかかわらず、競技役員が助言またはその他の支援を提供すること（競技指導を行う、長さの跳躍種目で失敗を示す場合を除き踏切地点を示す、レースで時間や距離差を教えるなど） コメント：ただし、規則 7.3(d)は、役員が自分の役割に必要なものを超えて競技者を支援してはならないことを明確に示している。具体的には、例として、長さの跳躍競技での無効試技での踏切ポイントを示す目的を除いて、跳躍競技での踏切位置の詳細を提供してはならないことを述べている。 e) 立位姿勢で競技する立位競技者が競技場所への移動に車いすを利用すること。 f) 転倒後、他の競技者から立ち上がることを手助けしてもらう以外に、前に進むための身体的な手助けを得ること。 コメント：競技者に不当に有利な状況を提供する物理的または技術的な動作または行動は、競技エリアでは許可されていない。通信に使用する能力のあるデバイスは、競技エリアで禁止されている。GPS 機能の付いたスピードメーターは、意思疎通機能がなければ持ち込んでもよい（規則 7.3(b)）。 招集所審判員は、持ち込む機器に意思疎通機能がないことを確認するため、競技用車いすとともに、ヘルメット、競技者の耳も検査する。また、検査はいつ実施されてもよい。この規則は、競技場にいるすべての競技者とそのガイドランナー（またはアシスタント）に適用される。競技者係は、競技者とそのガイドランナー（またはアシスタント）が常にこの規則に準拠してい
---	--

communicate. Note that further inspections may be conducted at any time. This rule applies to all athletes and their guide-runners (or assistants) on the field of play. Call Room Judges are advised to always check athletes and their guide-runners (or assistants) to ensure compliance with this rule. It is also not considered appropriate for ITOs and other Technical Officials to use cell phones, cameras or other similar devices while on the field of play except for an officiating purpose. 4. The following should not be considered assistance: a) Communication between the athletes and their coaches not placed in the competition area. In order to facilitate this communication and not to disturb the staging of the competition, a place in the stands, close to the immediate site of each Field Event, should be reserved to the athletes' coaches; Note: coaches and other persons otherwise complying with Rule 49.8 may communicate with their athlete(s). b) Medical examination / treatment and/or physiotherapy necessary to enable an athlete to participate or continue participation once on the competition area under Rule 7.1. c) Any kind of personal safeguard (e.g., bandage, tape, belt, support, wrist cooler, breathing aid etc.) or device (e.g. hearing amplifier/aid) for protection and/or medical purposes. The Referee, in conjunction with the Medical Delegate and, in some cases also an International Classifier, shall have the authority to verify any case should they judge that to be desirable. (See also Rule 30.5 and Rule 34.5) d) Heart rate or speed distance monitors or stride sensors or similar devices carried or worn personally by athletes during an event, provided that such device cannot be used to communicate with any other persons. e) Viewing by athletes competing in Field Events, of images of previous trial(s), recorded on their behalf by persons not placed in the competition area (see Rule 7.1 Note). The viewing device or images taken from it must not be taken into the competition area beyond the immediate area in which those providing the recording are placed. To ensure a better view of the images, the athlete may hold the device whilst communicating with the persons who have taken the images. f) Hats, gloves, shoes, items of clothing provided to athletes at official stations or when otherwise approved by the relevant referee. g) Ambulant athletes receiving physical support to recover to a standing position or wheelchair athletes to recover to an upright position by an	ることを確認することを推奨する。 また、ITO やその他の技術関係者が、競技目的の場合を除いて、携帯電話、カメラ、またはその他の同様のデバイスを使用することは適切ではないとみなされる。 7.4. 下記については助力とはみなされず許可する。 a) 競技区域外での競技者とコーチとのコミュニケーション。コミュニケーションを容易にするとともに、競技の進行の邪魔にならないよう、フィールド競技では、競技場所に近接した観客席の一角にコーチ席を設けることが望ましい。 注意：規則 49.8 に関与しないコーチや他の関係者は、この場所から競技者とコミュニケーションを取ることができる。 b) 競技者が競技を行うため、または、すでに競技区域にいる競技者が競技を継続するために必要な、規則 7.1 に定める診察、治療、理学治療。 c) 身体保護及び/あるいは医療目的のあらゆる身体保護具（例えば：包帯・絆創膏・ベルト・支持具、冷却機能付きリストバンド、携帯用酸素ボンベ等の呼吸補助具）、または器具（例えば：補聴器）。審判長は医事代表と、また必要に応じて国際クラシファイヤーと協力して、それらが競技者に望ましい物であるかどうか、それぞれ確認をする権限を有する。（規則 30.5 及び 34.5 参照） d) 競技者本人が携帯もしくは着用して使用する心拍計、速度・距離計、ストライドセンサー、その他の類似の機器。ただし、他者との通信に使用不可能なものに限る。 e) フィールド種目に出場している競技者が、当該競技者に代わり競技区域（規則 7.1 注意参照）の外にいる者によって録画されたそれ以前の試技の映像を見ること。その録画再生機器や録画映像が撮れたエリアから競技区域内に持ち込むことは認められない。画像をより詳しく見るために、競技者は画像を撮影した人とコミュニケーションをとりながら録画再生機器を手にしても良い。 f) 指定された場所で、あるいは審判長が認めた場合に渡す帽子、手袋、靴や衣類。 g) 競技を継続するために競技役員や組織委員会により指定された者が立位の競技者が立ち上がる手助けを受ける事や車いすの競技者が起き上がるために身体的支持を受ける事、あるいは医事関係者のも
---	--

official or other person designated by the LOC, to enable them to continue on the race or to access medical assistance. h) Electronic lights or similar appliance indicating progressive times during a race, including of a relevant record. i) The use of a flag, a strobe light, other visual device or the touching of the athlete by an official to signal the start of a race (see Rule 17.2 Note). 5. WPA recognises the special needs of athletes with a hearing impairment and is keen to encourage and facilitate their participation in competition. In cases where deaf-blind athletes are competing in an event the Technical Delegate shall have the authority to make appropriate modification to these rules as may be necessary to facilitate the effective participation of those deaf-blind athletes. In principal, no rule modification that disadvantages any other athlete will be allowed. Note: No hearing aid/amplification of external cochlear implant parts containing radio transmission or reception components shall be permitted in the competition area under Rule 7.3.b. Assistance – Track and Road Events 6. Athletes shall provide their own guide-runner(s). COMMENT: The intention of this rule is to ensure compliance with the IPC Athlete Nationality Policy and to protect athletes from being adversely impacted by a guide-runner that they do not know. 7. Guide-runners for athletes in Sport Classes T11-12 shall be permitted and shall not therefore be considered assistance or pacing. Athletes in Sport Class T11 shall compete accompanied by a guide-runner for all events. Athletes in Sport Class T12 have an option of being accompanied by a guide-runner or competing by themselves. Note: The LOC shall provide distinctive vest to identify guide-runners, that shall be distributed in the call room. 8. When a T11-12 athlete starts the event with a guide-runner, the athlete and guide-runner(s) must both finish the event with bona fide effort in accord with these rules for the performance to be recognised. 7.9.1 During a race, the method of guidance between an athlete and their accompanying guide-runner shall be through a tether. In addition, the athlete may receive verbal instruction from the guide-runner. The guide-runner must complete their task while running (or walking) and is not allowed to use any mechanical means of transport.	のとまで連れていくこと。 h) 競技中に光やそれに類似する機器で、競技中の経過時間や関連する記録を知らせること。 i) 旗、ストロボなど視覚を補助する機器や、競技役員がタッチすることでスタートを知らせること（規則 17.2 参照） 7.5. WPA は聴覚障害を持つ競技者が特別な支援を必要とすることを認識しており、そのうえで、かかる競技者の競技会への参加を奨励し、支援するものである。視覚と聴覚両方に障害のある競技者が競技する場合、技術代表は、かかる競技者が実際に競技に参加できるよう、必要に応じて規則に適切な変更を加える権限を有するものとする。原則として、ほかの競技者が不利になるような規則変更は認められない。 注意：規則 7.3(b)に基づき、競技区域内における無線機能を内蔵した補聴器や人工内耳の音声拡大機能の使用は一切認められない。 助カ-トラック種目及び道路種目 7.6. 競技者は自身でガイドランナーを手配しなければならない。 コメント：この規則の目的は、IPC 競技者国籍ポリシーの遵守を確実にし、知らないガイドランナーによる競技者の悪影響から保護することである。 7.7. 競技クラス T11-12 の競技者のガイドランナーは認められており、助力やペースメーカーとは見なされない。競技クラス T11 の競技者はすべての種目でガイドランナーとともに競技しなくてはならない。T12 では、ガイドランナーを伴うか、一人で競技するかは競技者の選択である。 注意：組織委員会は招集所でガイドランナーであることが識別できるベストを提供しなければならない。 7.8. T11-12 の競技者がガイドランナーを伴って競技を開始した場合、成績が承認されるためには、競技者とガイドランナーがともに規則を守り、誠実に努力し、当該種目を完走しなければならない。 7.9.1 競技中、競技者と伴走するガイドランナーの誘導方法はテザー使用を必須とする。さらに、ガイドランナーから口頭で指示を受けてもよい。ガイドランナーは走行（または徒歩）によって任務を完了しなければならない、機械的移動手段の使用は認められない。	助カ-トラック種目及び道路種目
---	--	------------------------

7.9.2 The tether attachment shall only be established between hand(s) and/or arm(s) of the athlete and their accompanying guide-runner. The athlete and their accompanying guide runner may not hold hands, wrists or any other part of the other's body so as to make the tether superfluous. 7.9.3 The athlete and their accompanying guide-runner shall retain the tether attachment from the start of the race until the end of the race. No release shall be allowed until after the athlete and their accompanying guide-runner have both reached the vertical plane of the nearer edge of the finish line and finished the race, except during the process of interchange of guide-runners. 7.9.4 At no point during a race shall an athlete or their guide-runner(s) be permitted to hold on to a stopper and/or any part of the middle section in a way that shortens the length of the tether. 7.9.5 If an athlete and/or guide-runner fails to comply with any part of this Rule 7.9, the competing pair (the athlete and guide-runner) shall be disqualified. COMMENT: For safety reasons, in all races, the guide-runner must not release the athlete before the finish line. It is sometimes difficult to determine if a release of the tether has taken place prior to the finish line. Therefore, at the Paralympic Games and WPA Championships, if the official is in doubt, they can refer to the Video Referee or the Chief Judge Photo Finish to make a determination. 7.10.1 The guide-runner is not allowed to push, pull or otherwise propel athletes in order to gain an advantage at any stage during a race. 7.10.2 Slingshotting is regarded as a technique whereby the guide-runner deliberately hurls their arm (attached to the athlete) forward in order to exert propulsion towards the athlete's running direction. Such a technique is not permitted at any stage during a race. 7.10.3 A guide-runner may assist an athlete who has tripped or fallen to regain their footing and/or orientation as long as such assistance does not provide any advantage to the athlete towards their running direction. 7.10.4 If an athlete and/or guide-runner fail to comply with any part of this Rule 7.10, the competing pair (the athlete and guide-runner) shall be disqualified. COMMENT: It is important for ITOs and other Technical Officials assigned at Track or Road Events to watch for pushing, pulling, propelling or slingshotting. The athlete must be the one dictating the running style and cadence of the event, not the guide-runner. If the guide-runner is dictating the running style this can often be observed where an athlete has an exaggerated	7.9.2 テザーによる結束は、競技者と伴走するガイドランナーの手または腕でのみでなされるものとする。競技者とガイドランナーは、テザーを緩みがあるようにして手、手首、その他身体の一部を持つてはいけな 7.9.3 競技者と伴走するガイドランナーは、スタートからレースを終えるまで常にテザーでつながって 7.9.4 競技中、競技者またはガイドランナーは、テザーの長さを短くする目的で、ストッパー及び/または中間部のいずれの部分も持つてはならない。 7.9.5 競技者及び/またはガイドランナーが規則7.9.に違反した場合、競技している2人（競技者及びガイドランナー）は失格となる。 コメント：安全上の理由から、すべてのレースで、ガイドランナーはフィニッシュラインの前に競技者と離れてはいけな。テザーのリリースがフィニッシュラインの前に行われたかどうかを判断することが難しい場合がある。したがって、パラリンピック競技大会とWPA競技会で、審判員が疑わしいと思った場合は、ビデオ審判長または写真判定員主任を参考にして判断することができます。 7.10.1 ガイドランナーは競技中のいかなる時点においても、レースを有利に進めるために競技者を押す、引っ張る等して前進を助けてはならない。 7.10.2 スリングショットは、競技者の進行方向に推進力を働かせるために、ガイドランナーが（競技者とつながっている）腕を故意に前方に力強く振り出す技法と見なされる。このような技法の使用はレース中のいかなる時点においても許されない。 7.10.3 つまずいたり倒れた競技者に対し、ガイドランナーが足場を回復するための手助けをしたいり方向を指示することは、走る後押しとなるような利益を提供しない限りにおいては問題ない。 7.10.4 競技者及び/またはガイドランナーが規則7.10に違反した場合、競技している2人（競技者及びガイドランナー）は失格となる。 コメント：ITOやトラック種目に割り当てられた他の審判員は、プッシュ、プル、推進、スリングショットを監視することが重要である。競技者は、ガイドランナーではなく、種目のランニングスタイルとリズムを指示しなければいけな。ガイドランナーがランニングスタイルを指示している場合、これは多くの場合、競技者が不自然に見える上腕または肩の動きが誇張されている場合に見られる。多くの場合、ビデオ分析を使用せずに、押し
--	---

upper arm or shoulder movement which seems unnatural. In many cases it may be difficult to observe pushing, pulling or propelling without the use of video analysis. Slingshotting is usually easy to observe at the finish line where the guide-runner will propel the athlete forward to ensure that the athlete finishes before the guide-runner. 7.11.1 For races of 5000m or longer athletes are allowed to use two guide-runners. However, only one interchange of guide-runners is permitted for each athlete per race. The interchange must take place without any hindrance to other athletes and must take place only on the back straight in track events, or at the designated location in Road events (See Rule 49.13). 7.11.2 Should there be an interchange of guide-runners, the athlete and the substituting guide-runner must both finish the event in order for the performance to be recognised. 7.12.1 The intention to interchange guide-runners must be notified in advance to the Referee and Technical Delegate. The Technical Officials will determine the conditions of the interchange and will communicate these in advance to the athletes. 7.12.2 If the interchange does not take place after the technical arrangement being made, the athlete shall be disqualified from the race. COMMENT: Technical Officials who are assigned to Track or Road Events must watch guide-runner exchanges carefully to ensure they occur in accordance with these rules. The guide-runner exchange should be established on the back straight, or at the pre-determined designated location in road events, and a Technical Official(s) should be assigned with ensuring that the guide-runners are properly positioned on the outside of the track/course in preparation for the guide-runner exchange. The assigned Technical Official must ensure that guide-runners preparing for exchange do not interfere with other events and activities that may be occurring nearby. For example, in track events, if there is a "rail camera" on the back straight guide-runners should not be positioned between the "rail camera" and competing athletes except during actual guide exchange. The assigned Technical Official must have a copy of the exchange specifics (that is the names of the athlete(s) who intend to interchange guide-runners and the lap(s)/location that these exchanges will occur). The assigned Technical Official shall ensure all guide-runner exchanges only occur as planned. After the exchange has occurred, the outgoing guide- runner shall be escorted out of the competition area by a Technical Official or accredited volunteer. If an exchange does not occur in accordance with the above process the assigned Technical Official	たり、引いたり、推進したりすることを監察することは困難である。スリングショットは通常、競技者がガイドランナーの前に確実にフィニッシュするようにガイドランナーが競技者を前方に推進するので、フィニッシュラインで簡単に監察できる。 7.11.1 5000m 以上のレースにおいては、競技者は2名のガイドランナーをつけることができる。ただし、ガイドランナーの交代は各レースそれぞれの競技者に1回のみとする。ガイドランナーを交代させる場合は、他の競技者の邪魔にならないようトラック競技の場合はバックストレート、道路競技の場合は指定された場所で行われる（規則 49.13 参照）。 7.11.2 ガイドランナーの交代があった場合、記録が承認されるためには競技者と交代したガイドランナーが2人とも最後まで走りきらなければならない。 7.12.1 ガイドランナーを交代する場合は、審判長と技術代表に事前にその旨通知しておかなければならない。競技役員はガイドランナー交代の条件を決定し、事前にその内容を競技者に伝える。 7.12.2 ガイドランナー交代のための技術的準備が行われた後、交代が行われなかった場合、当該競技者はその種目で失格となる。 コメント：トラック及び道路競技に割り当てられた審判員は、ガイドランナーの交代がこれらの規則に従って行われるよう注意深く観察する。ガイドランナーの交代はバックストレート、道路競技の場合は事前に指定された場所で行い、審判員は、ガイドランナー交代の準備として、ガイドランナーがトラック、またはコースの外側に適切に配置する。審判員は、交代の準備をしているガイドランナーが、近くで実施している他の種目や活動を妨害しないようにする。たとえば、後方に「レールカメラ」がある場合、実際のガイド交代時を除いて、「レールカメラ」と競技者の間にガイドランナーを配置しない。 審判員は、交代の詳細（ガイドランナーを交換する競技者の名前、交代が行われる周回数及び場所）のコピーを手元に準備する。審判員は、すべてのガイドとランナーの交代が計画どおりに行われるようにする。交代が行われた後、走り終えたガイドランナーは、審判員またはボランティアによって競技エリアの外に誘導される。 上記のプロセスに従って交代が行われない場合、審判員は、競技者を失格とするかどうかの最終決定のためにトラック審判長・道路競技審判長に報告する。
---	---

shall report this to the Track Referee/Road Race Referee for final determination. That is, whether or not to disqualify the athlete. 7.13.1. Some athletes in Sports Classes T12, T20, T35-38, T40-47, T61-64 and T71-T72 may require their starting blocks to be set for them by the Starter's Assistant. The Technical Delegate or TIC shall provide such athletes, their team coach, team assistant or team leader with a form to set out their requirements. 7.13.2. Subject to Rule 7.13.2.1, the Technical Delegate may, upon written request by either the athlete, their team coach, team assistant or team leader, permit an athlete's assistant to accompany the athlete on to the field of play to set the athlete's starting block(s). The athlete's assistant shall withdraw from the field of play prior to the start of the race. 7.13.2.1. An athlete's assistant may accompany athletes in Sports Classes T71- T72 on to the field of play, to ensure the correct positioning of the athlete on the start line and/or to set the athlete's starting block(s) only. For the avoidance of doubt, no written request to the Technical Delegate is required for such assistance. The assistant shall withdraw from the field of play prior to the start of the race. 7.13.3. To ensure a safe transfer for those athletes in Sport Class T12 who do not run with a guide runner, an assistant may accompany such athletes from the Call Room up to the field of play. For the avoidance of doubt, no written request to the Technical Delegate is required for such assistance. The assistant shall withdraw from the field of play prior to the start of the race. COMMENT: Any request to a Technical Delegate in this rule requires either the athlete, their team coach, team assistant or team leader to complete the relevant request form (such as a 'request for assistance form'). Completed forms must be presented to the TIC for approval by the Technical Delegate. If approved by the Technical Delegate the approved request form must be provided by either the athlete, their team coach, team assistant or team leader to the Call Room Judges at the Call Room and subsequently taken with the athlete to the start line. Where Call Room Judges are in doubt as to whether or not a request has been approved, they must immediately seek clarification from the Technical Delegate. Assistance - Field Events 14. Assistants for athletes in Sport Classes F31-33 and F51-54 will be permitted (one assistant per athlete per event) who can assist the athlete under the control and supervision of the Officials to ensure the athlete transfers safely to the throwing frame and assist athletes to strap into their throwing frame.	7.13.1 競技クラス T12、T20、T35-38、T40-47、T61-64 及び T71-T72 の一部の競技者は、出発係によるスターティングブロックの設置を要請することができる。技術代表または TIC は、必要と思われる競技者やその競技者の所属チームのコーチ、チームのアシスタントまたはチームリーダーに要請内容記入用紙を配布する。 7.13.2. 規則 7.13.2.1 に従い技術代表は、競技者、チームコーチチームアシスタントまたはチームリーダーから書面による要請に基き、競技者のアシスタントが競技者に同行して競技エリアに入り、競技者のスターティングブロックを設置することを許可することができる。競技者のアシスタントはレース開始前に競技エリア内から退去しなければならない。 7.13.2.1. T71-72の競技者のアシスタントは、スタート地点に赴き、スタートラインおよび/またはスターティングブロックが正しく設置されていることを確認するためだけに競技区域に入ることができる。念のために申し添えるが、このような補助については、技術代表への書面による申請は不要である。アシスタントはレース開始前に競技エリア内から退去しなくてはならない。 7.13.3 ガイドランナーを伴わない T12 の競技者は安全な移動を保証するために、招集所から競技エリアまでアシスタントが競技者と一緒に競技エリアに入ることができる。念のために申し添えるが、このような補助については、技術代表への書面による申請は不要である。アシスタントはレース開始前に競技エリア内から退去しなくてはならない。 コメント：技術代表へのリクエストについてこの規則では、競技者、チームコーチ、そのアシスタントまたはチームリーダーいずれかの人が関連するリクエストフォーム（「アシスタントリクエストフォーム」など）に記入する必要がある。完成したフォームは、技術代表の承認を得るために TIC に提出する。技術代表によって承認された場合、承認されたリクエストフォームは、競技者、チームコーチ、アシスタント、またはチームリーダーのいずれかの人が招集所の競技者係に提供され、その後、競技者と一緒にスタート地点に運ばれる。競技者係が、リクエストが承認されたかどうかについて疑問がある場合は、技術代表にすぐに説明を求める。 助力 - フィールド種目 7.14. 競技クラス F31-33 及び F51-54 の競技者はアシスタント（各競技者 1 種目につき 1 名）をつけることが認められる。アシスタントは、競技役員の指示と監督のもとで、競技者が安全に投てき台に移動できるよう競技者と競技役員を手助けをしたり、競技者の身体を投てき台に固定する手伝いをしたりできる。	
--	---	--

Note (i): Strapping must be only to the frame with non-elastic material. Note (ii): If an assistant is required, the assistant shall be physically capable of transferring and strapping their athlete to and from the throwing frame. Technical Officials, accredited volunteers, and other personnel are not permitted to assist with transferring and/or strapping athletes to or from their throwing frame. If an assistant is unable to provide such assistance, additional assistance may be permitted by another accredited member of the athlete's team, provided a request for such additional assistance is submitted in advance and approved by the Technical Delegate. Note(iii): After the athlete has been transferred to the throwing frame and strapping is completed, the assistant must withdraw from the throwing circle and the cage before each attempt, including warm-up trials, begin. Note(iv): The LOC shall provide distinctive vests to identify the assistants, that shall be distributed in the call room. COMMENT: In Paralympic Games and WPA Championships (see Part B – 3.1.2 (a) and (b)), the Referee may require the assistant(s) to withdraw from the field of play and be seated outside of the field of play while the athlete is not competing. Prior to the time that the assistant's athlete is about to compete and as the Referee reasonably considers necessary, the assistant may be enabled to prepare the athlete for competition. In WPA Recognised Competitions, other than those referred to in Part B 3.1.2 (a) and (b), the assistant may be permitted to administer water/refreshment to their athlete during the break between their third and fourth trials. Once that assistant's athlete has finished competing, the assistant shall again withdraw from the competition area. It is important to note assistants are only permitted for athletes in Sport Classes F31-33 and F51-54. If an athlete in different Sport Class requires assistance that athlete must complete a request for assistance form and submit this to the Technical Delegate for approval at least 24 hours prior to the event. Assistance is only permitted if the Technical Delegate approves the request. 7.15. In competitions other than those mentioned below the assistant must withdraw from the competition area once they have completed these tasks and must follow any directives from officials of the event while they are in the competition area. At Paralympic Games, WPA Championships and WPA Sanctioned Competitions must withdraw to a holding area once they have completed these tasks and must follow any directives from officials of the event while they are in the field of play.	注意(i): 投てき台への固定は、非伸縮性の材質でできたストラップを用いる。 注意(ii): アシスタントを伴う場合、そのアシスタントは競技者を投てき台にまたは投てき台からの移動、競技者を固定する手伝いができる者でなければならない。競技役員、承認されたボランティア、その他の者は、投てき台への/からの移動、競技者の固定の手助けは許可されていない。もし、その対応ができないアシスタントの場合、競技者のチームの他の承認されたメンバーによる追加の手助けを技術代表に事前に申請し承認された場合に限り許可される。 注意(iii): 競技者を投てき台に移動させ固定が終了したらアシスタントは各試技や練習試技が始まる前にサークルや囲いから離れなければならない。 注意(iv): 組織委員会は、アシスタントが識別できるようにピブスを招集所で配布しなければならない。 コメント: パラリンピック及び WPA 競技会 (PART-B 規則 3.1.2(a)及び(b)参照) において、競技者が競技をしていない間、審判長はアシスタントに対して競技エリアから離れ、競技エリア以外の場所に移動することを要請することができる。競技者が試技をしようとする前で、審判長が適切で必要と判断した場合、アシスタントは競技者が競技をするための準備の手助けをすることができる。PART-B 規則 3.1.2(a)及び(b)以外の WPA 競技会では、水や飲食物を提供するため、3 回目と 4 回目の試技の間にアシスタントの同行が認められる。試技が終了したら、アシスタントは FOP から離れなければならない。 アシスタントは競技クラス F31-33 及び F51-54 の競技者にのみ許可されていることを理解することは重要である。別の競技クラスの競技者がサポートを必要とする場合、競技者はサポートフォームのリクエストを記入し、イベントの少なくとも 24 時間前に技術代表に提出して承認を受ける必要がある。技術代表がリクエストを承認した場合のみ、サポートが許可される。 7.15. 下記に記述されている競技会以外ではアシスタントは上記手助けを終了次第、競技区域から離れなければならない。競技区域内においては、その種目の競技役員の指示に従わなければならない。 パラリンピック大会、WPA 世界選手権及び WPA 認定競技会ではアシスタントは手助け終了次第、指定エリアに移動し競技区域にいる間はその種目の競技役員の指示に従わなければならない。
---	---

16. For athletes in Sport Classes F11 and F12 one assistant may bring athletes to the throwing circle, the cage or Javelin runway. The assistant may assist the athlete by orientating them with the throwing circle or on the Javelin runway before each attempt. The assistant must leave the throwing circle or Javelin runway before each attempt begins. Once the athlete is oriented, the assistant may also provide acoustic orientation before, during and after each attempt. Athletes may only be escorted from the throwing circle or Javelin runway after the officials have determined whether or not the attempt was a valid one. Note: If the official in charge of the event decides that an assistant who is providing acoustic orientation is in an unsafe location then the official has the right to require the assistant to move. 17. For athletes in Sports Class T11 acoustic assistance is permitted during Long Jump, Triple Jump and High Jump. However, no visual modification to the existing facility is permitted. In events where acoustic assistance is being used complete silence shall be requested from spectators. Note: Whenever possible, to ensure silence, events in which acoustic assistance is being utilised should not be timetabled together with other running events. COMMENT: Often these events are scheduled at the beginning of a session where the fewest number of spectators are in the stadium. It is important that the sports presentation team, including the announcer are carefully observing the event to ensure the sports presentation does not disrupt the concentration of athletes and their assistants during the event. 18. During Jump Events athletes in Sports Classes T11 can be accompanied onto the field of play by two assistants to: a) act as a caller to provide acoustic orientation during the approach run in High Jump, Long Jump and Triple Jump, and/or; b) act as an escort to assist the athlete by positioning and orientating them on the runway before each attempt. Note (i): Acoustic orientation is permitted before, during and after each attempt. Once an attempt has begun, only acoustic orientation is allowed by the assistant(s) until after the officials have determined whether or not the attempt was a valid one. Note (ii): The assistant(s) may be positioned on or beside the Long or Triple Jump runway or behind the landing area. The assistant(s) may be in front of or behind the take-off area but shall not stand in the take-off area (powdered area) or landing area.	7.16. 競技クラス F11 及び F12 の競技者は、1 名のアシスタントが投てきサークル、囲いまたはやり投の助走路まで誘導することができる。そのアシスタントは各試技の前に投てきサークルまたはやり投の助走路に対する競技者の位置決めを助けることができる。アシスタントは試技が始まる前に投てきサークルまたはやり投の助走路を離れなければならない。競技者の位置が定まった後、そのアシスタントは、音響による方向指示を、各試技の前、最中、後に行うことができる。投てきサークルまたはやり投げの助走路からの競技者（に触れて）の誘導は、試技が有効か否かの判定を役員が下すまで（すなわち競技者が自身で 1 歩踏み出すまで）行ってはならない。 注意：担当の種目役員は、音響による方向指示を行うアシスタントが危険な場所にいと判断した場合、移動するよう要請する権利を有する。 7.17. 競技クラス T11 の競技者は、走幅跳、三段跳、走高跳種目の競技中に音響補助の使用が認められる。ただし、既存の設備に視覚的変更を加えることは一切認められない。音響補助が使用されている種目においては、観客に静粛を求めるものとする。 注意：静寂な状態が確保されるよう、音響補助が使用される種目は可能な限り他の走競技種目と同時進行にならないようにすべきである。 コメント：多くの場合、これらの種目は、スタジアムにいる観客の数が最も少ないセッションの開始時にスケジュールされる。アナウンサーを含むスポーツプレゼンテーションチームは競技を注意深く観察し、競技中にスポーツプレゼンテーションが競技者とそのアシスタントの集中を妨げないようにすることが重要である。 7.18. 競技クラス T11 の跳躍種目において、競技者は次の 2 名のアシスタントを競技区域に同伴することができる。 a) 走高跳、走幅跳、三段跳で助走時に音響による方向指示を行うコーラー役 b) 各試技の前に助走路で競技者の位置決めと方向づけを行うエスコート役 注意(i)：音響による方向指示は各試技の前後及び最中に行うことができる。試技が開始されたなら、試技が有効か否かの判定を役員が下すまでは、音響による方向指示のみが許される。(触れてはいけない) 注意(ii)：アシスタントは、走幅跳や三段跳の助走路上や脇、また砂場の後ろに位置してよい。アシスタントは、助走路上の踏切エリア前後に位置してよいが、踏切エリア(パウダー)の中や砂場に立ってはならない。
---	---

Note: (iii) The assistant(s) must not stand in a position that hinders the view of Officials nor run along-side or behind the athlete during an attempt. COMMENT: Athletes and their assistants may not physically touch each other until the Chief Judge has indicated that they may do so. This is normally after the attempt has been completed and the athlete has left the throwing circle, runway or landing area and the Chief Judge has raised the appropriate flag. 19. For athletes in Sports Class T/F12 visual modification of the existing facility is permitted during Field Events (i.e., Paint, chalk, powder, cones, flags, etc) at the discretion of the Technical Delegate. Acoustic signals may also be used. 20. For athletes in Sports Class T12, only one assistant is allowed to accompany the athlete onto the field of play to act as caller and/or escort in Jumping Events. The assistant shall observe Rule 7.18. 21. In Field Events, the assistant shall not conduct other than permitted under Rule 7.14 to 7.20. If the official in charge of the event decides that an assistant is in breach of these rules (e.g., coaching in competition area), the athlete and their assistant(s) shall be warned by the Referee and advised that, if there is any repetition, the athlete will be disqualified from that event subject to Rule 7.2. Note: The LOC shall arrange separate waiting areas for athletes and their assistants. 22. Some athletes in Sports Classes T/F20, T/F35-38, T/F42-47 and T/F61-64 may require their runway markers to be at a pre-set distance from the take-off board. In this case, prior to the competition, the markers shall be set with assistance from a Field Judge. This would also apply in the javelin. The Technical Delegate will provide the appropriate athletes and/or their team coach with a document on which to show their requirements. COMMENT: A request for information form is required to be completed by a responsible NPC official to outline their requirements prior to assistance being granted by the Technical Delegate. The Technical Delegate may approve assistance by the specified assistant of an athlete or, by a Field Judge. The determination will be made by the Technical Delegate to ensure there are no more people on the field of play than is absolutely necessary. Animals 23. No animals shall be brought into the competition area, including guide, medical assistance, emotional support or any other animals subject to special certification.	注意(iii) : アシスタントは、競技役員の視界を妨げるような位置に立つてはならず、また競技中に競技者と一緒に、あるいは競技者の後ろを走ってはならない。 コメント : 競技者とそのアシスタントは、審判員主任がそうすることができると指示するまで、物理的にお互いに触れてはならない。これは通常、試技が完了し、競技者が投てきサークル、助走路または着地エリアを離れ、審判員主任が適切な旗を掲げた後である。 7.19. 競技クラス T/F12 の競技者は、技術代表の裁量によってフィールド種目で既存の設備に視覚的変更（塗装、チョーク、パウダー、コーン、旗等）を加えることができる。音響による合図も使用できる。 7.20. 競技クラス T12 の競技者は跳躍種目でコーラー、エスコート、またはその両方の役割を果たす 1 名のアシスタントのみ、競技区域に同伴することができる。アシスタントは規則 7.18 を遵守しなくてはならない。 7.21. フィールド種目において、アシスタントは規則 7.14 から 7.20 で認められる行為以外のことを行ってはならない。アシスタントが規則に違反している（競技区域内で指導する等）と担当役員が判断した場合、競技者と同伴のアシスタントは、審判長より警告を受け、違反が繰り返された場合は規則 7.2 に従い、当該競技者は当該種目で失格となることが伝えられる。 注意 : 組織委員会は、競技者とそのアシスタントに別々の待機場所を用意する。 7.22. 競技クラス T/F20、T/F35-38、T/F42-47 及び T/F61-64 の競技者の中には、踏切板から一定距離の位置にマーカーを設置する必要のある競技者がいる可能性がある。その場合、マーカーは競技前にフィールド審判員の助けを得て設置するものとする。これはやり投げにも適用される。技術代表は、必要と思われる競技者やその競技者の所属チームのコーチに要請内容記入用紙を配布する。 コメント : 技術代表からの支援を受ける前に、NPC の責任者が情報を要求して、要件の概要を説明する必要がある。技術代表は、競技者の指定されたアシスタントまたはフィールド審判員による支援を承認することができる。決定は技術代表によって行われ、フィールドに絶対に必要な人数以上の人がいないことを確認する。 介助動物 7.23. 介助、医療補助、精神的サポート、その他の対象となるいかなる動物も競技区域内への立ち入りは一切認められない。
---	---

Rule 8: Warnings and Disqualification Bona Fide Participation, Unsporting and Improper Conduct 1. Athletes and relay teams shall participate in competitions in a bona fide manner and shall not engage in unsporting or improper conduct. Any athlete or relay team failing to comply with this Rule or the relevant technical regulations for that competition may be warned or disqualified. The applicable Referee shall have authority to warn or exclude from competition, any athlete or relay team guilty of breaches of this Rule or Rules 5.4, 6, 7, 17.5, 18.17, 18.18, 24.2, 24.5, 24.19 or 49.8(h)). Warnings may be indicated to the athlete by showing a yellow card, exclusion by showing a red card. Warnings and exclusions shall be entered on the result card and communicated to the Competition Secretary and to the other Referees. In respect of the application of this Rule 8, the Call Room Referee has authority starting from the Warm-up Area up to the competition area. In all other instances, the Referee applicable to the event in which the athlete is or was competing, shall have authority. The applicable Referee (where practicable after consulting the Competition Director) may warn or remove any other person from the competition area (or other area related to the competition including the Warm-up Area, Call Room and coaches seating) who is acting in an unsporting or improper manner or who is providing assistance to athletes that is not permitted by the Rules. Note (i): The Referee may, where the circumstances justify it; exclude an athlete or relay team without a warning having been given (See also Note to Rule 7.2). Note (ii): When excluding an athlete or relay team from competition under this Rule, if the Referee is aware that a yellow card has already been given, should show a second yellow card followed immediately by a red card. Note (iii): If a yellow card is given and the Referee is not aware that a previous yellow card was issued to that athlete or relay team at the competition, it shall, once this is known, have the same consequence as if it was a red card. The relevant Referee shall take immediate action to advise the athlete or relay team or their team of their exclusion. Note(iv): If a yellow and/or red card is issued to a guide-runner or an assistant for unsporting or improper conduct, then the yellow and/or red card issued is also deemed to have been issued to their respective athlete. COMMENT: The below Six key points are made to provide guidance and clarity in relation to the way in which cards are shown and recorded:	第 8 条 警告及び失格 誠実に力を尽くしての参加、反スポーツマンシップ行為及び不適切な行為 8. 1. 競技者およびリレーチームは、誠実に力を尽くして陸上競技会に参加しなければならず、反スポーツマンシップ行為や不適切な行為を行ってはならない。当該規則またはその競技会に関連する規則に従わない競技者およびリレーチームは、警告を受けるか失格となる場合がある。 審判長は、当該規則または、規則 5.4, 6, 7, 17.5, 18.17, 18.18, 24.2, 24.5, 24.19, 49.8(h)に違反があった競技者やリレーチームに警告を与えたり、当該競技会から除外したりする権限を持つ。警告はイエローカード、除外はレッドカードを示すことによって競技者に知らせる。警告や除外の事実は記録用紙に記入する。審判長が警告および除外処分を行った場合は、そのことを記録・情報処理員および他の審判長に知らせなくてはならない。 規則 8 の運用に関して、招集所審判長はウォーミングアップ場から競技場所に至るまでの権限を有する。その他の場合も含め、審判長は競技中だけでなく、競技を終えた後にも担当した種目について権限を持つ。 当該審判長は競技場所（ウォーミングアップエリアや招集所、コーチ席など競技に関連する場所）において、ふさわしくない行為や不適切な行為をしたり、競技者に規則で許可されていない助力を行ったりした場合、（競技会ディレクターに相談の上）警告を与え、除外することができる。 注意（i）：審判長は十分な根拠のある状況では、警告なしで競技者やリレーチームを除外する事ができる。〔参照 規則 7.2〔注意〕〕 注意（ii）：本条に基づき当該競技者やリレーチームを当該競技から除外する場合には、すでにイエローカードで警告が与えられている競技者に対しては、審判長は二枚目のイエローカードを示した後、直ちにレッドカードを提示する。 注意（iii）：審判長がすでに出されたイエローカードを認識しておらず、イエローカードによる警告を提示した場合、その後、二度目の警告である事実が判明した時点で、レッドカードを提示したのと同じ結果となる。審判長は、直ちに当該競技者やリレーチーム、もしくは所属チームに対して除外通知を行わなければならない。 注意(iv): ガイドランナーまたはアシスタントがスポーツマンシップに反する行為や不適切な行為を行ってイエロー及びまたはレッドカードが提示されたならば、関連する競技者にイエローまたは及びレッドカードが提示されたとみなす。 コメント：カードが示され記録される方法に関連して、以下の 6 通りガイドラインを示し、明確化する。	介 助 動 物 第 8 条 警告及び失格 誠実に力を尽くしての参加 反スポーツマンシップ行為及び不適切な行為
--	---	--

(1) Yellow and red cards can be given either for disciplinary reasons (refer mostly to this Rule) or for certain technical infringements that are disciplinary in nature. (2) Whilst it is normal and usually expected that a yellow card would have been given before a red card, it is envisaged that in the cases of particularly bad unsporting or improper behaviour or failing to participate in a bona fide manner, a red card can be given immediately. It should be noted that the athlete has in any case the opportunity to appeal such a decision to the Jury of Appeal. (3) There will be also some cases in which it is not practical or logical for a yellow card to have been issued. For example, the Note to Rule 7.2 specifically allows for an immediate red card if justified in cases covered by Rule 7.3(a) such as pacing in races. (4) A similar situation might also follow when a Referee issues a yellow card and the athlete or relay team responds in such an inappropriate manner that it is justified to then immediately give a red card. It is not essential for there to be two completely different and distinct in time instances of inappropriate behaviour. (5) As per Note (iii), in cases where a Referee is aware that the athlete or relay team in question has already received a yellow card during the competition and he proposes to issue a red card, the Referee should first show a second yellow card and then the red card. However, if a Referee does not show the second yellow card, it will not invalidate the issuing of the red card. (6) In cases where a Referee is not aware of a pre-existing yellow card, and they show only a yellow card, once this becomes known, the appropriate steps should be taken to disqualify the athlete as soon as possible. Normally, this would be done by the Referee advising the athlete directly or through their team. (7) In cases of relay events, cards received by one or more members of the team during any round of the event shall count against the team. Therefore, if one athlete receives two cards or two different athletes receive a yellow card in any round of the particular event, the team shall be regarded as having received a red card and shall be disqualified. Disqualification resulting from an infringement of a Technical Rule (other than Rule 8.1) 2. If an athlete is disqualified from an event for an infringement of a Technical Rule (except under Rule 8.1) any performance accomplished in the same round of that event up to the time of the disqualification shall not be valid. However, performances accomplished in a previous round of that event or other previous events shall	(1) イエローカードとレッドカードは、懲戒処分（主に当該規則を参照）だけでなく、懲戒的と考えられる性質を持つ特定の規則違反のいずれかで与えられることができる。 (2) レッドカードの前に、イエローカードが出されているのが一般的であり通常想定されることであるが、特に悪質な反スポーツ的または不適切な行為、または誠実な態度で競技に参加しなかった場合には、即時に（イエローカードなしで）レッドカードを出すことができる。この場合、競技者あるいはリレーチームは、かかる決定を Jury に上訴する機会が与えられていることを忘れてはならない。 (3) イエローカードを出すことが現実的でなく、さらに論理的でない場合もある。たとえば、規則 7.2 の注意は、レース中のペースングがあったなど規則 7.3 (a) に該当することが明確に証明されれば、即、レッドカードを出すことが特に認められる。 (4) 審判長がイエローカードを出した際に、競技者あるいはリレーチームが不適切な態度で応答したことで、即時にレッドカードを出す事が正当である場合、前項と同様に、即、レッドカードという状況になることもある。短時間の中で不適切な振舞いが続いた際に、それぞれに異なる事由をつける必要はない。 (5) 注意(iii)により、競技者あるいはリレーチームがその競技会中にすでにイエローカードを出されており、次に出されるカードがレッドカードとなることを審判長が認識している場合には、審判長は最初に 2 枚目のイエローカード、その後、レッドカードの提示をする。しかし、審判長が 2 枚目のイエローカードを表示しない場合であっても、レッドカードの提示は無効とはならない。 (6) 審判長がすでに出されたイエローカードを認識しておらず、イエローカードのみを表示した場合は、この事実が判明して時点で、できるだけ早くその競技者を失格させるための適切な措置を講じる。通常、これは審判長が直接競技者本人に、またはチームを通じて競技者に通告することによって行われる。 (7) リレー競技では当該競技会のどのラウンドであっても、一人または複数のチームメンバーが受けたカードは、チームに対して示されたものとしてカウントする。このため、もし、リレーに出場している一人の競技者がリレー競技の予選、決勝等のラウンドで 2 枚目のイエローカードを示されたのなら、当該リレーチームはレッドカードを示されたことになり、失格となる。 競技規則違反による失格（規則 8.1 非適用時） 8.2. 競技者が競技規則（規則 8.1 の適用を除き）に違反をして失格させられれば、その種目の同じラウンドで達成した記録は無効とする。しかし、前のラウンドまたは他の種目の記録は有効とする。この違反による失格は、その競技会でのその後の参加を妨げるものではない。
---	---

remain valid. Such disqualification from an event shall not prevent an athlete from taking part in any further event in that competition. Disqualification resulting from exclusion under Rule 8.1 3. If an athlete is excluded from competition under Rule 8.1, they shall be disqualified from that event. If the athlete's second warning occurs in a different event, they shall be disqualified only from the second event. Any performance accomplished in the same round of that event up to the time of the disqualification shall not be valid. However, performances accomplished in a previous round of that event or other previous events shall remain valid. Such disqualification shall prevent an athlete from taking part in all further events or rounds of events (including other events in which they are simultaneously participating and relays) in that competition. 4. When a relay team is excluded from competition under Rule 8.1, it shall be disqualified from that event. Performances accomplished in a previous round of that event shall remain valid. If the disqualification of the relay team was the consequence of (an) athlete(s) acting in a manner that would lead to a disqualification under Rule 8.1 if competing in an individual event, Rule 8.3 will be applicable to such athlete(s). Otherwise, such disqualification shall not prevent any athlete or relay of that team taking part in any other event(s) in that competition. Nothing shall prohibit the Referee taking action against an individual in accordance with Rule 8.1 and also taking action against that athlete's relay team in accordance with the same Rule, in relation to the same or a linked incident. 5. If the offence is considered serious, the Competition Director shall report it to WPA for consideration of further disciplinary action. COMMENT: Rule 8.3 shall be applied to an athlete whose second warning in the competition incurred in the relay race, or who had a direct exclusion in the relay race that led to the disqualification of the team. Rule 9: Competing Outside Sport Class – Eligibility In accordance with the IPC Classification Code, and general principles of classification, athletes will generally compete against athletes with the same Sport Class. The competition entry, qualification and/or eligibility documentation for Recognised Competitions may identify events where more than one Sports Classes are eligible to compete together. At the Paralympic Games and WPA Championships (see Part B - 3.1.2 (a) and (b)), the grouping of the Sport Classes shall in principle be in accordance with the Classification	規則 8.1 による除外となった結果による失格 8.3. 規則 8.1 に基づいて競技会から除外された競技者は、その種目で失格となる。2 度目の警告が別の種目で出た場合は 2 度目の種目で失格となる。その種目の同じラウンドで達成した記録は無効とする。しかし、前のラウンドまでの記録、またはそれまでに出場した他の種目の記録は有効とする。こうした失格により、同時参加している他の種目及びリレー種目を含めて、その競技会における以後のすべての種目やラウンドから除外される。 8.4. リレーチームが規則 8.1 により競技から除外処分を受けた場合、そのチームはそのリレー種目では失格としなければならない。除外処分を受ける前のラウンドまでの記録は有効となる。リレーチームの失格が規則 8.1 による競技者個人の行為の結果である場合、規則 8.3 が当該競技者に適用される。それ以外の場合、かかる失格は、競技者やリレーチームがその競技会の他の種目へ出場することを妨げるものではない。 但し、その競技者の 1 つまたは複数の行動が極めて悪質だと見なされる場合は、当該競技者に規則 8.1 を適用し、警告を与えたり競技会から除外したりすることができる。 8.5. 違反が重大であるとみなされた場合は、競技会ディレクターは不適格行為として W P A に報告しなければならない。 コメント：規則 8.3 はリレー競技中に 2 回目の警告を受けた競技者、また、リレー競技で当該チームの失格につながる除外を直接受けた競技者にも適用される。 第 9 条 競技クラス外での競技-参加資格 IPC クラス分け規程（IPC Classification Code）』及びクラス分け一般原則に従い、競技者は一般的に同じ競技クラスに属する競技者と競う。 認可競技会の参加申請、参加資格、参加資格基準に関する書類に、複数の競技クラスに属する競技者が一緒に競技できる種目を明記することができる。 パラリンピック競技大会及び WPA 競技会（PART-B 規則 3.1.2(a)及び(b)参照）における競技クラスのグループ分けは、原則として、付録 2 のクラス分け表に基づくものとする。	競技規則違反による失格（規則 8.1 非適用時） 規則 8.1 による除外となった結果による失格 第 9 条 競技クラス外での競技-参加資格
--	---	---

Hierarchy Table(s) in Appendix 2. This rule will not apply to Recognised Competitions taking place after the adoption of this version of WPA Rules and Regulations where entry criteria have been committed to prior to the date of adoption. Where more than one Sports Class competes together in Track and Field Events the WPA (Raza) Points System may be used to determine placings (as shall be determined by the LOC and the TD, depending on whether the event is organised as a 'single class event' or a 'combined class event'). When using the Raza Points System, the numbers after the decimal place should be rounded down. E.g. 1000.501 and 1000.499 would both be 1000pts. Only in the case of a tie would the numbers after the decimal place be considered. In exceptional and limited circumstances WPA shall be entitled to permit the grouping of Sport Classes that do not satisfy the Classification Hierarchy Table(s) in Appendix 2. Rule 10: Surveying and Measurements 1. The accuracy of the markings and installations for athletics facilities under Rules 3, 11.2, 11.3 and 39 shall be checked by an appropriately qualified surveyor who shall furnish appropriate certificates together with details of any check measurements made to the relevant body and/or the facility owner or operator. They shall be given full access to stadium plans and drawings and the latest measurement report for the purpose of this verification. 2. For Track and Field Events in the Paralympic Games and WPA Championships (see Part B - 3.1.2 (a) and (b)) all measurements shall be made with a calibrated certified steel tape or bar or with a scientific measuring device. The steel tape, bar or scientific measuring device shall be manufactured and calibrated according to international standards. The accuracy of the measuring equipment used in the competition shall have been verified by an appropriate organisation accredited by the national measurement authority. Other than at the Paralympic Games and WPA Championships (see Part B - 3.1.2 (a) and (b)) fiberglass tapes may also be used. Note: Concerning acceptance of World and/or Regional Records, see Rule 51.19.a. COMMENT: It should be noted that when the electronic measurement equipment is obviously not working properly all measurements need to be made using a calibrated steel tape or bar. Rule 11: Validity of Performances 1. No performance accomplished by an athlete will be valid unless it is accomplished at a WPA Recognised Competition (see Part B - 3.1.2). 2. Performances in events normally conducted in the stadium, made outside traditional athletics	この版の WPA 規則及び規程が採用された後に開催される許可競技会であっても、参加要件が採用日より前に決まっていた場合は、本規則は適用しない。 トラック種目およびフィールド種目で複数の競技クラスと一緒に競う場合は、WPA(Raza)ポイント方式で順位を決定することができる（ラザポイント方式採用の決定は、「単一競技クラス種目」と「複数競技クラス混合種目」のいずれとして行うかによって、大会組織委員会または技術代表が行うものとする）。ラザポイント方式を採用する場合、小数点以下の数字は切り捨てとなり、例えば、1,000.501 点と 1,000.499 点はいずれも 1,000 点として扱う。小数点以下の数字は、同点となった場合のみ、考慮する。 例外的かつ限定的な状況において、WPA は、上記及び付録 2 のクラス分け表に基づかない競技クラスのグループ分けを行う権限を有するものとする。 第 10 条 測量(検定)と計測 10.1. マークの正確性、及び規則 3、11.2, 11.3 及び規則 39 の設備の配置状況は、有資格測量者によって、計測の詳細と関連する組織・団体あるいは設備の所有者ないし運営者に対して提出された適切な検査済証とともにチェックされなければならない。この測量者は本目的のために、競技場の設計図や図面、最新の計測証明書などすべての情報にアクセスできるものとする。 10.2. パラリンピック競技大会及び WPA 競技会（PART-B 規則 3.1.2(a)及び(b)参照）における競技会のトラック及びフィールド競技の計測は、正しく目盛りが設定された鋼鉄製巻尺または高度計または科学計測装置で行われる。これらの計測機器は国際基準に従って製造され、正しく調整されたものでなければならない。競技会で使用される計測装置の精密度は、国の測定機関によって承認された適切な組織によって認証されていること パラリンピック競技大会及び WPA 競技会（PART-B 規則 3.1.2(a)及び(b)以外の競技会では、ファイバーグラス製巻尺を使用してもよい。 注意：世界記録及び/または地域記録の公認については規則 51.19.a を参照 コメント：電子測定機器が明らかに正しく機能していない場合、すべての測定は、校正済みのスチールテープまたはバーを使用して行う必要があることに注意すること 第 11 条 記録の有効性 11.1. 競技者の記録は、WPA による認可競技会（PART-B 規則 3.1.2 参照）で達成されたものでなければ有効としない。 11.2. 通常、競技場内で実施される種目の記録が、一般的な陸上競技場以外（例えば街角の広	第 10 条 測量（検定）と計測
--	--	---

facilities (such as those held on a temporary facility in town squares, other sporting facilities, beaches, etc.) or on a temporary facility built within a stadium shall be valid and recognised for all purposes, if they are made subject to all of the following conditions: a) the relevant governing body as provided in Part B – 3. has issued a permit for the event; b) a qualified panel of National Technical Officials are appointed to and officiate at the event; c) where applicable, equipment and implements in conformity with the Rules are used; and d) the event is conducted in a competition area or facility in conformity with the Rules and in respect of which a survey has been made in accordance with Rule 10 on the day of the event. COMMENT: When a competition described in under Rule 11.2 is held over more than one day, the survey should be made on the day of the first event. In either case if the surveyor can be satisfied that there will be no movement of or alteration to the facilities being surveyed, the survey may be completed up to two days prior to the day of the first event. 3. Performances in events conducted indoors or in an otherwise fully or partly covered venue where the length or other specifications of the facility do not comply with the rules for indoor competition shall be valid and recognised as if they were achieved outdoors on a 400m standard oval track, if they are made subject to all of the following conditions: a) the relevant governing body as provided in Part B – 3. has issued a permit for the event; b) a qualified panel of National Technical Officials are appointed to and officiate at the event; c) where applicable, equipment and implements in conformity with the Rules are used; d) in the case of an oval track, its length is greater than 201.2m (220 yards) but no greater than 400m; and e) the event is conducted in a competition area or facility in conformity with the Rules and in respect of which, if held on a temporary facility, a survey has been made in accordance with Rule 10. 4. Performances made in accordance with these Rules in Qualification Rounds, in deciding ties in High Jump, in any event or part of an event which is subsequently decreed void under the provisions of Rule 2.13.7, 18.1, 24.20 or 50.4b, will normally be regarded as valid for purposes such as statistics, records, rankings and the achievement of entry standards.	場、他のスポーツ施設、砂浜等に作られた仮設の施設）や競技場内に一時的に作られた施設で達成された場合は下記すべての条件を満たしていれば、すべての目的で認められる。 a) PART-B 規則 3 に規定されている統括団体が開催許可を出していること b) その競技に公認審判員が委嘱され、審判員によって審判運営がされていること c) 必要に応じて規則に合致した用器具が用いられていること d) その競技は競技規則に合致し、競技会当日に規則 10 に基づく計測が行われた競技場所や施設であること コメント：規則 11.2 に記載された競技会が 1 日以上にわたって開催される場合、最初の種目実施日までに検定を実施する必要がある。いずれの場合でも、検定員が検定対象の施設に変更の動きがないことを確認できる場合、検定は最初の種目実施日の 2 日前までに完了することができる。 11.3. 施設の長さやその他の仕様が室内競技規則に準拠していない、屋内や完全または部分的に屋内となる会場で行われる競技の記録は有効であり、以下のすべての条件を満たす場合には、室内記録としてではなく 4 0 0 m の楕円形のトラックであり屋外で実施される競技の記録として扱う。 a) PART-B 規則 3 に規定されている競技団体が競技会の開催を公認していること b) NTO（公認審判員）が指名され、当該競技会の審判にあたっていること c) 規則に準拠した機器や用器具が使用されていること d) 楕円形のトラックの 1 周が 201.2m（220 ヤード）より長く、400mを超えていないこと e) 規則に適合した競技エリアや競技施設で行われ、一時的に作られた仮設施設で行われる場合には、規則 10 に従って測量と計測が行われていること 11.4. 予選ラウンドで達成した記録、走り高跳の同順位、規則 2.13.7、18.1、24.20、または 50.4b の各規定により全部または一部で無効になった競技は規則に従って行われていれば、通常、統計、最高記録、ランキングや参加標準記録といった目的では有効なものとして扱われる。	第 11 条 記録の有効性
--	--	-----------------------------

COMMENT: When a result is achieved on a complying facility with no advantage gained and all related rules observed, the fact that it happened at a covered competition site does not prevent a result being listed among the outdoor equivalent distances and used for any statistical purpose (performances e.g. on covered 400m tracks and straights).

Rule 12: Video Recording

In the Paralympic Games and WPA Championships (see Part B - 3.1.2 (a) and (b)) and, whenever possible, in other competitions, an official video recording of all events to the satisfaction of the Technical Delegate(s) shall be made. It should be sufficient to demonstrate the accuracy of performances and any violation of the Rules, including the WPA Classification Rules and Regulations.

COMMENT: The appointment at any competition of a video Referee will significantly affect the practical oversight of many aspects of those competitions at which sufficient video collection and replay systems are available. The video Referee will generally be able to act proactively in respect of the track events (e.g., the start, running inside the lane line around the curve, jostling and obstruction, breaking from lanes too early, relay changeovers). If the amount of cameras and equipment is sufficient to play a similar role for some or all of the field events, they can undertake a similar role, but usually in a more reactive fashion when the on-field Referee requests further examination or review of a specific incident. In the case of the Track Events, the Video Referee will observe the races on one or more screens in the video room and then based on either their own observations or upon referral from a Referee or Chief Umpire in the competition area, examine one or more particular issues by looking at any replayed footage that might be available. If it is clear as a result that there has been an infringement of the Rules, then they should take the appropriate decision and convey it to the Track Referee and the Chief Photo Finish Judge. Similarly, if an umpire or Referee has reported a potential infringement, it should be checked by the video Referee and the appropriate advice provided and decision taken. In addition, official video footage will as in the past continue to be used to assist in dealing with protests and appeals. It is becoming common for experienced companies to provide an existing service for competitions rather than the LOC setting up their own. However, either option can be used.

Rule 13: Scoring

In a match where the result is to be determined by the scoring of points, the method of scoring shall be set out in the entry and eligibility documentation.

Rule 14: Wheelchair and Frame Running Requirements

(Sport Classes T32-34, T51-54 and T71-72)

コメント：規則に適合し、競技者に利点となるものは何もない施設において、関連するすべての規則に従って達成された記録は、同じ種目であれば、屋根付きの競技場で達成された記録（例：屋根付き 400mトラックや直走路で行われる競技の記録）であっても、屋外競技場で達成された記録と同じリストに記載され、統計目的で使用されることを妨げない。

第12条 ビデオ記録

パラリンピック及び WPA 競技会（PART-B 規則 3.1.2(a)及び(b)参照）及び、できるならば、その他の競技会においても、すべての種目において、技術代表が納得する形で、公式のビデオ撮影を行うものとする。ビデオ記録は、WPA クラス分け規則及び規程を含めて、競技内容の正確性と規則違反が立証できるものでなくてはならない。

コメント：ビデオ審判長の競技会での任命は、十分なビデオ収集及び再生システムが利用可能な競技会では、多くの場面で実際の監視に大きな影響がある。ビデオ審判長は、一般的に、トラック種目（例えば、スタート、曲走路の内側レーンへの入り込み、妨害や侵害、レーンからの早期離脱、リレーの引き継ぎなど）に関して積極的に行動することができる。フィールド種目の一部または全部について同様の役割を果たすのに十分な数のカメラと機器があれば、ビデオ審判長は、トラック同様の役割を担うことができるが、通常は、フィールドの現場にいる審判長からの特定の案件についての画像確認要請に対応する。


トラック種目の場合、ビデオ審判長は、ビデオルームにある1つまたは複数のスクリーンでレースを監察し、自分の所見に基づいて、または競技エリアにいる審判長や監察員主任からの照会に基づいて、利用可能な再生された画像を見て、特定の事案を解決する。その結果、規則違反が明らかな場合は、適切な決定を下したうえで、その決定内容をトラック審判長と写真判定員主任に報告しなければならない。同様に、監察員またはトラック審判長が規則違反の可能性を報告している場合は、ビデオ審判長によって確認され、適切な助言と決定がなされる。さらに、公式ビデオ映像は、これまでと同様に、抗議や上訴を扱うためにも使用される。近年では、組織委員会(LOC)が独自のシステムを手配するのではなく、経験豊富な会社が、競技会向けに構築された既存サービスを提供することが一般的になりつつある。ただしどちらの選択肢を使ってもよい。

第13条 得点

点数制によって順位を決定する競技会においての採点方法は、申し込み、及び参加資格に関する書面に記載されなければならない。

第14条 車いす及びフレームランニングに関する要件

(競技クラス T32-34、T51-54 及び T71-72)

1. General Wheelchair Requirements: a) At all WPA Recognised Competitions (see Part B - 3.1.2) the wheelchair shall have two (2) large rear wheels and one (1) small front wheel. b) All wheelchairs must have a functional braking system for safety purposes. c) No mechanical gears or levers are allowed for the purpose of propelling the wheelchair. d) The use of mirrors is not permitted in wheelchair track or road races. e) In all races the athlete must be able to turn the front wheel(s) manually left and right from straight-ahead tracking for steering purposes. Only hand operated mechanical steering devices are allowed. f) The use of fairings or similar devices for the purpose of improving aerodynamic performance is not permitted. g) No element of the wheelchair or its attachments or accessories may incorporate energy storing capacity (e.g., elasticity) for the purpose of enhancing performance. h) Devices attached to the wheelchair or athlete shall comply with Rule 7.4d (assistance) and shall not have the capability to communicate except to the athlete. Note: Unless approved by WPA and the Technical Delegate, no devices with transmission function for the purpose of event presentation or broadcasting shall be permitted at WPA Recognised Competitions. 2. Wheelchair Frame Requirements: a) No part of the frame of the wheelchair, or any attachments to it, (nor any part of the athlete's lower body including legs, ankles, and feet) shall extend forward beyond the hub of the front wheel nor backwards beyond the rearmost vertical plane of the rear wheels (including tyres). Additionally, the width of the frame, and any of its attachments, shall not be wider than the inclined plane of the pushing rims (as outlined in Figure 4).  Figure 4 – Inclined plane of the pushing rims	14.1. 車いすの要件全般 a) WPA 認可競技会 (PART-B 規則 3.1.2 参照) では、大輪 2 つ・小輪 1 つの車いすを使用するものとする。 b) すべての車いすは、安全の目的から、機能的な (制動制御) ブレーキシステムを備えていなくてはならない。 c) 車いすを推進するための機械的なギアやレバーの使用は一切認められない。 d) 車いすのトラック競技や道路競技でミラーの使用は認められない。 e) すべての競走競技において、競技者は手動で直進の状態から前輪を左右に操作できなければならない。機械的操舵装置は手で操作するもののみ認められる f) 車いす競技者の空気抵抗を低減するフェアリング等の使用は認められない。 g) 車いすの本体またはその付属物品または付属品は、性能を向上させる目的でエネルギー貯蔵能力 (例えば、伸縮性) を組み込むことができない。 h) 車いすまたは競技者に取り付けられる装置は、規則第 7.4d (助力) に準拠しなければならず、競技者が他者と通信する機能を持たないものとする。 注意：WPA 及び技術代表の承認がない限り、WPA 認可競技会では、イベントプレゼンテーションまたはテレビ放送の目的での送信機能を備えた装置使用は認められない。 14.2. 車いすフレームの要件 a) 車いすのフレームまたはその付属品の一部 (競技者の下半身、脚、足首、足を含む) は、前輪のバブを超えて前方に伸びたり、後輪 (タイヤを含む) の最後の垂直面を越えて後方に伸びてはならない。さらに、フレームの幅とその取り付け部分は、プッシュリムの傾斜面よりも広くなってはならない。(図 4 に概要を示す)。	第 13 条 得点 第 14 条 車いす及びフレームランニングに関する要件 14.1. 車いすの要件全般 14.2. 車いすフレームの要件
--	--	---

COMMENT: Call Room Judges will inspect all wheelchairs to ensure no attachments are outside of the inclined plane of the pushing rims. b) The maximum height from the ground to the bottom of the wheelchair frame shall be 50 cm. c) The frame structure must be made of a material which provides sufficient stability and stiffness for safety purposes. d) For the purpose of seat positioning, the athlete must ensure that their lower limb(s) are supported by a seat, a sling or foot tray. e) The use of Sideguards may be added to protect the athlete from the wheels and shall be in compliance with Rule 14.2 (a). 3. Wheel and Push-rim Requirements: a) The maximum diameter of the large wheel including the inflated tyre shall not exceed 70 cm. b) The maximum diameter of the small wheel including the inflated tyre shall not exceed 50 cm. c) Only one plain, round, push-rim is allowed for each large wheel. Note (i): This rule also applies for persons requiring a single arm drive wheelchair. Note (ii): For T32/33/51/52 athletes who may experience a limitation in their ability to stabilise the wrist during pushing, a modification shall be allowed so that a push-rim and wheel disk may be fused together and incorporated into the racing wheel. No other modification that would defeat the general intent of Rule 14.3 is allowed. Note (iii): No part of the athlete's body shall be strapped to the push-rim or to the wheel. Note (iv): All athletes competing in racing wheelchairs must only propel their racing chair through the pushing action exerted by the athletes' arm(s). The lower extremities (legs and feet), or any relevant prosthesis, are not permitted to touch the ground so as to propel the racing chair or stabilise it at the start. 4. Wheelchairs will be measured and inspected in the Call Room and once inspected shall not be taken from the competition area before the start of the event. Wheelchairs may be reexamined by the relevant Referee or other officials before or after the event on or off the field of play. 5. It is the responsibility of athletes to ensure that their wheelchair conforms to the requirements stipulated above. No event shall be delayed while an athlete makes adjustments to their wheelchair. If an athlete fails to comply with this Rule, then the athlete will not be permitted to start the event and shall be shown in the	コメント：招集所審判員は、すべての車いすを検査し、プッシュリムの傾斜面の外側にいかなる付属品もないことを確認しなければならない。 b) 車いすフレーム底部の地面からの高さは、50cm 以内とする。 c) フレーム構造は、安全のため、十分な安定性と強度を提供する材料で作られなければならない。 d) シートの位置決めのために、競技者は下肢がシート、スリングまたはフットトレイで支えられていなければならない。 e) 競技者を車輪から保護するために、サイドガードの使用を追加することができるが、規則 14.2 (a) に合致していなくてはならない。 14.3. 車輪及びプッシュリムの要件 a) 大輪の最大直径は、空気を充填したタイヤを含めて 70cm 以下とする。 b) 小輪の最大直径は、空気を充填したタイヤを含めて 50cm 以下とする。 c) プッシュリムは、特殊仕様ではない平らな円形のを各大輪に 1 つずつつけることができる。 注意(i)：この規則は、片腕で車いすを操作する競技者にも適用される。 注意(ii)：T32/33/51/52 クラスの競技者の場合、押しているとき手首を安定させる力が制限されるため、プッシュリムとホイールディスクを結合して組み込むことができるように改造を許可するものとする。規則 14.3 の一般的な主旨に反する改造は一切許されない。 注意(iii)：競技者のいかなる身体の部分もプッシュリムや車輪に縛り付けられてはならない。 注意(iv)：車いす競走競技に出場するすべての競技者は、競技者の腕が押す動作を介してのみ推進しなければならない。下肢（脚と足）または関連する人工装具は、競技用車いすを推進したり、開始時に安定させるために地面に触れることは許可されない。 14.4. 車いすは招集所で測定・検査され、検査された車いすは競技開始前に競技区域外に持ち出してはならない。競技開始前または競技開始後に、また競技場の中でも外でも、当該審判長もしくは他の競技役員が車いすの再検査を行う場合がある。 14.5. 上記の要件を満たす車いすを準備するのは競技者の責任である。競技者による車いすの調整で競技の開始が遅れることがあってはならない。競技者がこの規則に反した場合、スタートを許可されず、規則 6.21 に従ってリザルトに「DNS」と表示される。	14.3. 車輪及びプッシュリムの要件
--	--	-----------------------------------

results as “DNS” in accordance with Rule 6.16. 6. If the Relevant Referee believes that a wheelchair and/or the athlete using it represent a safety risk they shall be authorised to exclude the athlete and/or wheelchair from an event. Note (i): For safety, athletes should secure their lower limb(s) so they do not fall to the ground and cause injury. Note (ii): For safety, no part of the athlete’s lower body (including legs, ankles, and feet) shall extend beyond the rearmost vertical plane of the rear wheels (including tyres). COMMENT: It is important to note that there can be no devices attached to the wheelchair that can communicate or anything that gives the athlete any unfair advantage over other athletes in the event. Wheelchairs are measured and inspected in the Call Room, however for major competitions such as World Championships, Paralympic Games and Regional Games a courtesy pre-check of the racing wheelchairs for conformity should be conducted, including a check against the relevant advertising regulations of the competition. What to look for when checking a wheelchair for conformance to current requirements. It is advisable to use a stick or metre stick with marks at 50cm and 70cm as these are the two key dimensions of importance. Measure the wheel diameter by placing the “0” end of the measuring stick on the ground beside the wheel and measure parallel to the wheel. The diameter of the smaller wheel must not exceed 50cm while the diameter of the larger wheel(s) must not exceed 70cm. If the tyres are not inflated, they can still be checked, but advice given to the athlete or coach could include that it has not yet passed pre-check but will be checked again in the Call Room in any event. The same measuring stick can be used to ensure that the maximum height from the ground to the bottom of the wheelchair does not exceed a height of 50cm. While there is no issue with the overall length of the wheelchair, no part may extend beyond the wheel(s) in the front or rear of the wheels. The best way to measure for this is to move the chair to a wall. Wheel the chair backwards toward the wall; if the tyres touch the wall rather than the seating frame, then the chair is acceptable. The chair may also have other requirements, such as having a braking system and steering capacity which also need to be checked at the pre-check. Call Room Judges shall ensure that the racing wheelchair does not have any device on it which can “communicate” to anyone, other than the athlete, in accordance with Rule 14.1 (h). Regardless of whether a wheelchair is checked as	14.6. 当該審判長は、車いすまたは車いす競技者によって安全が脅かされるリスクがあると判断した場合、その競技者を除外する権限を有するものとする。 注意(i):安全のため、競技者は、競技中に地面に下肢のいかなる部分も接触しないようにまた怪我の原因とならないようにしなければならない。 注意(ii):安全のため、競技者のいかなる下半身、（脚、足首、足を含む）は、後輪（タイヤを含む）の最後の垂直面を超えてはならない。 コメント：車いすに取り付けられた通信可能な機器や、競技中に競技者が他の競技者に対して不当な優位性を与えるもの等がないかどうか注意する必要がある。 車いすは招集所で測定及び検査されるが、世界選手権、パラリンピック、地域競技大会などの主要競技会では、競技会独自の広告規程に対するチェックを含め、競技用車いすの適合性が遵守されるよう、より丁寧な事前確認を行う必要がある。 現在の要件への適合について車いすをチェックするときには準備しておくもの。50cm と 70cm のマークがスティックまたはメータースティックを使用することを推奨する。これらは重要な 2 つの主要な寸法であるため。ホイールの横の地面に測定スティックの「0」側を置いてホイールの直径を測定し、ホイールと平行に測定する。 小さいホイールの直径は 50cm を超えてはならず、大きいホイールの直径は 70cm を超えてはならない。タイヤが膨らんでいない場合でもチェックできるが、事前チェックに合格していないことが、競技者またはコーチに助言され、招集所で再度チェックされる。同じ測定棒を使用して、地面から車いすの底までの最大高さが 50cm を超えないようにすることができる。 車いすの全長に制限はないが、ホイールの前部または後部でホイールを超えてパーツが伸びることはない。これを測定する最良の方法は、椅子を壁に向かって後方に動かす。タイヤが座席フレームではなく壁に接触する場合は、その椅子は、問題がない。椅子には、ブレーキシステムとステアリング能力、その他の事前チェックが必要である。 競技者係は、規則 14.1 (h) に従って、競技者の車いすに、競技者が他者との誰かと「通信」できる装置がないことを確認する。車いすが事前チェックを受けているかどうかに関係なく、車いすは招集所で、競技者がチェアにいる状態でチェックする必要がある。 車いすの事前チェックに関与する ITO 及び他の技術担当者は、この規則と招集所で車いすをチェックする要件に完全に精通している必要があることに注意すること。	
---	---	--

part of a pre-check, it must be checked in the Call Room and with the athlete in the chair. It should be noted that ITOs as well as other Technical Officials involved in a pre-check of wheelchairs need to be completely familiar with this rule as well as the requirement to check the wheelchairs in the Call Room.

COMMENT: At competitions without a warm-up track or where the warm-up track is either not available or not of the same radius of the competition track, the Technical Delegate may consider permitting a single warm-up lap (It may not be a complete lap) for athletes in classes T32-34 and T51-T54 competing in 200m races and above to set their wheelchair compensators, provided that this does not create conflicts or significantly impact the competition schedule.

Frame Running Requirements

(Sport Classes T71-72)

7. General Frame Running Requirements:

- a) At all WPA Recognised Competitions (see Part B - 3.1.2) the Running frame shall have a support saddle, a body support plate, handlebars, two (2) rear wheels and one (1) front wheel.
- b) All Running frames must have a functional braking system for safety purposes.
- c) No mechanical gears or levers are allowed for the purpose of propelling the Running frame.
- d) The use of mirrors is not permitted in Frame Running events.
- e) In all races the athlete must be able to turn the front wheel left and right for steering purposes. Only hand operated mechanical steering handlebars are allowed.
- f) The use of fairings or similar devices for the purpose of improving aerodynamic performance of the athlete is not permitted.
- g) No element of the Running frame or its attachments accessories may incorporate energy storing capacity (e.g., elasticity) for the purpose of enhancing performance.
- h) Devices attached to the Running frame or athlete shall comply with Rule 7.4 (d) (assistance) and shall not have the capability to communicate except to the athlete.

Note: Unless approved by WPA and the Technical Delegate, no devices with transmission function for the purpose of event presentation or broadcasting shall be permitted at WPA Recognised Competition.

8. Running Frame Requirements:

- a) No part of the Running frame, or any attachments to it, shall extend forward beyond

コメント：ウォームアップトラックが無い競技会やウォームアップトラックが使用できない場合や、競技トラックと同じ半径ではないトラックの場合、技術代表は、200m以上のレースに出場するT32-34及びT51-54クラスの競技者が機械的操舵装置を設定するため、競技日程に重大な影響がない限りにおいて（競技用トラックでの）ウォームアップラップ（完全な周回でない場合もある）を許すことができる。

フレームランニングの要件

(競技クラス T71-72)

14.7. フレームランニングの一般的要件:

- a) WPA 認可競技会（PART-B 規則 3.1.2 参照）では、ランニングフレームには、サポートサドル、ボディサポートプレート、ハンドルバー、2つの後輪及び1つの前輪が含まれていなければならない（PART-B 規則 3.1.2を参照）。
- b) すべてのランニング用フレームは、安全の目的から、機能的な制動制御（ブレーキ）システムを備えていなくてはならない。
- c) ランニング用フレームを推進するための機械的なギアやレバーの使用は一切認められない。
- d) フレームランニング種目でのミラーの使用は認められない。
- e) すべての競走競技において、競技者は手動で前輪を左右に操作できなければならない。機械的操縦装置は手で操作するもののみ認められる。
- f) 競技者の空気抵抗を低減するフェアリング等の使用は認められない。
- g) ランニング用フレームの本体またはその付属物品または付属品は、性能を向上させる目的でエネルギー貯蔵能力（例えば、伸縮性）を組み込むことができない。
- h) ランニング用フレームまたは競技者に取り付けられる装置は、規則 7.4(d)（助力）に準拠しなければならず、競技者が他者と通信する機能を持たないものとする。

注意：WPA及び技術代表の承認がない限り、WPA認可競技会では、イベントプレゼンテーションまたはテレビ放送の目的での送信機能を備えた装置使用は認められない。

14.8. ランニング用フレームの要件:

- a) ランニング用フレーム、及び付属物のいかなる部分も前輪のハブ（車軸）より前に出てはならず、車い

the hub of the front wheel nor backwards beyond the rearmost vertical plane of the rear wheels (including tyres). Additionally, the width of the frame, and any of its attachments, shall not be wider than the length between the rear wheel hubs, excluding the rear wheels. b) The maximum length of the Running frame shall be 200cm, and the maximum width shall be 95cm including the tyres. c) The Frame structure must be made of a material which provides sufficient stability and stiffness for safety purposes. d) For the purpose of seat positioning, the Frame structure shall incorporate a saddle. e) Note: The saddle may have other shapes than the traditional type of race cycling saddle. f) For the purpose of athlete's stability, the frame structure shall incorporate a Body support plate. Note: For safety, the athlete may be strapped to the body support plate with a belt or an orthopaedic brace, to prevent the athlete from falling to the ground and causing injury. Hands may also be strapped to the handlebar. 9. Wheel Requirements: a) The maximum diameter of all wheels including the inflated tyre shall not exceed 72 cm. b) The rear wheels may incorporate a wheel guard on the inside only. 10. The Running frame shall comply with Rule 14.4 and Rule 14.6 for measurement and inspection purposes. 11. It is the responsibility of the athlete to ensure that their Running frame conforms to the requirements stipulated above. No event shall be delayed while adjustments to a Running frame are being done. If an athlete fails to comply with this Rule, then the athlete will not be permitted to start the event and shall be shown in the results as "DNS" in accordance with Rule 6.16. 12. For all athletes competing in Frame Running Events T71-72, they shall propel their Running frame with their feet and can do so forwards or backwards; SECTION III – TRACK EVENTS Rule 15: Track Measurements 1. The length of a standard running track shall be 400m. It shall consist of two parallel straights and two bends whose radii shall be equal. The inside of the track shall be bordered by a kerb of suitable material that should be coloured white, with a height of 50mm to 65mm and a width of 50mm to 250mm. The kerb on the two straights may be omitted and a white line 50mm wide substituted.	すのいかなる部分も後輪（タイヤを含む）の後端の垂直面より後方に突き出ているとはならない。加えて、フレームの幅、及びいかなる付属物も、両後輪のハブ（車軸）（後輪を除く）の内側におさまっていなければならない。 b) ランニング用フレームの長さは 200cm 以下、タイヤを含む幅は 95cm 以下とする。 c) フレーム構造は、安全のため、十分な安定性と強度を提供する材料で作られなければならない。 d) シートの位置決めのために、フレーム構造はサドルを組み込むものとする。 e) 注意：サドルは、従来のタイプの競技用サイクリングサドルとは異なる形状を有することができる。 f) 競技者の安定性のために、フレームの構造には、ボディサポートプレート(身体を支えるプレート)が組み込まれていなくてはならない。 注意：安全のために、競技者が地面に落ちて怪我をしないよう、競技者は、ベルトまたは整形外科用ブレースで、ボディサポートプレートに縛り付けてもよい。手もまたハンドルバーに縛り付けてもよい。 14.9. 車輪の要件: a) すべての車輪の最大直径は、空気を充填したタイヤを含めて 72cm 以下とする。 b) 後輪には内側に限り、車輪ガードを装着してもよい。 14.10. ランニング用フレームは、測定及び検査の目的で、規則 14.4 及び規則 14.6 に準拠していなければならない。 14.11. ランニング用フレームが上記の要件を満たしていることを確認するのは、競技者の責任である。ランニング用フレームの調整のために競技が遅延することはあってはならない。競技者がこの規則に従わない場合、スタートは許可されず、規則 6.16 に従ってリザルトに「DNS」と表示される。 14.12. T71-72 のフレームランニング種目で競技するすべての競技者について、ランニング用フレームは足で推進しなければならないが、進み方は、前向きでも後ろ向きでもかまわない。 第3部トラック競技 第15条 トラックの計測 15.1. 標準的なトラックの長さは 400mとする。トラックは平行している二つの直走路と、半径も同じとする二つの曲走路からなる。トラックの内側に適当な材質の縁石で境をする。縁石の色は可能な限り白とする。縁石は高さ 50 mm～65 mm、幅 50 mm～250 mmで縁石の色は可能な限り白とする。 2本の直走路については、縁石に替えて幅 50mmの白線でも良い。 曲走路の縁石の一部がフィールド競技のため、一時的にはずされる場合、縁石直下の場所に幅 50 mmの
---	---

If a section of the kerb on a bend has to be temporarily removed for field events, its place shall be marked with a white line 50mm in width and by cones or flags, minimum height 0.15m, placed on the white line so that the edge of the base of the cone or flag pole coincides with the edge of the white line closest to the track, and placed at intervals not exceeding 4m. (Flags shall be placed at an angle of 60° with the ground away from the track). This shall also apply to the outer half of the track in the case of starts for distance races where the field is started in two groups under Rule 17.11 and optionally to the straights, in this latter case, at intervals not exceeding 10m.

Note: All points at which the track changes from a curve to a straight or a straight to a curve shall be marked, in a distinctive colour 50mm x 50mm on the white line by the surveyor and a cone placed at such points during a race.

2. The measurement must be taken 0.3m outward from the kerb or, where no kerb exists on a bend, 0.2m from the line marking the inside of the track.




Figure 5 – Track Measurements (infield view)

3. The distance of the race shall be measured from the edge of the start line farther from the finish to the edge of the finish line nearer to the start.

4. In all races up to and including 400m, each athlete shall have a separate lane, with a width of $1.22\text{m} \pm 0.01\text{m}$, including the lane line on the right, marked by white lines 50mm in width. All lanes shall be of the same nominal width. The inner lane shall be measured as stated in Rule 15.2, but the remaining lanes shall be measured 0.2m from the outer edges of the lines.

Note: For all tracks constructed before 1 January 2004 for all such races, the lane may have a width of maximum 1.25m. However, when such a track is fully resurfaced, the lane width shall comply with this Rule.

5. In the Paralympic Games and WPA Championships (see Part B - 3.1.2 (a) and (b)) the track should allow for eight lanes minimum.

6. The lateral inclination of tracks towards the inside edge should not exceed 1:100 (1%) unless special circumstances exist which justify World Athletics providing an exemption, and the overall downward inclination in the running direction

白線を引き、高さ最低 150 mmのコーンあるいは旗を間隔 4m以内で、その底の縁がトラックにもっとも近い白線の端になるように（旗はグラウンドから 60 度の角度をなすように）置く。この方法は、規則 17.11 によるグループスタートの外側、そして縁石設置のない直走路にも適用されなくてはならない。後者の場合は間隔が 10m を超えないようにする。

注意：曲走路から直走路または直走路から曲走路にトラックから迂回する地点は、測量士によって白線上に 50mm×50mm の見分けのつく色で示され、レース中は、そこにコーンを設置しなければならない。

15.2. 計測は、縁石の外端から 0.3m 外方、そして曲走路において縁石がない場合は、ラインの外端から 0.2m のところを測る。

15.3. 競走距離は、スタートラインのフィニッシュラインに遠い方の端から、フィニッシュラインのスタートラインに近い方の端まで計測する。

15.4. 400m までのレースにおいて、各競技者は、幅 50mm の白色のラインで区切られた、右側のライン幅を含む最大幅 $1.22\text{m} \pm 0.01\text{m}$ のレーンを走らなければならない。すべてのレーンは同じ幅でなくてはならない。内側のレーンは、規則 15.2 の規定によって計測するが、その他のレーンはラインの外端から 0.2m のところで測る。

注意：2004 年 1 月 1 日以前に建造されたトラックに関しては、上記のいずれのレースでも、レーンの幅は最大 1.25m とする。しかしトラック舗装材を全面張り替えた時には、レーン幅は規則に合致させなくてはならない。

15.5. パラリンピック競技大会及び WPA 競技会 (PART-B 規則 3.1.2(a)及び(b))では、最少 8 レーンのトラックでなければならない。

15.6. トラックの内側レーン方向への最大許容傾斜度は、幅で 100 分の 1(1%)を超えないようにする。スタートラインからフィニッシュラインの間の走る方向への下りの傾斜は、どの位置であっても 1,000 分の 1(0.1%)を超えてはならない。

should not exceed 1:1000(0.1%) between any start and finish line.

Note: It is recommended that, for new tracks, the lateral inclination should be towards the inside lane.

7. Full technical information on track construction, layout and marking is contained in the World Athletics Track and Field Facilities Manual. This Rule gives basic principles only, which must be followed.

COMMENT: It should be noted that only tracks in accordance with the World Athletics Track and Field Facilities Manual should be used for World Championships and Paralympic Games.

Rule 16: Starting Blocks

1. Starting blocks may be used for sport classes T71-72 (Frame Running), T35-38, T40-47 and T61-64 in all races up to and including 400m (including the first leg of ambulant relay races of 4x100m, 4x200m and 4x400m) but shall not be used for any other race. Starting Blocks must be used for sport classes T11-13 and T20 in all races up to and including 400m (including the first leg of universal relay races). When in position on the track, no part of the starting block shall overlap the start line or extend into another lane, with the exception that, provided there is no obstruction to any other athlete, the rear part of the frame may extend beyond the outer lane line.

2. Starting blocks shall comply with the following general specifications:

a) The starting blocks shall consist of two foot plates, against which the athlete's feet are pressed in the starting position and which shall be mounted on a rigid frame. They shall be entirely rigid in construction and shall give no unfair advantage to the athlete. The frame shall in no way obstruct the athlete's feet as they leave the blocks.

b) The foot plates shall be sloped to suit the starting position of the athlete and may be flat or slightly concave. The surface of the foot plates shall accommodate the spikes in the athlete's shoes, either by using slots or recesses in the face of the foot plate or by covering the surface of the foot plate with suitable material permitting the use of spiked shoes.

c) The mounting of the foot plates on the frame may be adjustable, but it shall allow no movement during the actual start. In all cases, the foot plates shall be adjustable forward or backward in relation to each other. The adjustments shall be secured by firm clamps or a locking mechanism, which can be easily and quickly operated by the athlete.

d) They shall be fixed to the track by a number of pins or spikes, arranged to cause the minimum possible damage to the track. The arrangement shall permit the starting blocks to be quickly and

注意：新しいトラックの場合、幅の傾斜は内側のレーンの方向へ向けることが望ましい。

15.7. 競技場の建設、設計そしてマーキングに関するすべての技術的情報は、WA 陸上競技施設マニュアルに網羅されている。本規則では、守られるべき基本的な原則を示している。

コメント：世界選手権大会とパラリンピック競技大会には、WA 施設マニュアルに準拠したトラックのみを使用する必要があることに注意する。

第16条 スターティング・ブロック

16.1. 競技クラス T71-72 (フレームランニング)、T35-38、T40-47 及び T61-64 では、400m までのレース(立位の 4×100m リレー、4×200m リレー及び 4×400m リレーの第 1 走者を含む)においてはスターティング・ブロックを使用してもよいが、それ以外のレースでは使用してはならない。競技クラス T11-13 及び T20 では、400m までのレース (ユニバーサルリレーの第一走者を含む) においてはスターティング・ブロックを使用しなければならない。トラック上に設置した際、スターティング・ブロックのいかなる部分もスタートラインに重ねてはならず、その走者のレーンをはみ出してはならない。ただし、他の競技者を妨害しなければ、フレームの後部は外側レーンのラインからはみ出てもよい。

16.2. スターティングブロックは、次の一般仕様に適合したものでなければならない。

a) スターティングブロックは、競技者がスタートの態勢をとる際、足をセットする (足を押し付ける) 2 枚のフットプレートからなり、一つのフレームに固定される。これらは十分に堅固な構造で、競技者に不利益をもたらしものではない。フレームはスタート時に競技者が足を離す際に妨害するものであってはならない。

b) フットプレートは競技者のスタート姿勢に合うように傾斜がつけられ、平面またはやや凹面になっていてもよい。フットプレートの表面は競技者のスパイクシューズに適合させるように、溝もしくは窪みをつけるか、スパイクシューズの使用に耐えうる材質で覆う。

c) 堅固なフレーム上に固定されるフットプレートは調整できるものでよいが、実際にスタートする際には動くものであってはならない。どの場合もフットプレートは、それぞれ前後に動かして調節できなければならない。フットプレートは堅固な留具または錠仕掛によりしっかりと固定されなければならないが、競技者が容易にかつ速やかに操作できるものでなければならない。

d) フレームはトラックに与える損傷ができる限り僅かに済むように調整されたピンもしくは釘によって、トラックに固定しなければならない。すばやく容易に取りはずすようにしなければならない。ピンまたは釘の数、太さ、

easily removed. The number, thickness and length of pins or spikes depend on the track construction. The anchorage shall permit no movement during the actual start. e) When an athlete uses their own starting blocks, they shall comply with the above general description but otherwise may be of any design or construction, provided that they do not interfere with other athletes. Note: It is not a requirement for athletes in Sport Classes T35-38, T40-44 and T61-64 to use both foot plates when using a starting block. COMMENT: This Rule should also be interpreted so that: a) No part of the frame or footplates can overlap a starting line; b) The frame only (but not any part of the footplate) can extend into the outer lane provided there is no obstruction. This reflects the long-standing practice of athletes at the start of races on a bend placing their blocks at an angle to run the most direct line after the start. The use of lights, by deaf or hearing impaired athletes only, at the start of races is allowed and is not considered assistance. It should however be the obligation of the athlete or their team for the financing and supply of such equipment and its compatibility with the start system in use, unless at a particular meeting where there is an appointed technical partner who can provide it. 3. In the Paralympic Games and WPA Championships (see Part B - 3.1.2 (a) and (b)), performances submitted for ratification as a World/Regional Record for Sport Classes T11-13 and T20 shall require that the starting blocks be linked to a World Athletics approved Start Information System. The Start Information system shall not be activated for any other classes, even if the athlete uses blocks. 4. The LOC may insist that only starting blocks provided by them may be used. Note (i): Some athletes in Sports Classes T12, T20, T71-72 (Frame Running), T35-38, T40-47 and T61-64 may require their starting blocks to be set for them by the Starter's Assistant. Upon request, the Technical Delegate will provide the appropriate athletes and/or their team coach with a document on which they will be able to indicate their requirements (as per Rule 7.13). Note (ii): Use of personal starting blocks shall require approval from the Technical Delegate. COMMENT: It should be noted that the only classes of athletes who must use starting blocks are T11-13 and T20. For other classes they have the options of using starting blocks or other approved starting devices.	長さはトラックの構造による。スタート時に移動することのないよう十分に固定されていなくてはならない。 e) 競技者が自分のスターティング・ブロックを使用する場合はこれらの規則に適合していなければならない。他の競技者を妨害しないものであれば、デザインや構造はどのようなものでもさしつかえない。 注意：競技クラスT35-38、T40-44及びT61-64の競技者がスターティングブロックを使用する際、両方のフットプレート使用は必須条件ではない。 コメント：この規則は、以下のように解釈される： a) フレームまたはフットプレートのどの部分もスタートラインに重ならない。 b) 他への邪魔にならないことを条件に、フレームのみ（フットプレートを含んではならない）が外側のレーンに入り込んでもよい。これは、曲線でスタートする種目で競技者が走り出す角度は最短距離を取るためスターティングブロックは斜めに置かれる傾向があるというこれまでの経験による。レースのスタート時に聾者または聴覚障害のある競技者に限り、ライトの使用が許可され、助力とはみなさない。しかし、それを提供可能な技術パートナーが指定されているような競技会でない限り、資金調達及び機器の手配、さらにスタートシステムとの接続は、競技者または所属するチームの義務である。 16.3. パラリンピック競技大会及び WPA 競技会（PART-B 規則第 3 章 1. 2 (a) 及び (b) 参照）で、競技クラス T 1 1 – 1 3 及び T 2 0 の世界記録及び地域記録承認のためには、WA が認めたスタートインフォメーションシステムを使用しなくてはならない。その他のクラスにおいては、スターティングブロックを使用してもスタートインフォメーションシステムを起動させてはならない。 16.4. 組織委員会は、スターティングブロックの使用を組織委員会が用意するものに限ることができる。 注意(i)：競技クラス T12、T20、T71-72（フレームランニング）、T35-38、T40-47 及び T61-64 の一部の競技者は、出発係によるスターティングブロックの設置を要請することができる。技術代表は、（規則 7.13 に従い）必要と思われる競技者やその競技者の所属チームのコーチに要請内容記入用紙を配布する。 注意(ii)：個人のスターティングブロック使用に際しては、技術代表の許可が必要である。 コメント：スターティングブロックを使用する必要がある競技者のクラスは T11-13 と T20 だけであることに注意すること。他のクラスでは、スターティングブロックまたは他の承認されたスターティング装置を使用する選択肢がある。 単一のブロック、2 つのパーツから成るブロック、またはフ
--	---

There are some classes of athlete most notably amputees who require assistance in the form of a single block, two separate single blocks or two regular starting block rigid frames with one block on each frame. This would normally be approved by the Technical Delegate prior to the competition through the completion of a specific Request for Assistance form. In all cases, modifications of starting blocks shall not provide any additional advantage and must conform to the principles espoused in Part B – 7 of these rules.

Rule 17: The Start

Note: Unless otherwise stated, in relation to athletes in Sport Classes T11 and T12, any reference under this rule to “athlete” shall be interpreted as referring to both the athlete(s) and/or their guide-runner(s). In the event of a breach of a rule being committed by a guide-runner resulting in a warning or disqualification then the accompanying athlete shall consequently be warned or disqualified.

1. The position of the start of a race shall be denoted by a white line 50mm wide. In all races not run in lanes the start line shall be curved, so that all the athletes start the same distance from the finish. Starting positions in events at all distances shall be numbered from left to right, facing the direction of running.

Note (i): The 1500m start line, or any other curved start line, may be extended out from the outside bend lane to the extent that the same synthetic surface is available.

In all races of Sport Classes T11-13 and T20 up to and including 400m (including the first leg of ambulant relay races of 4x100m, 4x200m, 4x400m and the 4x100m universal relay), a crouch start and the use of starting blocks are compulsory.

Note (ii): A crouch start stance is not required by athletes in Sport Classes T35-38, T40-47 and T61-64.

Note(iii): It is acceptable for arm amputee athletes or those with short arms to use support pads on which to rest stumps at the start or to improve balance. Support pads may also be permitted for T61 athletes in races in which they intend to use a crouched start. Support pads must be completely behind the start line and not interfere with any other athlete.

COMMENT: It is anticipated that, in order to efficiently complete the start procedures and for larger meetings to appropriately introduce the competitors in the race the athletes, when assembled, should be positioned facing in the direction of the race.

2. All races shall normally be started by the report of the Starter’s gun fired upwards after they have ascertained that athletes are steady

レーンに 1 つのフットプレートしかないスターティングブロックで支援を必要とする特に切断者の競技クラスがいくつかある。これは通常、特定のリクエストフォームに記入することにより競技会の前に技術代表によって承認される。すべての場合において、スターティングブロックの設置支援は利益を提供するものではなく、これらの規則 PART-B 規則 7 で推奨される原則に準拠する必要がある。

第17条 スタート

注意：競技クラス T11 及び T12 の競技では、別途定めない限り本規定における競技者とは、競技者とガイドランナーを指す。ガイドランナーがルール違反を犯し警告を受けたり失格になった場合、結果として競技者が警告を受けたり失格したとみなされる。

17.1. スタートラインは幅 50 mmの白いラインで示す。レーンを使用しないレースでのスタートラインは、フィニッシュからの距離がどの競技者も同じになるようにカーブさせる。競走競技におけるレーン（含むオーダー）順は、走る方向に向かって左から右へ番号をつける。

注意(i)：1500m 競走及びその他の種目でスタートラインが曲線の場合、走路と同じ全天候舗装（素材・厚さ）であることを条件として、外側のレーンから外にはみ出して引くことができる。

競技クラス T11-13 及び T20 の 400m 以内の競走競技（4x100m、4x200m、4x400m と 4x100m ユニバーサルリレーの第 1 走者を含む）はすべて、スターティングブロックを使ったクラウチングスタートでなければならない。

注意(ii)：競技クラス T35-38、T40-47 及び T61-64 の競技者については、クラウチングスタート姿勢を義務付けない。

注意(iii): 上肢切断や腕が短い競技者は、スタートで切断面を支たり、バランスをとるためにサポートパッドを使用してもよい。サポートパッドは、クラウチングスタートをする競技クラス T61 競技者の使用も認められている。サポートパッドは、スタートライン手前に設置されなければならない、他の競技者の妨害になってはならない。

コメント：スタート時の手順を効率的に完了し、より大きな競技会において競技者を適切に紹介するためには、競技者は集合時、走る方向に向かって立つよう期待される。

17.2. すべての競走は、通常スターターが、すべての競技者が「用意」の構えで静止したと確認した時点で、スターターが上方に向けて構えたピストルの発射音

and in the correct starting position. If, for any reason, the Starter is not satisfied that all is ready for the start to proceed after the athletes are on their marks, they shall order all athletes to withdraw from their marks (the commands in English must be “stand up” or “wheel back”) and the Starter’s Assistants shall place them on the assembly line again. Note: If an athlete has a hearing impairment the starter or their assistant may use a flag, a strobe light or other visual device as well as a pistol to signal the start. In some circumstances, for athletes with both a vision and a hearing impairment, an official may touch an athlete to signal the start. COMMENT: The Starter must not initiate the start procedures before they are sure that the relevant timing team is ready as well as the Judges at the finish and in races up to and including 200m, the Wind Gauge Operator. The communication process between the start and the finish area and the timing team varies according to the level of the competition. At the Paralympic Games and WPA Championships (see Part B - 3.1.2 (a) and (b)) and many other high-level meetings there is invariably a service company responsible for the electronic timing and the Start Information System. In this case, there will be technicians who are responsible for communication. In other competitions a variety of communication systems are used – radios, phones, or by using flags or flashing lights. 3. The commands of the Starter must be in English only. For all races up to and including 400m (including ambulant relay races of 4x100m, 4x200m, 4x400m and the 4x100m universal relay) the command will be “On your marks” and then “Set”. When all athletes are “Set”, the gun shall be fired. An athlete shall not touch either the start line or the ground in front of it with their hands or their feet when on their marks. In races longer than 400m, the command will be “On your marks” and when all athletes are steady, the gun will be fired. In races longer than 400m athletes shall not touch the ground with their hand or hands during the start. 4. In races up to and including 400m after the “On your marks” command, an athlete shall approach the start line, assume a position completely within their allocated lane and behind the start line. For Sport Classes T11-13 and T20, both hands and at least one knee shall be in contact with the ground and both feet in contact with the foot plates of the starting blocks. At the “Set” command, an athlete shall immediately rise to their final starting position retaining the contact of the hands with the ground and of the feet with the foot plates of the blocks. In case of Wheelchair Races (classes T33-34 and T51-54), and Frame Running Events (classes T71-72) the following commands and positions are required. After the ‘On Your marks’	でスタートしなければならない。 競技者が位置についた後、何らかの理由でスターターが競技者のスタート手続きが整っていないと感じた場合、スタート位置を離れるよう競技者に命じ（英語の場合は“stand up”または“wheel back”と、指示をしなければならない）、出発係は競技者を再び定められた位置に整列させなければならない。 注意：聴覚障害を持った競技者がいる場合、スターターまたは出発係は旗、ストロボ光、その他の視覚的装置をスタート合図としてピストルと併用することができる。特定の状況においては、競技者が視覚と聴覚の両方に障害を持っている場合、役員が体に触れることでスタートの合図を行うことができる。 コメント：スターターは、決勝審判員や 200m までの種目では風力計測員さらには、関連するタイミングチームの準備ができていることを確認する前にスタート手順を開始してはならない。スタートとフィニッシュ及びタイミングチームとの間の連絡手段は、競技会のレベルによって異なる。パラリンピック競技大会及び WPA 競技会(PART-B 規則 3.1.2(a)及び(b)参照)やその他の多くのハイレベルの競技会では、常に写真判定とスタートインフォメーションシステム(SIS)を担当する提供会社が存在する。この場合、連絡調整を担当する技術者がいる。その他の競技会では、無線、電話、または旗やライトの点灯などを使用した、さまざまな連絡方法が使われている。 17.3. スターターの合図は英語のみとする。400m までの競走(4 x 100m、4 x 200m、4 x 400m 及び 4x100m ユニバーサルリレーを含む)において合図は「On your marks(お・ア・マークス：位置について)」 「Set (セット：用意)」の言葉を用いる。すべての競技者が「Set(用意)」となった時、信号器が発射される。競技者は位置についた時、スタートライン及びその前方のグラウンドに手や足を触れてはならない。400m を超える競走においては「On your marks (お・ア・マークス：位置について)」の言葉を用い、競技者が静止した時、信号機が発射される。400m を超える競走においては競技者はスタートの間、手（片手または両手）がグラウンドに触れてはならない。 17.4. 距離 400m 以内の競走競技においては、「On your marks（位置について）」の合図の後、競技者はスタートラインに進み、スタートライン手前の割り当てられたレーン内の位置につくものとする。競技クラス T11-13 及び T20 の競技者は、両手と少なくとも片方の膝を地面につき、両足がスターティングブロックの踏み板に接触していなければならない。「Set（用意）」の合図で、競技者は速やかに最終のスタート体勢に構えるものとする。その際、両手は地面に、両足はスターティングブロックの踏み板につけたままにしなければならない。 フレームランニング種目（T71-72）を含む車いす競走（T33-34 及び T51-54）の場合の合図とスタート位置は次のとおりとする。「On your marks（位置について）」の合図の後、競技者はスタートラインに進み、スタートライン手前の割り当てられたレーン内の位
--	---

command, an athlete shall approach the start line, assume a position entirely within their allocated lane and behind the start line. At the 'Set' command, an athlete should immediately take up their final starting position retaining the contact of the front wheel with the ground behind the line". COMMENT: In all races using crouch start, including Wheelchair Races and Frame Running Events, as soon as athletes are steady in their blocks or behind the line respectively, the Starter shall raise their arm in which they hold the gun, then they shall say "Set". They shall wait then for all the athletes to be steady and shall then fire the gun. The Starter must not raise their arm too early, especially when manual Timekeepers are being used. They are advised to raise their arm only when they feel they are about to give the command "Set". There is no rule that enables to determine the time that elapses between the commands "On your marks" and "Set" on one hand, and on the other hand, between the command "Set" and the gun shot. The Starter shall let the athletes go once they are all motionless in the correct starting position. Which means that they may have, for certain starts, to fire the gun quite quickly, but on the other hand, they may also have to wait longer in order to make sure that they are all steady in their starting position. 5. On the command "Set" for races up to 400m and "On your marks" for longer races all athletes shall at once and without delay assume their full and final set position. Where an athlete in the judgment of the Starter, a) After the command "Set" for races up to 400m and "On your marks" for longer races, and before the report of the gun, causes the start to be aborted, for instance by raising a hand and/or standing or sitting up in the case of a crouch start, without a valid reason, (such reason to be evaluated by the relevant Referee), or; b) Fails to comply with the commands "On your marks" or "Set" as appropriate, or does not place themselves in their final starting position after a reasonable time, or; c) After the command "On your marks" or "Set" disturbs (an)other athlete(s) in the race through sound, movement or otherwise, resulting in such athlete(s) committing what would otherwise be a false start, the Starter shall abort the start. The Referee may warn the athlete for improper conduct (disqualify in case of a second infringement of the Rule during the same competition), according to Rules 8.1 and 8.3. However, when an extraneous reason was considered to be the cause for aborting the start, or the Referee does not agree with the Starter's	置につくものとする。「Set（用意）」の合図で、競技者は速やかに最終のスタート体勢に構える。その際、車いすの前輪はスタートライン手前の地面に接触していなければならない。 コメント：クラウチングスタートによるすべてのレースでは、競技者がスターティングブロックで静止したなら、スターターは速やかにピストルを持った腕を上げ、「セット」と言う。スターターはすべての競技者が静止するのを待ってからピストルを撃つ。スターターは、特に手動計時で計時員が配置されている時は、腕をあまりにも早く上げてはならない。 スターターは、「セット」という合図をするその時になってから腕を上げるよう推奨されている。「オンユアマークス」と「セット」との間、そして「セット」と号砲との間にかかる時間を決める規則は存在しない。スターターは、全競技者の動きが正しいスタート姿勢で止まったなら速やかに走らせるべきである。つまり、あるスタートでは、ピストルを非常に早く打つこともあるし、他方、全競技者がスタート姿勢で静止するのを確かなものにするため、長めに待たなくてはならないこともあるということである。 17.5. 「On your marks（位置について）」または「Set（用意）」の合図で、競技者は、一斉にそして遅れることなく完全な最終スタート姿勢をとらなければならない。 スターターの判断において、 a) 「On your marks（位置について）」または「Set（用意）」の合図の後で、信号器発射の前に正当な理由もなく手を挙げたり、クラウチングの姿勢から立ち上がった場合（理由の正当性は審判長によって判断される）。 b) 「On your marks(位置について)」あるいは「Set(用意)」の合図に従わない、あるいは速やかに最終の用意の位置につかなかったとスターターが判断したとき。 c) 「On your marks（位置について）」あるいは「Set(用意)」の合図の後、音声や動作、その他の方法で他の競技者の妨害をし、その結果、その選手が他の競技者の不正スタートを生じさせたとき、（a～cの場合）スターターはスタートを中止する。 これら上記の場合、規則 8.1 及び 8.3 に従って審判長はスタートにおける不適切行為があったとして当該競技者に対して警告を与えることができる。同じ競技会の中で 2 度の規則違反があった場合は失格となる。 スタート中断の原因が競技者の責任でないと考えられる場合、あるいは審判長がスターターの判断に同意で
---	--

decision, a green card shall be shown to all the athletes to indicate that a false start was not committed by any athlete. COMMENT: The division of the start Rules into disciplinary matters (under Rule 17.2 and Rule 17.5) and false starts (Rules 17.7) ensures that the whole field was not penalised for the actions of a single athlete. It is important in order to maintain the integrity of the intention of this division and that Starters and Referees are as diligent in the application of Rule 17.2 and Rule 17.5 as in detecting false starts. Such conduct, whether wilful or unintentional perhaps through nervousness should cause Rule 17.2 and Rule 17.5 to be applied although where the Starter is of the view that it was unintentional, the application of Rule 17.2 only may be appropriate. Conversely, there will be instances in which an athlete is entitled to request a delay of the start for legitimate reasons. It is therefore vital that the Start Referee (in particular) pays attention to the environment and conditions surrounding the start, especially in relation to factors of which the Starter may not be aware because they are focussing on preparing themselves for the start and/or wearing headphones. In all such cases the Starter and Referee must act reasonably and efficiently and clearly indicate their decisions. If appropriate the reasons for the decisions can be announced to the athletes in the race and if possible or desirable also to the announcers, television team etc. through the communication network. A green card shall not be shown in any case when a yellow or red card has been issued. 6. In Wheelchair and Frame Running races of 800m or longer the Starter has the authority to recall a race for a restart (but is not obliged to do so) if a collision involving any athletes in the race occurs in the first 50m. This does not reduce or remove the authority of the Referee to take appropriate action on reports received from Umpires during this portion of the race. False Start 7. An athlete, after assuming a full and final starting position, shall not commence their start until after receiving the report of the gun. If, in the judgment of the Starter or Recalls, they do so any earlier, it shall be deemed a false start. When a World Athletics approved Start Information System is in use, the Starter and/or an assigned Recaller shall wear headphones in order to clearly hear the acoustic signal emitted when the System indicates a possible false start (i.e. when reaction time is less than 0.100 second). As soon as the Starter and/or an assigned Recaller hears the acoustic signal, and if the gun was fired, there shall be a recall and the Starter shall immediately examine the reaction times and any other available information from the Start Information System in order to confirm which, if any, athlete(s) is/are responsible for the recall.	きない場合は、競技者全員にグリーンカードを提示して不正スタートを犯した者がいないことを示す。 コメント：スタート規則を、懲戒事項（規則 17.2 及び 17.5）及び不正スタート（規則 17.7）に分割することにより、1 人の競技者の行為により、同組の他の競技者がとばっちりを受け処分されるといったことがないようになった。この規則の主旨の高潔性を維持するため、スターターと審判長が、規則 17.2 及び 17.5 の適用、さらには不正スタートの検出に忠実であることは重要である。 スターターが意図的ではないとの見方をし、規則 17.2 のみの適用が適切であるとするかもしれないが、意図的か、または例えば緊張に起因し故意かそうでないかにかかわらず起こりうる行為には、規則 17.2 及び 17.5 が適用されるべきである。 逆に、正当な理由により、競技者がスタートの遅れを要求する権利がある場合がある。したがって、スタート審判長は、スタートを取り巻く環境や条件、特にスターターは、スタート準備に集中しており、ヘッドフォンを着用していることもあるため、気づかないかもしれない要素に注意を払うことが重要である。 このような場合、スターターと審判長は合理的かつ効率的に行動し、意思決定を明確に示す必要がある。適切な方法としては、決定の理由は、そのレースの競技者に知らせるとともに、可能であれば、もしくは願わくば、アナウンサーやテレビチームなどにも通信ネットワークを介して通知する。 イエローカードまたはレッドカードが出された場合、グリーンカードは示してはならない。 17.6. 800m 以上の車椅子及びフレームランニング競走において、最初の 50m で競技者の衝突が起きた場合、スターターはリコール（呼び戻し）を行う権限を有する（義務ではない）。その場合でも、審判長がその間に監察員から受けた報告に基づいて適切な措置をとる権限は、リコールによって弱められたり、失われたりすることはない。 不正スタート 17.7. 競技者は、最終の用意の姿勢をとった後、信号器の発射音を聞くまでスタート動作を開始してはならない。もし、競技者が少しでも早く動作を開始したとスターターあるいはリコーラーが判断したときは不正スタートとなる。 WA が承認したスタートインフォメーションシステムが用いられているとき、スターターとリコーラーの両者またはそのいずれかが、そのシステムが不正スタート（即ち、反応時間が 0.100 秒未満の場合をいう）の可能性があることをシステムが示した時に発せられる音響をはっきり聞くためにヘッドフォンを着用しなければならない。スターターとリコーラーの両者、またはそのいずれかが、音響を聞いた瞬間、すでに出発の信号器が発射されていれば呼び戻し（リコール）しなければならない。そしてスターターはリコールの原因となった競技者がいれば、その競技者を特定するために、ただちにスタートインフォメーションシステムの反応時間及びその他入手可能な情報を確認しなければならない。	不正スタート
---	---	---------------

For the purposes of this Rule, the 'commencement of the start' is defined as follows: a) For those relevant Sport Classes where a crouch start is compulsory or optional (and the athlete elects to employ a crouch start) (see Rule 17.1 Note (ii) and Note (iii)), the commencement of the start is defined as any motion by an athlete that includes or results in one or both feet or lower limb prosthetic device(s) losing contact with the foot plate(s) of the starting blocks (or where starting blocks are not used, the ground), or one or both hands, stump(s), short arm(s) or upper limb prosthetic device(s) losing contact with the ground (or, if applicable, support pads); and b) In the case of a standing start, the commencement of the start is defined as any motion that results in one or both feet or lower limb prosthetic device(s) losing contact with the ground. If the Starter determines that prior to receiving the report of the gun, an athlete initiated a movement that was not stopped and continued into the commencement of their start (as defined above), it shall also be a false start. Note (i): When a World Athletics certified Start Information System is in operation, the evidence of this equipment shall be used as a resource by the relevant officials to assist in making a correct decision. Note (ii): Any other motion by an athlete shall not be considered to be the commencement of the start. Such instances may, if applicable, be subject to a disciplinary warning or disqualification. Note (iii): As athletes starting races in a standing position are more prone to over-balance, if such a movement is considered to be accidental, the start should be regarded as "unsteady". If an athlete is pushed or jostled over the line before the start, they should not be penalised. Any athlete causing such interference may be subject to a disciplinary warning or disqualification. COMMENT: Generally, no false start should be charged if the athlete has not lost contact with the ground or foot plates. For example, if an athlete moves their hips up, but then moves them down without their hands or feet losing contact with the ground or foot plates at any time, it should not result in a false start. It may be a reason to warn (or disqualify if there has been a previous warning) the athlete for improper conduct under Rule 17.5. However in cases of a "rolling start" where the Starter (or Recaller) is of the opinion that an athlete has effectively anticipated the start through some continuous movement even if they did not move their hands or feet before the gun sounded, the race should be recalled. This can be done by a Starter or Recaller but it will be the Starter who is in the best situation to judge such a case as only	本規則の主旨からして、スタート「開始」は、次のように定義される： a) クラウチングスタートをしなくてはならない競技クラスあるいはクラウチングスタートを選択できる競技クラス（規則 17.1 注意(ii)(iii)参照）では、スタートの開始は次のような動きとなった場合とする。片足・両足あるいは下肢義足・装具がスターティングブロックのフットプレートから離れようとしたとき（スターティングブロックを使用しない場合は地面）、あるいは両方の手、断端、短い腕あるいは上肢用義手が地面（スタート用サポートパッド）から離れようとしたとき、また： b) スタンディングでのスタート時は、スタートの開始は次のような動きとなった場合とする。片足・両足あるいは下肢義足・装具が地面から離れようとしたとき。 スターターがピストルの号砲前にこのような状況に気づいた場合、競技者が動きを止めず動きを開始した場合あるいはそのままスタートしてしまった場合（上記の記載の通りの動きを続けた場合）、不正スタートとなる。 注意(i)：承認済のスタートインフォメーションシステムが使われている場合、このシステムにより得られた証拠は、当該審判長によって正しい決定をするための一つの材料として使用される。 注意(ii)：競技者によるその他の動きは、スタートの開始とはみなさないものとする。そのような場合は、警告または失格処分の対象になる場合がある。 注意(iii)：立位（スタンディング・ポジション）でスタートする競技者の方がバランスを崩しやすいため、偶発的に動いてしまったと考えられる場合、そのスタートは「ふらつき」と見なされ不正スタートの対象として扱われるべきではない。スタート前に突いたり押されたりしてスタートラインの前に出してしまった競技者は、不正スタートとして罰せられるべきではない。そのような妨害を引き起こした競技者は、警告または失格処分の対象になる場合がある。 コメント：競技者が地面またはフットプレートとの接触を失っていない場合、一般的には、不正スタートは課されない。例えば、競技者が腰を上げたあと、手や足が地面やフットプレートとの接触を失うことなく、腰を下げるなら、不正スタートとはみなすべきではない。そのようなケースでは、規則第 17.5 に基づいて、不適切な行為として競技者に警告をあたえる（もしくは、それまでに警告があった場合は失格とする）理由となる。しかし、号砲前に、手や足を動かしてなくても、号砲のタイミングを予想し、何らかの連続的な動きで効果的にスタートしようとする「ローリングスタート」があったとスターター（またはリコーラー）が判断したなら、レースはリコール(呼び戻し)されなくてはならない。リコール(呼び戻し)はスターターまたはリコーラーによってなされるが、競技者が動き始めたとき、「ローリングスタート」の有無を判断できる最適な立場にあるのはスターターである。スターターが、号砲の前に競技者が動作を開始したと
--	---

they will know the position of their finger on the gun trigger when the athlete began their movement. In these cases where the Starter is sure that the athlete's movement began before the report of the gun, a false start should be awarded. In accordance with Note (iii) Starters and Referees should avoid being over-zealous in the application of Rule 17.7 to those events started from a standing position. Such instances are rare and usually occur unintentionally as it is easier to overbalance from a two-point start or a three-point start. It is not intended that same should be unduly penalised. If such a movement was considered to be accidental, Starters and Referees are encouraged to first consider calling the start "unsteady" and proceed according to Rule 17.2. However repeat practices during the same event may entitle the Starter and/or Referee to consider applying either the false start or disciplinary procedures, as might best be applicable in the situation. Note (iv): In practice, when one or more athletes make a false start, others are inclined to follow and, strictly speaking, any athlete who does so has also made a false start. The Starter should warn or disqualify only such athlete or athletes who, in their opinion, were responsible for the false start. This may result in more than one athlete being warned or disqualified. If the recalled or aborted start is not due to any athlete, no warnings shall be given, and a green card shall be shown to all the athletes. 8. Any athlete responsible for a false start shall be disqualified by the Starter. 9. In case of a false start, the Starter's Assistants shall proceed as follows: The athlete(s) responsible for the false start shall be disqualified and a red and black card (diagonally halved) shall be raised in front of them. If lane markers that provide for it are being used, then whenever a card is shown to the athlete(s) responsible for the false start, the corresponding indication should be shown on the lane marker(s). COMMENT: While it is the Starter who is responsible for disqualifying the athlete, the Starter's Assistant is the one to show the disqualification card to the athlete. If the athlete gives an immediate oral protest the Starter's Assistant would normally call the Start Referee over to discuss the situation with the athlete and make a decision as to allow or disallow the athlete to continue "under protest". Note: The reason for the diagonally halved cards was to provide a distinction between cards given for this purpose and those (the traditional all yellow or all red) cards given for disciplinary reasons – as each of these can be used in the start area. With this difference the reason for the card should be clearer both to the athletes as well as those observing the start, particularly	確信するなら、不正スタートが与えられるべきである。注意 (iii) に従って立位 (スタンディングポジション) でスタートする種目では、スターターと審判長は規則 17.7 の適用は過剰にならないようにする。こうした場合は、通常、両足の 2 点で支えたスタートはバランスを崩しやすいのであって、ほとんどが意図せずには発生している。従って過度に不利な処罰を与えるべきではない。このような動きが偶発的であると考えられた場合、スターターと審判長は、まずはスタートが「不安定」であるとみなし、規則 17.2 に従って対処することを推奨する。しかし、同じ組で同じことが繰り返されるなら、スターターおよび審判長は、状況に応じて不正スタートまたは懲戒手続きの適用を検討することができる。 注意(iv) : 実際は、1 人あるいはそれ以上の競技者が不正スタートをしたときには、他の競技者もそれにつられる傾向がある。厳格にいうと、それにつられたどの競技者も不正スタートとなる。スターターは、不正スタートをした責任があると判断される競技者だけに警告を与え、あるいは失格させる。従って 2 人以上の競技者が警告あるいは失格になることもある。スタートのリコールや中止した理由がどの競技者の責にも帰すべきものでなければ、警告は与えないでグリーンカードを競技者全員に見せる。 17.8. 一度の不正スタートでも責任を有する競技者は失格とする。 17.9. 不正スタートがあった場合、出発係は以下の手続きを行う。 不正スタートの責任がある競技者は失格となり、対象競技者の前で赤黒 (斜め半分形) 旗・カードを挙げる。 レーンナンバー標識が使用される場合には、不正スタートの責任を有する競技者にカードが示されたら、レーンナンバー標識にも同様の表示を行う。 コメント : 失格に対して責任を持っているのは、スターターだが、出発係が、失格カードを競技者に見せる。競技者が即座に口頭抗議を行う場合、出発係は通常、スタート審判長に連絡して競技者の状況を話し合い、競技者が「抗議中」として競技を継続することを許可または拒否するかを決定する。 注意 : 斜めに半分に分かれたカードの理由は、この目的のために与えられたカードと懲戒上の理由で与えられたそれらのカード (伝統的なオールイエローまたはオールレッド) を区別するためである。この違いにより、カードの理由は、競技者だけでなく、スタートを監察している人、特にアナウンサーやテレビやラジオのコメンテーターなどの即時情報を必要とする人の両方にとって明確になる。斜めに半分に分けたカードのサイズは A5
--	---

those in need of immediate information, such as the announcer or television or radio commentators. It is recommended that the size of the diagonally halved cards be A5 and that they be double sided. Note that the corresponding indication on the lane markers may remain yellow and red as previously, in order to avoid unnecessary expense in modifying existing equipment. 10. The Starter or any Recall Starter, who is of the opinion that the start was not a fair one, for whatever reason, shall recall the athletes by firing a gun or activating a suitable audible signal. COMMENT: The reference to a fair start does not relate solely to cases of a false start. This rule should also be interpreted as applying to other situations such as blocks slipping, a foreign object interfering with one or more athletes during a start etc. 5000m and 10,000m 11. When there are more than 12 people including athletes and their guide-runner(s) in a distance race, they may be divided into two groups for the purpose of the start. One group comprising approximately two thirds of the field shall be placed on the regular arced start line and the second group on a separate arced start line marked across the outer half of the track. The outer group shall run as far as the end of the first bend on the outer half of the track, which shall be marked by cones or flags. The separate arced start line shall be positioned in such a way that all the athletes shall run the same distance. Any athlete in the second group who fails to keep within the marked outer lanes during such a start will be disqualified on the same grounds as any athlete who runs out of their lane. The breakline for an 800m race indicates where the athletes in the second/outer group may join the athletes using the regular start in races which start at the normal (home straight) start finish line. For races that start in the back straight (200m start position) the track shall be marked at the beginning of the finish straight for group starts to indicate where athletes starting in the second/outer group may join the athletes using the regular start. This mark (breakpoint) shall be a 50mmx50mm mark on the line between lanes 4 and 5 (lanes 3 and 4 in a six-lane track) immediately before which a cone or flag is placed until the two groups converge. Rule 18: The Race Obstruction 1. If an athlete or the athlete's guide-runner is jostled or obstructed during an event so as to impede their progress, then: a) If the jostling or obstruction is considered unintentional or is caused otherwise than by an athlete or their guide-runner, the Referee may, if they are of the opinion that an athlete (or their team) was seriously affected in accordance with Rule 2.13.7, order that the race (for one, some	で、両面カードにすることを推奨する。レーンナンバー標識の対応する表示は、既存の機器の変更に不要な費用をかけないようにするために、以前と同じように黄色と赤色のままにする場合があることに注意する。 17.10. スターターもしくはリコーラーがスタートが公正に行われなかったと判断した時は、信号器を発射するか、聞き取ることのできる適切な信号音を出して、競技者を呼び戻さなければならない。 コメント：公正なスタート(フェアスタート)についての言及は、不正スタートのケースにのみ関連しているわけではない。この規則は、スターティングブロックが滑ったり、スタート時に 1 人以上の競技者に異物が干渉するなど、他の状況にも適用されると解釈されるべきである 5000m および 10000m 17.11. 該当する種目で 1 回のレースに競技者とガイドランナーあわせて 12 人を超える人数がいる場合、2 つのグループに分けてスタートさせてよい。競技者のおよそ 2/3 を第 1 グループとして通常のスタートラインに並ばせ、残りの第 2 グループは二つに分けられた外側のスタートラインに並ぶ。第 2 グループは、コーンまたは旗でマークされたトラックの最初の曲走路の終わりまで、決められたコースを走らなければならない。外側の弧形のスタートラインは、全競技者が同一の距離を走るように引かれなければならない。第 2 グループからスタートした競技者で決められた外側のレーンに留まらなかった競技者は、レーンから外れた競技者と同じ理由で失格になる。 800m のブレイクラインは通常のフィニッシュライン（ホームストレート）からスタートする競技者と第 2 グループ/外側の競技者が合流する地点である。バックストレート（200m スタート地点）からスタートするレースの場合、グループスタート用のメインストレートの始点にあるマークが第 2 グループでスタートした競技者と通常のスタートからスタートした競技者と合流する地点を示す。このマーク(ブレイクポイント)は 50mm×50mm でなければならない、第 4 レーンと第 5 レーン（6 レーンのトラックでは第 3 レーンと第 4 レーン）のライン上に置き、コーンまたは旗を二つのグループが合流する地点の直前に置く。 第 18 条 レース レースにおける妨害 18.1. 競技中、押されたり走路をふさがれたりして、競技者またはガイドランナーの前進が妨げられた場合の扱いは以下のとおりとする。 a) 上記妨害行為が意図的でない場合、または、競技者による以外の方法で引き起こされた場合、審判長は、そのような行為が特定の競技者（またはチーム）に深刻な影響をもたらしたと判断した場合は、規則 2.13.7 に従い競技者一人、または当該レースに関する複数名あるいは全員での再レースの実施を命	5 0 0 0 m お よ び 1 0 0 0 0 m
---	--	--

or all of the athletes) be re-held or allow the affected athlete (or team) to compete in a subsequent round of the event; b) If another athlete or their guide-runner is found responsible for the intentional jostling or obstruction by the Referee, such athlete or their team shall be liable to disqualification from that event. The Referee may, if they are of the opinion that an athlete was seriously affected in accordance with Rule 2.13.7, order that the race (for one, some or all of the athletes) be re-held excluding any disqualified athlete or team or allow any affected athlete (or team) (other than any disqualified athlete or team) to compete in a subsequent round of the event. In order for (a) and (b) to apply, the Referee must deem that the athlete (or team) affected (or whose guide-runner was affected) by the jostling or obstruction would likely have completed the race were it not for the jostling or obstruction. Note: In cases considered serious enough Rules 8.1 and 8.3 may also be applied. In both cases of Rules 18.1(a) and 18.1(b), such athlete (or team) should normally have completed the event with bona fide effort. COMMENT: Jostling should be understood as physical contact on one or more occasions with another athlete or athletes and/or guide runner(s) that results in an unfair advantage or causes injury or harm to them or, consequently, to another athlete or athletes. 2. In all races: a) including at least one bend, the direction of the race shall be left-hand inside. The lanes shall be numbered with the left-hand inside lane numbered 1; b) run entirely on the straight, the direction of the race may be either left-hand or right-hand inside, according to the available conditions; c) run in lanes (or any part of a race run in lanes), each athlete or the athlete's guide runner shall keep within their allocated lane from start to finish and, when running on a bend, shall not step or run on or inside the left-hand lane line or in the case of the inside lane, the kerb or line marking the border of the inside of the track; d) not run in lanes (or any part of races), an athlete or the athlete's guide-runner running on a bend, on the outer half of the track as per Rule 17.11, shall not step, run or wheel on or inside the kerb or line marking the applicable border (the inside of the track or the outer half of the track). COMMENT: The requirement for an athlete or an athlete's guide-runner to keep within their allocated lane from start to finish pursuant to	じるか、影響を受けた競技者（またはチーム）が当該種目の次のラウンドで競技することを認めることができる。 b) 別の競技者またはそのガイドランナーが上記妨害行為を意図的に引き起こしたと審判長が判断した場合、その競技者（またはチーム）は、当該種目で失格となる。審判長は、そのような行為が特定の競技者（またはチーム）に深刻な影響をもたらしたと判断した場合は、失格となった競技者（またはチーム）を除いて規則 2.13.7 に従い、競技者一人、または当該レースに関する複数名あるいは全員での再レースの実施を命じるか、影響を受けた競技者（またはチーム）（失格となった競技者やチームは除く）が当該種目の次のラウンドで競技することを認めることができる。 (a)及び(b)のいずれの場合においても、再レース等を認められる競技者（またはチーム）は、通常誠実に力を尽くして当該種目を完走した競技者（またはチーム）でなければならない。 注意：悪質と考えられる場合は、規則 8.1.(a)および規則 8.1.b)を適用することができる。規則 18.1(a)と 18.1(b)のいずれの場合においても、再レース等をもとめられる競技者（チーム）は、通常、誠実に力をつくして当該種目を完走した競技者（またはチーム）である。 コメント：押し合い（ジョスリング）とは、他の競技者との物理的な接触と理解する必要があり、それによって不当な利益を得たり、他の競技者に怪我をさせたり、危害を加えたりすることを引き起こす行為である。 18.2.すべてのレースにおいて a)少なくとも一つの曲走路を含むレースは、左手が内側になるように行う。またレーンナンバーは、左手側から順にレーン 1 とつける。 b)完全に直線のみを走る場合、走る方向は利用可能な条件に応じて、左手または右手を内側としてもよい。 c)レーンで行うレース（一部をレーンで行う場合も含む）では、各競技者またはガイドランナーはスタートからフィニッシュまで自分に割り当てられたレーンを走らなければならない。曲走路では、左側（内側）のライン上またはその内側（最も内側のレーンでは走路の境界を示す縁石またはライン）を踏んだり走ったりしてはならない。 d)レーンで行わない（一部をレーンで行わない場合も含む）すべてのレースの曲走路で、あるいは規則 17.11 に規定された第 2 グループを走る際に、各競技者またはガイドランナーは、境界を示すために設置されている縁石やラインの上や内側（トラックの内側、グループスタートでトラックの外側からのスタートした際の第 1 グループと第 2 グループの走路の境界の内側）を踏んだり、走ったりしてはならない。 コメント：規則 18.2.(c)に従って、競技者とガイドランナーがスタートからフィニッシュまで自分に割り当てられたレーンを走らなければならないという要件は、競技者	第 18 条 レ ー ス 18.1. レ ー ス に お け る 妨 害
---	--	--

Rule 18.2(c) does not require the athlete to finish the race in the same lane in which they started (subject to no other rules being broken).

3. During Wheelchair Races propulsion by any other method except the athlete pushing on the wheels or push-rims will result in disqualification.

4. During Wheelchair and Frame Running races an athlete coming from behind in an attempt to overtake carries the responsibility of ensuring full clearance of the chair being overtaken before cutting across. The athlete being overtaken has the responsibility not to obstruct or impede the incoming athlete once the front wheel(s) of the athlete are in sight.




Figure 6 – Wheelchair overtaking

Lane Infringement

5. in all races, if the Referee is satisfied, on the report of a Judge or Umpire or otherwise, that an athlete or the athlete's guide-runner has infringed Rule 18.2(c) or 18.2(d) they or in the case of a relay race, their team shall be disqualified unless the athlete:

a) is pushed or forced by another person or object to step, run or wheel outside their lane or on or inside the kerb or line marking the applicable border, or;

b) steps, runs or wheels outside their lane in the straight or outside the outer line of their lane on the bend, or;

c) in all races run in lanes (or any part of races run in lanes), touches once the line on their left, or the kerb or line marking the border of the inside of the track on a bend; provided that:

In the case of Wheelchair Races, the wheel of the racing chair does not remain in contact with the line for longer than the time that it takes the athlete to make two further pushes on the push-rim of the racing chair from the point at which the wheel of the racing chair first made contact with the line; and

In the case of Frame Running races, the wheel of the Frame Runner does not remain in contact with the line for longer than the time that it takes the athlete to make two further steps from the

が割り当てられたレーンでフィニッシュすることを要求するものではない。(ただし、他の規則に違反していないことを条件とする)

18.3. 車いす競走で競技中に競技者が車輪またはプッシュリムを押す以外の方法で車いすを進めた場合、その競技者は失格となる。

18.4. 車いす及びフレームランニング競走で競技中に他の競技者を追い抜こうとする際、追い抜く側の競技者は追い抜かれる側の競技者との間に十分な距離をあけてから前を横切らなければならない。追い抜かれる側の競技者は、後方から来る競技者の前輪が視界に入ったらその進行を妨げてはならない。

レーン侵害行為

レーン侵害行為

18.5. すべてのレース

規則 18.2.(c)または 18.2(d)を除き、競技者またはガイドランナーが本規則に違反し、審判長が審判員が監察員の報告に同意した場合は、その競技者、リレーの場合そのチームは失格となる。但し、以下の場合は、失格とならない。

a) レース中に、他の者や何らかの物によって押されたり、妨害されたりしたために、自分のレーン外、縁石やラインの上あるいは内側に足または車輪が入ったり走ったりした場合

b) レーンで行うレースの直走路において自分のレーン外を踏んだり走ったりした場合。またはレーンで行うレースの曲走路において自分のレーンの外側のラインを踏んだり、外側のレーンを走ったりした場合

c) レーンで行う（一部をレーンで行う場合も含む）すべてのレースの曲走路で、レーンの左側の線またはトラックの内側の境界線を示す線に 1 回（1 歩）だけ触れた場合。

車いすレースでは、車いすの車輪が最初にラインに触れた時点から競技者が車いすのプッシュリムを 2 回押した時点までラインに接触した場合、フレームランニングの場合、フレームランナーの車輪が最初にラインに触れた時点から競技者が 2 歩地面を蹴った時点までラインに接触した場合

point at which the wheel of the Frame Runner first made contact with the line. d) in all races not run in lanes (or any part of races not run in lanes), steps/wheels once on or completely over the kerb or line marking the applicable border (as defined in Rule 18.2(d)) on a bend. For Wheelchair and Frame Running races, only one wheel may be completely over the kerb/track border line and for no longer than it takes the athlete to make two further pushes on the push-rim of the racing chair from the point the wheel went over the kerb/track border, and for Frame Running, no longer than it takes the athlete to make two extra steps from the point the wheel first went over the kerb/track border. and no other athlete being jostled or obstructed so as to impede the other athlete's progress (see Rule 18.1) and no material advantage is gained (see Rule 18.6). In races with multiple rounds, any action defined in Rules 18.5(c) and 18.5(d) may be made only once during all rounds of an event by a particular athlete without the disqualification of that athlete. A second action will result in the disqualification of that athlete whether it was made in the same round or in another round of the same event. In the case of Relay Races, any second action (as described in this Rule 18.5(c) and 18.5(d) by an athlete who is a member of a team, regardless of whether made by the same or different athletes, will result in the disqualification of the team whether it happens in the same round or in another round of the same event. For the ratification of records, see Rule 51.17(d). 6. If material advantage is gained by an athlete by improving their position by any means including under the exceptions in Rule 18.5 or by removing themselves from a "boxed" position in the race by having stepped/wheeled or run inside the inside edge of the track at any point, the athlete (or team) shall be disqualified. COMMENT: Rule 18.6 specifically outlaws the practice of an athlete seeking to improve their position in races by moving onto the inside of the track (whether intentionally or after being pushed or jostled there by another athlete) to get out of a boxed position by running on the inside until clear. Whilst normally running on the inside of lane 1 in the straight (as distinct from doing so on the bend) would not lead to mandatory disqualification, the Referee has the power to disqualify in their discretion if this occurs and the athlete is advantaged even if the initial reason for being there was the result of being pushed or jostled. In such cases the athlete should take immediate steps to return to the track without seeking or gaining any advantage. Where a race is started in lanes and then continues not using separate lanes, Rules 18.1	d) レーンで行わない（一部をレーンで行わない場合も含む）すべてのレース（規則 18.2(d)参照）の曲走路で、走路の境界を示す縁石または白線を 1 回（1 歩）だけ踏んだり、完全に超えたり（内側にはいったり）した場合。車いすレースおよびフレームランニングレースでは、車輪が完全に縁石/トラック境界線を越えることができるのは 1 つだけであり、車輪が縁石/トラック境界線を越えた時点からレーサーのプッシュリムをさらに 2 回押すのにかかる時間を超えてはならない。またフレームランニングの場合は、車輪が縁石/トラックの境界線を越えた時点から競技者がさらに 2 歩進むのにかかる時間を超えてはならない。 また、他の競技者の進行を妨げるような押し合いや妨害行為を行わないこと（規則 18.1 参照）、及び実質的な利益を得ないこと（規則 18.6 参照）も条件とする。 複数のラウンドで行われるレースでは、規則 18.5(c) または 18.5.(d)に定められた行為は、ある競技者の当該種目のすべてのラウンドの中での 1 回の行為は失格とはならない。当該種目の同じラウンドで行われたか他のラウンドで行われたかに関わらず、2 回以上の行為があると当該競技者は、失格となる。 リレーの場合、規則 18.5(c)と 18.5(d)に定める違反を 2 回以上行ったら、違反したのが同一競技者か、そのチームの他の競技者によるものかに関わらず、また当該種目の同じラウンドで行われたか他のラウンドで行われたかに関わらず、当該チームは失格となる。 記録の公認については、規則 51.17(d)を参照のこと 18.6. TR18.5に規定されていないことを含む何らかの手段で、またはレース中にトラックの縁石の内側に足が入ったり走ったりして「囲まれた（ボックスポジション）」状況から抜け出すことによって、実質的な利益を得た場合、競技者（またはリレー・チーム）は失格となる。 コメント：規則 18.6 は、特に、競技者がレース中にトラックの内側に入り込むことにより（意図的でないとか他の競技者に押されたり妨害されて入り込んでしまったとかは関係なく）自身の位置取りをよくしようとしたり、周りを他の競技者に囲まれた状態から抜け出すためにスペースが見つかるまでトラック内側を走るといった行為を禁止する。通常、直走路の 1 レーン内側を走っている限りは（曲走路での行為とは別に）、強制的に失格に至ることはないが、もし、それが押されたり、妨害された結果、その場所にいたのだとしても、競技者が利益を得ていれば、審判長は、自らの裁量で失格する権限がある。そのような場合、競技者はいかなる利益を得ることなくトラックに戻るための速やかな措置を取る必要がある。 スタート時にはレーンが割り当てられ、スタート後にレーンを使用しないレースでは、規則 18.1 と 18.5 はそれぞれの場所（レーンを使用して走っている場所とレーンを使用しないで走っている場所）に適用される。従って、規則 18.5 (c)または、18.5.(d)に基づく違反
---	--

and 18.5 apply accordingly to each such part of the race. Therefore, only one infringement according to Rules 18.5(c) and 18.5(d) is allowed. A second infringement in the same race will result in disqualification. When determining whether the exception in Rule 18.5(c) applies in cases where some part of the shoe/foot/prosthesis or wheel is also to the left of the line, there is a requirement for at least some part of the outline of athlete's shoe/foot/prosthesis or wheel to be touching the line, i.e. some contact with the line (depicted by the outline of the relevant part of the shoe/foot/prosthesis or wheel) is required for this exception to apply. If this is not the case, then the exception does not apply. All lane infringements should be tracked in the competition data systems and shown in the start lists and results. In relation to the exception in Rule 18.5(c) for Wheelchair Racers, it is understood that, whilst there may only be a single contact, the duration of the contact of the wheel of the racing chair with the line may be for a prolonged period that might afford the athlete a material advantage. That being the case the athlete shall be permitted two pushes on the push rim of the racing chair from the point at which the racing chair first touched the line to bring themselves back within the lane (so as not to be touching the line) to the effect that, if the athlete makes a third push on the push rim of the racing chair whilst the racing chair is in contact with the line, the athlete shall be disqualified. In relation to the exception in Rule 18.5(c) for Frame Running races, it is understood that, whilst there may only be a single contact, the duration of the contact of the wheel of the Frame Runner with the line may be for a prolonged period that might afford the athlete a material advantage. That being the case the athlete shall be permitted two further steps from the point at which the wheel of the Frame Runner first touched the line to bring themselves back within the lane (so as not to be touching the line) to the effect that, if the athlete makes a third step whilst the wheel of the Frame Runner is in contact with the line, the athlete shall be disqualified. 7. In the Paralympic Games and WPA Championships (see Part B - 3.1.2 (a) and (b)) the start of the 800m event shall be run in lanes for as far as the nearer edge of the breakline where athletes may leave their respective lanes. The breakline shall be an arced line marked after the first bend, 50mm wide, across all lanes other than lane 1. To assist ambulant athletes in identifying the breakline, small cones or prisms, 50mmx50mm no more than 0.15m high, and preferably of different colour from the breakline and the lane lines, shall be placed on the lane lines immediately before the intersection of the lane lines and the breakline. If an athlete or their accompanying guide-runner does not follow this Rule he, or in case of a relay team their team,	は、1 回のみ認められる。同じレースで 2 回目の違反があった場合は失格となる。靴や足、義足、車輪の一部が内側の白線の左側にある場合に、規則 18.5(c)を例外的に適用するかどうか判断するには、少なくとも競技者の靴や足、義足、車輪の一部が左側（内側）の白線に接触しているかどうか、すなわち、（関連する靴や足、義足、車輪によって示される）白線に接触していることが要件となる。そうでない場合は適用されない。 レーン侵害に関するすべての違反は、競技データシステムに記録され、スタートリストと結果に表示されなくてはならない。 車いすレーサーに関する規則 18.5(c)の例外に関して、接触は 1 回だけであっても、レーサーの車輪とラインとの接触時間は、競技者に物質的なアドバンテージを与える可能性のある長時間である。その場合、競技者は、レーサーの車輪が最初にラインに触れた地点から（ラインに触れないように）レーン内に戻るためにレーサーのプッシュリムを 2 回押すことが許可されるものとする。レーサーの車輪がラインに接触している間に競技者がレーサーのプッシュリムを [3 回目] 押した場合、その競技者は失格となる。 フレームランニングレースに関する規則 18.5(c)の例外に関して、接触は 1 回だけであっても、フレームランナーの車輪とラインとの接触時間は、競技者に物質的なアドバンテージを与える可能性のある長時間である。その場合、競技者は、ランナーの車輪が最初にラインに触れた地点から（ラインに触れないように）レーン内に戻るために 2 回地面を蹴ることが許可されるものとする。ランナーの車輪がラインに接触している間に競技者が [3 回目] 地面を蹴った場合、その競技者は失格となる。 18.7. パラリンピック競技大会及び WPA 競技会 (PART- B 規則 3.1.2 参照)では、800m 競走は第一曲走路の終わりにマークされたブレイクラインの、スタート側により近い端までレーンを走る。競技者はこのブレイクラインから自分のレーンを離れることが許される。 ブレイクラインは、トラックの第 1 曲走路の終わりに引かれた第 1 レーン以外のすべてのレーンを横切る幅 50mm の円弧のラインである。立位の競技者がブレイクラインを確認しやすいように、ブレイクラインやレーンラインとは違う色で、50mm×50mm で高さ 0.15m 以下のコーン、角柱、または適当な目印となるものを各レーンとブレイクラインの交差する直前の各レーン上に置かねばならない。競技者またはガイドランナーが、本規則に違反した場合、その競技者、リレーの場合はそのチームは失格となる。
--	---

shall be disqualified. Note (i): For Wheelchair and Frame Running races, cones should not be placed on the track. Coloured flat markers 50mmx50mm may be placed immediately before the intersection of the lane lines at the breakline. COMMENT: In addition to the flags, some sort of flat marker may be placed on the track surface at the intersection of the lane lines immediately before the breakline; which may be more visible to athletes and not interfere with their performance. It is important that the colour of these flat markers, usually tape, must be a different colour to both the surface of the track and the white lines. It could be a coloured marker with a soft "flap" sticking up, as long as that will not disrupt athletes. Note (ii): For Wheelchair Races, a flag, 1.5m high must be positioned on both ends of the breakline. One on the infield and the other on the outside of the track. Note (iii): For Wheelchair Races, athletes may leave their respective lanes when the bottom of both rear wheels which are touching the ground have gone past the nearer edge of the breakline close to the start line. Note (iv): In WPA Approved Competitions (see Part B - 3.1.2 (d)), countries may agree not to use lanes. 8. For athletes in Sport Class T11and T12, in track events run entirely or partly in lanes, each shall be allocated 2 lanes. The start lines in a staggered start will be lanes 1, 3, 5 or 7. COMMENT: For the purpose of officiating, these two lanes should be viewed and marked as one lane (lanes 1 & 2 = lane 1, lanes 3 & 4 = lane 3, and so on). It is at the discretion of the athlete on which side of them their guide-runner shall run. Both the athlete and guide-runner must keep within their allocated lane (being the two allocated lanes together) from start to finish. Athletes in Sport Class T12 who do not compete with a guide-runner shall also be allocated two lanes. They may set their starting blocks anywhere along the start line within the allocated lane and must keep within their allocated lane from start to finish. Leaving the Track 9. An athlete and/or the accompanying guide-runner who during the course of a race voluntarily leaves the track prior to the finish, except in compliance with Rule 23.5(c) will not be allowed to continue in the race and shall be recorded as not finishing the event. Should the athlete and/or their guide-runner attempt to re-enter or continue in the race the athlete shall be disqualified by the Referee. Check-Marks 10. Except as stated in Rule 23.3, athletes may	注意(i)：車いす及びフレームランニング競走では、コーンや角柱をコース上に置いてはならず、代わりに、色付きの 50mmx50mm の平らなマーカーを、各レーンとブレイクラインの交差する直前の線上に置くことができる。 コメント：旗に加えて、ブレイクラインの直前の車線の交点のトラック表面に、ある種のフラットマーカーを配置できる。これは、競技者にとってより見やすく、パフォーマンスに干渉しないものが良い。これらの平らなマーカー（通常はテープ）の色は、トラックの表面と白い線の両方とは異なる色にする必要がある。競技者の邪魔にならない限り、色付きのマーカーに柔らかい「フラップ」が付いている場合もある。 注意(ii)：車いす競技では、ブレイクライン両端に、高さ 1.5m の旗を配置しなければならない。ひとつはインフィールド、もうひとつはトラック外側に置く。 注意(iii)：車いす競走では、後輪の地面についている下の部分がブレイクラインのスタートラインに近い側を通過したとき、自分に割り当てられたレーンから離れることができる。 注意(iv)：WPA 承認競技会(PART-B 規則 3.1.2 参照)では、当事国の合意によってレーンを使用しない場合がある。 18.8. 競技クラス T11 及び T12 の競技者について、レーンのすべてまたは一部を走るトラック種目では、それぞれに 2 レーンが割り当てられる。段階式スタートにおけるスタートラインはレーン 1、3、5、7 とする。 コメント：審判をするにあたり、これら 2 つのレーンを 1 つのレーンとして表示する必要がある（レーン 1 及び 2 をレーン 1、レーン 3 及び 4 をレーン 3 等）。ガイドランナーが競技者のどちら側を走るかは、競技者の裁量に委ねられている。競技者とガイドランナーの両方が、スタートからフィニッシュまで割り当てられたレーン（2 レーン分）にとどまる必要がある。ガイドランナーを伴わない T12 の競技者にも、2 レーンが割り当てられる。スターティングブロックは、割り当てられたレーン分の中であればスタートラインに沿ってどこに設置してもよく、競技者はスタートからフィニッシュまで割り当てられたレーンにとどまる必要がある。 トラックからの離脱 18.9. 規則 23.5(c)を遵守する場合を除き、レース中にフィニッシュ前に自らの意思でトラックを離れた競技者及びガイドランナーは、そのレースを継続することを認められず、完走しなかったものとして記録されるものとする。いったんトラックを離れた競技者がレースに戻ろうとした場合、審判長により失格が宣言されるものとする。 マーカー(チェックマーク) 18.10. 規則 23.3 で規定されたレースの全部ある
---	---

not make check-marks or place objects on or alongside the running track for their assistance. The Umpires shall direct the relevant athlete to adapt or remove any marks or objects not complying with this Rule. If they do not, the Umpires shall remove them. Note: Serious cases may further be dealt with under Rule 8.1 and Rule 8.3. Wind Measurement 11. All wind gauge equipment shall have been manufactured and calibrated according to international standards. The accuracy of the Measurement equipment used in the competition shall have been verified by an appropriate organisation accredited by the national measurement authority. 12. Non-mechanical wind gauges shall be used at all the Paralympic Games and WPA Championships (see Part B - 3.1.2 (a) and (b)) and for any performance submitted for ratification as a World/Regional Record. A mechanical wind gauge should have appropriate protection to reduce the impact of any crosswind. Where tubes are used, their length on either side of the measuring device should be at least twice the diameter of the tube. 13. The Track Referee shall ensure that the wind gauge for Track Events is placed beside the straight, adjacent to lane 1, and 50m from the finish line. It shall be positioned 1.22m high and not more than 2m away from the track. 14. The wind gauge may be started and stopped automatically and/or remotely, and the information conveyed directly to the competition computer. 15. The periods for which the wind velocity shall be measured are as follows: In the 100m event – for 10 seconds immediately following the start. In the 200m event – the wind velocity shall be measured for a period of 10 seconds commencing when the leading athlete enters the straight. 16. The wind gauge shall be read in metres per second, rounded to the next higher tenth of a meter per second, unless the second decimal is zero, in the positive direction (that is, a reading of +2.03 meters per second shall be recorded as +2.1; a reading of -2.03 meters per second shall be recorded as -2.0). Gauges that produce digital readings expressed in tenths of meters per second shall be constructed so as to comply with this Rule. Indication of Intermediate Times 17. Intermediate times and preliminary finishing times may be officially announced and/or displayed. Otherwise, such times must not be communicated to the athletes by persons in the competition area without the prior approval of	いは最初の一部をレーンで行うリレーを除き、競技者は自分の助けとするために、走路上及び走路脇にマークをつけたり、物を置いたりしてはならない。規則に違反しているマーカ―や物があれば、規則に合わせるよう、あるいは剥がしたり動かししたりするよう、監察員は当該競技者を指導する。指導に従わない場合には、監察員が取り除かなければならない。 注意：悪質な場合は規則 8.1 及び規則 8.3 を適用することができる。 風力測定 18.11. すべての風向風速計は国際標準規格によって認証されていなければならない。競技会で使用される風向風速計の精度は、各国の政府計量機関によって認定された適切な組織によって認証されているものでなければならない。 18.12. パラリンピック競技大会及び WPA 競技会 (PART-B 規則 3.1.2(a)及び(b)参照)ならびに世界/地域記録認定のために提出される成績には非機械的（超音波）風向風速計を使用しなければならない。機械的風向風速計は横風の影響を受けないように保護する。また円筒を使用する場合、計測器の両側は円筒の直径の少なくとも 2 倍の長さがなければならない。 18.13. トラック審判長は、風向風速計を直走路の第 1レーンに隣接してフィニッシュラインから 50mの地点に設置してあることを確認する。風向風速計の測定面は、トラックから 2m 以上離してはならず、高さは 1.22m でなければならない。 18.14. 風向風速計は自動、そして／あるいは遠隔操作によって計測され、計測結果は直接コンピューターに伝達・入力されてもよい。 18.15. 風速を計測する時間は次の通りとする。 100m：スターターの信号器の発射（閃光／煙）直後から 10 秒間 200m：先頭の走者が直走路に入ったときから 10 秒間 18.16. 風向風速計で秒速何 m かを読みとり、小数第 2 位が 0 でない限り、秒速 1m の 10 分の 1 の単位まで繰り上げる(+2.03m は+2.1m、-2.03m は-2.0m)。秒速 10 分の 1m 単位で表示できるよう製造された風向風速計は、上記規則に合致した仕様になっていなくてはならない。 途中時間の表示 18.17. 審判長に承認を受けた者または任命された者 1 名のみが、合意された 2 か所以下のそれぞれの場所において時間を読み上げることができるが、事前に承認を得ない限り、いかなる者も競技区域内で、時間を競技者に知らせてはならない。	トラックからの離脱 マーカ―（チェックマーク） 風力測定
---	--	---

the appropriate Referee who may authorise or appoint no more than one person to call times at each of no more than two agreed timing points. Athletes who receive intermediate times that have been communicated in violation of this Rule shall be considered to have received assistance and will be subject to the provisions of Rule 7.2. For Sport Class T12 in events of 800m and above, athletes who compete without a guide-runner may have assistance from personnel other than from competition officials, who will be permitted to call intermediate times from a designated area inside the competition area adjacent to the start line of the respective event where appropriate. The placement of this area shall be determined by the Technical Delegate. Note (i): Individuals who are placed in this location inside the competition area are not permitted to give any guidance to the athletes other than the reading of intermediate times. In violation of this Rule, the athlete concerned shall be warned or disqualified subject to Rule 7.2. Note (ii): The competition area, which normally also has a physical barrier, is defined for this purpose as the area where the competition is being staged and which has an access restricted to the competing athletes and to personnel authorised in accordance with the relevant Rules and Regulations. Drinking / Sponging and Refreshments 18. In Track Events of 5000m and 10000m, the LOC may provide water and sponges to athletes if weather conditions warrant such provision. a) An athlete and/or guide-runner may carry water, refreshment or sponges by hand or attached to their body provided such items are (i) carried from the start of the race; or (ii) collected from an official station during the race. Such items may be exchanged between an athlete and their guide-runner (or vice versa) at any time during the race. In addition, such items may be provided to athletes and/or guide runners for medical reasons, either from an official medical staff member appointed by WPA and/or LOC or at the direction of race officials. b) The carrying, collection or exchanging of water, refreshments or sponges during the race other than as permitted above is prohibited. An athlete and/or guide runner who breaches this Rule shall, for a first such offence, be warned by the Referee, normally by showing a yellow card. For a second offence, the Referee shall disqualify the athlete and/or guide runner, normally by showing a red card. Rule 19: The Finish 1. The position of the finish of a race shall be denoted by a white line 50mm wide. 2. The ambulant athletes shall be placed in the order in which any part of their torso (not the head, neck, arms, legs, hands or feet) reaches	本規則に違反し途中経過時間を知らされた競技者は、助力を受けたと見なされ規則 7.2 が適用される。 競技クラス T12 の 800m 以上の種目で、ガイドランナー無しで競技する競技者は競技役員以外の者からの助力を得ることが認められており、競技区域内に定められた当該種目スタートライン付近で途中計時を口頭で伝えることが許される。場所の決定は技術代表によりなされる。 注意(i)：競技区域内に入ることが許された者は途中時間を読む以外のアドバイスは許されない。この規則に従わなければ、規則 7.2 によって関係する競技者に警告が与えられたり、失格となる。 注意(ii)：競技区域は、通常、柵等で仕切られているが、上記規定の解釈上、競技が行われ、競技参加者と規則及び規程で認められた人員のみが立ち入ることのできる区域のことと定義される。 給水・スポンジ及び給食 18. 5000m 及び 10000m のトラック競技では、組織委員会は気象状況に応じて、競技者に水とスポンジを用意することができる。 a) 競技者および/またはガイドランナーは水、飲食物またはスポンジを手を持ったり身体につけたりしてもよい。(i)レースのスタートから持っているものまたは、(ii)レース中に公式供給所で受け取ったもの。それらの物をレース中に競技者とそのガイドランナーの間でいつでも交換できる。さらにそのような物は、大会役員や WPA 又は/及び LOC が任命した公式の医療スタッフの指示により競技者およびガイドランナーに医療的理由で提供される事もある。 b)規則 49.8(g)で許可されている場合を除き、レース中に水、飲食物、スポンジを持ち運んだり、受け取ったり、交換したりすることは禁止されている。この規則に違反した競技者および/またはガイドランナーに対して審判長は、それが 1 回目の違反であれば警告とし、通常はイエローカードの提示によりこれを知らせる。2 回目の違反があった競技者は失格させ、レッドカードを提示する。 第 19 条 フィニッシュ 19.1.1 フィニッシュは幅 50mm の白いラインで示す。 19.1.2. 競技者の順位は、その胴体(即ちトルソー)のことで、頭、首、腕、脚、手または足とは区別される)のいずれかの部分が前項のフィニッシュラインのスタートラ	途中時間の表示 給水・スポンジ及び給食
---	--	---

the vertical plane of the nearer edge of the finish line. 3. In Wheelchair and Frame Running races the athletes shall be placed in the order in which the centre of the axle of the leading wheel reaches the vertical plane of the nearer edge of the finish line as defined above. 4. In races for athletes in Sports Class T11 and T12 competing with a guide-runner the athlete must reach the nearer edge of the finish line in front of the guide-runner or the athlete will be disqualified. When photo finish is in use, the Chief Photo Finish Judge shall make this determination and apply any disqualification. In any other case, or where a Photo Finish image is not available, the Track Referee shall decide. 5. Event Time Limits (Sport Classes T32-34, T51-54 and T71-72) In Wheelchair and Frame Running Races of 1500m or longer, officials may conclude the event and clear the track after an agreed time limit has expired. Any athlete who has not completed the set distance when an event is concluded shall be shown in the official results as "DNF" (i.e., Did Not Finish). The referee has the authority to remove any athlete who has been overlapped. Comment: At the completion of Wheelchair and Frame Running races, some athletes tend to continue wheeling and/or running straight after crossing the finish line, rather than following the curve of the track. This can lead to potential collisions with other athletes. To prevent such incidents, all athletes should follow the curve of the lanes after finishing their race. Rule 20: Timing 1. Three alternative methods of timekeeping shall be recognised as official: a) Hand Timing; b) Fully Automatic Timing obtained from a Photo Finish System; c) For road races only - timing provided by a Transponder System. 2. Save for Wheelchair and Frame Running races, under Rule 20.1 (a) and Rule 20.1 (b) the time shall be taken to the moment at which any part of the body of an athlete (i.e., torso as distinguished from the head, neck, arms, legs, hands or feet) reaches the vertical plane of the nearer edge of the finish line. 3. In Wheelchair and Frame Running races the time shall be taken to the moment in which the centre of the axle of the leading wheel reaches the vertical plane of the nearer edge of the finish line as defined above. 4. Times for all finishers shall be recorded. In addition, whenever possible, lap times in races of 800m and over shall be recorded.	インに近い端の垂直面に到達したことで決める。 19.1.3. 車いすとフレームランニングのレースでは、競技者は先に定義したように、進行方向前方に位置する車輪の車軸の中心がフィニッシュライン手前端的垂直面に到達した順序で決まる。 19.1.4. ガイドランナーを伴う競技クラス T11 及び T12 の競走競技においては、競技者はガイドランナーより先にフィニッシュラインに到達しなければならない、そうしなかった場合は失格となる。写真判定を使用している場合、写真判定員主任は失格を判断し適用しなくてはならない。写真判定を使用していない場合、または写真判定画像で確認できない場合は、トラック審判長が決定する。 19.1.5. 競技時間制限（競技クラス T32-34、T51-54 および T71-72） 1500m 以上の車いす及びフレームランニング競走においては、合意された時間経過後、競技役員は種目を終了し、トラックから競技者を片づけることができる。種目終了までに所定の距離を完走しなかった場合、競技者の公式成績は DNF（途中棄権）と記録されるものとする。審判長はトラック上に残っている全競技者を移動させる権限がある。 コメント：車いすおよびフレームランニングレースでは一部の競技者はフィニッシュラインを超えてトラックの縁石に沿って進まず、まっすぐ進む傾向がある。この状況では、他の競技者と接触事故を巻き起こす危険がある。そのような危険を避けるために競技者は競技終了後トラックの縁石に沿って進むべきである。 第 20 条 計時 20.1. 公式の計時方法として、次の 3 つが認められる。 a) 手動計時 b) 写真判定システムによる全自動計時（電気計時） c) 自動応答計時システムによる計時（道路競走に限定） 20.2. 車いす及びフレームランニングレースを除き、規則 20.1(a)及び 20.1(b)における計時は、競技者の胴体（トルソー：頭、首、腕、脚、手、足を含まない部分）がフィニッシュラインのスタートラインに近い方の端の垂直面に到達した瞬間をとらなければならない。 20.3. 車いす及びフレームランニングレースにおける計時は、進行方向前方に位置する車輪の車軸の中心が上記のフィニッシュライン手前端的垂直面に到達した瞬間まで時間を測るものとする。 20.4. 全完走者の時間を計時する。また、可能な限り 800m 以上のレースのラップタイムを計時しなければならない。	第 19 条 フィニッシュ 第 20 条 計時
--	--	---

Hand Timing	手動計時	手動計時
5. The Timekeepers shall be in line with the finish and where possible, they should be placed at least 5m from the outside lane of the track. In order that they may all have a good view of the finish line, an elevated stand should be provided. 6. Timekeepers shall use manually operated electronic timers with digital readouts. All such timing devices are termed “watches” for the purpose of the Rules. 7. The lap and intermediate times shall be recorded either, by designated members of the timekeeping team using watches capable of taking more than one time, or by additional Timekeepers, or by transponders. 8. The time shall be taken from the flash / smoke of the gun. 9. Three official Timekeepers (one of whom shall be the Chief Timekeeper) and one or two additional Timekeepers shall time the winner of every event and any performances for record purposes. The times recorded by the additional Timekeepers’ watches shall not be considered unless one or more of the official Timekeepers’ watches fail to record the time correctly, in which case the additional Timekeepers shall be called upon, in such order as has been decided previously, so that in all the races, three watches should have recorded the official winning time. 10. Each Timekeeper shall act independently and without showing their watch to, or discussing their time with, any other person, shall enter their time on the official form and, after signing it, hand it to the Chief Timekeeper who may examine the watches to verify the reported times. 11. For all hand-timed races, times shall be read and recorded as follows: a) For races on the track, unless the time is an exact 1/10th of a second, the time shall be read and recorded to the next longer 1/10th of a second, e.g. 10.11 shall be recorded as 10.2; b) For races partly or entirely outside the stadium, unless the time is an exact whole second, the time shall be converted and recorded to the next longer whole second, e.g., for the Marathon 2:39:44.3 shall be recorded as 2:39:45. 12. If, after converting as indicated above, two of the three watches agree and the third disagrees, the time recorded by the two shall be the official time. If all three watches disagree, the middle time shall be official. If only times from two watches are available and they disagree, the longer time shall be official. 13. The Chief Timekeeper, acting in accordance with the Rules mentioned above, shall decide the	20.5. 計時員は、フィニッシュラインの延長線上に位置する。できれば、外側のレーンから少なくとも 5m のところに 1 列に並ぶ。フィニッシュラインがよく見えるように階段式のスタンドを用意する。 20.6. 手動計時は、計時員がデジタル式のストップウォッチで計時する。このような計時装置は、すべて規則の中で「時計」という。 20.7. ラップタイムは、複数の記録をとることができる時計を使用している計時員、予備の計時員、あるいはトランスポンダーシステムで計時する。 20.8. 計時は、スタート信号器の閃光または煙から計測する。 20.9. 各レースの第 1 着の時間及び記録のために計時すべき他の競技者の時間は、3 人の任命された計時員（そのうち 1 人は計時員主任）と 1～2 人の予備に任命された計時員が計時する。 予備計時員の時間は、1～2 人の任命された計時員が適切な計時に失敗した場合に事前に決めた順序によって採用され、いつの場合でも 3 個の時計で時間を記録する。 20.10. 各計時員は独立して行動し、他の計時員に時計を見せたり相談したりすることなく自己の計時した時間を所定の用紙に記入し、署名後計時員主任に提出する。計時員主任は、報告された時間を確認するため時計を検査することができる。 20.11. 手動計時によるすべてのレースでは、計時は以下のようにする。 a) トラックレースでは、ちょうど 0.1 秒で終わる以外は次の 0.1 秒として変換され記録される。すなわち、10 秒 11 は 10 秒 2 と記録される。 b) レースの一部または全部が競技場外で行われる場合の計時は、ちょうど秒で終わる以外は次の秒で読み取られ記録される。例えば、マラソンでは 2:39:44.3 は 2:39:45 と記録される。 20.12. 上記に示したように変換した後、3 個の時計のうち 2 個が一致し、1 個が異なっている場合は、2 個の時計が示す時間を公式記録とする。もし、3 個の時計がそれぞれ異なった時間を示すときは、中間の時間をもって公式記録とする。なんらかの理由で、2 個の時計のみ有効でそれぞれが異なった時間となった場合は、遅い方の時間を公式記録とする。 20.13. 計時員主任は必要に応じて本条の規定を適用し、各競技者の公式時間を決定し、公式記録	

official time for each athlete and provide the results to the Competition Secretary for distribution. Fully Automatic Timing and Photo Finish System The System 14.A Fully Automatic Timing and Photo Finish System must have been tested and have a certificate of accuracy within 4 years of the competition, including the following: a) The System must record the finish through a camera positioned in the extension of the finish line producing a composite image. i) For competitions as defined in Part B - 3.1.2, this composite image must be composed of at least 1000 images per second. ii) For other competitions, this composite image must be composed of at least 100 images per second. In each case, the image must be synchronised with a uniformly marked time scale graduated in 0.01 seconds. b) The System shall be started automatically by the Starter's signal, so that the overall delay between the report from the muzzle, or its equivalent visual indication and the start of the timing system is constant and equal to, or less than 0.001 seconds. 15.In order to confirm that the camera is correctly aligned and to facilitate the reading of the Photo Finish image, the intersection of the lane lines and the finish line shall be coloured black in a suitable design. Any such design must be solely confined to the intersection, for no more than 20mm beyond, and not extended before, the nearer edge of the finish line. Similar black marks may also be placed on each side of the intersection of an appropriate lane and the finish line to further facilitate reading. COMMENT: If we want to define a minimum in order to achieve the accuracy required in Rule 20.24, a composite of at least 100 component images per second is required. To achieve the accuracy demanded in Rule 22.2 for determining fastest losers by reference to times read to 0.001 second where times achieved by athletes are identical to 0.01 second then a composite of at least 1000 component images per second would be required. Most photo finish systems can operate at 1000 images per second or greater. 16.The placing of the athletes shall be identified from the image by means of a cursor with its reading line guaranteed to be perpendicular to the time scale. 17.The System must automatically determine and record the finish times of the athletes and must be able to produce a printed image which shows the time of any athlete. Additionally, the	を公表のため記録・情報処理員に提供する。 写真判定(電気計時)システム 20.14. 写真判定システムは競技会前 4 年以内に精度検査を受け、発行された精度証明書のあるものでなければならない。 a) 当該システムは、フィニッシュラインの延長線上に設置されたカメラを通してフィニッシュを記録し、合成画像を生成できるものでなければならない。 i) PART-B 規則 3.1.2 の競技会の場合、合成画像は秒あたり少なくとも 1,000 枚の画像から合成されなければならない。 ii) その他の競技会の場合、合成画像は秒あたり少なくとも 100 枚の画像から合成されなければならない。 いずれの場合においても、画像は 0.01 秒毎に均等に目盛りされた時間尺度と同期していなければならない。 b) 当該システムは、スターターの合図によって自動的に作動するものとし、ピストルの発射音または同等の可視指示と計時装置の時間差が安定的に 0.001 秒以下であるようにする。 20.15. カメラが正しく設置されていることを確認するために、また、写真判定画像が読み取りやすいようにするために、レーンラインとフィニッシュラインの交差部分は適切なデザインで黒く塗る。そのようなデザインは当該交差部分のみに施し、フィニッシュラインのスタートラインに近い方の端から向こう側に 20mm 以内にどめ、手前にはみ出してはならない。記録をより読み取りやすくするため、レーンラインとフィニッシュラインの交差部分の両側に同様の黒マークを置いてよい。 コメント：規則 20.24 で要求される精度を達成するために最小値を定義したい場合は、1 秒間に少なくとも 100 個のコンポーネント画像の合成が要求される。競技者が達成したタイムが 0.01 秒と同じである 0.001 秒まで読み込んだタイムを参照して最速の敗者を決定するための規則 22.2 で要求されている精度を達成するためには、1 秒間に少なくとも 1000 枚のコンポーネント画像の合成が必要になる。ほとんどの写真判定システムは、毎秒 1000 枚以上の画像で動作することができる。 20.16. 競技者の順位は、時間目盛りに対して垂直であることが保証されている読み込みラインのカーソルを用いて画像から読み取る。 20.17. 当該システムは、各競技者のフィニッシュタイムを自動的に測定・記録し、各競技者の時間が表示された写真を作成できるものでなければならない。自動作成された情報及び手入力情報（競技開始・終了時刻など）の変更は、写真の時間目盛と一覧表	写真判定（電気計時）システム
--	--	------------------------------

system shall provide a tabular overview which shows the time of every athlete. Subsequent changes of automatically determined values and manual input of values (such as start time, finish time), shall be indicated by the system automatically in the time scale of the printed image and the tabular overview. 18. A System which operates automatically at the finish, but not at the start, shall be considered to produce Times provided that the system was started in accordance with Rule 20.8 or with equivalent accuracy. The image may be used as a valid support in order to determine placings and adjust time intervals between athletes. Note: If the timing mechanism is not started by the Starter's signal, the time-scale on the image shall indicate this fact automatically. 19. A system which operates automatically at the start but not at the finish, shall be considered to produce neither Hand nor Fully Automatic Times and shall not therefore be used to obtain official times. Operation of the System 20. The Chief Photo Finish Judge shall be responsible for the functioning of the System. Before the start of the competition, they will meet the technical staff involved and familiarise themselves with the equipment, checking all applicable settings. In cooperation with the Start Referee (or if one is not appointed, the relevant Track Referee) and the Starter, they shall initiate a zero control test, before the beginning of each session, to ensure that the equipment is started automatically by the Starter's signal within the limit of 0.001 second. They shall supervise the testing of the equipment and ensure that the camera(s) is correctly aligned. 21. There should be at least two photo finish cameras in action, one from each side. Preferably, these timing systems should be technically independent, i.e., with different power supplies and recording and relaying the report of the Starter's signal, by separate equipment and cables. Note: Where two or more Photo Finish cameras are used, one should be designated as official by the Technical Delegate (or International Photo Finish Judge where appointed) before the start of the competition. The times and places from the images of the other camera(s) should not be considered unless there is reason to doubt the accuracy of the official camera or if there is need to use the supplementary images to resolve uncertainties in the finishing order (i.e., athletes wholly or partially obscured on the image from the official camera). 22. In conjunction with their Assistants, the Chief Photo Finish Judge shall determine the placing of the athletes and, as a consequence, their official times. They shall ensure that these results are correctly entered in or transferred to the	上に自動的に表示されなければならない。 20.18. スタート時には自動的に作動しないが、フィニッシュ時に自動的に作動するシステムは、規則 20.8 またはそれと同等の正確さで作動するのであれば、手動計時とみなす。画像は、順位を決定し、競技者間の時間間隔を調整するための有効なサポート資料として使用してもよい。 注意：写真判定システムがスターターの合図で作動しなかった場合、画像上の時間目盛りはこの事実を自動的に示すものでなくてはならない。 20.19. スタート時には自動的に作動するが、フィニッシュ時に自動的に作動しないシステムは、手動計時と写真判定システムのいずれでもないと思われ、公式タイムの計測には使用されない。 システムの操作 20.20. 写真判定員主任は、そのシステムの機能について責任を負う。主任は競技会の開始前に関係技術者と打ち合わせ、写真判定システムについて理解しすべての設定についても監督する。写真判定員主任は、スタート審判長（もし指名されていない場合は、関連するトラック審判長）とスターターの協力を得て、そのシステムが自動的にスターターの信号器の合図で承認された写真判定装置がつまり 0.001 秒以内で正しく作動するかどうかのゼロ・コントロールテストを、各セッション（午前・部または夜の部）の開始前に実施しなければならない。また、機器のテストとカメラの正確な設置について監督しなければならない。 20.21. できればトラックの両側に、少なくとも 1 台ずつ写真判定システムを作動させるようにする。これらのシステムは、技術的に独立したシステムが別々の動力源で別々の機器やケーブルによって、スターターの信号器の発信を記録し、連携できることが望ましい。 注意：2 台以上の写真判定システムを使用する場合、1 台は競技会の開始前に技術代表（あるいは指名された国際写真判定員）から公式システムとして指定されなければならない。もう 1 台のカメラの時間と順位については、公式カメラの正確性に疑問があるか、着順判定の不明確な点を正すために補助カメラとしての必要性が生じた場合以外には参考としない。（必要性がある場合の例：競技者の全身または一部が公式カメラの画像で確認できないとき） 20.22. 写真判定員主任は、補助役の判定員と協同して、競技者の着順を決定し、引き続き彼らの公式時間を決定する。主任は、これらの着順と時間が競技結果システムに正確に入力し転送されていること、そして記録・情報処理員に渡したことを確かめねばならない。主任はまた、規則 19.4 により、必要な判	システムの操作
--	---	----------------

competition results system and conveyed to the Competition Secretary. They shall also make any necessary determination and disqualification under Rule 19.4. COMMENT: At major events where the technology is available, the photo finish image is often immediately provided on the video board or published on the internet. It has become the practice to provide athletes, or persons on their behalf, who are considering making a protest or appeal the opportunity to see the photo, in order to avoid time being spent on any unnecessary protests or appeals. 23. Times from Photo Finish System shall be regarded as official unless for any reason the appropriate official decides that they obviously must be inaccurate. If such is the case, the times of the back-up Timekeepers, if possible adjusted based on information on time intervals obtained from the Photo Finish image, shall be official. At the discretion of the TD, such back-up Timekeepers may be appointed where any possibility exists of failure of the timing system. 24. Times shall be read and recorded from the Photo Finish image as follow: a) For all track races up to and including 10,000m, unless the time is an exact 0.01 second the time shall be converted and recorded to the next longer 0.01 second, e.g. 26:17.533 shall be recorded as 26:17.54. b) For all races held partly or entirely outside the stadium, all times not ending in three zeroes shall be converted and recorded to the next longer whole second, e.g., for the Marathon, 2:09:44.322 shall be recorded as 2:09:45. Note: Events held according to Rule 11.2 shall be considered to be conducted inside the stadium for timing and recording of performance. Transponder System 25. The use of Transponder Timing Systems complying with the World Athletics Rules for Road Race Events is permitted provided that: a) None of the equipment used at the start, along the course or at the finish line constitutes a material obstacle or barrier to the progress of an athlete; b) The weight of the transponder and its housing carried or worn by the athletes is not significant; c) The System is started by the Starter's gun or synchronized with the start signal; d) The System requires no action by an athlete during the competition, at the finish or at any stage in the result processing; e) For all races, the time shall be converted to 0.1 second and recorded to the whole second. All read times not ending in zero shall be converted	断や失格を決定しなくてはならない。 コメント：テクノロジーが利用可能な主要競技会では、写真判定画像は、大型映像(ビデオボード)にすぐに提供されるか、もしくはインターネット上に公開されることがよくある。不必要な抗議や訴えに費やされる時間を減らすために、写真を見る機会を抗議または上訴することを検討している競技者またはその代理人に写真判定画像を見る機会を提供することが今では通常の手続きとなっている。 20.23. 写真判定システムで記録された時間は、何らかの理由で担当競技役員が明らかに不正確であると判定した場合以外は公式時間とする。不正確な事例が発生した場合は、調整可能であれば写真から得られた時間差を基礎としながら、予備計時員の時間を公式のものとする。技術代表の判断により、写真判定装置がうまく作動しない可能性に備え、予備計時員を任命してもよい。 20.24. 写真判定による時間は、次のように写真仕上げ画像から読み取り記録される。 a) 10000m(を含む)以下のレースの時間は 0.01 秒表示の写真判定システムによって計時され 0.01 秒単位とする。厳密に 0.01 秒とならない場合は次のより長い 0.01 秒に変換する(切上げる)。 例： 26:17.533 → 26:17.54 b) 全部または一部が競技場外で行われるレースでは、秒未満の下 3 桁が厳密に「.000」にならない場合は、次のより長い 1 秒に変換する(切上げる)。 例： 2:09:44.32 → 2:09:45 注意：規則 11.2 に従って行われた種目の計時と記録の扱いは、競技場内で行われた種目として見なす トランスポンダーシステム 20.25. 道路競技における WA 競技規則に準拠したトランスポンダーシステムは、次の条件が整えば認められる。 a) スタート地点及びコース沿道あるいはフィニッシュ地点で使用される機器のいずれもが、競技者の前進に重大な障害または障壁になってはいない。 b) 競技者が身に着けるトランスポンダーやその入れ物は、負担にならない重さである。 c) システムはスターターの信号器によって始動するか、スタート合図に同期している。 d) システムは競技会の間やフィニッシュ地点または記録集計のいかなる過程でも、競技者が何かをする必要がない。 e) すべてのレースは 0.1 秒単位で計測され、0.1 秒表示がゼロでない場合、次の秒に切り上げる。マラソンの例では 2:39:44.3 は 2:39:45 と記録される。	トランスポンダーシステム
--	---	---------------------

and recorded to the next longer whole second, e.g., for the Marathon, 2:39:44.3 shall be recorded as 2:39:45; Note: The official time shall be the time elapsed between the firing of the starting gun (or the synchronised start signal) and the athlete reaching the finish line. However, the time elapsed between an athlete crossing the start line and the finish line can be made known to them, but will not be considered an official time. f) It is recommended that judges and/or video recording(s) also be provided to assist in determining the finishing order and the identification of athletes. 26. The Chief Transponder Timing Judge shall be responsible for the functioning of the System. Before the start of the competition, they will meet the technical staff involved and familiarise themselves with the equipment, checking all applicable settings. They shall supervise the testing of the equipment and ensure that the passing of the transponder over the finish line will record the athlete's finish time. In conjunction with the referee, they shall ensure that provision is made for the application, when necessary, of Rule 20.25 (f). COMMENT: Transponder timing is acceptable for World Record performances in races outside of the stadium. Rule 21: Seedings, Draws and Qualification in Track Events Rounds and Heats 1. Qualification Rounds shall be held in Track Events in which the number of athletes is too large to allow the competition to be conducted satisfactorily in a single round (final). Where Qualification Rounds are held, all athletes must compete in, and qualify through, all such rounds except that the relevant governing body, may, for one or more events, authorise the conduct of additional Qualification Round(s) either at the same competition or at one or more earlier competition(s) to determine some or all of the athletes who shall be entitled to participate and in which round of the competition. Such procedure and any other means (such as e.g. achieving entry standards during a specified period, by specified placing in a designated competition or by specified rankings) by which an athlete is entitled to participate, and in which round of the competition, shall be set out in the regulations for each competition. 2. The Qualification Rounds shall be arranged by the appointed Technical Delegates. If no Technical Delegates have been appointed, they shall be arranged by the LOC. The following tables shall, in the absence of extraordinary circumstances, be used to determine the number of rounds, and the number of heats in each round, to be held and the qualification procedure, i.e., those to advance by place (P) and time (T), for each round of Track	注意：公式の時間は信号器のスタート合図（または同期したスタート信号）から競技者がフィニッシュラインに到達するまでの時間である。ただし、非公認ではあるが、競技者がスタートラインを通過してからフィニッシュラインに到達するまでの時間を知らせることができる。 f) 着順の決定及び競技者の特定の助けとなるよう、審判員やビデオ記録を準備することを推奨する。 20.26. トランスポンダー主任は、システムの機能について責任を持つ。競技のスタート前に、担当の技術スタッフと打ち合わせ、装置を理解し、すべての設定を確認する。また、機器のテストを監督し、トランスポンダーのフィニッシュライン上通過時に競技者のフィニッシュ時間が記録されることを確認する。審判長と協力して、必要に応じて規則 20.25(f)適用の準備をしなければならない。 コメント：トランスポンダーによる時間は、競技場外でのレースにおいて、世界記録公認の対象となる。 第 21 条 トラック競技における予選の組み合わせ、抽選及び通過 予選 21.1. トラック競技における予選は、参加競技者が多数のため、決勝 1 回では満足に競技が運営できないときに行う。予選ラウンドを行う場合、全競技者が参加し、予選によって次のラウンドに進むようにしなければならないが、各加盟団体は一つあるいは複数の種目で、その競技会の中で、あるいはそれに先立つ別の競技会の結果で、参加資格を与える競技者の一部または全部を決めたり、その競技会のどのラウンドから出場することができるかを定める権限を持つ。どの競技者に参加資格を与え、どのラウンドから出場できるかという手順や考え方（特定の期間に達成された参加標準記録、指定競技会での順位やランキング等）については、各競技会の大会要項等に記載されなければならない。 21.2. 予選の組み合わせと予選通過の条件は技術代表が以下のように決める。もし技術代表が任命されていない場合は組織委員会が決める。 トラック種目のラウンド数、各ラウンドにおける組数、各ラウンドの予選通過者の決め方は、特別な事情がない限り、次の表を使用する。トラック競技で次のラウンドへの進出は、順位(P)及び記録(T)と表示される。	第 21 条 トラック競技における予選の組み合わせ 抽選及び通過 21.1. 予選
--	--	---

Events: Note: The applicable regulations may specify, following consultation with the Technical Delegate(s) where appointed, how vacant positions due to withdrawals in semi-finals and finals may be filled by the next ranked athlete(s) following the previous round after those qualified. a) Whenever possible, athletes of each nation or team and the best-performed athletes shall be placed in different heats in all Qualification Rounds of the competition. In applying this Rule after the first round, the required exchanges of athletes between heats should, to the extent possible, be made between athletes seeded in the same "group of lanes" according to Rule 21.4 (b). b) When heats are being arranged, it is recommended that as much information as possible about the performances of all athletes should be considered and the heats drawn so that, normally, the best performers reach the final. COMMENT: The Qualification Rounds should determine in the best possible way the athletes who will take part in the next round and eventually the final. This includes avoiding where possible the clashing of the best performed athletes (determined generally on performance in the qualification period but also taking into account such matters as outstanding recent career records) in the same heats as also applies to athletes from the same nation or team. For major competitions, at least, the basis of the seeding should be the best times achieved by each athlete in valid conditions (including with wind readings for the relevant events) during the predetermined period. This period will usually be specified in the Technical Regulations or in the document setting out the entry conditions and standards for the competition. Where there is no such specification, then the Technical Delegate(s) or the LOC should decide the basis on which the seeding will be determined. Such factors as performances achieved during training or tests, even if they appeared to look like competition or notions about what an athlete might "be worth" but has never achieved, should not be taken into account in seeding. The requirements of the Rule in relation to the "best performed athletes" does require some deviation from the strict protocol outlined above. For example, an athlete who might normally be seeded in a high position might not have any, or only a poor, valid performance in the predetermined period (through injury, illness, ineligibility or in the case of indoor meetings only have outdoor results). Whilst they would normally be placed lower or at the bottom of the seeding list, adjustment should be considered by the Technical Delegate(s). Similar principles should be applied to avoid a clash in a Qualification Round between athletes considered to be the favourites to place highly in the event if the results of the previous round would strictly dictate that they should be in the	注意：当該規定は、任命された技術代表との協議を経て、準決勝および決勝において棄権により空いたレーンについて、前ラウンドで当該ラウンドに進出する資格を獲得した競技者の次にランク付けされた競技者をどのように補充することを特定している。 a) 各国または各チームの競技者及び最も良い記録を持つ競技者は、競技会の予選ラウンドにおいて可能な限り異なった組に入れる。最初のラウンド後、この規則を適用するにあたっては各組間で競技者の交換が必要な場合は可能な範囲で、規則 21.4(b)に従い、同じ「レーン・グループ」間で行う。 b) 組編成にあたっては、できるだけ全競技者の成績を考慮し、もっともよい記録を持っている競技者が決勝に残れるように編成することが望ましい。 コメント：予選ラウンドは、次のラウンドに進み、最終的に決勝に進出する競技者を可能な限り最良の方法で決定しなければならない。これには、同じメンバーまたはチームの競技者だけでなく、上位記録を保持した競技者（一般的には参加標準記録有効期間の記録で決定されるが、直近の顕著な記録などもまた考慮される）が予選の同じ組に入らないよう可能な限り配慮すること含まれる。 主要競技会では、少なくとも、組み合わせの基本となるのは、事前に決められた期間中の有効な条件（関連種目の風速を含む）で各競技者が達成した最も良い記録でなければならない。この期間は通常、競技注意事項または競技会のエントリー条件と基準を定めた文書に明記される。そのような仕様がな場合、技術代表または組織委員会(LOC)は、組み合わせが決定される基本原則を決定すべきである。トレーニングやテストで得られた記録などの要素は、組み合わせにおいて考慮されるべきではない。最も良い記録を持つ競技者に関連する規則の要件では、上記で概説した厳密な適用条件からいくらかの逸脱を必要とすることもある。例えば、通常上位に組み分けされる可能性のある競技者が、所定の期間（怪我、病氣、資格停止、または室内競技会で屋外の記録しか持たないなど）で、有効記録を持たないとか、持っても良くないといったとき、その競技者は通常、組み合わせリストの下位置かれるが、技術代表による調整が検討されるべきである。 優勝候補者とみなされる競技者同士の予選ラウンドでの衝突を避けるために同様の原則を適用すべきである。 同時に、同じ国またはチームの競技者が異なる組になるよう調整する必要がある。 このような場合、組み合わせの調整は組み分けへ原案が出た直後に行うが、レーンを決める前に行うべきである。 これらの原則を適用する際には、競技者の入れ替えは：	
---	--	--

same heat. At this same time any adjustments to ensure as much as possible that athletes from the same nation or team are in different heats should also be made. In all such cases adjustments of the seeding should be made after the initial allocation to the heats but before any draw is made for the lanes. In applying these principles exchanges of athletes should be made:

- a) In the first round, between athletes with a similar ranking on the list of best valid performances during the pre-determined period; and
- b) In subsequent rounds, between athletes seeded in the same "group of lanes" according to Rule 21.4 (b).

Following these principles is more important in competitions in which the number of rounds has been reduced in some events - making accurate and well considered seeding vital to achieving both a fair and an athletically appealing outcome. For lower level competitions, the Technical Delegate(s) or the LOC may consider the use of different principles to achieve a similar final outcome.

100m, 200m, 400m,											
Declared Entries	First Round			Second Round			Semi-Finals				
	Heats	Place	Time	Heats	Place	Time	Heats	Place	Time		
9-16	2	3	2								
17-24	3	2	2								
25-32	4	3	4				2	3	2		
33-40	5	4	4				3	2	2		
41-48	6	3	6				3	2	2		
49-56	7	3	3				3	2	2		
57-64	8	3	8	4	3	4	2	4			
65-72	9	3	5	4	3	4	2	4			
73-80	10	3	2	4	3	4	2	4			
81-88	11	3	7	5	3	1	2	4			
89-96	12	3	4	5	3	1	2	4			
97-104	13	3	9	6	3	6	3	2	2		
105-112	14	3	6	6	3	6	3	2	2		

800m, 4x100m, 4x200m, 4x400m											
Declared Entries	First Round			Second Round			Semi-Finals				
	Heats	Place	Time	Heats	Place	Time	Heats	Place	Time		
9-16	2	3	2								
17-24	3	2	2								
25-32	4	3	4				2	3	2		
33-40	5	4	4				3	2	2		
41-48	6	3	6				3	2	2		
49-56	7	3	3				3	2	2		
57-64	8	2	8				3	2	2		
65-72	9	3	5	4	3	4	2	4			
73-80	10	3	2	4	3	4	2	4			
81-88	11	3	7	5	3	1	2	4			
89-96	12	3	4	5	3	1	2	4			
97-104	13	3	9	6	3	6	3	2	2		
105-112	14	3	6	6	3	6	3	2	2		

1500m											
Declared Entries	First Round			Second Round			Semi-Finals				
	Heats	Place	Time	Heats	Place	Time	Heats	Place	Time		
16-30	2	6	0								
31-45	3	8	0				2	6	0		
46-60	4	6	0				2	6	0		
61-75	5	5	0				2	6	0		

a) 第 1 ラウンドにおいて、あらかじめ決められた期間中に有効な最も良い記録のリストで同様のランキングを有する競技者との間で、そして：

b) 次のラウンドでは、規則 21.4(b)に基づく同様のランキングを有する競技者の間で。

これらの原則に従うことは、いくつかの種目でラウンド数を減らした競技ではより重要となる。公平でかつ陸上競技の魅力アピールを達成するためには、正確かつ十分に考慮された組み分けが不可欠である。下位レベルの競技会では、技術代表または組織委員会 (LOC) は、同様の最終結果を達成するために、異なる原則の使用を検討してもよい。

5000m <table><tr><th>Declared</th><th colspan="3">First Round</th><th colspan="3">Second Round</th><th colspan="3">Semi-Finals</th></tr><tr><th>Entries</th><th>Heats</th><th>Place</th><th>Time</th><th>Heats</th><th>Place</th><th>Time</th><th>Heats</th><th>Place</th><th>Time</th></tr><tr><td>20-40</td><td>2</td><td>8</td><td>0</td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td>41-60</td><td>3</td><td>10</td><td>0</td><td></td><td></td><td></td><td>2</td><td>8</td><td>0</td></tr><tr><td>61-80</td><td>4</td><td>8</td><td>0</td><td></td><td></td><td></td><td>2</td><td>8</td><td>0</td></tr><tr><td>81-100</td><td>5</td><td>6</td><td>0</td><td></td><td></td><td></td><td>2</td><td>8</td><td>0</td></tr></table> 10,000m <table><tr><th>Declared</th><th colspan="3">First Round</th></tr><tr><th>Entries</th><th>Heats</th><th>Place</th><th>Time</th></tr><tr><td>28-54</td><td>2</td><td>10</td><td>0</td></tr><tr><td>55-81</td><td>3</td><td>7</td><td>0</td></tr><tr><td>82-108</td><td>4</td><td>5</td><td>0</td></tr></table>										Declared	First Round			Second Round			Semi-Finals			Entries	Heats	Place	Time	Heats	Place	Time	Heats	Place	Time	20-40	2	8	0							41-60	3	10	0				2	8	0	61-80	4	8	0				2	8	0	81-100	5	6	0				2	8	0	Declared	First Round			Entries	Heats	Place	Time	28-54	2	10	0	55-81	3	7	0	82-108	4	5	0																																																																																																																																																																																																																																																																				
Declared	First Round			Second Round			Semi-Finals																																																																																																																																																																																																																																																																																																																																																						
Entries	Heats	Place	Time	Heats	Place	Time	Heats	Place	Time																																																																																																																																																																																																																																																																																																																																																				
20-40	2	8	0																																																																																																																																																																																																																																																																																																																																																										
41-60	3	10	0				2	8	0																																																																																																																																																																																																																																																																																																																																																				
61-80	4	8	0				2	8	0																																																																																																																																																																																																																																																																																																																																																				
81-100	5	6	0				2	8	0																																																																																																																																																																																																																																																																																																																																																				
Declared	First Round																																																																																																																																																																																																																																																																																																																																																												
Entries	Heats	Place	Time																																																																																																																																																																																																																																																																																																																																																										
28-54	2	10	0																																																																																																																																																																																																																																																																																																																																																										
55-81	3	7	0																																																																																																																																																																																																																																																																																																																																																										
82-108	4	5	0																																																																																																																																																																																																																																																																																																																																																										
The following alternative tables shall be used for the specific class or class combination as denoted in the respective table. For class combination not entirely covered by the below tables, the above regular tables shall normally be applied, otherwise an appropriate table shall be determined by the Technical Delegate.																																																																																																																																																																																																																																																																																																																																																													
100m, 200m, 400m, 800m (T11-12) <table><tr><th>Declared</th><th colspan="3">First Round</th><th colspan="3">Second Round</th><th colspan="3">Semi-Finals</th></tr><tr><th>Entries</th><th>Heats</th><th>Place</th><th>Time</th><th>Heats</th><th>Place</th><th>Time</th><th>Heats</th><th>Place</th><th>Time</th></tr><tr><td>5-8</td><td>2</td><td>1</td><td>2</td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td>9-12</td><td>3</td><td>1</td><td>1</td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td>13-16</td><td>4</td><td>1</td><td>4</td><td></td><td></td><td></td><td>2</td><td>1</td><td>2</td></tr><tr><td>17-20</td><td>5</td><td>1</td><td>7</td><td></td><td></td><td></td><td>3</td><td>1</td><td>1</td></tr><tr><td>21-24</td><td>6</td><td>1</td><td>6</td><td></td><td></td><td></td><td>3</td><td>1</td><td>1</td></tr><tr><td>25-28</td><td>7</td><td>1</td><td>5</td><td></td><td></td><td></td><td>3</td><td>1</td><td>1</td></tr><tr><td>29-32</td><td>8</td><td>1</td><td>8</td><td>4</td><td>1</td><td>4</td><td>2</td><td>1</td><td>2</td></tr></table> 1500m (T11-12) <table><tr><th>Declared</th><th colspan="3">First Round</th><th colspan="3">Second Round</th><th colspan="3">Semi-Finals</th></tr><tr><th>Entries</th><th>Heats</th><th>Place</th><th>Time</th><th>Heats</th><th>Place</th><th>Time</th><th>Heats</th><th>Place</th><th>Time</th></tr><tr><td>7-12</td><td>2</td><td>3</td><td>0</td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td>13-18</td><td>3</td><td>2</td><td>0</td><td></td><td></td><td></td><td></td><td></td><td></td></tr></table> 5000m, 10000m (T11-12) <table><tr><th>Declared</th><th colspan="3">First Round</th><th colspan="3">Second Round</th><th colspan="3">Semi-Finals</th></tr><tr><th>Entries</th><th>Heats</th><th>Place</th><th>Time</th><th>Heats</th><th>Place</th><th>Time</th><th>Heats</th><th>Place</th><th>Time</th></tr><tr><td>11-20</td><td>2</td><td>5</td><td>4</td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td>21-30</td><td>3</td><td>3</td><td>1</td><td></td><td></td><td></td><td></td><td></td><td></td></tr></table> 1500m, 5000m (T32-34 and T51-54) <table><tr><th>Declared</th><th colspan="3">First Round</th><th colspan="3">Second Round</th><th colspan="3">Semi-Finals</th></tr><tr><th>Entries</th><th>Heats</th><th>Place</th><th>Time</th><th>Heats</th><th>Place</th><th>Time</th><th>Heats</th><th>Place</th><th>Time</th></tr><tr><td>11-20</td><td>2</td><td>5</td><td>0</td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td>21-30</td><td>3</td><td>3</td><td>1</td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td>31-40</td><td>4</td><td>5</td><td>0</td><td></td><td></td><td></td><td>2</td><td>5</td><td>0</td></tr></table> 10000m (T32-34 and T51-54) <table><tr><th>Declared</th><th colspan="3">First Round</th><th colspan="3">Second Round</th><th colspan="3">Semi-Finals</th></tr><tr><th>Entries</th><th>Heats</th><th>Place</th><th>Time</th><th>Heats</th><th>Place</th><th>Time</th><th>Heats</th><th>Place</th><th>Time</th></tr><tr><td>13-24</td><td>2</td><td>6</td><td>0</td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td>25-36</td><td>3</td><td>4</td><td>0</td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td>37-48</td><td>4</td><td>3</td><td>0</td><td></td><td></td><td></td><td></td><td></td><td></td></tr></table> 4x100m, 4x100m Universal Relay, 4x400m (T11-13, T33-34, T51-52 and T53-54) <table><tr><th>Declared</th><th colspan="3">First Round</th><th colspan="3">Second Round</th><th colspan="3">Semi-Finals</th></tr><tr><th>Entries</th><th>Heats</th><th>Place</th><th>Time</th><th>Heats</th><th>Place</th><th>Time</th><th>Heats</th><th>Place</th><th>Time</th></tr><tr><td>5-8</td><td>2</td><td>0</td><td>4</td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td>9-12</td><td>3</td><td>0</td><td>4</td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td>13-16</td><td>4</td><td>0</td><td>8</td><td></td><td></td><td></td><td>2</td><td>0</td><td>4</td></tr></table>																				Declared	First Round			Second Round			Semi-Finals			Entries	Heats	Place	Time	Heats	Place	Time	Heats	Place	Time	5-8	2	1	2							9-12	3	1	1							13-16	4	1	4				2	1	2	17-20	5	1	7				3	1	1	21-24	6	1	6				3	1	1	25-28	7	1	5				3	1	1	29-32	8	1	8	4	1	4	2	1	2	Declared	First Round			Second Round			Semi-Finals			Entries	Heats	Place	Time	Heats	Place	Time	Heats	Place	Time	7-12	2	3	0							13-18	3	2	0							Declared	First Round			Second Round			Semi-Finals			Entries	Heats	Place	Time	Heats	Place	Time	Heats	Place	Time	11-20	2	5	4							21-30	3	3	1							Declared	First Round			Second Round			Semi-Finals			Entries	Heats	Place	Time	Heats	Place	Time	Heats	Place	Time	11-20	2	5	0							21-30	3	3	1							31-40	4	5	0				2	5	0	Declared	First Round			Second Round			Semi-Finals			Entries	Heats	Place	Time	Heats	Place	Time	Heats	Place	Time	13-24	2	6	0							25-36	3	4	0							37-48	4	3	0							Declared	First Round			Second Round			Semi-Finals			Entries	Heats	Place	Time	Heats	Place	Time	Heats	Place	Time	5-8	2	0	4							9-12	3	0	4							13-16	4	0	8				2	0	4	次の代替表は、それぞれの表に示されている特定のクラスまたはクラスの組み合わせに使用される。以下の表で完全にカバーされていないクラスの組み合わせについては、通常、上記の通常の表が適用される。それ以外の場合、適切な表は技術代表によって決定される									
Declared	First Round			Second Round			Semi-Finals																																																																																																																																																																																																																																																																																																																																																						
Entries	Heats	Place	Time	Heats	Place	Time	Heats	Place	Time																																																																																																																																																																																																																																																																																																																																																				
5-8	2	1	2																																																																																																																																																																																																																																																																																																																																																										
9-12	3	1	1																																																																																																																																																																																																																																																																																																																																																										
13-16	4	1	4				2	1	2																																																																																																																																																																																																																																																																																																																																																				
17-20	5	1	7				3	1	1																																																																																																																																																																																																																																																																																																																																																				
21-24	6	1	6				3	1	1																																																																																																																																																																																																																																																																																																																																																				
25-28	7	1	5				3	1	1																																																																																																																																																																																																																																																																																																																																																				
29-32	8	1	8	4	1	4	2	1	2																																																																																																																																																																																																																																																																																																																																																				
Declared	First Round			Second Round			Semi-Finals																																																																																																																																																																																																																																																																																																																																																						
Entries	Heats	Place	Time	Heats	Place	Time	Heats	Place	Time																																																																																																																																																																																																																																																																																																																																																				
7-12	2	3	0																																																																																																																																																																																																																																																																																																																																																										
13-18	3	2	0																																																																																																																																																																																																																																																																																																																																																										
Declared	First Round			Second Round			Semi-Finals																																																																																																																																																																																																																																																																																																																																																						
Entries	Heats	Place	Time	Heats	Place	Time	Heats	Place	Time																																																																																																																																																																																																																																																																																																																																																				
11-20	2	5	4																																																																																																																																																																																																																																																																																																																																																										
21-30	3	3	1																																																																																																																																																																																																																																																																																																																																																										
Declared	First Round			Second Round			Semi-Finals																																																																																																																																																																																																																																																																																																																																																						
Entries	Heats	Place	Time	Heats	Place	Time	Heats	Place	Time																																																																																																																																																																																																																																																																																																																																																				
11-20	2	5	0																																																																																																																																																																																																																																																																																																																																																										
21-30	3	3	1																																																																																																																																																																																																																																																																																																																																																										
31-40	4	5	0				2	5	0																																																																																																																																																																																																																																																																																																																																																				
Declared	First Round			Second Round			Semi-Finals																																																																																																																																																																																																																																																																																																																																																						
Entries	Heats	Place	Time	Heats	Place	Time	Heats	Place	Time																																																																																																																																																																																																																																																																																																																																																				
13-24	2	6	0																																																																																																																																																																																																																																																																																																																																																										
25-36	3	4	0																																																																																																																																																																																																																																																																																																																																																										
37-48	4	3	0																																																																																																																																																																																																																																																																																																																																																										
Declared	First Round			Second Round			Semi-Finals																																																																																																																																																																																																																																																																																																																																																						
Entries	Heats	Place	Time	Heats	Place	Time	Heats	Place	Time																																																																																																																																																																																																																																																																																																																																																				
5-8	2	0	4																																																																																																																																																																																																																																																																																																																																																										
9-12	3	0	4																																																																																																																																																																																																																																																																																																																																																										
13-16	4	0	8				2	0	4																																																																																																																																																																																																																																																																																																																																																				

Note: For World Championships and Paralympic Games, alternate tables may be included in the relevant Technical Regulations. COMMENT: The most complex event for seeding progressions is the 800m as it crosses both the laned events and non-lane events where seed performances are needed. This is critical for lane assignments as the progressions are based generally on finish place and time in the previous race and athletes are ranked according to seed times or performance in previous race, which are better than seed times are used (as noted in Rule 21.3 (b) below). Ranking and Composition of Heats 3. For the first round, the athletes shall be placed in heats using the zigzag distribution with the seeding determined from the relevant list of valid performances achieved during the predetermined period. a) After the first round, the athletes shall be placed in the heats of subsequent rounds in accordance with the following procedures: For events of 100m to 400m inclusive, and relays up to and including 4x400m, seeding shall be based upon placings and times of each previous round. For this purpose, athletes shall be ranked as follows: i) Fastest heat winner ii) 2nd fastest heat winner iii) 3rd fastest heat winner, etc. iv) Fastest 2nd place v) 2nd fastest 2nd place vi) 3rd fastest 2nd place, etc (Concluding with) vii) Fastest time qualifier viii) 2nd fastest time qualifier ix) 3rd fastest time qualifier, etc. b) For other events, the original performance lists shall continue to be used for seeding, modified only by improvements in performances achieved during the earlier round(s). c) The athletes shall then be placed in heats in the order of seeding in a zigzag distribution, e.g., three heats will consist of the following seedings: <table><tr><td>A</td><td>1</td><td>6</td><td>7</td><td>12</td><td>13</td><td>18</td><td>19</td><td>24</td></tr><tr><td>B</td><td>2</td><td>5</td><td>8</td><td>11</td><td>14</td><td>17</td><td>20</td><td>23</td></tr><tr><td>C</td><td>3</td><td>4</td><td>9</td><td>10</td><td>15</td><td>16</td><td>21</td><td>22</td></tr></table> d) In all cases, the order in which heats are to be run shall be determined by draw after the composition of the heats has been decided. COMMENT: For the first round in order to reduce the number of heats required, it is acceptable and normal for additional available lanes (for example a ninth lane on a straight or oval track) to be used in races up to and including 400m and to have more than one athlete in a lane at the start of an 800m race. The random draw to determine the order in	A	1	6	7	12	13	18	19	24	B	2	5	8	11	14	17	20	23	C	3	4	9	10	15	16	21	22	注意：世界選手権大会とパラリンピック競技大会については、これと別の表が競技注意事項の中に加えられることがある。 コメント：次ラウンドの組み合わせが最も複雑な種目は、組み分け方法がレーンを使う場合と使わない種目の両方がある 800m である。次ラウンドの組み合わせは一般に前のレースのフィニッシュ順位と時間に基づいており、競技者は前のレースの時間または記録に従ってランク付けされるため、これはレーン割り当てにとって重要である。 ランキングと予選の組合せ 21.3. 最初のラウンドにおいて、競技者は予め決められた期間内に達成された当該種目の有効な記録のリストからシードを決定し、ジグザク配置によって予選の組を決める。 a) 予選ラウンド等を行った後、下記の手順により、次のラウンドの組編成がなされる。 100mから 400m及び 4×400mリレーを含むリレーの種目は、その前のラウンドの順位と記録に基づいて組み分けする。そのために、競技者を以下のようにランキング分けをする。 i) 予選 1 位の中で 1 番速い者 ii) 予選 1 位の中で 2 番目に速い者 iii) 予選 1 位の中で 3 番目に速い者 iv) 予選 2 位の中で 1 番速い者 v) 予選 2 位の中で 2 番目に速い者 vi) 予選 2 位の中で 3 番目に速い者 (時間で通過した者) vii) 1 番目に速い者 viii) 2 番目に速い者 ix) 3 番目に速い者 b) その他の種目は、前のラウンドの記録によって編成する。 その他の種目では、元の成績リストは組み分けのために引き続き使われ、前のラウンドで記録が更新されたときのみ修正する。 c) 競技者はジグザク配置による順番で組み分けされる。 例：3 組の場合は次のような組編成になる。 <table><tr><td>A</td><td>1</td><td>6</td><td>7</td><td>12</td><td>13</td><td>18</td><td>19</td><td>24</td></tr><tr><td>B</td><td>2</td><td>5</td><td>8</td><td>11</td><td>14</td><td>17</td><td>20</td><td>23</td></tr><tr><td>C</td><td>3</td><td>4</td><td>9</td><td>10</td><td>15</td><td>16</td><td>21</td><td>22</td></tr></table> d) すべての場合において、走るべき組の順序は組の編成が決定された後、抽選によって決められる。 コメント：第 1 ラウンドでは、組数を減らすために、400m までのレースでは、追加レーン（例えば直走路や曲走路の第 9 レーン）を使用すること、800m のスタートでは 1 レーンに 2 人の競技者を入れることが許容され、普通に実践されている。 各組の実施順序を決定するランダム抽選は、公平さに基づいている。中距離及び長距離のレースでは、最終組を走る競技者は、次ラウンド進出のために出すべき記録を知ることができる。短い距離のレースで	A	1	6	7	12	13	18	19	24	B	2	5	8	11	14	17	20	23	C	3	4	9	10	15	16	21	22	ランキングと予選の組合せ
A	1	6	7	12	13	18	19	24																																																
B	2	5	8	11	14	17	20	23																																																
C	3	4	9	10	15	16	21	22																																																
A	1	6	7	12	13	18	19	24																																																
B	2	5	8	11	14	17	20	23																																																
C	3	4	9	10	15	16	21	22																																																

which the heats are conducted is based on fairness. In middle and long-distance races, the athletes running in the last heat will know as far as qualifying by times the performance they have to realise in order to qualify. Even with the shorter races there is a fairness aspect as weather conditions can change (rain suddenly falling or an alteration in wind strength or direction). Fairness dictates that order be determined by chance.

Draw for Lanes

4. For events 100m to 800m inclusive, and relays up to and including 4x400m, where there are several successive rounds of a race, lanes will be drawn as follows:

a) In the first round and any additional Qualification Round as per Rule 21.1, the lane order shall be drawn by lot;

b) **For any round after the first round**, athletes shall be ranked in accordance with the procedure shown above.

For an eight-lane track, three draws will then be made. When there are fewer or more than eight lanes, the principles in the following system with the necessary modifications should be used:

Lane Allocations Table

LANE DRAW (based on ranking procedure)	1st DRAW	2nd DRAW	3rd DRAW
100m	3, 4, 5 & 6	2 & 7	1 & 8
200m	5, 6 & 7	3, 4 & 8	1 & 2
400m & Relays (up to / including 4 x 400m) and 800m	4, 5, 6 & 7	3 & 8	1 & 2

VI LANE DRAW (based on ranking procedure)	1st DRAW	2nd DRAW	3rd DRAW
ALL RACES	3/4 & 5/6	7/8	1/2

Note (i): **Ambulant 800m races** may be run with one or two athletes in each lane. **However, at the Paralympic Games and WPA Championships (see Part B-3.1.2(a) and (b)), assigning two athletes in one lane should normally only be done in the first round**, unless because of ties or advancement by the Referee **or the Jury of Appeal**, there are more athletes in a race of a subsequent round than **lanes available**. **At WPA Sanctioned Competitions and WPA Approved Competitions 800m races may also be run without lanes using an arced start line or group starts.**

Note (ii): In any 800m race, including a final, where for any reason there are more athletes competing than lanes available, the Technical Delegate shall determine in which lanes more than one athlete will be drawn.

Note (iii): when there are more lanes than

も、気象条件が変わることがある（雨が突然降る、風の強さや方向が変わる）など公平性に関わる要素が存在する。組の順序は恣意的でなく偶然によって決定されることは公平性において重要である。

レーンの決定

21.4. 100mから 800mまで、また 4×400mまでのリレー競走で複数のラウンドが行われる場合は、そのレーン順は下記によって決める。

a) 最初のラウンドと規則 21.1 により追加的に行う予備予選ラウンドにおいて、レーン順は全員（または全チーム）を抽選で決める。

b) **最初のラウンド以降**は上記で示された手順により、各組終了後、競技者は次のようにランク付けされ抽選される。

8レーンのトラックの場合、3つのグループに分けて抽選を行う。8 レーン未満の場合、または 9 レーン以上の場合は、次の考え方を原則とし、必要な変更を加えて適用する。

注意(i)：立位の 800m 競走は、それぞれのレーンで 1 人または 2 人の競技者が走ってもよい。**パラリンピック大会および WPA 選手権大会（Part B-3.1.2(a) および (b)参照）では、同成績あるいは審判長またはジュリーの判断で次のラウンドに進出する競技者の数が利用可能なレーンを超える場合を除き、1レーンに 2 人の競技者を割り当てることは、通常、最初のラウンドのみとする。**WPA 認定競技会では、8 0 0 m 競走は弧状のスタートラインの使用やグループスタートさせることで、レーンを使用せずに実施することもできる。

注意(ii)：800m 競走においては、決勝を含めて何らかの理由により利用できるレーン数より競技者が多い場合、技術代表は複数の競技者をどのレーンに入れるか決定しなければならない。

注意(iii)：競技者数よりレーン数が多い場合は、常

athletes, the inside lane(s) should always remain free. COMMENT: With regard to Note (ii), there is no exact specification as to how the Technical Delegates should act as the situations which may give rise to it may vary greatly. However, this issue only affects the running of the first bend of the race and is not as important as the allocation of lanes in a shorter race. Technical Delegate(s) are advised to place the additional athlete(s) in the lane(s) where the "double-up" will cause least inconvenience - usually the outer lanes so that the athletes are not running around a tighter bend together. As to Note (iii), where a stadium has more than eight lanes available, the Technical Delegate(s) (or if none the LOC) should decide in advance which lanes are to be used for this purpose. For example, in the case of a nine-lane oval track, lane one would not be used in cases where less than nine athletes are taking part in a race. Consequently, for the purposes of Rule 21.4, lane 2 is regarded as lane 1 and so on. The allocation of lanes for T11-12 track races when a 9-lane track is being used is as follow: lanes 1-2, 3-4, 5-6, 7-8 are allocated to athletes and guide-runners with the outside lane (9) remaining free. Single Rounds 5. For any track events where only a single round (final) is required, lanes/starting positions shall be drawn by lot, except at the Paralympic Games and WPA Championships under Part B - 3.1.2 (a) and (b), for Track Events running entirely in lanes i.e., 100m, 200m, 400m, 4x100m lanes shall be drawn according to the ranking determined from the relevant list of valid performance achieved during that predetermined period and Rule 21.4 b) (i) (ii) (iii). COMMENT: The intent of this rule is to ensure that where there may not be sufficient athletes at a competition to justify heats and finals, that the better athletes are not disadvantaged by random lane draws. Therefore, at the Paralympic Games and WPA Championships seed times/performance achieved during a predetermined time period as specified in the technical regulations for the competition will be used to determine lane draws. 6. Where it is decided to conduct a series of races in an event rather than rounds and finals, the Regulations for the competition shall set out all relevant considerations including seedings and draws and the method by which the final results will be determined. 7. An athlete shall not be allowed to compete in a heat or lane other than the one in which their name appears, except in circumstances which, in the opinion of the Referee, justify an alteration. Progression 8. In all Qualification Rounds, unless otherwise provided by alternate tables permitted under Rule	に、内側のレーン（1レーンに限らず）を空けるべきである。 コメント：注意(ii)に関しては、技術代表がそうした状況にどのように対処すべきか、という明確な指針はない。しかし、この問題はレースの第一曲走路にしか影響せず、短距離レースでのレーンの割り当てほど重要ではない。技術代表は、1レーンに2人を入れるにあたり、そのレーンに配置される競技者の不便を最小限にするよう配慮が必要であり、通常では、競技者が急なカーブを走らなくてよいように、外側のレーンを使うことが多い。 注意(iii)については、競技場に8レーンよりもっとある場合は、技術代表（いない場合は、組織委員会(LOC)が）は、この目的のためにどのレーンを使用するかを事前に決定する必要がある。例えば、9レーンの周回トラックの場合、9人未満の競技者が競技に参加するとき、第1レーンは使用しない。したがって、規則21.4の目的のために、第2レーンは第1レーンとみなされ、以下同様である。9レーントラックが使用されている場合のT11-12トラックレースのレーンの割り当ては次のとおり。外側の第9レーンは空のまま、レーン1-2、3-4、5-6、7-8が、競技者とガイドランナーに割り当てられる。 単一ラウンド（予選のない決勝レース） 21.5. 予選がなく単一ラウンド（決勝）しかないトラック種目では、パラリンピック競技大会及びWPA競技会（PART-B 規則3.1.2(a)及び(b)参照）以外では抽選で決定する。パラリンピック競技大会及びWPA競技会では、すべてレーンを走るトラック種目、すなわち100m、200m、400m、4 x 100mでは、レーン順は、所定の期間中に達成された有効なパフォーマンスリスと及び規則21.4 b) (i)(ii)(iii)により決定されたランキングに従って決定する。 コメント：この規則の目的は、競技会で予選と決勝を実施するのに十分な競技者がいない可能性がある場合に、より良い競技者がランダムなレーン抽選によって不利にならないようにするためである。したがって、パラリンピック競技大会及びWPA競技会では、競技会の規則で指定されている所定の期間中に達成された時間/記録がレーン抽選を決定するために使用される。 21.6. 予選・決勝の方法以外で行われるレースでは、シードや抽選などラウンドの通過方法を含む必要な競技運営方法を決めておかなければならない。 21.7. 競技者はその氏名が載せられている組以外の組で競技することは許されないが、審判長が組合せを変更したほうが適当だと考えた場合はその限りではない。 次ラウンドへの進出 21.8. 規則21.2に基づく別表がない限り、予選では少なくとも各組の1着と2着は次のラウンドに出場	単一ラウンド（予選のない決勝レース） 次ラウンドへの進出
---	---	--

21.2, at least the first and second places in each heat shall qualify for the next round and it is recommended that, where possible, at least three in each heat should qualify.
Except where Rule 22 applies, any other athletes may qualify by place or by time according to Rule 21.2 the particular Technical Regulations, or as determined by the Technical Delegate(s). When athletes are qualified according to their times, only one system of timing may be applied.

Note: If the Technical Delegate decides different tables are to apply, it is recommended in races longer than 800 metres where rounds are conducted, that only a small number of athletes qualify by time.

COMMENT: Where tables are prescribed in the regulations for a competition it is usual that the principle set out in Rule 21.8 will have been incorporated. Where not, the Technical Delegates or LOC should follow same principle when establishing the progression table to be used. There will however be occasions when Rule 22 may cause a variation to be applied, particularly where there is a tie for the last qualifying position based on place. In such cases, it may be necessary for one less athlete to progress on time. In circumstances where there are sufficient additional lanes available, or in the case of the 800m (where a lane at the start may be used for more than one athlete) or a non-laned race, the Technical Delegate(s) may decide to progress an additional athlete(s). Because of the provision within Rule 21.8 that for time qualification only one system of timing may be applied it is important for back-up timing systems to be available for qualification rounds in case the primary system (usually photo finish) fails. In the event that only times from different timing systems are available for two or more heats, the Technical Delegates in conjunction with the Track Referee should determine, within the circumstances of the particular competition, the fairest method for determining those athletes who should proceed to the next round. Where additional lanes are available, it is recommended that this option be considered first.

One Day Meetings

9. In WPA Approved Competitions under Part B - 3.1.2 (d), athletes may be seeded, ranked and/or allocated to lanes in accordance with the applicable regulations for the competition or any other method determined by the LOC but preferably notified to the athletes and their representatives in advance.

COMMENT: In one day meetings, if there is only a "final" round but with more than one race, the races should be arranged according to any applicable regulations for the meeting or the series of meetings of which it is a part. If there are none then it is usual for allocation of athletes to the various "races" to be undertaken by the LOC or if requested by the appointed Technical Delegate(s).

する資格があり、可能な限り各組 3 着まで出場の資格を与えることが望ましい。規則 22 の適用以外では、規則 21.2 により着順または時間、特別に設けられた競技規定、または技術代表による決定のいずれかによって競技者を次のラウンドに進出させてもよい。競技者が時間によって資格が与えられる場合には、その決定方法は同一の計時方法に限る。
注意：技術代表が異なる方法を適用する場合、予選が行われる 800m 以上のレースでは、時間により次ラウンドへの進出資格が与えられる競技者は少数とすることを推奨する。

コメント：組み合わせのためのテーブルが競技会規定で定められている場合、規則 21.8 に定める原則が組み込まれているのが通常である。そうでない場合、技術代表者または組織委員会(LOC)は、使用する次ラウンド進出基準を確立する際に同じ原則に従うべきである。ただし、規則 22 により、特に着順に基づいて最後の枠が同成績で決まる場合には、バリエーションが適用される場合がある。そのような場合には、時間での次ラウンド進出者を 1 人減らす必要がある。利用可能なレーンが十分にある場合、または 800m の場合（スタート時のレーンが 2 人以上の競技者に使用される場合）またはレーン以外のレースの場合、技術代表は追加競技者の進出を判断することがある。
1 つのタイミングシステムのみが適用されると規則 21.8 に規定されているため、優先的に使用しているシステム（通常は写真判定）に障害が発生した場合に備え、バックアップタイミングシステムを予選ラウンドに用意することが重要となる。技術代表は、2 つ以上の組に異なるタイミングシステムからの時間しか得られない場合、審判長と協働して、特定の競技会の状況の中で、次ラウンド進出者を決定するための公平な方法を決定しなければならない。追加レーンがある場合は、この選択肢を最初に検討することは推奨される。

1 日開催の競技会

21.9. PART-B 規則 3.1.2 の WPA 承認競技会では、競技者は適用される競技会規定や組織委員会が定めた他の方法によって組分け、順位付け、レーンの割り当てが行われるが、その内容は事前に競技者や競技者の代理人に通知することが望ましい。

コメント：1 日のみで実施される競技会では、「決勝」ラウンドのみだが複数のレースがある場合、レースは、競技会またはその競技会が属している一連の競技会シリーズのための開催規定に従って実施される必要がある。もし規定が存在しなければ、様々な「レース」への競技者の割り振りは、組織委員会、もしくは任命されているなら技術代表が行うのが、一般的である。

このような競技会では、競技者の最終順位がどのように決定されるかについても、同様の考慮がなされる。い

Similar considerations apply to how the final ranking of the athletes in such events will be made. In some meetings the “race(s)” other than the main race are regarded as separate races and are not considered for the overall ranking but in others the results of more than one race are “combined” to give the overall ranking. It is highly advisable to ensure that whichever is to apply for the competition is also notified to the participants in advance as it may affect prizes and other considerations. Minimum Times between Rounds. 10. The following minimum times must be allowed, when practicable, between the last heat of any round and the first heat of a subsequent round or final: Up to and including 200m : 45 minutes Over 200m up to and including 1000m : 90 minutes Over 1000m : Not on the same day Rule 22: Ties 1. If the Judges or the Photo Finish Judges are unable to separate the athletes for any place according to Rules 19.2, Rule 19.3, and 20.18, 20.22 or 20.25 (as may be applicable), it shall be determined to be a tie and the tie shall remain. Tie for ranking position (according to Rule 21.3 (a)) 2. If there is a tie for any ranking position under Rule 21.3 (a), the Chief Photo Finish Judge shall consider the actual times recorded by the athletes to .001 second and if it is equal, the tie shall remain and lots shall be drawn to determine the higher ranking position. Tie for last qualifying position based on place 3. If after the application of Rule 22.1, there is a tie for a last qualifying position based on place, if there are lanes or positions available (including lane sharing in 800m races) the tying athletes shall be placed in the next round. If that is not practicable lots shall be drawn to determine which athlete(s) shall be placed in the next round. 4. Where qualifying for the next round is based on place and time (e.g., the first three in each of two heats plus the next two fastest), and there is a tie for the last qualifying position based on place, placing the tied athletes in the next round shall reduce the number of athletes qualifying based on time. Tie for last qualifying position based on time 5. If there is a tie for a last qualifying position based on time, the Chief Photo Finish Judge shall consider the actual times recorded by the athletes to .001 second and if it is equal, the tie shall remain. If there are lanes or positions available (including lane sharing in 800m races) the tying athletes shall be placed in the next round. If that is not practicable lots shall be drawn to determine which athlete(s) shall be placed in the next round.	くつかの競技会では、メインレース以外の「レース」は別レースとみなされ、総合ランキングとして考慮されないが、他の競技会では、各レースの結果はひとつにまとめられて総合ランキングになるものもある。賞品やその他の考慮事項に影響を及ぼす可能性があるため、その競技会では、どちらの順位づけが適用されるのかなど、事前に参加者に通知することを強く推奨する。 次ラウンドまでの最小時間 21.10. 一つのラウンドの最後の組と次のラウンドの最初の組、あるいは決勝競技との間には、最小限次の時間をおかなければならない。 200m (含めて) まで : 45 分 1000m (含めて) まで : 90 分 1000m を超える種目については同一日としない。 第 22 条 同成績 22.1. 決勝審判員もしくは写真判定員が規則 19.2、19.3、20.18、20.22、または 20.25 により、どの順位においても競技者を区別することが不可能なとき、それは同成績と決定され、同成績はそのままとする。 規則 21.3(a)による同順位 22.2. (着順ではなく) 時間を元にして規則 21.3(a)によるランキングの順位が同じ場合は、写真判定員主任は 0.001 秒の実時間を判定しなければならない。それでも同じであれば同成績とし、ランキングの順位を決める抽選を行う。 着順による最後の 1 枠が同順位 22.3. 規則 22.1 を適用しても、着順による最後の 1 枠を決めるにあたり同成績がいる場合、空きレーンがあるか、走る場所がある (800m 競走でレーンに複数割り当てする場合を含む) のであれば、同成績者は次のラウンドに進めるようにするべきである。不可能なら、次ラウンドへの進出者は抽選により決める。 22.4. 着順と時間で次ラウンド進出者を決める方法 (例 : 2 組で行い、各組 3 着までと 4 着以下の上位記録 2 名が次ラウンド進出) において、着順で決める最後の 1 枠が同成績だった場合、同成績 (同着) の競技者を次ラウンドに進出させ、その分、時間に基づいて次ラウンドへの進出を認める競技者の数を減らす。 時間による最後の 1 枠が同順位 22.5. 時間による最後の 1 枠に同成績がいる場合、写真判定主任は 0.001 秒の実時間を考慮しなければならない。それでも同じであれば同成績とする。空きレーンがあるか、走る場所がある (800m 競走でレーンに複数割り当てする場合を含む) のであれば、同成績者は次のラウンドに進めるようにするべきである。不可能なら、次ラウンドへの進出者は抽選により決める。	第 22 条 同成績 規則 21.3 (a) による同順位 着順による最後の 1 枠が同順位 時間による最後の 1 枠が同順位
--	--	---

Rule 23: Relay Races 1. Lines 50mm wide shall be drawn across the track to mark the distances of the legs and to denote the scratch line. 2. In ambulant relay races of 4x100m, 4x200m relays and for the first and second take-overs in the 4x100m universal relays, each take-over zone shall be 30m long, of which the scratch line is 20m from the beginning of the zone. For wheelchair relay races of 4x100m and 4x400m and for the third take-over in the 4x100m universal relay, the take-over zone shall be 40m long of which the scratch line is 30m from the beginning of the zone. The zones shall start and finish at the edges of the zone lines nearest the start line in the running direction. For each takeover conducted in lanes, a designated official shall ensure that the athletes are correctly placed in their takeover zone. The designated officials shall also ensure that Rule 23.3 is observed. COMMENT: The Umpires must ensure that each athlete from each team takes their position in the correct lanes or position. The Starter's Assistants will be responsible for the positioning of the first runners and for ensuring that each is supplied with a baton when required. They may also be assigned to assist at any takeover zones which subsequently occur at the start line. Chief Umpires for each takeover zone and the umpires placed at their disposal will be responsible for the positioning of the subsequent runners. When all athletes are correctly positioned, the zone Chief Umpire should advise the relevant other officials by the agreed means of communication – which for major competitions would usually be by radio. They must also ensure that for all takeovers the outgoing runners' feet, prosthetic device(s) and both rear wheels are completely inside the zone before they commence their movement which eventuates in either the taking of the baton or the touch. This movement may not commence at any point outside the zone. 3. When all or the first portion of a relay race is being run in lanes, an athlete or guide-runner may place one check-mark on the track within their own lane, by using adhesive tape, maximum 5cmx40cm, of a distinctive colour which cannot be confused with other permanent markings. No other check-mark may be used. The Umpires shall direct the relevant athlete(s) to adapt or remove any marks not complying with this Rule. If they do not, the Umpires shall remove them. Note (i): Serious cases may further be dealt with under Rule 8.1 and Rule 8.3. Note (ii): For the 4x100m universal relay, the Technical Delegate(s) may, upon request, permit an assistant at each take-over zone, to help the athlete with the placement of a distinctive check-mark on the track within their own lane.	第23条 リレー競走 23.1. 幅 50 mmのラインをトラックに横に引いて、各区域の距離とセンターラインを示す。 23.2. 立位の4×100mと4×200mリレーの全走者間、及びユニバーサル 4x100mリレーの第1走者と第2走者間、第2走者と第3走者間のテイクオーバーゾーンは 30mとし、ゾーンの入口から 20mが基準線となる。ゾーンは、走る方向においてスタートラインに近い端を基点とする。車いすの 4×100mリレーと4×400mリレーの全走者間、及びユニバーサル 4x100mリレーの第3走者と第4走者間、のテイクオーバーゾーンは 40mとし、ゾーンの入口から 30mが基準線となる。ゾーンは、走る方向においてスタートラインに近い端を基点とする。レーン内で行われる各バトンの受け渡しについて、担当する競技役員は、各競技者が正しいテイクオーバーゾーンの位置にいることを確認する。また、その競技役員は規則 23.3（マーカ―の数とサイズ）が確実に遵守されるようにしなければならない。 コメント：監察員は、各チームの各競技者が正しいレーンまたは位置で自身の位置をとるようにしなければならない。出発係は、最初のランナーの配置と各バトンを実際に渡す責任がある。出発係はまた、テイクオーバーゾーンのスタートラインを支援するために割り当てられることもある。 各テイクオーバーゾーンの監察員主任と配置された監察員は、次走者の位置取りが正しいかどうかの責任を負う。 すべての競技者がゾーンに正しく位置についたら監察員主任は、合意された連絡手段（主要競技会では通常無線機）によって、関係する他の競技役員に連絡する必要がある。 監察員はまた、各テイクオーバーにおいて、バトンを受け取る際、あるいはタッチの際に移動を開始する前に、出走するランナーの足がゾーンに完全に入っていることを確認しなければならない。この動きは、ゾーン外のいかなる場所で開始されてもいけない。 23.3. レーンでリレーを行う場合、競技者またはガイドランナーは大きさが最大 50mmx400mm で他の恒久的なマーキングと混同しないようなはっきりとした色の粘着テープをマーカ―として 1 か所、自らのレーン内に貼ることが許される。それ以外のマーカ―の使用は認められない。この規則に違反するマーカ―があれば、規則に合わせるよう、あるいは剥がしたり動かしたりするよう、監察員は当該競技者を指導しなければならない。指導に従わない場合には、監察員が取り除かなくてはならない。 注意(i)：悪質と考えられる場合は、規則 8.1 または 8.3.を適用することができる。 注意(ii)：4x100m ユニバーサルリレーでは、技術代表は、要求に応じて、各テイクオーバーゾーンで競技者が自身のレーンにチェックマークを置く手助けを、アシスタントが行うことを許可できる。	第23条 リレー競走
---	---	------------------------------

4. The relay baton shall be a smooth hollow tube, circular in section, made of wood, metal or any other rigid material in one piece, the length of which shall be 28cm to 30cm. The outside diameter shall be 40mm (±2mm) and it shall not weigh less than 50g. It should be coloured so as to be easily visible during the race. Note: For wheelchair relays in the Paralympic Games and WPA Championships (see Part B – 3.1.2 (a) and (b)), the LOC shall provide helmet socks to each team of a distinctive colour so as to be easily identified during the race. COMMENT: For the Wheelchair relay races helmet socks shall be required to be worn by athletes in addition to or in place of helmet numbers. Where this is required, the LOC shall ensure that helmet socks are available. The Call Room Judges are responsible for ensuring that the helmet socks are checked in the Call Room. 5. a) A baton shall be used for all Relay Races held in the Stadium and shall be carried by hand throughout the race except as stated in Rule 23.6 for wheelchair relays, amputee relays and 4x100m universal relays. At least in the Paralympic Games and WPA Championships (see Part B - 3.1.2 (a) and (b)), each baton shall be numbered and of a different colour and may include a timing transponder. Note: If possible, the allocation of the colour to each lane or starting order position should be shown on the start list. b) Athletes and guide-runners are not permitted to wear gloves or to place material (other than those permitted by Rule 7.4(c) or substances on their hands or on the baton in order to obtain a better grip of the baton. c) If dropped, the baton shall be recovered by the athlete or guide-runner who dropped it. They may leave their lane to retrieve it provided that, by doing so, they do not lessen the distance to be covered. In addition, where the baton is dropped in such a way that it moves sideways or forward in the direction of running (including beyond the finish line), the athlete or guide-runner who dropped it, after retrieving it, must return at least to the point where it was last in their hand before continuing in the race. Provided this procedure is adopted and no other athlete or guide-runner is impeded, dropping the baton shall not result in disqualification. If an athlete or guide-runner does not follow this Rule, their team shall be disqualified. 6. The baton shall be passed within the take-over zone. The passing of the baton commences when it is first touched by the receiving athlete or guide-runner and is completed the moment it is in the hand of only the receiving athlete or guide-runner. In relation to the take-over zone, it is only the position of the baton that is decisive, and not the position of the bodies of the athletes.	23.4. バトン継ぎ目のない木材、または金属その他の硬い物質でつくられ、断面が丸く、滑らかで中空の管でなければならない。長さは 28cm～30cm で、直径は 40 mm (±2mm)、重さは 50g 以上とする。またレースにおいて、容易に識別できる色でなければならない。 注意：パラリンピック競技大会及び WPA 競技会 (PART-B 規則 3.1.2(a)及び(b)を参照)の車いすリレーの場合、レース中に簡単に識別できるよう、組織委員会は各チームに識別できる色のヘルメットソックスを提供する。 コメント：車いすリレーでは、競技者はヘルメット番号に加えて、またはヘルメット番号の代わりにヘルメットソックスを着用しなければならない。これが必要な場合、組織委員会はヘルメットソックスが用意されていることを確認しなければならない。招集所審判員は招集時にヘルメットソックスの着用確認をする責任がある。 23.5. a) 規則 23.6 にある車いすリレー、切断競技者リレー及び 4 x 100mユニバーサルリレーを除き、バトンは競技場内で行われるすべてのリレー競技で使用され、レース中は手で持ち運ばなければならない。少なくともパラリンピック及び WPA 選手権 (PART-B 規則 3.1.2(a),(b)参照)では、各バトンに番号を付し異なる色とする。また、トランスポンダーシステムを組み込んでもよい。 注意：可能であれば、各レーンに割り当てられたバトンの色をスタートリストに記しておくこと。 b) 競技者及びガイドランナーは、バトンを受け取りやすくする目的で手袋をはめたり (規則 7.4(C)で認められた以外の) 何かを手およびバトンに付けたりすることはできない。 c) もしバトンを落した場合、落とした競技者またはガイドランナーがバトン拾って継続しなければならない。この場合、距離が短くならないことを条件にバトン拾うために自分のレーンから離れてもよい。加えて、そのような状況でバトンを落としたとき、バトンが横や進行方向 (フィニッシュラインの先も含む) に転がり、拾い上げた後、競技者またはガイドランナーはバトンを落とした地点に戻ってレースを再開しなければならない。上記の手続きが適正になされ、他の競技者またはガイドランナーを妨害しない限りは、バトンを落としても失格とはならない。一方、競技者またはガイドランナーがこの規則に従わなければ、そのチームは失格となる。 23.6. バトンは、テイクオーバーゾーン内で「パス」をおこなわなくてはならない。ここでいうバトンの「パス」は、受け取る競技者またはガイドランナーにバトンが触れた時点に始まり、受け取る競技者またはガイドランナーの手の中に渡った時点で完了となる。テイクオーバーゾーン内では、バトンの位置のみが決定的なものであり、競技者の身体的位置ではない。テイクオーバーゾーンの外でのバトンの「パス」は失格となる。該当する場合、規則 18.5(b)が適用される。
---	---

Passing of the baton outside the take-over zone shall result in disqualification. Rule 18.5(b) shall apply when relevant. COMMENT: The application of Rule 18.5(b) may be necessary when an athlete, during the takeover, steps outside the allocated lane inside the takeover zone without material advantage gained and other athletes obstructed. In determining the position of the baton, it is the whole baton which must be considered. Umpires must be diligent to ensure that they observe any contact by the outgoing runner with the baton prior to the baton entering the takeover zone, particularly in 4x400m ambulant relays. If the outgoing runner even touches the baton prior to the baton being inside the zone, the team will be subject to disqualification. They must also ensure that the baton is only in the hand of the receiving athlete before it "leaves" the takeover zone. For wheelchair relays (T33-34, T51-52 and T53-54), ambulant relays (T42-47, T61-64) and the 4x100m universal relay the Take-over shall be by a touch on any part of the body of either the incoming or outgoing athlete. The first touch must be within the Take-over Zone. Pushing the outgoing athlete to gain advantage during Take-over shall result in disqualification. Note: For the 4x100m universal relay, the helmet worn by the wheelchair athlete is considered as a part of the body. 7. Athletes and guide-runners before and/or after the completion of the Take-over, should keep in their lanes or zones or maintain position until the course is clear to avoid obstruction to other athletes and guide-runners. Rule 18.2 and Rule 18.5 shall not apply to those athletes and guide-runners. If an athlete or guide-runner impedes a member of another team by running out of position or lane at the finish of their leg, Rule 18.1 shall be applied. 8. Baton Exchange for T11-13 Relays: a) Either the athlete or the guide-runner can carry the baton; b) The baton exchange may take place between either guide-runners or athletes without restriction, except that the conditions of the method of guidance must be met; c) A fair exchange is established when the baton carrier passes the baton to the baton receiver within the take-over zone; d) Once the outgoing athletes and/or guide-runner leaves the take-over zone they can re-enter the take-over zone to receive the baton (i.e., if they go too early); e) One (1) assistant per take-over zone will be allowed on the track to help with the positioning of any T12 athlete competing without a guide-	コメント：規則 18.5.(b)が適用されるのは、バトンパスをおこなっている最中に、実質的な利益を得ず、他の競技者が妨害されることもなく、テイクオーバーゾーンの割り当てられたレーンの内側を踏んだ場合に適用されることがある。バトンの位置を決めるにあたっては、バトン全体を考慮する必要がある。監察員は、バトンがテイクオーバーゾーンに入る前に、特に立位の4x400m 以上のリレーで、次走者がバトンに触れる位置を確実に監察する必要がある。バトンがゾーン内に入る前に受け取り側の競技者がバトンに触れても、チームは失格となる。監察員はまた、競技者がゾーンから出る際には、バトンが受け取り側の競技者の手の中だけにあることを確認しなければならない。 車いすリレー（T33-34、T51-52 及び T53-54）、立位のリレー（T42-47、T61-64）及び 4x100m ユニバーサルリレーの場合、テイクオーバーは渡す競技者または受け取り側の競技者のいずれかのボディの任意の部分タッチすることによる。最初のタッチはテイクオーバーゾーン内である必要がある。テイクオーバーの最中に、次走者を押す行為によって利益を得ようとした場合は失格となる。 注意：4x100m ユニバーサルリレーでは、車いすの競技者が着用するヘルメットは体の一部と見なされる。 23.7. テイクオーバーを完了する前、最中、後、競技者及びガイドランナーは他の競技者への妨害を避けるため、走路が空くまで自分のレーンまたはその位置（ゾーン）にとどまる。規則 18.2、規則 18.5 は適用されない。競技者がバトンを渡し終えた後、自分の位置やレーンの外を走ること、他のチームのメンバーを妨害したときは、規則 18.1 が適用される。 23.8. 競技クラス T11-13 のリレー競技におけるバトン引き継ぎ a) バトンは競技者とガイドランナーのいずれが持ってもよい。 b) バトンの引き継ぎは、誘導方法に関する要件が満たされてさえいれば、ガイドランナー同士で行っても、競技者同士で行ってもかまわない。 c) 所定のテイクオーバーゾーン内で渡す側から受け取る側にバトンが手渡されたときに、公正なバトンの引き継ぎが行われたと見なされる。 d) テイクオーバーゾーンを一度出てしまった次走者は、テイクオーバーゾーンに戻ってバトンを受け取ることはできる（走り始めるのが早すぎた場合）。 e) 競技クラス T12 の競技者が伴走者なしで競技する場合、競技者の位置決めを補助するためのアシスタントを各テイクオーバーゾーンに 1 名ずつトラック上に配置することが認められる。アシスタントは、スタート前に	
---	---	--

runner. The assistant must leave the competition area prior to the start of the event and must remain in a position designated by the technical officials which does not interfere with the conduct of the race. In violation of this rule, the athlete shall be warned or disqualified subject to Rule 7.2.

9. If during the race an athlete takes or picks up the baton of another team, their team shall be disqualified. The other team should not be penalised unless an advantage is obtained.

10. Each member of a relay team may run one leg only. Any four athletes and with their accompanying guide-runner(s) from among those entered for the competition, may be used in the composition of the relay team for any round. However, once a relay team has started in a competition, up to a total of four additional athletes who have been entered in the same race and their corresponding guide-runners may be used as substitutes in the composition of the team. If a team does not follow this Rule, it shall be disqualified.

Note: The substitution of guide-runners shall not count towards the overall substitution of athletes.

11. The composition of a team and the order of running for a relay shall be officially declared no later than one hour before the published first call time (the time by which the athletes must be present in the Call Room) for the first heat of each round of the competition. Further alterations must be verified by a medical officer appointed by the LOC and may be made only until the final call time (the time at which the athletes are listed to depart the Call Room) for the particular heat in which the team is competing. The team shall compete as named and in the declared order. If a team does not follow this Rule, it shall be disqualified. At WPA Recognised Competitions (see Part B - 3.1.2) relays can be contested in accord with clusters of Sports Classes and associated team composition requirements stipulated in the Table below.

Sports Class/es	Relay Team Composition Requirements
T11-13	Must include a minimum of one (1) Sports Class T11 athlete and can only include a maximum of one (1) Sports Class T13 athlete.
T33-34	Must include at least one (1) Sports Class T33 athlete
T35-38	Can only include a maximum of two (2) Sports Class T38 athletes
T42-47, T61-64	Can only include a maximum of two (2) Sports Class T46/47 athletes
T51-52	Must include at least one (1) Sports Class T51 athlete
T53-54	Must include at least one (1) Sports Class T53 athlete

Team composition, running order and eligible Sport Classes for the 4x100m universal relay are stipulated as follows:

- The team must include two (2) male and two (2) female eligible athletes.
- A maximum of two (2) athletes must be selected from the following Sports Classes: T13, T46/47, T38, T54.

競技エリアから離れ、競技進行の妨げにならないよう、競技役員に指定された場所にいないといけない。この規則に違反した場合、規則 7.2 により、競技者は警告を受けるか、または失格となる。

23.9. レース中、競技者が他チームのバトンを使ったり、拾い上げた場合、そのチームは失格となる。相手チームは、有利にならない限り失格とはならない。

23.10. リレーメンバーが走ることができるのは 1 区間だけである。リレーチームの編成メンバーは、どのラウンドにおいてもその競技会に申し込んでいる競技者とそのガイドランナーであれば出場することができる。ただし、いったんリレー競技が開始された後は、その後のラウンドを通して、その競技会にエントリーしている 4 人まで、またそれに対応するガイドランナーに限り、交代要員として使うことができる。この規則に従わなければ、チームは失格となる。

注意：ガイドランナーの交代は、競技者交代の数に含まれない。

23.11. リレーチームの編成は、各ラウンドの第 1 組目の第 1 次招集時刻の 1 時間前まで(それまでに競技者が招集所にいなくてはならない時間)に正式に申告しなければならない。一度申告したらその後の変更は、その組の招集完了時刻(競技者が招集所を出発する時間)までに組織委員会が任命した医務員の判断がない限り認められない。各チームは申告された競技者がその順番で走らなければならない。この規則に従わなければ、そのチームは失格となる。

WPA 認可競技会(PART-B 規則 3.1.2 参照)における競技クラスとチーム構成に関する要件は以下のテーブルによる。

競技クラスチーム構成要件

T11-13 T11 クラスは 1 名以上。T13 クラスは 1 名以下。

T33-34 T33 クラスは 1 名以上。

T35-38 T38 クラスは 2 名以下。

T42-47, T61-64 T46/47 クラスは 2 名以下。

T51-52 T51 クラスは 1 名以上。

T53-54 T53 クラスは 1 名以上。

4x100m ユニバーサルリレーのチーム構成、走順、及び競技クラスは、次のように規定される。

- チームには、男性 2 名と女性 2 名の資格ある競技者が含まれていなければならない。
- 次の競技クラス (T13、T46/47、T38、T54) から 2 名以下。
- 残りの 2 名は、以下の表に記載されている他の競技クラスから選ぶ。

- The remaining two (2) athletes must be selected from any of the other Sport Classes outlined in the table below.
- The running order must be in accordance with the below table :

Running Order	Eligible Classes
First Leg	T11-13
Second Leg	T42 – 47, T61 - 64
Third Leg	T35 -38
Fourth Leg	T33 - 34, T51- 54

COMMENT: In all relay races, strategy plays an important role. For example, some teams may select the fastest runner first, second fastest second etc., with the slowest runner finishing the race. Other teams could use a completely different strategy. For the 4x100m universal relay it is not that simple. Unlike the ambulant and wheelchair relay races, for the 4x100m universal relay there are additional requirements. Firstly, the team must be composed of two (2) male and two (2) female athletes. Secondly, a predetermined running order must be respected at all times during the race, which means that each leg shall be run by athletes from different Sport Classes as described in the above table. Finally, only a maximum of two (2) athletes may be selected from the following Sports Classes: T13, T46/47, T38, and T54. Therefore, depending on the team's strategy, they may choose none (0), one (1) or two (2) athletes from these classes. It is very important to note that regardless of the team's strategy, only a maximum of two (2) athletes from the previous Sport Classes can be selected. As an example, where a team has selected a T13 and T54 athlete for the First and Fourth Leg respectively, then for the Second and Third Legs they cannot select participants from Sport Classes T38 or T46/47.

12.The 4x100m including the 4x100m universal relay race shall be run entirely in lanes.

13.The 4x200m race may be run in any of the following ways:

- where possible, entirely in lanes (four bends in lanes)
- in lanes for the first two legs, as well as that part of the third leg up to the nearer edge of the breakline described in the Rule 18.7, where athletes may leave their respective lanes (three bends in lanes),
- in lanes for the first leg up to the nearer edge of the breakline described in Rule 18.7, where athletes may leave their respective lanes (one bend in lanes).

Note: Where not more than four teams are competing and option (a) is not possible, it is recommended that option (c) should be used.

- 走順は、以下に示すとおりとする：

走順 参加資格のある競技クラス
 第 1 走 T11-13
 第 2 走 T42-47、T61-64
 第 3 走 T35-38
 第 4 走 T33-34、T51-54

コメント：すべてのリレーレースでは、戦略が重要な役割を果たす。たとえば、チームによっては、最初に最速のランナーを選択し、次に 2 番目に速いランナーなどを選択して、最も遅いランナーがレースを終了する場合がある。他のチームは、完全に違う戦略を使ってもよい。4x100m ユニバーサルリレーの場合、それほど単純ではない。立位や車いすのリレーレースとは異なり、4x100m ユニバーサルリレーには追加の要件がある。まず、チームは男性競技者 2 人と女性競技者 2 人で構成される必要がある。第 2 に、レース中は常に所定の走行順序を尊重する必要がある。つまり、上記の表に記載されているように、各区間は異なる競技クラスの競技者によって走らなければならない。最後に、競技クラス T13、T46/47、T38、及び T54 から最大 2 人の競技者のみを選択できる。したがって、チームの戦略に応じて、これらのクラスから競技者を 1 人も選ばないか、1 人または 2 人選ぶこともできる。チームの戦略に関係なく、前述の競技クラスから最大 2 人の競技者しか選択できないことに注意することが非常に重要である。例として、チームが第 1 区間と第 4 区間にそれぞれ T13 と T54 競技者を選択した場合、第 2 区間と第 3 区間には競技クラス T38 または T46 / 47 から参加者を選択できない。

23.12. 4x100m ユニバーサルリレーを含む 4x100mリレーでは、完全にレーンを走る。

23.13. 4x200mリレーは、以下のいずれの方法で走ってもよい。

- 可能ならば完全にレーンを走る（レーンで四つの曲走路を走る）。
- はじめの二人の走者はレーンで走り、第 3 走者は同様に規則 18.7 で述べたブレイクラインの手前段までレーンで走り、その後レーンを離れることができる（レーンで三つの曲走路を走る）。
- 規則 18.7 で述べたブレイクラインの手前段まで第 1 走者が走り、その後レーンを離れる（レーンで一つの曲走路を走る）。

注意：4 チーム以内で競走する場合及び上記 (a) が不可能な場合、(c) の方法がとられるべきである。

14.The 4x400m race may be run in either of the following ways: a) in lanes for the first leg, as well as that part of the second leg up to the nearer edge of the breakline described in Rule 18.7 where athletes may leave their respective lanes (three bends in lanes), b) in lanes for the first leg up to the nearer edge of the breakline described in Rule 18.7, where athletes may leave their respective lines (one bend in lanes). Note: In relay races other than visually impaired and wheelchair, where not more than four teams are competing, it is recommended that option (b) should be used. 15.For all takeovers, athletes are not permitted to begin running or wheeling outside their take over zones and shall start within the zone. If an athlete does not follow this Rule, their team shall be disqualified. 16.The athletes/guide-runners in the third and fourth legs of the 4x400m relay race shall, under the direction of a designated official, place themselves in their waiting position in the same order (inside to out) as the order of their respective team members as they enter the last bend. Once the incoming athletes/guide-runners have passed this point, the waiting athletes/guide-runners shall maintain their order and shall not exchange positions at the beginning of the take-over zone. If an athlete/guide-runner does not follow this Rule, their team shall be disqualified. Note: In the 4x200m relay race (if this event is not run entirely in lanes) where the previous leg is not run in lanes, the athletes/guide-runners shall line up in the order of the start list (inside to out). 17.For wheelchair relays, relays for Sports Classes T11-13 (i.e., involving guide-runners) and 4x100m universal relay, where it is required for the relay to be run in lanes, each team shall be allocated two adjacent lanes. The athletes/guide-runners may use either of their two allocated lanes. The lines on the inner of the two allocated lanes shall be extended across the outer of the two allocated lanes to mark the distances of the stages and to denote the scratch lines. Changes will take place as for lanes 1, 3, 5 and 7. The extension-of-start and exchange box lanes should be done with tape of the same colour and width as the existing lane markings. 18.In any ambulant relay race, when lanes are not being used, including when applicable, in 4x200m and 4x400m, waiting athletes/guide-runners can take an inner position on the track as incoming team members approach, provided they do not jostle or obstruct another athlete/guide-runner so as to impede their	23.14. 4×400mリレーでは、以下のいずれかの方法で走ることができる。 a) 第1走者はレーンで走り、第2走者は同様に規則 18.7 で述べたブレイクラインの手前端までレーンで走り、その後レーンを離れることができる（レーンで三つの曲走路を走る）。 b) 第1走者は規則 18.7 で述べたブレイクラインの手前端までレーンで走り、その後レーンを離れることができる（レーンで一つの曲走路を走る）。 注意：視覚障害と車いす以外のリレー競走では、4チーム以内で競走する場合には、上記(b)の方法が推奨される。 23.15. すべてのテイクオーバーにおいては、テイクオーバーゾーン外から走り出しはならず、そのゾーンの中でスタートしなければならない。この規則に従わなければ、そのチームは失格となる。 23.16. 4×400mリレーの第3、第4走者／ガイドランナーは審判員の指示に従い、前走者が第2曲走路入り口を通過した順序で、内側より並び待機する。一度前走者・ガイドランナーがその地点を通過したら、待機している走者／ガイドランナーは、テイクオーバーゾーンの始まりではこの順序を維持しなくてはならない。違反した場合は、そのチームを失格とする。 注意：4×200mリレーにおいて、レーンを完全に走行するのではなく途中でブレイクする方法で実施されるならば、前走者がレーン内走行でない場合、次走者はスタートリストの順番で内側より外側に一列に並び。 23.17. 車いすリレー、競技クラス T11-13（ガイドランナーを必要とする）リレー及び 4 x 100m ユニバーサルリレーでレーンを使用する必要がある場合、各チームに隣接した2レーンを割り振るものとする。競技者とガイドランナーは割り当てられた2レーンのどちらを走行してもよい。2レーンのうち内側のほうのレーン上に引かれた線を外側の方のレーンまで延長して、各区間の距離やスタートラインを示すものとする。第1、第3、第5、第7レーンについては変更が生じる。スタートラインの延長や引き継ぎ区域の線引きは、レーンのマーキング用に用いられているものと同色・同幅のテープを使って行うべきである。 23.18. 4×200mリレーと4×400mリレーも含めた立位によるどのリレー競走においても、レーンが使用されていない場合は、次走者は、他の走者の進行をじやますために妨害したり押しのけたりしないならば、走って来るチーム走者が近づくにつれてトラックの内側に移動できる。4×200mリレーと4×400mリレーの場合には、次走者は規則 23.16 で規定された順番を
--	---

progress. In 4x200m and 4x400m, waiting athletes/guide-runners shall maintain their order in accordance with Rule 23.16. If an athlete/guide-runner does not follow this Rule, their team shall be disqualified. COMMENT: Chief Umpires must remain at the zone to which they and their Umpires have been assigned. Once the athletes are correctly placed in their lanes and the race has started, zone Chief Umpires and those Umpires assigned to them are responsible for reporting any infringements of both these Rules as well as any other infringements particularly those under Rule 18. 19. In any wheelchair relay race, when lanes are not being used, including when applicable, in 4x200m and 4x400m, waiting athletes will be allocated two adjacent lanes, in their order in accordance with Rule 23.16. The waiting athletes may use either of these two lanes but must remain in these two lanes until after the takeover has been completed. In wheelchair relay races waiting athletes cannot take up an inner position or any other position than in the two allocated lanes. If an athlete does not follow this Rule, their team shall be disqualified. 20. In the case of relay events not covered by this Rule, the relevant competition regulations should specify any particular rules that should be applied and the method by which the relay should be conducted. SECTION IV - FIELD EVENTS Rule 24: General Conditions Practice Trials at the Competition Area 1. At the competition area and before the beginning of the event, each athlete may have practice trials. In the case of throwing events, the practice trials will be in draw order and always under the supervision of the Judges. COMMENT: Whilst in the past the Rules specified that there should be two practice trials for each athlete in throwing events, there is currently no such specification. Rule 24.1 should be interpreted as allowing whatever number of practice trials that may be included in the warm-up time available. Whilst for major events, two remains a standard practice, this is regarded as a minimum and should time be available and some or all of the athletes request additional practice trials, this can be permitted. 2. Once a competition has begun, athletes are not permitted to use, for practice purposes, a) The runway or take-off area; b) Implements; c) The circle or runway or the ground within the sector with or without implements. The use of implements outside the circle or runway is prohibited at any time.	維持する。もし競技者／ガイドランナーが、この規則に従わないならば、そのチームは失格となる。 コメント：監察員主任は、自身と配下の監察員が割り当てられているゾーンに留まっている必要がある。競技者が自分のレーンに正しく配置されてレースが開始されたら、監察員主任とそれに割り当てられた監察員は、これらの規則の違反、及び他の違反、特に規則 18 に違反したものを報告する責任がある。 23.19. レーンで行わない 4×200mリレーと 4×400mリレーも含めた車いすのよるいかなるリレー競走においても、次走者は規則 23.16 で規定された順番を維持するにあたり、2 レーンが与えられる。次走者は、2 レーンのどこにいてもよいが、テイクオーバーが完了するまでこの 2 レーン内に位置しなくてはならない。車いすリレーではトラックの内側や与えられた 2 レーン以外の場所に移動してはならない。もし競技者が、この規則に従わないならば、そのチームは失格となる。 23.20. この規則に当てはまらないリレー競技の場合、適用される規則とどのような方法でリレーを実施するかを、関連する競技会規則で指定する必要がある。 第 4 部 フィールド競技 第 24 条 総則 競技場所での練習試技 24.1. 各競技者は、競技開始前に競技場所において練習を行うことが許される。投てき競技では、あらかじめ決められた試技順で、常に審判員の監督のもとで練習を行う。 コメント：過去には、規則には、各競技者が投てき種目において各競技者には 2 回の練習試技が必要であると規定されていたが、今では、そのような決まりはない。規則 24.1 は、ウォームアップ時間が許す限り何回でも認められると解釈されるべきである。大規模競技会の場合、2 回は標準的な練習試技回数だが、これは最小限とみなされ、時間が許すなら、一部またはすべての競技者による追加の練習試技要求は認められる。 24.2. 競技が開始されたら競技者は練習の目的で次のものを使用することはできない。 a) 助走路や踏切場所 b) 用具 c) 用具を持つ持たないに関係なく、サークルや助走路または着地場所 但し、サークルや助走路以外での用具の使用は、いかなる場合でも禁止する。	第 4 部 フィールド競技 第 24 条 総則
---	--	---

COMMENT: In the Long Jump or Triple Jump, athletes are not allowed to use the track for warm up when the track is being used for competition at the same time. They must stay within the immediate confines of the competition area and observe carefully the instructions of the Officials. As a Referee, an ITO must control the event site, and warn athletes who wander away from the competition area without permission. The issuance of a Yellow Card or Red Card is appropriate depending upon the circumstances. The application of this Rule should not prevent an athlete from touching or preparing their selected implement in readiness for their trial provided that it does not endanger, delay or obstruct another athlete or other person. It is particularly important that the Judges interpret this Rule reasonably so as to ensure the competition proceeds in an efficient manner and the athlete is able if they so choose to take their trial immediately when their time begins. Markers 3. a) In Field Events where a runway is used, markers shall be placed alongside it, except for High Jump where the markers can be placed on the runway. An athlete may use one or two markers (supplied or approved by the LOC) to assist them in their run-up and take-off. If such markers are not supplied, they may use adhesive tape but not chalk or similar substance nor anything that leaves indelible marks; b) For throws made from a circle, an athlete may use one marker only. This marker may be placed only on the ground in the area immediately behind or adjacent to the circle. It must be temporary, in position only for the duration of each athlete's own trial, and shall not impair the view of the judges. No personal markers may be placed in or beside the landing area. c) The Judges shall direct the relevant athlete to adapt or remove any marks not complying with this Rule. If they do not, the Judges shall remove them. Note (i): Serious cases may further be dealt with under Rule 8.1 and Rule 8.3. Note (ii): Each marker shall be comprised of a single piece only. COMMENT: If the ground is wet the adhesive tape used for High Jump can be fixed to the ground by drawing pins of several colours. The requirement for each marker to be a single piece should be interpreted sensibly by the Referee. If for example the manufacturer has used two pieces of material to make a single marker which is intended to be used that way, this marker should be allowed. Similarly, if the athlete chooses to place both their markers in the same place, that is also acceptable. In the case of the High Jump, an athlete who tears the tape they are given into one or more pieces to make a	コメント：走幅跳または三段跳では、トラックが競技に同時に使用されている場合、競技者はトラックをウォームアップに使用することはできない。彼らは競技エリアのすぐ近くに留まり、役員の指示を注意深く守らなければならない。ITO は審判長として、競技会場を管理し、許可なく競技エリアから離れる競技者に警告する必要がある。状況に応じて適切にイエローカードまたはレッドカードを提示する。この規則を適用しても、他の競技者や他の人を危険にさらしたり、遅らせたり、妨害したりしない限り、競技者が次に試技準備のために自身が選んだ器具に触れたり、準備したりすることを妨げてはならない。効率的な方法で競技会の進行を保証するために審判員が合理的にこの規則を解釈し、競技者が彼の持ち時間が始まると直ちに試技を始めることができることは、特に重要である。 マーカー 24.3. a) 助走路が使われるフィールド競技では走高跳を除いて、マーカーは助走路の外側に置かなければならない。走高跳だけは助走路内に置くことができる。競技者は助走や踏切をしやすくするためにマーカー（組織委員会が準備したもの、または承認したもの）を 2 個まで使うことができる。マーカーが準備されない場合、粘着テープを使用することができるがチョークや類似品及び消えないマークは使用できない。 b) サークルから行う投てき競技ではマーカーを 1 個だけ使用することができる。このマーカーはサークルの直後あるいはサークルに接して置く。マーカーは各競技者の試技中に一時的に設置し、審判の視界を遮るものであってはならない。着地場所あるいはその脇に個人所有のマーカーを設置することはできない。 c) この規則に違反するマーカーがあれば、審判員は当該競技者に対し、規則に合わせるか剥がすように指導する。指導に従わない場合は、審判員が剥がさなくてはならない。 注意(i)：悪質と考えられる場合は、規則 8.1 または 8.3.を適用することができる。 注意(ii)：それぞれのマーカーは単一の物でできていること。 コメント：地面が濡れている場合、粘着テープは数色のピンを刺して地面に固定することが可能である。各マーカーが単一のものであることの要件は、審判長によって分かりやすく解釈されるべきである。例えば、製造業者が 2 つの部品を使用して、そのように使用することを意図した単一の構造を作る場合、それは許されるべきである。同様に、競技者がマーカーを同じ場所に置くことを選択した場合、または走高跳で、テープを細かく裂き、より鮮明に目立たせる目的で異なる形の単一マーカーを作った場合は、それぞれ許容されるべきである。	マーカー
--	--	-------------

single marker of a different shape to stand out more clearly, that should also be acceptable.

Performance Markers and Wind Socks

4.
a) A distinctive flag or marker may also be provided to mark the existing World Record and, when appropriate, the existing Regional, National or Meeting Record.

b) One or more wind sock(s) should be placed in an appropriate position in all jumping events, Discus Throw and Javelin Throw, to show the athletes the approximate direction and strength of the wind.

Competing Order and Trials

5. Except where Rule 24.6 applies, or the applicable regulations provide otherwise, the athletes shall compete in an order drawn by lot. If an athlete by their own decision makes a trial in an order different from that previously determined, **they shall be warned (or disqualified in case of a second infringement) according to Rule 8.1 and Rule 8.3 shall be applied.** In the case of a warning the result of the trial (valid or failure) will stand. If there is a Qualification Round, there shall be a fresh drawing of lot for the final.

6. Except for the High Jump no athlete shall have more than one trial recorded in any one round of trials of the competition.
In all ambulant Field Events, except for the High Jump, where there are more than eight athletes, each athlete shall be allowed three trials and the eight athletes with the best valid performances shall be allowed three additional trials unless the applicable regulations provide otherwise.

COMMENT: In situations in the horizontal Field Events where there are more than eight athletes, only the eight athletes with the best valid performances are allowed any additional trial(s). This requires an athlete to have a measured mark recorded from a fair jump or throw in at least one of their first three trials. Where fewer than eight athletes achieve such a valid performance it is only those athletes who are allowed any additional trial(s) even though it will mean fewer than eight athletes proceeding.

In the case of the last qualifying place, if two or more athletes have the same best performances, Rule 24.22 shall be applied. If it is thus determined that there has been a tie, the tying athletes shall be placed in the final allowed any additional trials. In the case of a tie in High Jump for the last qualifying place, it shall be resolved as described in Rule 24.22 below.

In Seated Throwing Events, six consecutive trials shall be staged for each athlete, which for the avoidance of doubt may be held in two or more pools. In the Paralympic Games and WPA Championships (Part B - 3.1.2 (a) and (b)), it is recommended that the competing order for six consecutive trials shall be in reverse ranking

パフォーマンス・マーカーと吹き流し

24.4.

a) 明瞭な旗またはマーカーを置いて現在の世界記録、また必要であれば、現在の地域、国、大会の記録を示すことができる。

b) 競技者がおおよその風向と風力を知ることができるように、すべての跳躍競技と円盤投・やり投においては、適切な場所に一つ以上の吹き流し状のものを置く。

試技順と試技

24.5. 規則 24.6 が適用される場合を除き、または適用される競技注意事項に特段の定めがある場合を除き、競技者は抽選で決められた試技順に従って競技しなくてはならない。競技者が自身の判断で事前に決められた試技順とは異なる順番で試技を行った場合、**警告があたえられ（または 2 回目の違反である場合は失格とする）**規則 8.1 と規則 8.3 を適用しなければならない。警告を与える場合、その試技の結果は有効・無効にかかわらず記録される。予選ラウンドが実施される場合、決勝ラウンドの試技順は新たに抽選で決める。

24.6. 走高跳と座位の投てき種目を除き各競技者が各ラウンドで許されるのは 1 回の試技のみである。走高跳を除くすべての立位のフィールド競技で 8 人を超える競技者が競技を行う場合には、各競技者は 3 回の試技が許される。その中で上位の有効な成績を得た競技者 8 人には、さらに 3 回（大会開催規程で定められている場合はその回数）の試技が許される。

コメント：長さを競うフィールド競技で 8 名を超える競技者が出場している場合、全員が 3 回の試技終了後、上位記録の 8 名のみが 4 回目以降の試技を行うことができる。この要件として、最初の 3 回の試技の少なくとも 1 回で、正しい跳躍または正しい投てきで結果が記録される必要がある。最初の 3 回の試技で有効な結果が記録された競技者が 8 名未満であっても、4 回目以降の試技を行うことができるのは、最初の 3 回の試技で 1 回でも有効な結果が記録された競技者のみである。

最後の通過順位において、2 人以上の競技者が同じ最高記録であった場合、規則 24.22 を適用する。このようにしても同成績であったならば同成績の競技者はそれぞれあと 3 回試技を行うことができる。走高跳の同成績は、後述の規則 24.22 により解決する。

座位の投てき種目では、各競技者とも 6 回の連続試技で実施するが、誤解を避けるため 2 つ以上のプールで行われてもよい。パラリンピック及び WPA 選手権 (PART-B 規則 3.1.2(a)及び(b)参照)では、6 連投の試技順は、参加標準記録の対象期間に達成された資格記録上位リストの逆の順番(最も記録の良い競技者が最後となる)とすることを推奨する。

競技者が 8 人以下の場合には、大会開催規程で特に定められていなければ、各競技者に 6 回の試技が許される。前半の 3 回のラウンドで有効試技が一つもない競技者も後半の試技が許されるが、その試技順

order recorded from the relevant list of valid performances achieved during the predetermined period. Where there are eight athletes or fewer, each athlete shall be allowed six trials unless the applicable regulations provide otherwise. If more than one fails to achieve a valid trial during the first three rounds of trials, such athletes shall compete in subsequent rounds of trials before those with valid trials, in the same relative order according to the original draw. In both cases: a) The competing order for any subsequent rounds of trials shall be in the reverse ranking order recorded after the first three rounds of trials unless the applicable regulations provide otherwise; b) When the competing order is to be changed and there is a tie for any position, those tying shall compete in the same relative order according to the original draw. Note (i): For High Jump, see Rule 25. Note (ii): If one or more athlete(s) is permitted by the Referee to continue in a competition under protest in accordance with Rule 50.5, such athletes shall compete in all subsequent rounds of trials before all other athletes continuing in the competition and if more than one, in the same relative order according to the original draw. Note (iii): The regulations of the relevant governing body may specify the number of trials (provided it is no more than six) and the number of athletes which may progress to each additional round of trials after the third. Note (iv): In ambulant Field Event, the regulations of the relevant governing body may specify that the competing order be changed again after any further round of trials after the third. COMMENT: When an athlete has retired from an event either by their own decision or by a decision made in accordance with Rule 2.2, they may take no further part in that round of that event, including, in the case of High Jump, in a jump-off for first place. Recording of Trials 7. Except in High Jump, a valid trial shall be indicated by the measurement taken. For the standard abbreviation and symbols to be used in all other case see Rule 2.20.3 Completion of Trials 8. The Judge shall not raise a white flag to indicate a valid trial until a trial is completed. The judge may reconsider a decision if they believe they raised the incorrect flag. The completion of a valid trial shall be determined as follows:	は有効試技のある競技者の前とし、複数いる場合は当初のスタートリスト順とする。 両方の場合は： a) 大会開催規程で特に定めていなければ、後半の 3 回の試技順は、前半の 3 回までの試技で記録した成績の低い順とする。 b) 後半の試技で前半の試技順を変更するにあたって、いずれかの順位に同成績がいる場合、そうした競技者の試技順は当初のスタートリスト順とする。 注意(i)：走高跳については規則 25 を参照。 注意(ii)：規則 50.5 の下で審判長が競技の継続を許可し一人または複数の競技者が「抗議中」として競技を継続する場合、後半 3 回のラウンドでは、「抗議中」の競技者は他の競技者より先に競技を行うものとする。そのような競技者が複数名存在する場合、競技の順番は当初のスタートリスト順とする。 注意(iii)：統括団体はその開催規程により、試技回数（6 回より多くてはならない）や、前半 3 回行った後の試技に出場できる競技者数を定めることができる。 注意(iv)：立位のフィールド種目において、組織委員会(LOC)はその開催規定により、3 回目の試技後、その後の試技の試技順を変更してもよい。 コメント：競技者が自分の意思により、あるいは規則 2.2 により競技を途中で止めた場合、当該競技者はその競技のその後の試技をおこなうことはできない。走高跳での 1 位決定のためのジャンプオフにも出場できない。 試技の記録 24.7. 走高跳以外の種目で、有効試技だった場合は、計測された数値が表示されねばならない。有効試技でなかった際に使用するべき標準的な略語と記号については規則 2.20.3 を参照のこと。 試技の完了 24.8. 審判員は、試技が完全に完了するまでは有効を示す白旗を挙げてはならない。審判員は間違った旗を挙げたと判断したら、判定を再考する。試技完了は以下に基づいて決定される。	試技の記録 試技の完了
--	---	---

a) In the case of High Jump, once the Judge has determined that there is no failure according to these Rules; b) In the case of Horizontal Jumps, once the athlete leaves the landing area in accordance with these Rules; c) In the case of throwing events for ambulant athletes, once the athlete leaves the circle or runway in accordance with these Rules; d) In the case of seated throwing events, once the implement has landed within the landing sector. COMMENT: This is why it is important for the judge in the field (for a Throwing Event) or landing area (for a horizontal jumping event) to ensure that there is a prism or mark in the case where a Chief Judge raises the incorrect flag in error. Qualification Rounds 9. A Qualification Round shall be held in Field Events in which the number of athletes is too large to allow the competition to be conducted satisfactorily in a single round (final). Where a Qualification Round is held, all athletes shall compete in, and qualify through, that round except that the body having the control over a competition may for one or more events authorise the conduct of additional Qualification Round(s) either at the same or at one or more earlier competition(s) to determine some or all of the athletes who shall be entitled to participate and in which round of the competition. Such procedure and any other means (such as e.g. achieving entry standards during a specified period, by specified placing in a designated competition or by rankings) by which an athlete is entitled to participate, and in which round of the competition, shall be set out in the regulations for each competition. Performances accomplished in a Qualification Round shall not be considered as part of the final. COMMENT: While the performance will not count as part of the final, if a World Record is achieved and all other criteria as required for submission as a World Record, it can still be considered by WPA as a World Record performance. 10. The athletes shall normally be divided into two or more groups at random, but wherever possible athletes of each nation or team shall be placed in different groups. Unless there are facilities for the groups to compete at the same time and under the same conditions, each group should start its practice trials immediately after the previous group has finished. 11. It is recommended that, in competitions of more than three days, a rest day be provided between qualifying competitions and the finals in the High Jump. 12. The conditions for qualifying, the qualifying	a) 走高跳の場合、当該規則で規定された失敗が無い確認後、有効が決定される。 b) 長さの跳躍の場合、当該規則に基づき、審判員が、競技者が着地場所から離れたことを確認した際、有効が決定される。 c) 立位の投てき競技の場合、当該規則に基づき競技者がサークルまたは助走路から離れたことを確認した後、有効が決定される。 d) 座位投てき種目は、投てき物が所定の落下区域に落下したとき。 コメント：これが、フィールド（投てき競技の場合）または着陸エリア（水平跳躍競技の場合）の審判員が、審判員主任が誤って正しくない旗を挙げた場合に、プリズムまたはマークがあることを確認することが重要となる理由である。 予選 24.9. 参加競技者が多過ぎ決勝が適正に実施できない時は予選を行う。予選ラウンドがある時は全競技者が競技をし、その中から決勝進出者が選ばなければならない。予選ラウンドを行うに際しては、統括団体は一つあるいは複数の種目で、その競技会の中で、あるいはそれに先立つ別の競技会で、参加資格を与える競技者の一部または全部を決めることや、その競技会のどのラウンドから出場することができるかを定める権限を持つ。どの競技者に参加資格を与え、どのラウンドから出場できるかという手順や考え方（特定の期間に達成された参加標準記録、指定競技会での順位やランキング等）については、各競技会の開催規程に記載する。予選や他の追加的予備予選の記録は決勝記録の一部とはみなさない。 コメント：記録は決勝の一部としてみなされないが、世界記録が達成され、世界記録として申請するために必要なすべての基準が満たされた場合には、WPAは世界記録として考慮する。 24.10. 予選は通常では競技者を 2 あるいはさらに多くのグループに無作為に分けて実施するが、できるならば同じ国やチームの競技者は異なった組にする。複数のグループが同時に同条件で競技できる施設がない時は前のグループの競技が終了した後、ただちに次のグループが練習試技を開始すべきである。 24.11. 競技会が 3 日を超えて行われる時、走高跳は、予選と決勝の間に 1 日の休息日をおくことが望ましい。 24.12. 予選の通過標準記録及び決勝の競技者数など予選の条件は、技術代表が決定する。技術代	予選
---	--	------------------

standard and the number of athletes in the final, shall be decided by the Technical Delegate(s). If no Technical Delegate(s) have been appointed the conditions shall be decided by the LOC. It is desirable that there should be at least 12 athletes in the final unless otherwise provided in the Regulations for the competition. Note: The applicable regulations may specify how vacant positions due to withdrawals in finals may be filled in by athletes ranked next following the qualification round after those qualified. COMMENT: This essentially means that if there is a tie for the 12th position for a final, more than 12 may be selected for the final. While there is no "maximum" number for qualification, it would not be unusual for more than 12 athletes to be part of the final group. 13. In a Qualification Round, apart from the High Jump, each athlete shall be allowed up to three trials. Once an athlete has achieved the qualifying standard, they shall not continue in the Qualification Round. 14. In the Qualification Round for the High Jump, the athletes, not eliminated after three consecutive failures, shall continue to compete according to Rule 25.2 (including passing a trial) until the end of the last trial at the height set as the qualifying standard, unless the number of athletes for the final has been reached as defined in Rule 24.12. Once it is determined that an athlete will be in the final, they shall not continue in the Qualification Round. 15. If no athletes, or fewer than the required number of athletes, achieve the pre-set qualifying standard, the group of finalists shall be expanded to that number by adding athletes according to their performances in the qualifying competition. In the case of the last qualifying place, if two or more athletes have the same best distances or heights in the overall results of the competition Rule 24.22 shall be applied. If it is determined that there is still a tie, the tying athletes shall be placed in the final. 16. When a Qualification Round for the High Jump is held in two simultaneous groups, it is recommended that the bar be raised to each height at the same time in each group. It is also recommended that the two groups be of approximately equal strength. COMMENT: It is important when seeding High Jump qualifying groups that the requirements of Rule 24.10 and Rule 24.16 are both observed. The Technical Delegates and the ITO/Referee must follow closely the progress of the Qualification Rounds of the High Jump to ensure that on the one hand, the athletes must jump (or indicate that they are passing) as long as they are not eliminated under Rule 25.2 until the qualifying standard has been reached (unless the number of athletes for the final has been reached as defined in Rule 24.12) and on the other hand,	表をおかない場合は、組織委員会が諸条件を定める。特別な競技会規定がない限り決勝は少なくとも 12 人とする。 注意：決勝に出場する資格のある競技者が棄権した場合の扱いについて、前ラウンドに進出する資格を獲得した競技者の次にランク付けされた者で補充することを、適用する競技注意事項で定めることができる。 コメント：これは基本的に、決勝に向けて 12 位に同順位がある場合、決勝で 12 位以上が選択される可能性があることを意味する。予選に参加する競技者の人数に上限はないが、決勝で 12 名以上いてもよい。 24.13. 走高跳を除く種目の予選は、各競技者は 3 回までの試技が許される。一度予選通過標準記録に達した競技者は、予選でその後の試技は許されない。 24.14. 走高跳の予選では、3 回続けて失敗した競技者を除き、規則 25.2（試技のパスを含む）に従って、設定された予選通過標準記録の高さにおける最後の試技が終了するまで競技を続ける。但し、規則 24.12 に定める決勝進出数に達した場合は除く。決勝進出が決定した競技者は、予選の試技を続けることはできない。 24.15. もし事前に決められた予選通過標準記録を突破した競技者がいなかったり、必要数に満たなかったりした時は、決勝進出者は予選成績により追加補充する。最後の通過順位に同記録の競技者が複数名いる場合は競技全体の結果から規則 24.22 を適用して決める。その結果、同成績の場合は、同成績の競技者は決勝に進める。 24.16. 走高跳の予選で二つのグループが同時に行われる場合、各高さにバーを上げるタイミングは同時が望ましい。二つのグループは、おおよそ同じ強さのレベルに分けることが望ましい。 コメント：走高跳の予選グループの組み合わせでは、規則 24.10 と規則 24.16 の要件が両方とも遵守されていることが重要である。技術代表と ITO／審判長は、走高跳の予選の進捗状況を綿密に追跡しなければならない。一方で競技者は、規則 25.2 に従って競技を終えなければ、予選通過記録に到達するまで（規則 24.12 で規定されている競技者の人数に達していない限り）跳躍（またはパスすることを意思表示）し続けなくてはならず、他方、2 つのグループでの競技者全体の順位付けは、規則 25.9 に従って解決される。まだ競技が続くかどうかにかかわらず決勝に進出する人数が確定
---	--

any tie between athletes in the overall standings in the two groups is resolved according to Rule 25.9. Close attention must also be kept to the application of Rule 24.14 to ensure that athletes do not unnecessarily continue in the competition once it is certain that they will be in the final regardless of what may happen to the other athletes continuing to compete in the Qualification Round.

Time Allowed for Trials

17. The official responsible shall indicate to an athlete that all is ready for the trial to begin, and the period allowed for this trial shall commence from that moment.

If the time allowed elapses after an athlete has started their trial, that trial should not be disallowed.

If after the time for a trial has begun, an athlete decides not to attempt that trial, it shall be considered a failure once the period allowed for the trial has elapsed. The following times shall not be exceeded. If the time is exceeded, unless a determination is made under Rule 24.18, the trial shall be recorded as a failure:

Maximum Times Allowed

Number of athletes remaining in the competition

Number of athletes remaining in the competition	High Jump	Other Ambulant Events	Seated Throw Events
More than 3 (or for the very first trial of each athlete)	1min	1min	1min
2 or 3	1.5min	1min	1min
1	3min	-	-
Consecutive trials	2min	2min	1min

Note (i): For Seated Throws Events, an extra minute shall be added between the third and fourth throws.

COMMENT: In a practical sense, the Chief Judge or the Referee is in a position to allow additional time between throws if they determine that the athlete is not ready, or if the officials are not ready. For Seated Throwing the time clock should be initiated after the responsible judge has passed the implement to the athlete and when the sector is ready, and officials are out of the way. This may require some sort of audible instruction from the Chief Judge to the athlete. When the athlete finishes the third throw, and the measurement is completed the time clock must be initiated for the one-minute break. During the one-minute break period the implement should not be provided to the athlete unless the athlete requests it. If the athlete asks for the implement before the one minute break has elapsed, then the time for the fourth throw shall commence immediately (i.e., at the moment the implement is handed to the athlete and when the sector is ready, and officials are out of the way).

Note (ii): A clock that shows the remaining time

したなら、競技者がそれ以上不必要な競技を続けることのないよう、規則 24.14 の適用に注意を払う必要がある。

試技時間

24.17. 担当審判員は、競技者に試技を開始するための用意が完了していることを示さなくてはならず、試技時間はこの瞬間からカウントダウンが始まる。

競技者が試技時間内に競技を開始していれば、試技の完了前に試技時間が経過しても、その試技は認められる。

試技時間のカウントダウンが始まった後に競技者がその試技を行う意思がない場合、制限時間が過ぎるのを待って無効試技として扱う。
次の試技時間は、通常の場合を超えてはならない。試技時間を越えたら規則 24.18 を除き、無効試技として記録する。

有効試技時間

残っている競技者数

走高跳	その他立位種目	その他座位種目
4人以上及び		
1 回目の試技	1 分	1 分
2～3 人	1 分 30 秒	1 分
1 人	3 分	—
連続試技	2 分	2 分

注意(i)：座位投てき種目では、3 回目と 4 回目の投てきの間に 1 分を追加する。

コメント：実際には、審判員主任または審判長は、競技者の準備ができていないと判断した場合、または競技役員の準備ができていないと判断した場合、投てきの間に追加の時間を設けることができる立場にある。

座位の投てきの場合、時計は、担当する審判員により投てき用具が競技者に渡された後、落下域の準備が整っており、役員が離れたときに開始する必要がある。こうするには、審判員主任から競技者への口頭の指示が必要になる場合がある。競技者が 3 回目の投てきを終了し、測定が完了したら、1 分間の休憩のために時計を動かす必要がある。

1 分間の休憩時間中、競技者がリクエストしない限り、用具は競技者に提供されるべきではない。

1 分間の休憩が経過する前に競技者が用具をリクエストした場合、4 回目のスローの時間は直ちに開始される（すなわち、用具が競技者に渡された時点で、セクターの準備が整い、役員は離れる）。

注意(ii)：試技をするために許される残り時間（試


allowed for a trial should be visible to an athlete or to the vision impaired athlete's assistants. In addition, an official shall raise and keep raised, a yellow flag, during the final 15 seconds of the time allowed. Alternate visual indication may also be approved. Note (iii): In the High Jump, any change in the time period allowed for a trial, except the time specified for consecutive trials, shall not be applied until the bar is raised to a new height. The number of athletes remaining in the competition is determined at the time the bar is placed to the new height. COMMENT: To be clear, the time limit will not change in the final round of any horizontal Field Event, once only 2 or 3 athletes remain to take their trials. Note (iv): When only one athlete (who has won the competition) remains in High Jump and is attempting a World Record or other record relevant to the competition, the time limit shall be increased by one minute beyond those set out above. COMMENT: This can be a troubling situation for Officials where more than one class of athlete has been combined for a specific competition. Where this is the case if an athlete in one class has "won the event" for their class they can ask for the bar to be moved to a height of their choosing if the Technical Specifications for the competition allow this or if the Technical Delegate determines that it is appropriate to allow this practice. This may disrupt the competition for the other class(es) within the competition. Note (v): For the first trial of any athlete upon entering the competition, the time allowed for such trial will be 1 minute. Note (vi): When calculating the number of athletes remaining in the competition this should include those athletes who could be involved in a jump off for first place. Note (vii): In Field Events for Sport Classes 11 and 12 where athletes receive assistance from Callers or Escorts, the time allowed shall begin from the moment when the official responsible is satisfied that the athlete has completed the process of orientation. Should any athlete request verbal confirmation of the starting of the timing clock; an official shall give such confirmation. COMMENT: Whilst the Judges should always use a system which notifies or calls the next athlete who is to take their trial plus the one who is to follow, this is essential when the time allowed for an athlete to take their trial is 1 minute. They must also ensure that the competition area is completely ready for the next trial before calling the athlete and then starting the clock. The Judges and the Referee in particular must be fully aware of the current competition environment when deciding when to start the	技時間)を示す時計は競技者または視覚障がい競技者のアシスタントに見えるように設置する。これに加えて試技に許される時間(試技時間)が残り15秒になった時から審判員は黄旗を挙げ続けるか、その他の方法で適切に知らせる。他の視覚的表示も認められる。 注意(iii):走高跳の場合、試技時間の変更はバーが新しい高さに上げられるまで適用しない。ただし例外として連続試技となるとときには定められた時間を適用する。高さを競う跳躍競技では、バーが新たな高さに設置された時点で引続き競技が行える競技者の数が決まる。 コメント: 明確にすると、水平種目のフィールド競技の最終ラウンドでは、残りの競技者が2人か3人になった時点で、試技時間は変更されない。 注意(iv):走高跳で優勝が決まり競技者が一人となり、世界記録かその他大会記録等に挑戦する場合には、定められた制限時間より1分延長しなければならない。 コメント:これは、特定の競技会で複数のクラスの競技者が組み合わされている場合、競技役員にとって厄介な状況になる可能性がある。これが当てはまる場合、あるクラスの競技者がクラスで「種目で優勝した」場合、競技会の技術仕様で許可されているか、または技術代表がこの試技を行うこと決定した場合、バーを選択した高さに移動するように要求できる。これにより、競技会内の他のクラスの競技が中断される可能性がある。 注意(v):どの競技者も競技開始時、最初の試技時間は1分のみとする。 注意(vi):残りの競技者の数を数える際は第1位決定試技に残る可能性がある競技者も含めなければならない。 注意(vii):競技クラス11及び12のフィールド種目で競技者がコーラーまたはエスコートの介助を受ける場合、競技制限時間は、競技者が位置確認を終えた競技担当役員が断した時点から始まるものとする。競技時計の作動開始について競技者が口頭による確認を求めた場合、担当役員はこれを行うものとする。 コメント:審判員は、次に試技を行う競技者、加えてその後に試技する競技者に(順番であることを)通知または呼び出すシステムを常に使用すべきであるが、特に、競技者の制限時間が1分のときには、必須である。審判員はまた、競技者を呼び出し、制限時間用の時計をスタートする前に、競技エリアが次の試技のために完全に準備されていることを保証しなければならない。審判員と審判長は、特に時計をスタートさせる時間を決定するときや「タイムアウト」となり無効試技を宣告するとき、現在置かれた競技会環境を十分に理解していなければならない。
--	---

clock or to “time out” and call a failure. Particular circumstances which should be taken into account are the availability of the runway for an athlete’s trial in High Jump and Javelin Throw (when Track Events are being held simultaneously in the same competition area) and the distance for athletes to walk to and through the cage to reach the circle to take their trial in discus Throw. To be clear, the time limit will not change in the final round of any horizontal Field Event, once only 2 or 3 athletes remain to take their trials. Note (viii): If the athlete loses orientation and requires to be re-oriented, the clock shall be stopped and only restarted (to include any elapsed time already recorded) once orientation has again been completed. COMMENT: Additional time is not permitted in this situation. Time is simply suspended for the duration of the reorientation of the athlete. Note (ix): In Seated Throwing Events, the time allowed shall begin from the moment when the throwing implement has been presented to the athlete after the throwing frame has been fixed to the throwing circle and the athlete has been positioned and strapped on that frame. COMMENT: The time may be started earlier if the athlete has not been positioned within the allocated time period. And, where the athlete is ready, as indicated in the commentary under Note (i) on Rule 24.17, the time should start when the sector is free of officials. It is also important to note that the count-down clock must be placed in such a position so that the athlete can see it. Note (x): The time for consecutive trials will be applied for any consecutive trial regardless of it being in the same round for a replacement trial, at the same height or consecutive heights in High Jump or when the order is changed at the end of a round of trials. The time for consecutive trials will be applied if it is longer than the time allowed for the trial based on the calculation of the number of athletes remaining in the competition. However, when an athlete, based on the calculation of the number of athletes remaining in the competition, is entitled to a longer time, then that will be applied. Substitute Trials 18.If, for any reason beyond their control, an athlete is hampered in a trial and is unable to take it, or the trial cannot be correctly recorded, the Referee shall have the authority to award them a substitute trial or to re-set the time either partially or in full. No change in the order shall be permitted. A reasonable time shall be allowed for any substitute trial according to the particular circumstances of the case. In cases when the competition has progressed before the substitute trial is awarded, it should be taken before any	考慮すべき特別な状況は、走高跳とやり投で競技者が試技をはじめるにあたり（同じ競技エリアでトラック種目が同時に行われている場合）、助走路が使用可能な状態になっているかどうか、及び円盤投で競技者が試技をはじめるあたり歩いて囲いの奥にあるサークルに到達するまでの距離である。長さのフィールド競技では、残りの競技者が2～3名の時でも制限時間は変更しない。 注意(viii)：競技者が方向感覚を失い位置確認のやり直しを求めた場合は、競技時計を一時停止し、位置確認終了後、計時を再開するものとする（一時停止前に経過した時間は含める）。 コメント：この状況では、追加の時間は許可されていない。競技者が方向指示を再度行っている間、時間は単に一時停止される。 注意 (ix)：座位競技者投てき種目における競技制限時間は、投てき台が投てきサークルに固定され、位置決めがなされ、競技者の身体が投てき台に縛り付けられた後に、投てき物が競技者に手渡された時点から始まるものとする。 コメント：競技者が割り当てられた時間内に配置されなかった場合、時間は早く開始される。また、規則 24.17 の注意 (i) の解説に示されているように、競技者の準備が整っている場合は、落下域に審判員がいないときに開始する必要がある。 カウントダウンクロック(残り時間を示す時計)は、競技者がそれを見られるように、そのような位置に配置する必要があることに注意することも重要である。 注意(x):連続試技の時間は、走高跳では、連続試技を行う同じ高さまたは連続した高さで、または次の高さで試技順が変更された場合に関係なく、当該競技者が連続して試技を行う際に適用される。連続試技の時間は、残っている競技者の人数に適用する試技時間より長い場合に適用される。但し、残りの競技者の数え方により、競技者がより長い時間の権利を有する場合にはその時間が適用される。 試技のやり直し 24.18. 競技者の責によらない理由により、試技の途中で競技者が妨害されたり、競技ができなかったり、あるいは正確に記録することができない場合、審判長は試技のやり直しや制限時間の一部または全部を修正させる権限を有する。試技のやり直しは、個々の状況に応じて適当な時間をおいてから行うものとする。試技順の変更は認めるべきではないが、試技のやり直しが認められる前に競技が先に進行した場合、やり直しの試技はその時点で終了していない他の競技者の試技よりも前に行われるべきである。
---	---

other subsequent trials are then made. COMMENT: There are several situations in which it may be appropriate for an athlete to be given a substitute trial including where because of procedural or technical failure a trial is not measured and it is not possible for a re-measurement to be accurately made. Whilst this should be avoided by good systems and backups, with technology being used more and more provision needs to be made for when things do go wrong. As no change in the competition order should be permitted (unless the problem is not immediately discovered and the competition has continued), the Referee must decide how long should be allowed for the substitute trial taking into account the specific circumstances of each particular case. Absence during Competition 19. An athlete may not leave the immediate area of the event during the progress of the competition, unless they have the permission of, and is accompanied by, an official. If possible, a warning should be given first, but for subsequent instances or in serious cases the athlete shall be disqualified. If an athlete subsequently is not present for a particular trial, it will be counted as a failure once the period allowed for the trial has elapsed. COMMENT: This should not be interpreted as preventing an athlete from crossing the track to speak to their coach. Change of Competition Area or Time 20. The Technical Delegate(s) or the appropriate Referee shall have the authority to change the place or time of the competition if, in their opinion, the conditions justify it. Such a change should be made only after a round of trials has been completed. Note: Neither the wind strength nor its change of direction is sufficient condition to change the place nor time of the competition. COMMENT: The phrase "round of trials" instead of "rounds" is designed to ensure a clear difference between a "round of trials" within a Field Event competition and a "round of the competition" (i.e., a Qualification Round or a final). If the conditions make it impossible to complete a round of trials before a change of place or time is made, the Technical Delegate (through the Referee) or Referee should normally void those trials already completed in that round of trials (always depending on and evaluating the conditions and the results of the trials up to the time of the interruption) and recommence the competition at the beginning of that round of trials. See also Rule 11.4. Result 21. Each athlete shall be credited with the best of	コメント：競技者がやり直し試技を与えられることが適切な場合がいくつかある。例えば、手続き上または技術上の不備のために試技が測定されず、正しく再計測することが不可能な場合などである。こうしたことは、良いシステムとバックアップによって回避されるべきであるが、技術が使用されるにつれて、事態が悪化したときに備え、ますます準備をする必要がある。試技やり直しでは、試技順序の変更は認められておらず（問題を直ちに発見されずに競技が進行してしまった場合を除き）、審判長は、それぞれの特定の事情の状況を考慮して、試技のやり直しまでどれだけの時間を取るべきかを決定しなければならない。 競技中の離脱 24.19. 審判員の許可を得ることなく、かつ審判員が伴わない限り、競技者は競技の進行中に競技場所を離れることはできない。これに違反すれば警告の対象となり、それが二度目の警告であったり、悪質な場合は失格となる。試技を行うべき順序の際に競技者が不在の場合は、その試技時間が過ぎれば無効試技とする。 コメント）これは競技者がトラックを横切りコーチと会話することを妨げるものではない。 競技場所・競技時刻の変更 24.20. 当該審判長または技術代表は、その競技場所の状態から見て、競技場所あるいは競技時刻を変更した方が適切と考えた時は競技場所あるいは競技時刻を変更することができる。しかし、その変更は 1 つのラウンド（ある高さや試技回数）が終わった後にすべきである。 注意：風の強さや方向の変化は絶対的な条件ではない。 コメント：「ラウンド」ではなく「試技のラウンド」というフレーズは、フィールド種目における「試技のラウンド」と「競技会のラウンド」（すなわち、ケオリフィケーションラウンド（予選）と決勝）との明確な違いが理解できるよう配慮されている。 もし、状況が試技のラウンドが終了することを不可能にしている場合、技術代表（審判長を介して）または審判長は、通常、その試技のラウンドですでに終わっている試技を無効とし（常に中断の時点までの状況と試技の結果による）、その試技のラウンドの最初から再開すべきである。規則 11.4. 参照すること 競技成績 24.21. 各競技者はそれぞれが行ったすべての試技	試技のやり直し 競技中の離脱 競技場所・競技時刻の変更 競技成績
---	---	--

all their trials, including in the case of High Jump, those achieved in resolving a tie for the first place. Ties 22. Except for the High Jump, the second best performance of the athletes having the same best performances shall determine whether there has been a tie. Then, if necessary, the third best, and so on. If the athletes are still equal following the application of this Rule 24.22, it shall be determined to be a tie. Except for the High Jump, in the case of a tie for any place, including first place, the tie shall remain (See Rules 25.9, Rule 25.10). Hopping Technique 23. For athletes in Classes T42-44 the hopping technique is permitted during the approach in Jumping Events. A. VERTICAL JUMP Rule 25: General Conditions 1. Before the competition begins, the Chief Judge shall announce to the athletes the starting height and the subsequent heights to which the bar will be raised at the end of each round of trials, until there is only one athlete remaining having won the competition, or there is a tie for first place. COMMENT: Normally this is done at the Technical Meeting if it was not already included in the team manual or technical information concerning the event. It should be remembered that minor adjustments can still be made at the competition site by the Chief Judge to preserve the interests of all of the athletes. Trials 2. An athlete may commence jumping at any height previously announced by the Chief Judge and may jump at their own discretion at any subsequent height. Three consecutive failures, regardless of the height at which any of such failures occur, disqualify from further jumping except in the case of a tie for first place. The effect of this Rule is that an athlete may pass their second or third trial at a particular height (after failing first or second time) and still jump at a subsequent height. If an athlete passes a trial at a certain height, they may not make any subsequent trial at that height, except in the case of a jump-off for first place. 3. Even after all the other athletes have failed, an athlete is entitled to continue jumping until they have forfeited their right to compete further. 4. Unless there is only one athlete remaining and they have won the competition: a) The bar should never be raised by less than 2cm in the High Jump after each round of trials, and; b) The increment of the raising of the bar should	のうち最もよかった記録で評価されるものとし、走高跳の場合、同成績となった競技者が 1 位決定のために行った追加試技も含む。 同成績 24.22. 走高跳を除くフィールド競技では、最高記録が同じである競技者の 2 番目の記録で同成績かどうかを決める。それでも決められない時は 3 番目の記録で以下同様にして決める。もし競技者が規則 24.22 を適用しても同一成績であるなら同成績とする。走高跳を除き、どの順位においても同成績の場合は 1 位の場合も含めて同成績は、そのままとする。(規則 25.9、) 25.10 参照) ホッピング 24.23. 競技クラス T42-44 競技者は、跳躍種目における助走は、ホッピングが許される。 A. 高さの跳躍 第 25 条 総則 25.1. 競技会が始まる前に審判長または審判員主任は、競技者に最初の高さと、優勝が決まって一人だけになるまで、あるいは第 1 位決定のための競技者が決まるまでの、各ラウンド終了後に上げられるバーの高さを告知しなければならない。 コメント：競技会に関するチームマニュアルや技術情報にまだ含まれていない場合、通常はテクニカルミーティングで協議する。すべての競技者の利益を守るために、審判員主任は競技会場でマイナーな調整を行うことができることを覚えておくこと。 試技 25.2. 競技者は審判長または審判員主任から前もって告知されたどの高さから始めてもよく、以降の高さについてどの高さを跳んでもよい。3 回続けて失敗すれば、その高さがどの高さであろうと次の試技を続けることはできない。ただし、同成績の第 1 位を決める場合を除く。 本条により競技者はある高さで（1 回目あるいは 2 回目の試技を失敗した後に）2 回目あるいは 3 回目の試技をパスしても、次の高さを引き続き試技できる。もし競技者がある高さの試技を行わない場合、第 1 位決定のジャンプオフの場合を除き、その高さで次の試技を行うことはできない。 走高跳において、他のすべての競技者が競技を終えていて、ある競技者がその場に不在の場合、与えられた試技時間が経過した後、審判長は、その競技者は競技を放棄したとみなすものとする。 25.3. ほかの競技者が権利を失った後でも、競技者は自分が権利を失うまで、さらに試技を続けることができる。 25.4. 競技者が最後の一人になり、優勝が決まるまでは、 a) バーは走高跳で 2 cmより少ない上げ方をしてはならない。 b) またバーの上げ幅を増してはならない。	同成績 ホッピング A. 高さの跳躍 第 25 条 総則 試技
--	---	---

never increase. These Rules shall not apply once the athletes still competing agree to raise it to a World Record height directly. After an athlete has won the competition, the height or heights to which the bar is raised shall be decided by the athlete, in consultation with the relevant Judge or Referee. Measurements 5. All measurements shall be made, in whole centimetres, perpendicularly from the ground to the lowest part of the upper side of the bar. 6. Any measurement of a new height shall be made before athletes attempt such height. A remeasurement should be made if the bar has been substituted. In all cases of Records, the Judges shall also re-check the measurement before each subsequent Record attempt if the bar has been touched since last measured. Prosthetic Device(s) 7. For athletes competing in High Jump Events in sport classes T61-64, the use of prosthetic device(s) is mandatory. The relevant Official shall ensure that Rule 6.12.1(b) is observed. a) If the prosthetic device(s) is lost during the run-up then the athlete cannot continue without the prosthesis. The athlete shall fix/adjust the prosthetic device(s) and recommence the trial provided they are within the time allowed for the trial; b) If the prosthetic device(s) is lost during the process of jumping and the prosthetic device(s) does not clear the bar it shall be counted as a failure and recorded as such. Crossbar 8. The crossbar shall be made of fiberglass, or other suitable material but not metal, circular in cross-section except for the end pieces. It shall be coloured so as to be visible to all sighted athletes. The overall length of the crossbar shall be 4.00m $\pm$ 0.02m in the High Jump. The maximum weight of the crossbar shall be 2kg in the High Jump. The diameter of the circular part of the crossbar shall be 30mm$\pm$1mm. The crossbar shall consist of three parts - the circular bar and two end pieces, each 30mm-35mm wide and 0.15-0.20m long for the purpose of resting on the supports of the uprights. These end pieces shall have one clearly defined flat surface on which the bar rests on the crossbar supports. This flat surface may not be higher than the centre of the vertical cross section of the crossbar. The end pieces shall be hard and smooth. They shall not be of, or covered with rubber or with any other material which has the effect of increasing the friction between them and the supports. The crossbar shall have no bias and, when in	残っている競技者が二人以上でも世界記録を超える高さにバーを上げることに全員が同意したなら上記規則を適用しなくてもよい。 競技者の優勝が決まった後、バーを上げる高さまたはバーの上げ幅は当該審判員または審判長と相談の上、競技者が決定する。 計測 25.5. (走高跳では)計測は 1 cm刻みで、地面から垂直にバーの上部の一番低いところで計測する。 25.6. バーを新しい高さに上げた時には、競技者が試技を開始する前にその高さを計測する。バーが交換された場合は再計測が必要となる。記録（世界記録と地域記録）への挑戦の際、計測後の試技でバーに触れた時は、複数の審判員は次に行われる試技の前にその高さを再確認しなければならない。 義肢 25.7. 競技クラス T61-64 の走高跳では、義肢(複数も)の使用は必須とする。関係する役員は規則 6.12(b)(下肢用義肢の使用)について確認しなくてはならない。 a) 助走中に義肢が脱落した場合、競技者は義肢を装着していない状況では競技を続けることはできない。競技者は制限時間内に義肢を再装着／調整し競技を再開しなくてはならない。 b) 跳躍の最中に義肢が脱落し、脱落した義肢がバーを越えることができなかった場合、無効試技とみなされ、そのように記録される。 バー 25.8. バーはファイバーグラスあるいは金属を除く他の適当な材質でつくられたもので、その断面は両端を除き円形とする。全ての競技者が見分けることができるように着色されていなければならない。バーの長さは走高跳で 4.00m ($\pm$0.02m) とする。バーの最高重量は走高跳で 2kg とする。バーの円形部分の直径は 30 mm ($\pm$1 mm) とする。 バーは三つの部分からなる。円形の棒とバー止に載せるための幅 30 mm$\sim$35 mm、長さ 0.15m$\sim$0.20m の 2 個の両端である。これらの両端の部分は支柱のバー止の上に置く部分がはっきりと平坦なかまぼこ形あるいは半円形でなければならない。 この平坦な部分は、バーの垂直断面の中心より高い位置にあってはならない。両端の部分は硬く滑らかでなければならない。そしてこれらはバーとバー止の摩擦を増す効果のあるゴムや他の材質で作られていたり覆われていたりしてはならない。 バーはゆがんでいてはならず、バー止にのせた時、最大	計測 義肢 バー
---	--	--

place, shall sag a maximum of 20mm. Control of elasticity: Hang a 3kg weight in the middle of the crossbar when in position. It may sag a maximum of 70mm in High Jump.  Figure 7 – Alternative ends for crossbar Placings 9. If two or more athletes clear the same final height the procedure to decide the places will be the following: - The athlete with the lowest number of jumps at the height last cleared shall be awarded the higher place; - If the athletes are equal following the application of the above Rule the athlete with the lowest total of failures throughout the competition up to and including the height last cleared, shall be awarded the higher place; - If the athletes are still equal following the application of this Rule the athletes concerned shall be awarded the same place unless it concerns the first place; - If it concerns the first place a jump-off between these athletes, it shall be conducted in accordance with Rule 25.10, unless otherwise decided, either in advance according to the Technical Regulations applying to the competition, or during the competition by the Technical Delegate or the Referee if no Technical Delegate has been appointed. If no jump-off is carried out, including where the relevant athletes at any stage decide not to jump further, the tie for first place shall remain. COMMENT: There are a number of ways in which a jump-off may be cancelled/terminated: - by provision in advance of the competition set out in the regulations; - by decision during the competition by the Technical Delegate (or Referee if there is no Technical Delegate); - by decision of the athletes not to jump further prior to or at any stage of the jump-off. Whilst any decision by the Technical Delegate or Referee not to conduct a jump-off should be made before the start of the event, there may be circumstances where this might not be possible such as where conditions at the place of competition make it impossible or undesirable to begin or continue with a jump-off. The Referee	20 mmのたわみまで許される。 弾力性の調整：バー止めに載せた時、バーの中央に 3kg の錘を吊す。その時、最大走高跳で 70 mmたわんでもよい。 順位 25.9. もし二人以上の競技者が最後に越えたのが同じ高さだったとき、順位の決定は以下の手続きで行う。 - 最後に越えた高さで、試技数のもっとも少なかった競技者を勝者とする。 - 上記規則の方法でなお同じ条件の場合は、その試技全体、即ち最後に越えた高さを含めたすべての試技のうち無効試技数がもっとも少なかった競技者を勝者とする。 - この規則の方法でなお同じ条件の場合は、第 1 位に関する場合を除き、同成績の競技者は同順位とする。 - 第 1 位に関して、これらの競技者間のジャンプオフは、事前に公表された競技会で適用される競技規則の中で、あるいは競技会開幕後、しかしその種目開始前に技術代表、技術代表が指名されていない場合は審判長によって、実施しないとの取り決めがない場合は規則 25.10 に従って行われる。当該競技者がもうこれ以上跳躍しないと決めた場合を含みジャンプオフが実施されない場合、同成績により第 1 位となる。 コメント：ジャンプオフがキャンセル/終了される方法は、いくつかある。 - 規定であらかじめ明記していること。 - 技術代表（または技術代表がいなければ審判長）による、競技の最中の決定。 - これ以上跳ばないという競技者たちによる決定。技術代表または審判長によるジャンプオフを実施しないことに決定は、競技の開始前に行わなければならないが、ジャンプオフの開始または計測が、競技場所の条件により不可能または望ましくない場合など、これが不可能な場合もある。審判長は、この状況に対処するために規則 2.13 または規則 24 の下で自身の権限を使用することができる。	順位
--	--	------------------

could use their powers under Rules 2.13 or Rule 24 to deal with this situation.

Jump-off

10.If there is a jump-off:

- a) The athletes concerned must jump at every height until a decision is reached or until all of the athletes concerned decide not to jump further;
- b) Each athlete shall have one jump at each height;
- c) The jump-off shall start at the next height determined in accordance with Rule 25.1 after the height last cleared by the athletes concerned;
- d) If no decision is reached the bar shall be raised if more than one athlete concerned were successful, or lowered if all of them failed, by 2cm;
- e) If an athlete does not attempt a height in a jump-off they automatically forfeit any claim to the first place. If only one other athlete then remains they are declared the winner regardless of whether they clear that height.

High Jump – Example

What follows is a 'worked example' only Heights announced by the Chief Judge at the beginning of competition:

1.75m; 1.80m; 1.84m; 1.88m; 1.91m; 1.94m; 1.97m; 1.99m...

Athlete	Heights (m)							Failures	Jump Off			Pos.
	1.75	1.80	1.84	1.88	1.91	1.94	1.97		1.91	1.89	1.91	
A	0	XO	0	XO	X-	XX		2	X	0	X	2
B	-	XO	-	XO	-	-	XXX	2	X	0	0	1
C	-	0	XO	XO	-	XXX		2	X	X		3
D	-	XO	XO	XO	XXX			3				4

A, B, C and D all cleared 1.88m.

The Rule regarding ties now comes into operation; **all four athletes have the same number of jumps at height last cleared. Now**, the Judges add up the total number of failures, up to and including the height last cleared, i.e., 1.88m.

"D" has more failures than "A", "B" or "C", and is therefore awarded fourth place. "A", "B" and "C" still tie and as this concerns the first place, they shall have one more jump at 1.91m which is the next height after the height last cleared by the athletes tying.

As all the athletes tying failed, the bar is lowered to 1.89m for another jump-off. As only "C" failed to clear 1.89m, the two other tying athletes, "A" and "B" shall have a third jump-off at 1.91m which only "B" cleared and is therefore declared

ジャンプオフ（第 1 位決定戦）

25.10. ジャンプ実施の場合次の手順となる。

- a) 当該競技者は決着がつくまで、あるいはすべての当該競技者がこれ以上跳躍しないと決めるまで、すべての高さで跳躍しなければならない。
- b) 各競技者の各高さでの跳躍は 1 回とする。
- c) ジャンプオフは当該競技者が、規則 25.1 によって最後に越えた次の高さから始める。
- d) もし決着がつかない場合、すなわち二人以上の競技者が成功した場合はバーを上げ、全員が失敗した場合はバーを下げ、その上げ下げの幅は 2cm とする。
- e) もし跳躍しない競技者がいた場合は自動的により高い順位になる権利は剥奪される。その結果一人の競技者だけが残った場合は、たとえその高さを試みなくとも、その競技者が勝者となる。

例（走高跳）

同記録で順位判定の対象となる競技者についてのみ記入競技会の前に審判員主任から告知された高さ：

1.75m ; 1.80m ; 1.84m ; 1.88m ; 1.91m ; 1.94m ; 1.97m ; 1.99m...

A、B、C、D はいずれも 1.88m を 2 回目に成功した。同成績に関する規則が適用される：**4 人すべての競技者は最後の有効試技の高さで同じ数の試技をおこなっている。つぎに、審判員は同記録を生じた高さ、すなわち 1.88m までの無効試技数を数える。**

D は A、B、C よりも無効試技数が多いので第 4 位となる。A、B、C はなお第 1 位の同成績であるので、同成績となった成功試技の次の高さの 1.91m でさらに追加試技を行う。

全員が失敗したので、バーを 1.89m に下げて追加試技を行う。C だけがこの高さを失敗したので、C の第 3 位が決まり、A と B は 1.91m の高さでさらに追加試技を行う。B だけが成功したので勝者となる。

the winner. COMMENT: When an athlete unilaterally decides to withdraw from a jump-off, the other athlete (if only one remains) will be declared the winner in accordance with Rule 25.10 (e). It is not necessary for that athlete to attempt the applicable height. Where more than one athlete remains in the jump-off, the jump-off continues with those athletes, with the athlete who withdrew being placed according to their then finishing place, they having forfeited any right to any higher placing, including first, then remaining. Extraneous Forces 11. When it is clear that the bar has been displaced by a force not associated with an athlete (e.g., a gust of wind): a) If such displacement occurs after an athlete has cleared the bar without touching it, then the trial shall be considered successful, or; b) If such displacement occurs under any other circumstance, a replacement trial shall be awarded. Rule 26: High Jump Competition 1. An athlete shall take off from one foot. 2. An athlete fails if: a) After the jump, the bar does not remain on the supports because of the action of the athlete whilst jumping, or; b) They touch the ground including the landing area beyond the vertical plane through the nearer edge of the crossbar, either between or outside the uprights with any part of their body, without first clearing the bar. However, if when they jump, an athlete touches the landing area with their foot and in the opinion of the Judge, no advantage is gained; the jump for that reason should not be considered a failure. c) They touch the crossbar or the vertical section of the uprights when running up without jumping. Note (i): To assist in the implementation of this Rule a white line 50mm wide shall be drawn (usually by adhesive tape or similar material) between points 3m outside of each upright, the nearer edge of the line being drawn along the vertical plane through the nearer edge of the crossbar. Note (ii): Athletes in Sport Class T11 may touch the bar as an aid to orientation before commencing the run up. If, on so doing, the athlete dislodges the bar this will not count as an attempt. Note (iii): Athletes in Sport Class T12 may place an appropriate visual aid on the bar. COMMENT: For clarity, in the application of this	コメント：1人の競技者が一方的にジャンプオフから撤退を決定した場合、他の競技者（1人だけが残っている場合）は、規則 25.10.(e)に従って勝者と宣言される。このとき、その競技者は該当する高さに挑戦する必要はない。2人以上の競技者がジャンプオフに残っている場合、残った競技者によってジャンプオフは続くが、撤退した競技者は、ジャンプオフ開始前の順位で確定となり、1位をはじめより上位の順位を得る権利を失う。 外力 25.11. 跳び越える時、競技者には関係のない力（例えば突風）によってバーがバー止からはずれた場合は、 a) 競技者がバーに触れないで跳び越えた後であれば、その試技は成功とする。 b) その他の状況では、再試技が許される。 第 26 条 走高跳競技会 26.1. 競技者は片足で踏み切らなければならない。 26.2. 次の場合は無効試技とする。 a) 跳躍した後、バーが競技者の跳躍中の動作によってバー止にとどまらなかった時。 b) バーを越える前に、バーの助走路側の垂直面より着地場所側の、またはその垂直面を支柱から左右に延長した着地場所側の、地面あるいは着地場所に身体のいかなる部分でも触れた時。ただし、競技者が跳躍した時に足が着地場所に触れたが、審判員がなんら有利にならなかったと判断した場合には、無効試技とみなさない。 c) 助走して跳躍せずにバーまたは支柱の垂直部分に接触した場合 注意(i)：判定を補助するために、バーの助走路側の面ならびにその延長上で両支柱の外側 3m までの地面に、粘着テープなどで幅 50mm の白線を引く。その白線を踏んだり踏み越えたりした時は無効試技とする。 注意(ii)：競技クラス T11 の競技者は、試技のための助走開始前に方向確認の助けのためにバーをさわってもよい。 その行為の際にバーが落ちてても、試技とはみなさない。 注意(iii)：競技クラス T12 の競技者は、適当な視覚補助のための物をバーに取り付けることが許される。 コメント：明確にするために、この規則の適用では、規	外力 第 26 条 走高跳 競技会
--	---	---

Rule, the powers of the Referee under Rules 2.13 and Rule 24 should also be considered to reach a fair result for all athletes in the event. If it is not possible for any reason to finally determine any immediate oral protest before the competition continues, the athlete may, for example, be allowed to continue to compete “under protest” in order to preserve their rights. Runway and Take-off Area 3. The minimum width of the runway shall be 16m and the minimum length of the runway shall be 15m except in the Paralympic Games and WPA Championships (see Part B - 3.1.2 (a) and (b)), where the minimum shall be 25m. 4. The maximum overall downward inclination in the last 15m of the runway and take-off area shall not exceed 1:167 (0.6%) along any radius of the semi-circular area centred midway between the uprights. The landing area should be placed so the athlete’s approach is up the inclination. Note: Runways and take-off areas to the 2018/19 specifications remain acceptable. 5. The take-off area shall be generally level and free from any material inclination and shall be in accordance with Rule 26.4 and the World Athletics Track and Field Facilities Manual Apparatus Apparatus 6. Any style of uprights or posts may be used, provided they are rigid. They shall have supports for the crossbar firmly fixed to them. They shall be sufficiently tall as to exceed the actual height to which the crossbar is raised by at least 0.10m. The distance between the uprights shall be not less than 4.00m no more than 4.04m. 7. The uprights or posts shall not be moved during the competition unless the Referee considers that either the take-off or landing area has become unsuitable. In such a case, the change shall be made only after a round of trials has been completed. 8. The supports shall be flat and rectangular, 40mm wide and 60mm long. They shall be firmly fixed to the uprights and immovable during the jump and shall each face the opposite upright. The ends of the crossbar shall rest on them in such a manner that, if the crossbar is touched by an athlete, it will easily fall to the ground, either forwards or backwards. The surface of the supports shall be smooth. The supports shall not be of, or covered with, rubber or with any other material which has the effect of increasing the friction between them and the end pieces of the crossbar, nor may they have any kind of springs.	則 2.13 及び規則 24 に基づく審判長の権限も、種目に参加するすべての競技者が公正な結果が得られるように考慮される。競技が継続する前に何らかの理由で即時抗議を最終的に決定することが不可能な場合、競技者は、例えば、彼の権利を維持するために「抗議中」に競技を続けることを許可される場合がある。 助走路と踏切場所 26.3. 助走路の幅は 16m 以上、距離 15m 以上とする。ただし、パラリンピック競技大会及び WPA 競技会(PART-B 規則 3.1.2(a)及び(b)参照)では 25m とする。 26.4. 支柱間の中間点を中心とし、必要最小限の半径を満たした半円部内での助走路と踏切地点の最後の 15m の最大許容傾斜度は、下方に 167 分の 1 (0.6%)を超えてはならない。着地場所は競技者の助走が登り購買となるように設置する。 注意：2018/2019 仕様の助走路と踏切場所は引き続き認められるものとする。 26.5. 踏切場所は水平、あるいは、どの傾斜も規則 26.4 及び WA 陸上競技施設マニュアルの条件と一致していなければならない。 用器具 26.6. 支柱は、堅固であればどんな形でも差支えない。そして、それにはバーをしっかりと固定できるバー止がなければならない。 支柱はバーの上端より少なくとも 0.10m 高くなければならない。支柱の間隔は、4.00m～4.04m とする。 26.7. 審判長が、踏切あるいは着地場所が適当でなくなったと判断しない限りは競技中に支柱を移動することはできない。 もし移動する時は、その高さの試技が完了してからでなければならない。 26.8. バー止は、平らで長方形とし、幅 40mm、長さは 60mm とする。バー止は、支柱にしっかりと固定され、跳躍中は動いてはならず、反対側の支柱に向きあうように取りつける。バーの両端は競技者がバーに触れたら、前方にでもまた後方にでも容易に落ちるように、バー止の上に置かなければならない。バー止の表面は滑らかでなければならない。 バー止は、バーエンド部分とバー止の表面が摩擦を増加する効果のあるゴムや他の材質で覆わないようにする。また、バネのようなものも一切使用しないようにする。 バー止めは、バーの両端直下の踏切場所と同じ高さとする。	助走路と踏切場所 用器具
--	---	--

The supports shall be the same height above the take-off area immediately below each end of the crossbar.




Figure 8 – High Jump uprights and crossbar

9. There shall be a space of at least 10mm between the ends of the crossbar and the uprights.

Landing Area

10. For the Paralympic Games and WPA Championships under Part B - 3.1.2 (a) and (b), the landing area shall be not smaller than 6m long x 4m wide x 0.7m high behind the vertical plane of the crossbar.

Note: The uprights and landing area should also be designed so that there is a clearance of at least 0.1m between them when in use, to avoid displacement of the crossbar through a movement of the landing area causing contact with the uprights.

COMMENT: For other competitions, the landing area should measure not less than 5m long x 3m wide x 0.7m high.

Team of Officials

For a High Jump Event, it is recommended to allocate the available officials as follows:

1) The Chief Judge will watch over the whole of the event and verify the measurements. They must be provided with two flags - white to indicate if the trial is valid and red if it is a failure. They must place themselves so as to manage two matters in particular:

a) Frequently it happens that the cross-bar having been touched by an athlete trembles on the supports. The Chief Judge, depending on the position of the cross-bar, must decide when the vibrating of the bar must be stopped and the appropriate flag raised—particularly the special situations as covered in Rule 25.11 and

b) Since the athlete may not touch the crossbar, the vertical section of the uprights or ground beyond the vertical plane of the nearer edge of the crossbar it is important to keep a watch on the position of the athletes feet in situations where when deciding not to complete a trial they run to the side or goes “under” the bar.

2) Judges (1) and (2) on either side of the landing area and slightly standing back in charge

26.9. 支柱とバーの両端との間は、少なくとも 10 mm あげなければならない。

着地場所

26.10. パラリンピック競技大会及び WPA 競技会 (PART-B 規則 3.1.2(a)及び(b)参照)では、着地場所は、バーの垂直面後方に少なくとも幅 6m×奥行き 4m×高さ 0.7m 以上とする。m以上とする。

注意：支柱と着地場所との間隔は、競技者の落下時、着地場所が動いて支柱に接触しバーが落ちるのを避けるため、少なくとも 100 mmはあけるようにする。

コメント：他の競技会では、着地場所は、長さ 5m×幅 3m×高さ 0.7m 以上でなければならない。

競技役員チーム

走高跳の場合、以下のように競技役員を配置することが推奨される。

1) 審判員主任は、競技全体を監視し、計測結果を確認する。審判員主任は、2つの旗を用意しなければならない - 試技が有効であることを示す白旗と無効であることを示す赤旗。審判員主任は、特に2つの問題を管理しやすい場所に位置しなければならない。:

a) 競技者がタッチしたクロスバーがバー止めで震えることがよくある。審判員主任は、特に、規則 25.11 にある特別な状況においてクロスバーの位置に応じて、バーの揺れを止める時期を決め、適切な旗を掲げなければならない。

b) 競技者はクロスバー、クロスバーの手前の縁の垂直面より先の地面に触れてはならないので、競技者が跳躍せずに、着地場所の脇やバーの下に走り込んだとき競技者の足の位置を監視し続けることは重要である。

2) 審判員 (1) と (2) は着地場所の両側のやや後方に位置し、クロスバーの交換を担当し、また上記

of replacing the cross-bar when it falls and assisting the Chief Judge in applying the above Rules. 3) Judge - a recorder scoring the results sheet and calling each athlete (and the one who is to follow). 4) Judge in charge of the scoreboard (trial-number-result). 5) Judge in charge of the clock indicating to the athletes that they have a certain time to take their trial. 6) Judge in charge of athletes. Note (i): This is the traditional setting-up of the officials. In major competitions, where a data system and electronic scoreboards are available, specialised personnel are certainly required. To be clear in these cases, the progress and scoring of a Field Event is followed by both the recorder and by the data system. Note (ii): Officials and equipment must be placed in such a way as not to obstruct the athlete's way nor impede the view of the spectators. Note (iii): A space must be reserved for a wind-sock to indicate the wind direction and strength B. HORIZONTAL JUMPS COMMENT: These rules apply equally to both the Long Jump and Triple Jump, except for variations for T11 and T12 class athletes, set-up and jumping. Rule 27: General Conditions Runway 1. The minimum length of the runway shall be 40m, measured from the relevant take-off line to the end of the runway. It shall have a width of 1.22m ± 0.01m and shall be marked by white lines 50mm in width. Note: For all tracks constructed before 1 January 2004 the runway may have a width of maximum 1.25m. However, when such a runway is fully resurfaced, the lane width shall comply with this Rule. 2. The maximum lateral inclination of the runway should be 1:100 (1%) unless special circumstances exist which justify World Athletics providing an exemption and in the last 40m of the runway the overall downward inclination in the direction of running shall not exceed 1:1000 (0.1%). The Take-off Board and Take-off Area 3. The take-off shall be marked by a board sunk level with the runway and the surface of the landing area. The edge of the board which is nearer to the landing area shall be the take-off line.	規則を審判員主任が適用する際に支援する。 3) 審判員 – 記録表を記入し、各競技者（及びさらにその次の競技者）を呼び出す記録者 4) スコアボード（試技回数-競技者のナンバー-結果）を担当する審判員 5) 試技の残り時間を競技者に示す時計を担当する審判員 6) 競技者を担当する審判員 注意(i)：これは競技役員の伝統的な配置である。データシステムと電子スコアボードが利用可能な大規模な競技会では、専門の人材が必ず必要である。このような場合には、フィールド種目の進捗状況と結果は、記録者とデータシステムの双方で記録される。 注意(ii)：競技役員及び用具は、競技者を妨害したり、観客の視界を妨げたりしないように配置されなければならない。 注意(iii)：風の方向と強さを示すために、吹き流しのためのスペースを確保する必要がある。 B. 長さの跳躍 コメント：これらのルールは、走幅跳と三段跳の両方に等しく適用されるが、T11 及び T12 クラスの競技者のバリエーション、セットアップ、及びジャンプは例外である。 第 27 条 総則 助走路 27.1. 踏切線から計測した助走路の最短距離は 40m とする。助走路の幅は 1.22m ± 0.01m とし、助走路の両側に幅 50 mm の白いラインを引かなければならない。 注意：2004 年 1 月 1 日以前に建造された競技場において助走路の幅は最大 1.25m でよい。但し、こうした助走路を全面改修する場合には、この規則に完全に適合させなければならない。 27.2. 助走路の最大許容傾斜度は、WA が例外を認めるに足る特別な状況がある場合を除き、幅で 100 分の 1（1%）にすべきであり、助走の方向で最後の 40m の下方傾斜度は 1,000 分の 1（0.1%）を超えてはならない。 踏切板及び踏切エリア 27.3. 踏切地点を示すために助走路及び砂場の表面と同じ高さに踏切板を埋める。踏切板の砂場に近い方の端を踏切線と呼ぶ。	B. 長さの跳躍 第 27 条 総則 助走路 踏切板及び踏切エリア
---	--	--

Note: The take-off board can be constructed as a single piece of board 0.30m wide with a 0.20m white section and a 0.10m in a contrasting colour, i.e. the take-off board and blanking board can be one piece.

4. Construction. The take-off board shall be rectangular, made of wood or other suitable rigid material in which the spikes of an athlete's shoe will grip and not skid and shall measure $1.22\text{m} \pm 0.01\text{m}$ long, $20\text{cm} (\pm 2\text{mm})$ wide and not more than 10cm deep. It shall be white. In order to ensure that the take-off line is clearly distinguishable and in contrast to the take-off board, the ground immediately beyond the take-off line shall be in a colour other than white. (see Figure 9A)




Figure 9A-Take-off board with blanking board

5. The use of video or other technology, to assist the Judges in deciding the application of Rule 28.1, **is to be used** at all levels of competition. However, **for competitions under Part B-3.1.2 (c) and (d)**, if no technology is available, a plasticine indicator board placed immediately beyond the take-off line may still be used.

The plasticine indicator board shall consist of a rigid board, 10cm ($\pm 2\text{mm}$) wide and $1.22\text{m} \pm 0.01\text{m}$ long made of wood or any other suitable material and shall be painted in a contrasting colour to the take-off board. Where possible, the plasticine should be of a third contrasting colour. The board shall be mounted in a recess or shelf in the runway, on the side of the take-off board nearer the landing area. The surface shall rise from the level of the take-off board to a height of 7mm ($\pm 1\text{mm}$). The edges shall be cut away such that the recess, when filled with plasticine the surface of the plasticine nearer to the take-off line shall be at an angle of 90° (see Figure 9B).




Figure 9B – Take-off board and plasticine indicator board

注意：踏切板は、幅 200mm の白色部分と幅 100mm の対照的な色部分が一体となった、幅 300mm の単一の板として作成することができる。即ち、踏切板設置位置の窪みを、踏切板とくぼみを埋める器具とを一体で形成したものでよい。

27.4. 構造 — 踏切板は競技者の靴のスパイクがグリップし滑らない木または他の強固な材質でつくられた直方体のもので長さ $1.22\text{m} \pm 0.01\text{m}$ 、幅 20cm ($\pm 2\text{mm}$) で、厚さは 10cm 以内とする。踏切板は白色でなくてはならない。踏切線の位置を明確にし、踏切板と対比できるように、踏切線よりも着地場所側は白以外の色でなければならない。(図 9A 参照)

27.5. ただし、Part B-3.1.2 (c) および (d) の競技会において、こうした機器が使用できない場合は、踏切線のすぐ先に設置した粘土板を使用することができる。

粘土板は幅 10cm ($\pm 2\text{mm}$)、長さ $1.22\text{m} \pm 0.01\text{m}$ の木あるいは他の材質の強固な板で作り、踏切板とは区別できる別の色でなければならない。可能な限り粘土も他の二つの色と区別できる色とする。粘土板は、砂場に近い踏切板の縁の窪みに埋める。その表面は、踏切板の水平面から 7 mm ($\pm 1\text{mm}$) 盛り上がっていないなければならない。粘土板は、粘土を埋めた時は助走路に近い縁が 90° の角度となるように隅を削り取る。(図 9B 参照)

When mounted in this recess, the whole assembly shall be sufficiently rigid to accept the full force of the athlete's foot.

The surface of the board beneath the plasticine shall be of a material in which the spikes of an athlete's shoe will grip and not skid.

The plasticine can be smoothed off by means of a roller or suitably shaped scraper for the purposes of removing the footprint of an athlete.

Note: Where in construction of the runway and/or take-off board there was previously provision for the placement of a plasticine indicator board and such board is not used, this recess should be filled by a blanking board flush with the take-off board.

6. For athletes in Sport Classes T11 and T12, the take-off area shall consist of a rectangle of 1.00m x 1.22m ± 0.01m as depicted in Figure 10, which must be prepared in such a way (by use of chalk, talcum powder, light sand, etc.) that the athlete leaves an impression on the area with their take-off foot. The edge of the take-off area which is nearer to the landing area shall be the scratch line.




Figure 10 – Take-off Area for athletes in Sport Classes T11 and T12

The Landing Area

7. The landing area shall have a minimum width of 2.75m and a maximum width of 3m. It shall, if possible, be so placed that the middle of the runway, if extended, would coincide with the middle of the landing area.

Note (i): When the middle of the runway is not in line with the middle of the landing area, a tape, or if necessary, two tapes, should be placed along the landing area so that the above is achieved (see Figure 11).

Note (ii): For Sport Classes T11-12 and the purposes of safety, it is strongly recommended that the minimum distance between the axis of the runway and the sides of the landing area be 1.75m (see Figure 10). If this recommendation cannot be met the Technical Delegate may require additional safety measures.

窪みに粘土板が埋められた時は、全体が競技者の脚力を受け止めるのに十分固くなくてはならない。

粘土板の表面は、競技者の靴のスパイクをしっかり捕らえ、滑らない材質でなければならない。

粘土は、競技者の足跡を除去するためにローラーあるいは適当な形のヘラで平らにならす。

注意：助走路の踏切板部分にあらかじめ粘土板を設置するように施工されている場合、粘土板を使用しないのであれば、その窪みは埋める必要がある。

27.6. 競技クラス T11 及び T12 の競技者の踏切エリアは、下図に示すとおり 1.00m×1.22m の長方形とし、競技者の踏み切りの痕跡が残るよう（チョーク、タルカムパウダー、砂等を使って）準備しなければならない。踏切エリアの着地エリアに近いほうの端をスクラッチライン（踏切境界線）とする。

着地場所

27.7. 砂場の幅は 2.75m～3mとする。砂場は、できればその中央と助走路の中央の延長が一致するように位置させる。

注意(i)：助走路の中心線が砂場の中央と一致しない場合には助走路の中心線の延長の両側を同じ幅とし、上記の規定の幅となるように状況に応じ砂場の片側または両側にテープを貼らなければならない。（図 11 参照）

注意(ii)：競技クラス T11-12 の競技者の安全確保のため、助走路の中心線から着地エリア両端までの距離は 1.75m 以上とすることを強く推奨する。（図 10 参照）これが不可能な場合、技術代表は追加的な安全措置を要請できる。




Figure 11 – Centralized Long Jump / Triple Jump landing area

COMMENT: Where new facilities are developed at which it is envisaged that athletes with vision impairment will compete in, at least one pit should be built with an increased width (3.50m instead of maximum 3.00m as in the World Athletics Rules).

8. The landing area should be filled with soft damp sand, the top surface of which shall be level with the take-off board.

Distance Measurements

9. The measurement of each Jump shall be made immediately after each valid trial (or after an immediate oral protest made under Rule 50.5). All jumps shall be measured from the nearest break in the landing area made by any part of the body or anything that was attached to the body at the time it made a mark to the take-off line, or take-off line extended. The measurement shall be taken perpendicular to the take-off line or its extension.

10. For athletes in Sport Classes T11 and T12 all jumps shall be measured from the nearest break in the landing area perpendicular to the nearest impression left by the take-off foot or its extension. Where an athlete does not take off from the take-off area, but before it, measurement will be made to the edge of the take-off area furthest from the landing area.

11. In all horizontal jumping events, distances shall be recorded to the nearest 0.01m, rounded down to the nearest 0.01m if the distance measured is not a whole centimetre.

COMMENT: As long as no irregularity has been committed, each trial must be measured whatever the distance reached, including for the reasons that other trial measurements may become critical in determining countbacks or whether an athlete will proceed to subsequent rounds. Except where Rule 50.5 is applied, under normal practice no trial during which an irregularity has been committed should be measured. Judges should carefully use their discretion in applying any alternate practice and usually only in special cases.

Unless video measuring is being used, for every valid trial a marker (usually metal) should be placed in a vertical position at the place of the imprint left by the athlete in the landing area nearest to the take-off line. The marker is passed through the loop at the end of the graduated

コメント：視覚障がい者が競技することが想定される新たな施設が計画されるなら、IPC の推奨するように、少なくとも 1 つのピットを WA 規則よりも幅を広げて (WA 規則の最大 3.00m ではなく 3.50m) 構築する必要がある。

27.8. 砂場は柔らかい湿った砂で満たされ、上部表面は踏切板と水平にしなければならない。

距離計測

27.9. 跳躍の計測は有効試技終了後 (または、規則 50.5 に定める口頭による即時抗議が行われた後)、直ちに行わなければならない。跳躍距離は、身体のかなる部分または着地時に身に付けていたすべてのものが着地場所に残した痕跡の踏切線に最も近い箇所から踏切線またはその延長線上の地点までを計測する。計測は踏切線もしくはその延長線に対して直角に行う。

27.10. 競技クラス T11 及び T12 の競技者の跳躍はすべて、着地場所に残した痕跡の踏切線に最も近い箇所から踏切足が残した最も近い痕跡またはその延長線までを計測するものとする。踏切エリアの手前で踏み切った場合は、着地場所から最も遠くに位置する踏切エリアの端までの距離を計測するものとする。

27.11. 長さを競う跳躍種目において、その距離は、cm 未満の端数を切り捨てた 0.01m 単位で記録しなければならない。

コメント：無効試技でない限り、どれだけ跳んだかの距離にかかわらず、すべての試技を測定しなくてはならない。順位を決めるため、また次のラウンドに進出できるかどうかなどの理由による。規則 50.5 が適用される場合を除き、通常では、無効試技は計測されない。審判員は特殊な場合にのみ、与えられた裁量の範囲内で慎重に判断を行う。

ビデオ距離計測が使用されている場合を除いて、有効な試技ごとにマーカー (通常は金属製) を、踏切線に最も近い着陸エリアに競技者が残した痕跡に垂直に刺す必要がある。巻尺の"ゼロ"はマーカーに合わせ、テープは水平に引き出し、地面に浮かさないように注意する。

metal tape so that the “zero” is on the mark. The tape should be pulled out horizontally taking care not to place it on any rise in the ground.

The measurement of the distance of a jump for Class T11 and T12

Chalk powder may be used for the powder in the 1.00m x 1.22m ± 0.01m take-off area. Measuring the jump is made from the nearest impression left by the take-off foot (within the chalk powder), if within the area. If the take-off is made before the take-off area, the measurement is made from the edge of the take-off area furthest to the landing area (see below figure 12).




Figure 12 – Measurement of the distance in horizontal jumps for Class T11 and T12

Wind Measurement

12. The wind gauge shall be the same as described in Rule 18.11 and Rule 18.12. It shall be operated as described in Rules 18.14 and Rule 18.15 read as per Rule 18.16.

13. The relevant Field Events Referee shall ensure that the wind gauge is placed 20m from the take-off line. It shall be positioned 1.22m high and not more than 2m away from the runway.

The wind velocity shall be measured for a period of 5 seconds from the time an athlete passes a mark placed alongside the runway, for the Long Jump 40m from the take-off line and for the Triple Jump 35m. If an athlete runs less than 40m or 35m, as appropriate, the wind velocity shall be measured from the time they commence their run.

Prosthetic Device(s)

14. For athletes competing in horizontal Jumping Events in sport classes T61-64, the use of prosthetic device(s) is mandatory. The relevant Official shall ensure that Rule 6.12.1(b) is observed.

a) If the prosthetic device(s) is lost during the run-up then the athlete cannot continue without the prosthetic device(s). The athlete shall fix/adjust the prosthetic device(s) and recommence the trial provided they are within the time allowed for the trial;

b) If the prosthetic device(s) is lost during the process of jumping and the mark where the prosthetic device(s) lands is the closest mark to the take-off board in the landing area, then that

競技クラス T11 及び T12 のジャンプ距離の測定

1.00m x 1.22m ± 0.01m の踏切エリアのチョークパウダーが使用される。ジャンプの測定は、踏切エリア内に痕跡がある場合、踏切足（チョークパウダー内）が残した着地エリアに最も近い痕跡から行われる。踏切が踏切エリアの手前に行われた場合、測定は踏切エリアの最も遠い端から着陸エリアまで行われる（図 12 を参照）。

風力測定

27.12. 風向風速計は、規則 18.11 及び 18.12 に記載のものを使用し、規則 18.14 及び 18.15 に従って操作し、規則 18.16 に従って読みとる。

27.13. 当該審判長は、風向風速計を踏切線から 20m の地点に設置していることを確認する。風向風速計の測定面は、助走路から 2m 以上離してはならず、高さは 1m220 (±50mm) でなければならない。

風速は競技者が踏切板から走幅跳で 40m、三段跳で 35m 離れ、助走路の脇に置かれたマークを通過する時から 5 秒間計る。もし競技者が 40m または 35m よりも短い距離の助走をする場合は、助走を開始した時から計る。

義肢

27.14. 競技クラス T61-64 の競技者が長さの跳躍種目で競技する場合、義肢（複数も）の使用は必須とする。関係する役員は規則 6.12 (b)（下肢用義肢の使用）について確認しなくてはならない。

a) 助走中に義肢が脱落した場合、競技者は義肢を装着していない状況では競技を続けることはできない。競技者は制限時間内に義肢を再装着／調整し競技を再開しなくてはならない。

b) 跳躍中に義肢がはずれた場合、義肢が着地エリア内に落下し、その痕跡が踏切板に最も近いときはその痕跡を起点として計測する。

is the mark that the trial will be measured from; c) If the prosthetic device(s) lands outside the landing area (whether closer to or further from the take-off line than the closest mark to the take-off board in the landing area), it shall be counted as a failure and recorded as such. Rule 28: Long Jump The Competition 1. An athlete fails if: a) he while taking off (at any time prior to the instant at which they cease contact with the take-off board or ground), breaks the vertical plane of the take-off line with any front part of their take-off foot/shoe or prosthetic device, whether running up without jumping or in the act of jumping, or; Note: It will not be considered a failure, if the break of the vertical plane is made by a loose part of the shoe (e.g. shoelace). Comment: Since the intent of Rule 28.1a focuses on the position of the front of the take-off shoe/foot or prosthetic device, it is not relevant if the vertical plane should be broken in other ways, for example by their hands or arms or a cap or piece of jewellery falling from the athlete's body during the take-off. Similarly, a loose shoelace or the like is not relevant to the adjudication even if it breaks the plane. b) he takes off from outside either end of the board, whether beyond or before the extension of the take-off line or; c) he employs any form of somersaulting whilst running up or in the act of jumping or; d) after taking off, but before their first contact with the landing area, they touch the runway or the ground outside the runway or outside the landing area; or e) in the course of landing, they touch the border of, or the ground outside the landing area closer to the take-off line than the nearest break made in the sand or; f) he leaves the landing area in any manner other than that described in Rule 28.2. 2. When leaving the landing area, an athlete's first contact by foot with its border or the ground outside shall be further from the take-off line than the nearest break in the sand. (Which may be any mark made on overbalancing completely inside the landing area or when walking back closer to the take-off line than the initial break on landing.) Note: This first contact is considered leaving. 3. An athlete shall not be regarded to have failed if: a) he runs outside the white lines marking the runway at any point; or	c) 義肢が着地エリアの外側に落下した場合、(着地場所に残した踏切板から最も近い痕跡より踏切線に近くても遠くても関係なく) その試技は無効とみなされ、そう記録されるものとする。 第 28 条 走幅跳 競技会 28.1. 次のような場合は無効試技とする。 a) 競技者が踏切を行う際、跳躍しないで走り抜ける中で、あるいは跳躍の動きの中で (いかなる時も踏切板から離れる前に、または地面から離れる前に)、踏切足または踏切足の靴の前部のどこか、または義肢のどこかが踏切線の垂直面より前に出た場合。 注意：靴本体ではなく、靴紐など靴の緩んだ部分が踏切線の垂直面より前に出た場合は、無効試技と見なさない。 コメント：規則 28.1a は、踏切時の靴、足の前部と義肢の位置に着目しており、踏切動作中に手や腕、身に着けていた帽子やアクセサリーが落ちたりといった、他の身体部位や身に着けているアイテムが垂直面を超えるかどうかは関係ない。同様に、靴紐の緩みなどが垂直面を出たとしても、判定には影響しない。 b) 踏切線の延長線より先でも手前でも、踏切板の両端よりも外側から踏切った時。 c) 助走あるいは跳躍動作中に宙返りのようなフォームを使った時。 d) 踏切後、着地場所への最初の接触前に助走路あるいは助走路外の地面あるいは着地場所の外側の部分に触れた場合 e) 着地の際、砂に残った最も近い痕跡よりも踏切線に近い砂場の外の境界線または地面に触れた時。 f) 規則 28.2 に定める以外の方法で着地場所を離れた場合。 28.2. 着地場所を離れる際、競技者の足が砂場との境界線上または砂場外の地面へ最初に触れる位置は踏切線に最も近い痕跡よりも踏切線より遠くなくてはならない。(痕跡とは、着地場所内において着地で最初に残した痕跡よりも踏切線に近い方に完全にバランスを崩したり、あるいは歩いて戻ってできたすべてを含む)。 注意：この行為を着地場所からの離脱とみなす。 28.3. 以下の場合、競技者は試技無効とはならない。 a) 助走の途中どこかの地点で助走路を示す白線の外側にはみ出た場合。	第 28 条 走幅跳 競技会
--	--	------------------------------

b) except as described in Rule 28.1 (b), they take off before reaching the board. c) under Rule 28.1 (b) a part of their shoe/foot is touching the ground outside either end of the take-off board (or take-off area for Sport Classes T11 and T12), before the take-off line; or d) if in the course of landing, they touch, with any part of their body, or anything attached to it at that moment, the border of, or the ground outside the landing area, unless such contact contravenes Rule 28.1 (d) or Rule 28.1 (e); or e) he walks back through the landing area after having left the landing area in the manner described in Rule 28.2. Take-off line and Scratch line 4. The distance between the take-off line and the far end of the landing area shall be at least 10m and, where possible, 11m. 5. The take-off line shall be placed between 1m and 3m from the nearer end of the landing area. 6. For athletes in Sport Classes T11 and T12, the distance between the scratch line and the far end of the landing area shall be at least 10m. The scratch line shall be placed between 1m and 3m from the nearer end of the landing area. COMMENT: Team of Officials For a Long Jump or Triple Jump Event, it is recommended to allocate the available officials as follows: 1) The Chief Judge will watch over the whole of the event. 2) Judge checking whether the take-off has been made correctly and measuring the trial. They must be provided with two flags - white to indicate if the trial is valid and red if it is a failure. When the jump has been measured, it is advised that the judge stands in front of the take-off board, holding the red flag, while the landing area is levelled and, if relevant, the plasticine board is replaced. A cone may be used instead or in addition. (In some competitions this position is assumed by the Chief Judge of the event.) 3) Judge at the landing point determining the position of the nearest break in the landing area to the take-off line, to insert the spike/prism and then, if a tape is being used, hold the tape on the 0. When video measuring is being used, no judge will normally be required on site for this purpose. When an optic system of measuring is being used on site, two judges are needed at the landing point, one to plant the marker in the sand, the other one to read the result on the optic apparatus. 4) Judge - a recorder scoring the results sheet and calling each athlete (and the one who is to follow).	b) 規則 28.1(b)に定める場合を除き、踏切板の手前で踏み切った場合。 c) 規則 28.1(b)において、踏切線（またはT11 や 12 競技クラスの踏切エリア）より手前で競技者の靴または足の一部が踏切板のいずれかの端の外側の地面を踏んだ場合。 d) 着地の際に、身体の一部またはその時に身に着けていたものが着地場所の境界線またはその外側の地面に接触した場合。ただし、規則 28.1(d)または(e)に該当する場合は除く。 e) 規則 28.2 に定めるとおりの方法で着地場所をいったん離れた後に着地場所を通って戻ってきた場合。 踏切線及びスクラッチライン 28.4. 踏切線と砂場の遠い端との距離は、少なくとも 10m、可能であれば 11m とする。 28.5.踏切線は、砂場の近い端から 1m～3mに位置しなくてはならない。 28.6. 競技クラス 11 及び 12 において、スクラッチラインと砂場の遠い端との距離は少なくとも 10mとする。スクラッチラインは、着地エリアの助走路寄りの縁から 1m～3mの位置に引かなくてはならない。 コメント：競技役員チーム 走幅跳と三段跳の場合、以下のように競技役員を配置することが推奨される。 1) 審判員主任は、競技全体を監視する。 2) 踏み切りが正しく行われたかどうかを判断し、試技を計測する審判員。審判員は、2 つの旗を用意しなければならない - 試技が有効であることを示す白旗と無効であることを示す赤旗。跳躍が計測されたら、審判員は踏切板の前に立ち、砂場を平らにしている間は、赤旗を掲げる。必要であれば粘土板の交換も行う。赤旗の代わりに、もしくは赤旗にくわえて、助走路にコーンを置いてもよい。（いくつかの競技会では、この役目は、審判員主任の任務であると想定されている）。 3) 着陸地点において、踏切線に最も近い痕跡を確定する審判員。ピン／プリズムを刺し、巻尺が使用されている場合には、巻尺を 0 に保持することを決定する。ビデオ距離計測が使用されている場合、この目的のためには、通常審判員は必要ない。光波が使用されているときは、2 人の審判員が必要となり、一人はプリズムを刺し、ひとりは光波の数値を読む。 4) 審判員 - 記録表を記入し、各競技者（及びさらにその次の競技者）を呼び出す記録者	踏切線及びスクラッチライン
--	---	-----------------------------

5) Judge in charge of the scoreboard (trial-number-result). 6) Judge in charge of the wind-gauge positioned at a point 20 metres from the take-off board. 7) one or more Judges or assistants in charge of levelling the landing area after each trial. 8) Judge or an assistant in charge of replacing the plasticine. 9) Judge in charge of the clock indicating to the athletes that they have a certain time to take their trial. 10) Judge in charge of athletes. Note (i): This is the traditional setting-up of the officials. In major competitions, where a data system and electronic scoreboards are available, specialised personnel are certainly required. To be clear in these cases, the progress and scoring of a Field Event is followed by both the recorder and by the data system. Note (ii): Officials and equipment must be placed in such a way as not to obstruct the athlete's way nor impede the view of the spectators. Note (iii): A space must be reserved for a wind-sock to indicate the wind direction and strength. Rule 29: Triple Jump Rules 27 and 28 apply to the Triple Jump with the following variations: The Competition 1. The Triple Jump shall consist of a hop, a step and a jump in that order. 2. The hop shall be made so that an athlete lands first on the same foot as that from which they have taken off; in the step they shall land on the other foot, from which, subsequently, the jump is performed. It shall not be considered a failure if, during a trial, an athlete, touches the ground with the "sleeping" leg. Note: Rule 28.1 (d) does not apply to the normal landings from the hop and step phases. Take-off Line and Scratch Line 3. The distance between the take-off line for men and the far end of the landing area shall be at least 21m. 4. For WPA Recognised Competitions, there should be a separate take-off board for men and women. For athletes in eligible Sport Classes it is recommended that the take-off line will normally be set at 11m for men and 9m for women. For athletes in Sport Classes T11 it is recommended that the scratch line shall be a	5) スコアボード（試技回数-競技者のナンバー-結果）を担当する審判員 6) 踏切板から 20m の地点に位置する風向風速計を担当する審判員 7) 各試技後に 1 人またはそれ以上の、着地エリアを水平にすることを担当する審判員または補助員 8) 粘土板の交換を担当する審判員または補助員 9) 試技の残り時間を競技者に示す時計を担当する審判員 10) 競技者を担当する審判員 注意(i)：これは競技役員の伝統的な配置である。データシステムと電子スコアボードが利用可能な大規模な競技会では、専門の人材が必ず必要である。このような場合には、フィールド種目の進捗状況と結果は、記録者とデータシステムの双方で記録される。 注意(ii)：競技役員及び用具は、競技者を妨害したり、観客の視界を妨げたりしないように配置されなければならない。 注意(iii) 風の方向と強さを示すために、吹き流しのためのスペースを確保する必要がある。 第 29 条 三段跳 規則 27 と 28 及び次に加える条項を三段跳に適用する。 競技会 29.1. 三段跳はホップ、ステップ及びジャンプの順で成立っている。 29.2. 競技者はホップで踏切った同じ足で最初に着地し、ステップでは反対の足で着地し、つづいてジャンプを行う。 試技中に“振り出し足”が地面に触れても、無効試技とはならない。 注意：規則 28.1(d)は、ホップとステップによる着地には適用せず、最後のジャンプ後にのみ適用する。 踏切線及びスクラッチライン 29.3.男子の踏切線は、砂場の遠い方の端から少なくとも 21m以上とする。 29.4. WPA 認可競技会では、踏切板を男女で分けるなければならない。対象の競技クラスの踏切線は、通常、男子は 11m、女子は 9m 地点に設置するのが望ましい。 競技クラス T11 の踏切線は、少なくとも男子 9m、女子 7m 地点が推奨される。	第 29 条 三段跳 競技会 踏切線及びスクラッチライン
---	--	--

minimum 9m for men and 7m for women. Note: the exact distance from the scratch line/take-off line to pit shall be determined for each competition in consultation with the Technical Delegate. For safety purposes, a different scratch line/take-off line can be used if approved by the Technical Delegate. 5. Between the take-off board and the landing area there shall, for the step and jump phases, be a take-off area of 1.22m ± 0.01m wide providing firm and uniform footing. Note: For all tracks constructed before 1 January 2004, this take-off area may have a width of maximum 1.25m. However, when such a runway is fully resurfaced, the lane width shall comply with this Rule. COMMENT: It should be noted that in the Triple Jump it is not a failure (for that reason alone) if the athlete: a) Touches the white lines or the ground outside between the take-off line and the landing area; Or b) If the athlete lands in the pit in the step phase through no fault of their own (i.e. the judges incorrectly indicated the take-off board) - in which such case the Referee would normally offer the athlete a substitute trial. It is, however, a failure if the landing of the jump is not within the landing area C. THROWING EVENTS FOR AMBULANT ATHLETES COMMENT: Practice trials at the competition area Athletes in Field Events are entitled to warm-up at the competition area prior to the start of the competition. For ambulant throwers, previously athletes were given two practice throws, there is now no such specification and athletes shall be allowed as much warm-up and practice throwing as the warm-up time permits. At the Paralympic Games and WPA Championships (see Part B - 3.1.2 (a) and (b)) the standard practice is still two Official practice throws are given and in the official throwing order as drawn by lot. See the differences for secured throwers in the rule respecting Seated Throwing Requirements (Rule 35.5). Rule 30: General Conditions Comment: Unless specific rule differences are contained within Section D- THROWING EVENTS FOR SEATED ATHLETES, the General Conditions and specific event rules contained within this Section C, equally to ambulant and seated throws. Implements 1. The implements used (not otherwise unique to Para Athletics) shall comply with current World	注意：スクラッチライン/踏切線から着地エリアまでの実際の距離は、競技会ごとに技術代表と協議して決定するものとする。安全のために技術代表が認めれば、ほかのスクラッチライン/踏切線を使用してもよい。 29.5. ステップとジャンプを行う踏切板と砂場の間は踏切区域といい、その区域は少なくとも幅 1.22m±0.01m で、堅く均一の足場を備えていなければならない。 注意：2004 年 1 月 1 日以前に建造された競技場について、踏切区域の幅は最大 1.25m でよい。但し、こうした助走路を全面改修する場合には、この規則に完全に適合させなければならない。 コメント：競技者が次の場合、三段跳では（その理由だけで）無効試技ではないことに注意すること。 a) 踏切線と着陸エリアの間の白い線または外側の地面に触れる。 あるいは b) 競技者が自分の過失なしにステップ場面で着地エリアに着地した場合（つまり、ジャッジが踏切板を誤って示した場合）-このような場合、審判長は通常、競技者に再試技を指示する。 ただし、着地が着地エリア内でない場合は無効試技である。 C. 立位競技者の投てき種目 コメント：競技エリアでの練習試技 フィールド競技に参加する競技者は、競技開始前に競技エリアでウォームアップすることができる。 立位競技者の場合、以前は 2 回の練習投てきが許されていたが、現在はそのような仕様はなく、競技者はウォームアップ時間の許す限りウォームアップと練習投てきを許可されている。 パラリンピック競技大会及び WPA 競技会（PART-B 規則 3.1.2(a)、及び(b)参照）では、標準の練習は抽選で決定された公式の投てき順序で 2 回の公式練習投てきが許される。座位の投てき要件に関する規則（規則 35.5）で、座位の投てき者との違いを参照すること。 第 30 条 総則 コメント：特定のルールの違いがない限り Section D-座位競技者の投てき競技に含まれる一般受験および本 Section C に含まれる特定の競技規則は、立位投てきと座位投てきに等しく適用される。 公式用具 30.1. 投てき用具(パラ陸上競技独特のものを除く)は WA の規格に合致したものでなければならない。	C. 立位競技者の投てき種目 第 30 条 総則 公式用具
--	--	---

Athletics specifications. Only those implements which hold a current valid World Athletics Product Certificate of approval may be used at WPA Recognised Competitions (see Part B - 3.1.2). The Para Athletics Implement Weights lists are set out in Appendix 1. Note: In WPA Recognised Competitions under Part B - 3.1.2, athletes must only use the implement weights relevant to their Sport Class (as outlined in Appendix 1). 2. The weights of Implements listed in Appendix 1 and not otherwise identified by World Athletics specifications must be verified by the Technical Delegate to confirm the implement is compliant. Note: This refers to implements unique to Para Athletics that are not documented within World Athletics Rule 187 or related appendices. 3. Except as provided below, all such implements shall be provided by the LOC. The Technical Delegate(s) may, based on the relevant Technical Regulations of each competition, allow athletes to use their own personal implements or those provided by a supplier, provided that such implements are World Athletics certified, checked and marked as approved by the LOC before the competition and made available to all athletes. Unless the Technical Delegate decides otherwise, not more than two implements may be submitted by any athlete for any throwing event in which they are competing. Note: "World Athletics certified" implements may include older models that previously held a certificate but are not in production any longer. COMMENT: It is becoming increasingly common for the LOC to provide a lesser range of implements than in the past (largely due to the cost of purchases). This increases the responsibility of Technical Managers and their assistants to closely check all personal implements presented for competitions – to ensure that they comply with the Rules as well as being on the World Athletics list of certified products. Implements which do not currently have but have previously had a World Athletics certificate may be accepted for competition if they comply with the Rules 4. No modification shall be made to any implements during the competition. No spitting or application by other means of human body fluids on any implement, is permitted. Assistance 5. The following shall be considered assistance and are therefore not allowed: a) The taping of two or more fingers together. If taping is used on the hands and fingers, it may be continuous provided that as a result no two or more fingers are taped together in such a way that the fingers cannot move individually. The taping should be shown to the Chief Judge before	WPA 認可競技会 (PART-B 規則 3.1.2 参照) では、有効な WA 認証がある用具のみ使用できる。 パラ陸上競技用器具重量の一覧表は、付録 1 に記載している。 注意：PART B-規則 3.1.2 に記された WPA 認可競技会では、競技者は付録 1 に示されている通り、自身の競技クラス用の重量の用器具を使用しなくてはならない。 30.2. 付録 1 に記載され、WA 仕様であることが別途示されていない用器具は、所定の仕様を満たしていることが技術代表によって検証確認されなければならない。 注意：上記は、WA 規則第 187 条及び関連付則に掲載のないパラ陸上競技独特の用具についてのみ適用する。 30.3. 以下に述べる場合を除き用具は組織委員会が用意する。技術代表は該当する各競技会規定に基づき、競技者個人所有または製造会社提供の用具の使用を認めることができる。ただし、それらが WA 認証済みで、競技前に組織委員会により検査を受け合格のマークが記しており、技術代表により承認されたうえで、すべての競技者が使用できることが条件となる。技術総務が特に決めない限り、投てき種目に出場する競技者は、どの種目であっても、2 個までの個人所有の投てき物の使用（持ち込み）が認められる。 注意：競技者個人所有の用具の使用を認める際には、以前に WA 承認用具として認められているが、現在では製造されていないが現行規格に一致した古いモデルも含む。 コメント：組織委員会(LOC)は、以前に比べ、提供する投てき物の種類を減らす傾向にある（主に購入費用のため）。これにより、技術総務とその補佐役は、競技のために提出されたすべての個人持ち込み用具を厳密にチェックし、規則に準拠し、WA 承認用具リストに載っていることを確認する。現在 WA 証明書を持っていないが、かつて WA の証明書を持っており、検査の結果、仕様の基準を満たしていれば競技会での使用が認められる。 30.4. 競技会中はどの用具に対しても変形させたり調整したりしてはならない。唾液や体液を用具に吹き付けたりすることは許されない。 助力 30.5. 以下に掲げるものは助力とみなされ、認められない。 a) 2 本またはそれ以上の指にテープを巻くこと。もし手や指にテープを使用する場合は、2 本あるいはそれ以上の指にテープを巻き、それぞれの指が独立して動かせないような巻き方をしてはならない。手や指にテープを使用する場合、競技開始前に審判員主任に見せなければならない。	助力
--	--	------------------

the event starts; b) The use of any device of any kind, including weights attached to the body, which in anyway provides assistance when making a trial; c) The use of gloves; d) The spraying or spreading by an athlete of any substance in the circle or on their shoes nor the roughening of the surface of the circle. Note: If the Judges are aware, they shall direct any athlete not complying with this rule to correct the situation. If the athlete does not, such trial(s) shall be a failure. It shall also be judged as a failure, if a trial is completed before the noncompliance is noticed. The Referee shall decide what action shall be taken. In all cases considered serious enough, Rule 8.1 may also be applied. 6. The following shall not be considered assistance and are therefore allowed: a) The use by an athlete, in order to obtain a better grip, of a suitable substance on their hands only. A shot putter may use such substances on their neck. b) The placement by an athlete, in the Shot Put and Discus Throw, on the implement, of chalk or a similar substance. All substances used on the hands and on the implements shall be easily removable from the implement using a wet cloth and shall not leave any residue. COMMENT: The importance here is that athletes may apply substances to their hands or on the implements, but they shall be easily removable from the implement using a wet cloth. If they cannot be removed easily using a wet cloth then the substances cannot be used under any circumstances. In practice the Officials are responsible for ensuring that the substance is removed from the implement prior to it being returned to the implement rack. It is important to note that this applies to Shot Put and Discus only. A javelin thrower may not apply any substance to the implement. However, there is no provision which would restricts a javelin thrower from using any substance on their hands (but not the implement) that complies with Rule 30.6 (a). c) The use of taping on the hands and fingers that is not in contravention of Rule 30.5 (a). Throwing Circle 7. The rim of the circle shall be made of band iron, steel or other suitable material, the top of which shall be flush with the ground outside. It shall be at least 6mm thick. The inside and top of the rim shall be white. The ground surrounding the circle may be concrete, synthetic, asphalt, wood or any other suitable material.	b) 試技を行う際に、身体に重りを装着する等、何らかのかたちで助けとなる用具を使用すること。 c) 手袋を着用すること。 d) サークル内または靴に何らかの物質を吹き付けたりまき散らしたりすること、または、サークルの表面をざらざらにすること。 注意：審判員が助力行為に気づいたら、この規則に従わない競技者に対して、是正するよう指示しなければならない。競技者が従わなければ、その試技は無効としなければならない。規則違反に気づく前に試技が行われていた場合、審判長はどのような判定をするか決めなければならない。違反に気づく前に試技を行っていたとしても、無効試技としなければならない。悪質と考えられる場合、規則 8.1 を適用することができる。 30.6. 以下に掲げるものは助力とみなされず、認められる。 a) 握りをよくするために手だけに適切な物質をつけること。砲丸投の競技者は首にそのような物質をつけることが認められる。 b) 砲丸投と円盤投で、競技者がチョーク等の物質を用具につけること。ただし、手のひらや用具についた物質は、ぬれた布で簡単に拭きとれ、後に残らないものでなければならない。 コメント：ここで重要なのは、競技者が物質を自分の手または用具に塗布してもよいが、それらは濡れた布で用具から簡単に取り除けるものでなければならない。濡れた布で簡単に取り除くことができない場合は、いかなる状況でも使用できない。 競技役員は、物質が器具ラックに戻される前に、物質が器具から取り除かれていることを確認する責任がある。これは砲丸投と円盤投にのみ適用されることにも注意すること。やりの投てき者は用具に物質を使うことはできないが、（用具ではなく）手に物質を使用することを制限する規定はない。規則 30.6(a)参照 c) 規則 30.5(a)の規則違反にならない手や指のテーピング。 投てきサークル 30.7. 投てきサークルの縁枠は、帯鉄、鋼鉄、その他の適切な物質で出来ていなければならない、その上部は外側の地面と同一平面になっていなければならない。投擲サークルの周りの地面は、コンクリート、合成材、アスファルト、木材等の適切な物質を用いることができる。 投擲サークルの内側は、コンクリート、アスファルト等の頑丈で滑りにくい物質を用いることができる。内側の表	投てきサークル
--	--	--


The interior of the circle may be constructed of concrete, asphalt or some other firm but not slippery material. The surface of this interior shall be level and $2\text{cm} \pm 6\text{mm}$ lower than the upper edge of the rim of the circle.

In the Shot Put, a portable circle meeting these specifications is permissible.

8. The inside diameter of the circle shall be $2.135\text{m} \pm 0.005\text{m}$ in the Shot Put and $2.50\text{m} \pm 0.005\text{m}$ in the Discus Throw. The rim of the circle shall be at least 6mm thick and shall be white.

Note: The circular ring should preferably be coloured other than white so that the white lines required by Rule 30.8 are clearly visible.

Figure 13 – Layout of Shot Put circle



A white line 50mm wide shall be drawn from the top of the rim extending for at least 0.75m on either side of the circle. The white line may be painted or made of wood or other suitable material. The rear edge of the white line shall form a prolongation of a theoretical line through the centre of the circle at right angles to the centre line of the landing sector.

面は水平で、投擲サークルの縁枠の上端より $2\text{cm} \pm 6\text{mm}$ 低くしなければならない。

砲丸投については、下記の仕様を満たす移動式サークルの使用が認められる。

30.8. サークルの内側の直径は、砲丸投で $2.135\text{m} (\pm 0.005\text{m})$ 、円盤投で $2.50\text{m} (\pm 0.005\text{m})$ とする。サークルの縁枠の厚さは少なくとも 6 mm とし白色とする。

注意：円形のリングは規則 30.8 によって求められている白線がはっきり見えるように白以外の色であることが望ましい。

幅 50mm の白線を、サークルの両側に少なくとも 0.75m の長さにつく。その線は塗装するか、あるいは木材またはその他の適当な材質でつくる。白線の後縁は着地場所の中心線に対して直角でサークルの中心を通る直線上にあるようにしなければならない。




Figure 14 – Layout of Discus circle

Javelin Throw Runway

9. The minimum length of the runway shall be 30m except at the Paralympic Games and WPA Championships (see Part B - 3.1.2 (a) and (b)), where the minimum shall be 33.50m. Where conditions permit, the minimum length should be 36.50m. It shall be marked by two parallel white lines 50mm wide and 4m apart. The throw shall be made from behind an arc of a circle drawn with a radius of 8m. The arc shall consist of at least a 70mm wide strip painted or made of wood or a suitable non-corrodible material like plastic. It shall be white and be flush with the ground. Lines shall be drawn from the extremities of the arc at right angles to the parallel lines marking the runway. These lines shall be white, at least 0.75m long and at least 70mm wide. The maximum lateral inclination of the runway should be 1:100 (1%) unless special circumstances exist which justify World Athletics providing an exemption and, in the last 20m of the runway the overall downward inclination in the direction of running shall not exceed 1:1000 (0.1%).

やり投の助走路

30.9. やり投の助走路の長さは最短 30m とする。ただし、パラリンピック競技大会及び WPA 競技会 (PART-B 規則 3.1.2(a) 及び (b) 参照) においては、最短 33.50m とする。条件が許せば 36.50m 以上であることが望ましい。助走路は幅 50mm のラインで、間隔 4m の平行線で示される。投てきは半径 8m のスターティングラインの後方から行う。このスターティングラインは幅 70mm 以上で、じかに塗装した白線または白く塗られた木板あるいはプラスチックのような耐腐食性の適切な物質でグラウンドと同じ高さにつくる。スターティングラインの両端から助走路を示す 2 つの平行線に直角にそれぞれラインを引く。この二つのラインは、いずれも幅 70mm、長さ 0.75m とする。助走路の最大許容傾斜度は、WA が例外を認めるに足る特別な状況がある場合を除き、幅で 100 分の 1 (1%) にすべきであり、助走の方向で最後の 20m の下方傾斜度は 1,000 分の 1 (0.1%) を超えてはならない。




Figure 15 – Javelin Throw runway and landing sector (not to scale)

Landing Sector

10. The landing sector shall consist of cinders or grass or other suitable material on which the implement makes an imprint.

11. The maximum overall downward inclination of the landing sector, in the throwing direction, shall not exceed 1:1000 (0.1%).

12.

a) Except for the Javelin Throw, the landing sector shall be marked with white lines 50mm wide at an angle of 34.92° such that the inner edge of lines, if extended, would pass through the centre of the circle.

Note: The 34.92° sector may be laid out accurately by making the distance between the two points on the sector lines 20m from the centre of the circle 12m ± 0.05m (20 × 0.60m) apart. Thus, for every 1m from the centre of the circle, the distance across shall be increased by 0.60m.

着地場所

30.10. 着地場所は、痕跡が残るシンダーや芝生または他の適当な素材でつくらなければならない。

30.11. 着地場所の最大許容下方傾斜度は投げる方向で 1,000 分の 1(0.1%)とする。

30.12.

a) やり投を除いて、着地場所の範囲は、サークルの中心で交わる 34.92 度の角度をなす幅 50 mmの白線の内側の縁で示す。

注意：34.92 度の角度は、投てき角度を示すラインがサークルの中心から 20mの地点において 12m ± 0.05m(20 × 0.60m)の間隔になるようにすると正確に設定できる。このように中心から 1m離れるに従って 0.60m ずつ増さねばならない。

		試技
b) In the Javelin Throw, the landing sector shall be marked with white lines 50mm wide such that the inner edge of the lines, if extended, would pass through the two intersections of the inner edges of the arc, and the parallel lines marking the runway and intersect at the centre of the circle of which the arc is part (see Figure 15). The sector is thus about 28.96°. COMMENT: The landing sector shall be of an even surface soft enough to ensure that the place of the initial fall of the implement can be clearly established by the Judges. The landing surface should not allow the implement bounce backwards thus creating a risk that the measuring point is obliterated. Trials 13. In the Shot Put and Discus Throw, implements shall be thrown from a circle, and in the Javelin Throw, from a runway. In the case of trials made from a circle, an athlete shall commence their trial from a stationary position inside the circle. An athlete is allowed to touch the inside of the rim. In the Shot Put, they are also allowed to touch the inside of the stop board described in Rule 31.2. COMMENT: There is no restriction on how, or from which direction, an athlete may enter the circle nor in the case of the shot put is there any restriction on making contact with the stop board during this process. The relevant requirement is that once inside they must adopt a stationary position before commencing their trial. A stationary position means that an athlete having entered the circle to make their trial and before doing so adopts a stance in which both feet are simultaneously in firm contact with the ground inside the circle and with no contact with the top of the rim or the ground outside. Such contact to be sufficiently long in time to be visible to the judges. There is no requirement for the arms or hands of other parts of the athlete's body to be stationary. 14. It shall be a failure if an athlete in the course of a trial: a) Releases the shot or the javelin other than as permitted under Rule 31.1 and Rule 33.1; b) After they have stepped into the circle and begun to make a throw, touches with any part of their body the top (or the top inside edge) of the rim or the ground outside the circle; Note: However, it will not be considered a failure if the touch occurs during any first rotation at a point completely behind the white line which is drawn outside the circle running, theoretically, through the centre of the circle. Note(i): It will not be considered a failure at any time, if the touch, including of the top of the stopboard, or, in the case of Javelin Throw, the throwing arc or lines marking the runway, is	b) やり投の着地場所の範囲は、幅 50 mmの白線で角度を示し、その白線の内側の縁を延長すると円弧と平行する助走路を示す白線が交差する 2 つのポイントを通過し、円弧の中心で交わるようになる(図 1 2 参照)。着地場所の範囲の角度は、28.96 度とする。 コメント：落下域は、投てき物が最初に落下した場所を、審判員が明確に定めることができるよう、十分な柔らかい表面でなければならない。落下域の表面は、投てき物が後方に跳ね返らないようになっているべきである。さもないと、計測ポイントが消滅する危険性がある。 試技 30.13. 砲丸投、円盤投はサークルから、やり投は助走路から投てきを行う。サークルから行う試技では競技者はサークルの内側で静止の状態から投げ始めなければならない。競技者はサークルの縁枠の内側に触れてもよい。砲丸投では規則 31.2 に示すとおり足留材の内側に触れてもよい。 コメント：競技者がどのように、またはどの方向からサークルに入るかについての制限はなく、砲丸投の場合、この動作中に足留材に触れることについての制限はない。関連する要件は、競技者が試技を開始する前に、一旦、静止姿勢を取らなければならないということである。 静止姿勢とは、試技を行うためにサークルに入った競技者が、試技を開始する前に、両足で同時にサークル内の地面をしっかりと踏み、縁枠の上部や地面に接触しない姿勢を取ることである。審判員がその様子を確認できる、十分な時間を取っていることが必要である。その際、競技者の身体の一部である手や腕が静止している必要はない。 30.14. 競技者が試技中に、次のことをした時は 1 回の無効試技とする。 a) 砲丸あるいはやりを規則 31.1 及び規則 33.1 で定められた以外の方法で投げた時。 b) サークル内に入って投てきを始めた後、身体の一部がサークルの縁枠の上部（または上部内側角）あるいはサークルの外側の地面に触れた時。 注意：ただし、サークルに入り最初の回転動作を行う際に、サークルの中心を見通してサークルの両側の外に引かれた脇の白線より完全に後方のサークルの外側の地面に足が触れても、無効とはみなさない。 注意(i): 靴の緩んだ部分（靴紐など）や衣類、身体につけていたその他のアイテム（帽子など）が、投てき開始時、投てき中または投てき後に、足留材上部ややり投げの場合は、スターティングラインや助走路	

made by a loose part of the shoe (e.g. shoelace) or clothing, or if the touch is made by any other item (e.g. cap) which was attached to the body at the time of the start of throw and became detached during or after the throw. c) In the Shot Put, touches with any part of their body any part of the stop board other than its inner side (excluding its top edge which is considered to be part of the top); COMMENT: Officials must be careful here to use appropriate judgement. For example, if an athlete's shoelace touches the top of the stop board it is not a failure, but if the bottom of their shoe touches the top of the stop board it is. d) In the Javelin Throw, touches with any part of their body the lines which mark the runway or the ground outside. Note (ii): It shall be considered a failure if the discus strikes the far side of the cage (left side for a right-handed thrower when facing the landing sector or the right side for a left-handed thrower when facing the landing sector) after the release of the implement. Note (iii): It will not be considered a failure if the discus strikes the near side of the cage (right side for a right-handed thrower when facing the landing sector or the left side for a lefthanded thrower when facing the landing sector) after the release of the implement, then lands within the landing sector outside the limits of the cage, provided that no other Rule is infringed, including Rule 30.16. COMMENT: The limits of the cage shall be defined as the boundary formed by the cage and the gates, when in position, completed by an imaginary straight line drawn between the ends of the cage/gates closest to the landing sector. It is clarified that the top inside edges of the rim of the circle and of the stop board are considered to be part of the top of the rim and stop board respectively. This means that should an athlete make contact with the top inside edge of either the rim or the stop board then they will be considered thereby to have made a failure. The addition of the Note to Rule 30.14 (b) about the first rotation applies to rotational techniques used by athletes in Shot Put and Discus Throw. It should be interpreted that any "incidental" touch of the top of the rim or the ground outside in respect of the back half of the circle during the first rotation should not of itself be regarded as a failure. The addition of Note(i) to Rule 30.14 confirms that the intent of Rule 30.14 (b) is to respect the purpose of the circles or runway's limits so that the athlete complies by remaining in the circle or runway until they exit correctly. It is, unless they overbalance, only the position of their feet / shoes which is critical. It is not relevant, if the top of the iron band or, in the case of Javelin Throw, the throwing arc or lines	を示す線などに触れたとしても、無効とは見なされない。 c) 砲丸投で身体の中の部分を問わず、足留座位の内側以外の場所（足留材の上部水平面の一部とみなされる縁はうちがわではない）に触れた時。 コメント：競技役員は、適切な判断をするためにここで注意する必要がある。たとえば、競技者の靴ひもが足留材の上部に触れた場合、それは無効試技ではないが、靴の下部が足留材の上部に触れた場合は無効試技である。 d) やり投で身体の中の部分を問わず、助走路を示したラインや助走路の外側の地面に触れた時 注意(ii)：競技者の投げた円盤が、競技者に遠い側の囲い（着地場所に対して、右効きの競技者は左側、左利きの競技者は右側）に当たった場合は無効試技とみなす。 注意(iii)：競技者の投げた円盤が、競技者に近い側の囲い（着地場所に対して右利きの競技者であれば右側、左利きの競技者であれば左側）に当たり、投てき物が囲いの境界より前方にある着地場所内に着地した場合は、規則 30.16 を含む他の規則に違反していなければ無効試技とはみなさない。 コメント：囲いの境界とは、囲いと門口が所定の位置にある時に、着地場所に最も近い左右の囲いまたは門口の端の間に架空の直線によって引かれるものと定義する。 サークルの縁の上端、及び足留材の上端は、それぞれの上端の一部であると解釈されることが明らかにされている。これは、競技者が縁または足留材の上端に接触した場合には、無効試技とみなされることを意味する。 1 回目の回転についての規則 30.14(b)の注釈の追加は、砲丸投、円盤投で競技者が使用する回転技術に適用される。第 1 回目の回転中のサークル後半部に関して、縁部の上端または外側の地面への「偶発的な」接触は、その事実だけでは無効試技とはみなさないと解釈されるべきである。加えて、規則 30.14(b)が意図しているのはサークルの限界を定めた目的を重視し、競技者がサークルから正しく出るまでサークル内にとどまることを遵守させることである。バランスを崩しすぎない限り、重要なのは足や靴の位置だけである。サークルの縁の鉄製円形のリング上端部や外側の地面、あるいは足留材の上部に、緩んだ靴紐などが触れたり、試技中に競技者の身体から落ちた帽子やアクセサリーが触れたりしても関係ない。
---	--

marking the runway, the ground outside or the top of the stopboard is touched by a loose shoelace or the like or for example a cap or piece of jewellery falling from the athlete's body during the trial. 15. Provided that, in the course of a trial, the Rules relative to each throwing event have not been infringed, an athlete may interrupt a trial once started, may lay the implement down inside or outside the circle or runway and may leave the circle or runway. Note: All the moves permitted by this Rule shall be included in the maximum time for a trial given in Rule 24.17. COMMENT: In these circumstances, there is no restriction on how, or from which direction, an athlete may leave the circle or runway if they choose to do. The relevant requirement is that no other Rule is or has already been infringed. 16. It shall be a failure if the shot, the discus, or the head of the javelin in contacting the ground when it first lands touches the sector line, the ground or any object (other than the cage as provided in Note (ii) to Rule 30.14) outside the sector line. 17. It shall be a failure if the athlete leaves the circle or runway before the implement has touched the ground, or a) for throws made from a circle, if, when leaving the circle, the athlete's first contact with the top of the rim or the ground outside the circle is not completely behind the white line which is drawn outside the circle running, theoretically, through the centre of the circle. Note: The first contact with the top of the rim or the ground outside the circle is considered leaving. b) in the case of the Javelin Throw, if when leaving the runway, the athlete's first contact with the parallel lines or the ground outside the runway is not completely behind the white line of the arc or the lines drawn from the extremities of the arc at right angles to the parallel lines. Once the implement has touched the ground, an athlete will also be considered to have left the runway correctly, upon making contact with or behind a line (painted, or theoretical and indicated by markers beside the runway) drawn across the runway, four metres back from the end points of the throwing arc. Should an athlete be behind that line and inside the runway at the moment the implement touches the ground, they shall be considered to have left the runway correctly. COMMENT: The second and third sentences in Rule 30.17 (b) are designed to speed up the judging process and not to create an additional method of calling a failure on the athlete. The	30.15. 各投てき競技の規則に反しない限り、競技者は一度始めた競技を中断してよい。その上で、投てき用具をサークルや助走路の中でも外でも一旦下に置いてよく、サークルや助走路から出てよい。 注意：この項で許される動作は、規則 24.17 の制限時間に含まれる。 コメント：このような状況では、競技者がどのように、またはどの方向から、サークルまたは助走路を離れることができるかについては制限がない。関連する要件は、他の規則が侵害されていないか、既に侵害されていないことである。 30.16. 砲丸・円盤・やりの頭部が最初に着地して残した痕跡が区画ラインや区画ラインの外側地面あるいは他の物体（規則 30.14 注意(ii)による囲いを除いて）に触れた場合は、無効試技とする。 30.17. 投げた用具が着地する前に競技者がサークルや助走路から出た場合や以下の場合、無効とする。 a) サークルからの投てきでは、サークルを出る時は、縁枠の上部またはサークルの外側の地面に最初に触れるのは、サークルの中心を見通してサークルの両側に引かれている白線より完全に後方でなくてはならない。 注意：縁枠の上部もしくはサークル外の地面に最初に触れたとき、サークルからの離脱とみなす。 b) やり投の場合は、競技者が助走路を離れる時に助走路を示す平行線あるいは助走路外のグラウンドに最初に触れる場所は、スターティングライン及び脇に引かれた白線の完全に後方でなければならない。用具が一度地面に触れた後に、競技者がスターティングラインの 4m 後方で助走路を横切って引かれたライン（塗装されているか、もしくは助走路脇のマークで示されたイメージ上のライン）に触れるかより後ろに下がった場合、助走路を離れたと見なされる。投てき物が落下した時に、助走路内においてもそのラインより後方であれば助走路を離れたとみなしてよい。 コメント：規則 30.17(b)の 2 番目と 3 番目の条文は、判定の過程をスピードアップすることが目的であり、競技者にさらなる無効試技を提供するためではない。「4m マーク」の目的は、審判員が白旗を掲げて、	
---	--	--

purpose of the “4m marks” is solely to enable the Judges to raise the white flag and begin measuring the trial once the athlete retreats behind this point (in the same way as they would do if they had otherwise correctly left the runway). The only requirement is that there is no other reason for calling a failure and that the implement has touched the ground before the white flag is raised. Necessarily, if the athlete for whatever reason never progresses past the “4m marks” when making their throw then the flag can be raised once the implement has landed. 18. After each throw, implements shall be carried back to the area next to the circle or runway and never thrown back. Measurements 19. In all throwing events, distances shall be recorded to the nearest 0.01m, rounded down to the nearest 0.01m if the distance measured is not a whole centimetre. 20. The measurement of each throw shall be made immediately after each valid trial (or after an immediate oral protest made under Rule 50.5): a) from the nearest mark made by the fall of the shot or discus, to the inside of the circumference of the circle along a line to the centre of the circle; b) in Javelin Throw, from where the head of the javelin first struck the ground to the inside edge of the arc, along a line to the centre of the circle of which the arc is part. COMMENT: As long as no irregularity has been committed, each trial must be measured whatever the distance reached, including for the reasons that other trial measurements may become critical in determining countbacks or whether an athlete will proceed to subsequent rounds. Except where Rule 50.5 is applied, under normal practice no trial during which an irregularity has been committed should be measured. Judges should carefully use their discretion in applying any alternate practice and usually only in special cases. Unless video measuring is being used, for every valid trial a marker (usually metal) should be placed in a vertical position at the place of the imprint left by the implement in the landing area nearest to the circle/arc. The marker is passed through the loop at the end of the graduated steel tape so that the “zero” is on the mark. The tape should be pulled out horizontally taking care not to place it on any rise in the ground. Rule 31: Shot Put Competition 1. The shot shall be put from the shoulder with one hand only. At the time an athlete takes a stance in the circle to commence a put, the shot shall touch or be in close proximity to the neck or the chin and the hand shall not be dropped below this position during the action of putting. The	このポイントの後ろに出た時点で距離の計測を開始できるようにすることだけである（そうでなければ、助走路から正しく出たとみなさる）。白旗が上がる前に、やりが白線手前の助走路に触れたことだけでは、無効試技とする理由にはならない。もし競技者がやりの落下前に 4m マーク後方の助走路内に下がったときには、落下すると同時に白旗を上げる。 30.18. 投てきが終わったら、用具はサークルや助走路のところへ運んで返さなければならない。投げ返してはならない。 距離の計測 30.19. 投てき競技において、その距離は、cm未満の端数を切り捨てた 0.01m 単位で記録しなければならない。 30.20. 投てきの計測は、有効試技終了後（または、規則 50.5 に定める口頭による即時抗議が行われた後）、直ちに以下のとおり行うものとする。 a) 砲丸または円盤の落下による痕跡のサークルにもっとも近い地点から、サークルの中心をつなぐ線上のサークルの内側まで。 b) やり投では、やりの頭部が最初に落下した痕跡から、スターティングラインの中心をつなぐ線上のスターティングラインの内側まで。 コメント：無効試技でない限り、どれだけ飛んだかの距離にかかわらず、すべての試技を測定しなくてはならない。順位を決めるため、また次のラウンドに進出できるかどうかなどの理由による。規則 50.5 が適用される場合を除き、通常では、無効試技は計測されない。審判員は、代替え措置を適用する際には慎重に裁量権を行使すべきであり、通常は特別な場合にのみ適用される。ビデオ距離計測が使用されている場合を除いて、有効な試技ごとにマーカー（通常は金属製）を、サークルの円弧に最も近い着陸エリアに競技者が残した痕跡に垂直に刺す必要がある。鋼尺の“ゼロ”はマーカーに合わせ、巻尺は水平に引き出し、地面に浮かせないように注意する。 第 31 条 砲丸投競技会 31.1. 砲丸は肩から片手だけで投射する。競技者がサークルの中で投射を始めようと構えた時には、砲丸は、あごまたは首につけるか、あるいはまさに触れようとする状態に保持しなければならない。投射の動作中は、その手をこの状態より下におろしてはならない。また、砲丸を両肩を結ぶ線より後にもっていてもいけない。	距離の計測 第 31 条 砲丸投 競技会
---	---	--

shot shall not be taken behind the line of the shoulders.

Note (i): Cartwheeling techniques are not permitted.

Note (ii): For Sport Classes F33-34, F52-57 from start to finish, the movement of the shot shall be a straight, continuous putting action.

Note (iii): For Sport Class F32, lateral movement of the shot away from the chin or neck during the putting action is allowed and the requirement for putting the shot in a straight, continuous putting action is waived provided that no other element of this rule is contravened.

COMMENT: Of importance is that the shot shall be “put” not “thrown”. Taking the shot behind the line of the shoulders is how it looks when someone throws it rather than putting it. The hand cannot drop below the chin, the shot cannot be taken behind the line of the shoulders and the shot must not be thrown.

Stop Board

2. The stop board shall be white and made of wood or other suitable material in the shape of an arc so that the inner surface aligns with the inner edge of the rim of the circle and is perpendicular to the surface of the circle. It shall be placed so that its centre coincides with the centre line of the landing sector (Figure 13) and shall be firmly fixed to the ground or to the concrete surrounding the circle.

Note: Stop boards to the 1983/84 World Athletics specifications remain acceptable.




Figure 16 – Shot Put stop board (top and side view)

Measurements

3. The stop board shall measure 0.112m to 0.30m wide, with a chord of 1.21m ±0.01m for an arc of the same radius as the circle and 0.10m±0.008m high in relation to the level of the inside of the circle adjacent to the stop board.

Shot

4. The shot shall be of solid iron, brass or any metal not softer than brass, or a shell of such metal filled with lead or other solid material. It

注意(i)：カート・ウィーリング（前方倒立回転）投法は許可されない。

注意(ii)：競技クラス F33-34 及び F52-57 の砲丸投においては、投てき動作は始めから終わりまで連続的かつ継続的な動作でなければならない。

注意(iii)：競技クラス F32 の砲丸投では、本規則の他の条項に違反していない限り、投てき動作において顎または首から離れての側方動作(横投げ)も認められ、動作をまっすぐに連続するための要件は免除される。

コメント：重要なのは、動作が「Throw(投げる)」ではなく「Put(押し出す)」ことである。肩のラインの後ろで動作することは、砲丸を押し出すのではなく投げたときの様子である。つまり、手が顎より下に下がったり、肩のラインの後ろで動作してはならず、砲丸を投げてはいけない。

足留材

31.2. 構造－足留材は白く塗装し木または他の適当な材質でつくったもので、形は内側の縁がサークルの内側の縁と合致するような円弧であり、サークルの表面に対して垂直となるようにする。扇形の区画線の中央に位置し(図 13)、地面もしくはサークル周囲のコンクリートにしっかり固定できるようにつくらなければならない。

注意：WA1983/1984 仕様の足留材は引き続き許可される。

寸法

31.3.足留材は幅0.112m～0.30m、サークルと同じ半径の弧の弦の長さは 1.21m（±0.01m）、サークルの内側の表面に隣接している足留材の高さを 0.10m（±0.008m）とする

砲丸

31.4. 砲丸は、鉄、真ちゅう、真ちゅうより軟らかくかない金属球、または上記の金属の殻（から）に鉛そ

shall be spherical in shape and its surface finish shall be smooth. There shall be no loose parts.

Information for manufacturers: to be smooth, the surface average height must be less than or equal to 1.6µm, i.e., a roughness number N7 or less.

5. The shot shall conform to the following specifications:

Shot						
Minimum weight for admission to competition and acceptance of a						
Record	2.000kg	3.000kg	4.000kg	5.000kg	6.000kg	7.260kg
Information for manufacturers						
Range for supply of implement for competition	2.005kg	3.005kg	4.005kg	5.005kg	6.005kg	7.265kg
	2.025kg	3.025kg	4.025kg	5.025kg	6.025kg	7.285kg
Minimum Diameter	80mm	85mm	95mm	100mm	105mm	110mm
Maximum Diameter	100mm	110mm	110mm	120mm	125mm	130mm

COMMENT: Team of Officials

For a Shot Put event, it is recommended to allocate the available officials as follows:

- 1) The Chief Judge will watch over the whole of the event.
- 2) Two Judges checking whether the put has been made correctly and measuring the trial. One must be provided with two flags - white to indicate if the trial is valid and red if it is a failure. When the put has been measured, it is advised that the Judge stands in the circle holding the red flag, while the implement is returned, and the landing area is cleared. A cone may be placed in the circle instead. (In some competitions this position is assumed by the Chief Judge of the event.) Where EDM is not in use the second Judge should pull through and hold the measuring tape in such a way that it passes through the centre of the circle.
- 3) Judge immediately after the throw placing a marker indicating the point from which the trial is to be measured.
- 4) Judge positioning the spike/prism at the point where the marker has been placed ensuring the tape is on the zero mark.
- 5) Judge in charge of retrieving the implements and returning them to the implement stand or placing them in the return chute.
- 6) Judge - a recorder scoring the results sheet and calling each athlete (and the one who is to follow)
- 7) Judge in charge of the scoreboard (trial-number-result).
- 8) Judge in charge of the clock indicating to the athletes that they have a certain time to take their trial.


他の材質をつめたものとする。砲丸の形状は球形でその表面の仕上げは滑らかとする。凸凹があってはならない。
製造会社向けの情報：滑らかであるためには表面の荒さは 1.6µm 以下、即ちラフネスナンバー N7 以下でなければならない。

31.5. 砲丸は下記の仕様に一致しなければならない。

コメント：競技役員チーム

砲丸投の場合、以下のように競技役員を配置することが推奨される。

- 1) 審判員主任は、競技全体を監視する。
- 2) 砲丸の投法が正しいかを確認し、試技を計測する 2 人の審判員。1 人は、2 種類の旗を用意しなければならない - 試技が有効であることを示す白旗と無効であることを示す赤旗。距離が計測されたら、審判員は、砲丸戻しと、落下域の準備ができるのを待つ間、サークルの中に立ち、赤旗を掲げる。赤旗の代わりに、サークルにコーンを置いてよい。(競技会によっては、この役目は、審判員主任の任務であると想定されている)。EDM を使用しない場合、もう一人の審判員は、巻尺を引っ張り、サークル中央に通す。
- 3) 試技終了直後に試技を測定するための痕跡にマーカーを置く審判員。
- 4) 落下域において距離計測のために痕跡マーカーにピン／プリズムを刺し、巻尺を 0 に位置をピンに合わせ持つ審判員。
- 5) 落下域から戻ってくる投てき器具を受け取り、置き場に戻す担当の審判員
- 6) 審判員 - 記録表を記入し、各競技者（及びさらにその次の競技者）を呼び出す記録者
- 7) スコアボード（試技回数-競技者のナンバー-結果）を担当する審判員
- 8) 試技の残り時間を競技者に示す時計を担当する審判員

9) Judge in charge of athletes. 10) Judge in charge of the implement stand. Note (i): This is the traditional setting-up of the officials. In major competitions, where a data system and electronic scoreboards are available, specialised personnel are certainly required. To be clear in these cases, the progress and scoring of a Field Event is followed by both the recorder and by the data system. Note (ii): Officials and equipment must be placed in such a way as not to obstruct the athlete's way nor impede the view of the spectators. Rule 32: Discus Throw Discus 1. The body of the discus may be solid or hollow and shall be made of wood, or other suitable material, with a metal rim, the edge of which shall be circular. The cross section of the edge shall be rounded in a true circle having a radius of approximately 6mm. There may be circular plates set flush into the centre of the sides. The plates shall be tightly fixed and not able to be rotated. Alternatively, the discus may be made without metal plates, provided that the equivalent area is flat and the measurements and total weight of the implement correspond to the specifications. There shall be no loose parts. Each side of the discus shall be identical and shall be made without indentations, projections or sharp edges. The sides shall taper in a straight line from any point on a circle of a radius of 25mm to 28.5mm from the centre of the discus to the beginning of the curve of the rim. The profile of the discus shall be designed as follows. From the beginning of the curve of the rim the thickness of the discus increases regularly up to the maximum value D. This maximum value is achieved at a distance of 25 mm to 28.5mm from the axis of the discus Y. From this point up to the axis Y the thickness of the discus is constant. Upper and lower side of the discus must be identical; also the discus has to be symmetrical concerning rotation around the axis Y. The discus, including the surface of the rim shall have no roughness and the finish shall be smooth and uniform throughout.  Figure 17 – Discus	9) 競技者を担当する審判員 10) 投てき物置き場担当の審判員 注意(i)：これは競技役員の伝統的な配置である。データシステムと電子スコアボードが利用可能な大規模な競技会では、専門の人材が必ず必要である。このような場合には、フィールド種目の進捗状況と結果は、記録者とデータシステムの双方で記録される。 注意 (ii)：競技役員及び用具は、競技者を妨害したり、観客の視界を妨げたりしないように配置されなければならない。 第 32 条 円盤投 円盤 32.1. 円盤の胴体は、中身が充填されていても中空でもよく、木またはその他の適当な材質と金属の縁枠でできており、縁枠の角は円くなっている。縁の断面は半径 6mm の正しい円弧とする。金属の板を両面の中心に水平にはめこんでもよい。金属の板はしっかりと固定され、回転することが無いようにする必要がある。別の仕様として、もしその部分が平面であり、用具の寸法や総重量が仕様に一致していれば金属板なしで円盤をつくってよい。凸凹があってはならない。円盤の両面は同一であり、くぼみや突起がなく、縁が鋭利なものであってはならない。円盤の両面は、円盤の中心から半径 25mm～28.5mm の外側のどの箇所からも、縁の円弧の始まるところまで真っすぐに傾斜させ、厚みを減じる。 円盤の断面は、次のように設計されていなければならない。縁の曲線部の始めから円盤の厚みは、縁の最大厚の D の部分まで規則的に増加する。厚みが最大になるのは、円盤の軸 Y から 25mm～28.5mm の距離のところである。 この部分から円盤の軸 Y のところまで厚さは一定である。円盤の上面、下面ともに同一でなければならない、また軸 Y の周りの回転に関してバランスがとれなければならない。 円盤の縁の表面はで凸凹がなく、仕上がりは全体が円滑でかつ均一でなければならない。
--	--

2. The discus shall conform to the following specifications:

Discus					
Minimum weight for admission to competition and acceptance of a					
Record	0.750kg	1.000kg	1.500kg	1.750kg	2.000kg
Information for manufacturers					
Range for supply of implement for competition	0.755kg	1.005kg	1.505kg	1.755kg	2.005kg
	0.775kg	1.025kg	1.525kg	1.775kg	2.025kg
Outside diameter of metal rim					
Min.	166mm	180mm	200mm	210mm	219mm
Max.	172mm	182mm	202mm	212mm	221mm
Diameter of metal plate or flat centre are					
Min.	50mm	50mm	50mm	50mm	50mm
Max.	57mm	57mm	57mm	57mm	57mm
Thickness of metal plate or flat centre area					
Min.	33mm	37mm	38mm	41mm	44mm
Max.	38mm	39mm	40mm	43mm	46mm
Thickness of metal rim (6mm from edge)					
Min.	10mm	12mm	12mm	12mm	12mm
Max.	13mm	13mm	13mm	13mm	13mm

COMMENT: Team of Officials

For a Discus Throw Event, it is recommended to allocate the available officials as follows:

- 1) The Chief Judge will watch over the whole of the event.
- 2) Two Judges checking whether the throw has been made correctly and measuring the trial. One must be provided with two flags – white to indicate if the trial is valid and red if it is a failure. When the throw has been measured, it is advised that the Judge stands at the entrance to the cage holding the red flag, while the implement is returned, and the landing area is cleared. A cone may be placed at this point instead. (In some competitions this position is assumed by the Chief Judge of the event.) Where EDM is not in use the second Judge should pull through and hold the measuring tape in such a way that it passes through the centre of the circle.
- 3) Judge immediately after the throw placing a marker indicating the point from which the trial is to be measured. If the implement lands outside the sector either this Judge or the one with the spike/prism (whichever is closer to the line) should indicate this by holding their arm outstretched. No indication is required for a valid trial.
- 4) Judge positioning the spike/prism at the point where the marker has been placed ensuring the tape is on the zero mark.
- 5) one or more Judges or assistants in charge of retrieving the implements and returning them to the implement stand or placing them in the return device. Where a tape is used for measurement, one of these Judges or assistants should ensure that the tape measure is taut in order to ensure a correct measurement.

32.2. 円盤は下記の仕様に一致しなければならない。

コメント：競技役員チーム

円盤投の場合、以下のように競技役員を配置することが推奨される。

- 1) 審判員主任は、競技全体を監視する。
- 2) 投てきが正しくなされたかを確認し、試技を計測する 2 人の審判員。1 人は、2 種類の旗を用意しなければならない – 試技が有効であることを示す白旗と無効であることを示す赤旗。距離が計測されたら、審判員は、円盤戻しと、落下域の準備ができるのを待つ間、サークルの中に立ち、赤旗を掲げる。赤旗の代わりに、サークルにコーンを置いてよい（いくつかの競技会では、この役目は、審判員主任の任務であると想定されている）。EDM を使用しない場合、もう一人の審判員は、巻尺を引っ張り、サークル中央に通す。
- 3) 落下域において、距離を計測のための痕跡を確認する審判員。もし円盤が角度線の外に落下した場合、この審判員もしくはプリズムを持っている審判員は、（角度線に近い方のどちらか）その事実を、腕を外に向けるようなしぐさで伝える。有効試技の場合はこのような合図は不要である。
- 4) 落下域において距離計測のために痕跡にピン／プリズムを刺し、巻尺を 0 に位置をピンに合わせて持つ審判員。
- 5) 円盤を回収し、置き場に戻す、もしくは返送車に置く、1 人以上の審判員もしくは補助員。巻尺を使用して計測する場合は、審判員または補助員のうちの 1 人は、正確な計測を確実に行うために巻尺がきちんと引っ張られた状態にあるかを確認する。

6) Judge - a recorder scoring the results sheet and calling each athlete (and the one who is to follow). 7) Judge in charge of the scoreboard (trial-number-result). 8) Judge in charge of the clock indicating to the athletes that they have a certain time to take their trial. 9) Judge in charge of athletes. 10) Judge in charge of the implement stand. Note (i): This is the traditional setting-up of the officials. In major competitions, where a data system and electronic scoreboards are available, specialised personnel are certainly required. To be clear in these cases, the progress and scoring of a Field Event is followed by both the recorder and by the data system. Note (ii): Officials and equipment must be placed in such a way as not to obstruct the athlete's way nor impede the view of the spectators. Note (iii): A space must be reserved for a wind-sock to indicate the wind direction and strength. Discus Cage (Rule 190) COMMENT: There are many variations on enclosures or cages for athletes with an impairment but safety for Officials, spectators and athletes is paramount. The Discus Cage is also used for club throw. 3. All discus throws shall be made from an enclosure or cage to ensure the safety of spectators, officials and athletes. The cage specified in this Rule is intended for use when the event takes place in the field of play with other events taking place at the same time or when the event takes place outside the field of play with spectators present. Where this does not apply, and especially in training areas, a much simpler construction may be satisfactory. Advice is available, on request, through national organisations or from the WPA Office. 4. The cage should be designed, manufactured and maintained so as to be capable of stopping a 2kg discus moving at a speed of up to 25 meters per second. The arrangement should be such that there is no danger of ricocheting or rebounding back towards the athlete or over the top of the cage. Provided that it satisfies all the requirements of this Rule, any form of cage design and construction can be used. 32.5.1. The cage should be U-shaped in plan as shown in Figure 18. The width of the mouth should be 6m, positioned 7m in front of the centre of the throwing circle. The end points of the 6m wide mouth shall be the inner edge of the cage netting. Provisions must be made in the	6) 審判員 – 記録表を記入し、各競技者（及びさらにその次の競技者）を呼び出す記録者 7) スコアボード（試技回数-競技者のナンバー-結果）を担当する審判員 8) 試技の残り時間を競技者に示す時計を担当する審判員 9) 競技者を担当する審判員 10) 投てき物置き場担当の審判員 注意(i)：これは競技役員の伝統的な配置である。データシステムと電子スコアボードが利用可能な大規模な競技会では、専門の人材が必ず必要である。このような場合には、フィールド種目の進捗状況と結果は、記録者とデータシステムの双方で記録される。 注意(ii)：競技役員及び用具は、競技者を妨害したり、観客の視界を妨げたりしないように配置されなければならない。 注意(iii)：風の方向と強さを示すために、吹き流しのためのスペースを確保する必要がある。 円盤投用囲い コメント：障がいのある競技者のエンクロージャーや囲いには多くのバリエーションがあるが、競技役員、観客、競技者の安全が最も重要である。円盤投用囲いはこん棒投にも使用される。 32.3. 円盤投は観衆、役員、競技者の安全を確保するために囲いの中から投げる。この規則で明記された囲いは、この種目が競技場の外で観客と一緒に実施される時に、あるいはこの種目が競技場の中で他の種目と同時に実施される時に使用することを目的としている。この条件が当てはまらない時、特に練習場においては、もっと簡単な構造でも構わない。国内主催団体もしくは WPA オフィスから指導があった場合にはそれに従う。 32.4. 囲いは 2kg の円盤が秒速 25m の速度で動く力を防止できるように設計し、製作されなければならない。この仕様は円盤を制止するために囲いの鋼材に当たり競技者の方へはね返ったり、囲いの上部から外側に飛び出したりしないようにする。この規則の必要事項を満たせば、囲いの形状や構造はどのようにしてもよい。 32.5.1. 囲いの形状は図 18 に示してあるように U 字型とする。U 字型の門口は 6m とし、投てきサークルの中心から 7m 前方の位置とする。開口部の幅 6m は囲いのネットの内側で計らなければならない。パネルあるいは掛け網のもっとも低い部分の高さは 4m 以上とし、囲いの両側ともに開口部から 3m の地点では高さ 6m 以上とする。	円盤投用囲い
--	---	---

design and construction to the cage to prevent a discus from forcing its way through any joints in the cage, the netting, underneath the netting panels or draped netting. 32.5.2. The netting panels or draped netting must be fixed in a way that the width of the mouth is the same at each height of the netting. The height of the netting panels or draped netting at their lowest point should be at least 4m, progressively increasing towards the front of the cage to a height of at least 6m for the 3m nearest the front of the cage on each side. 3.5.3. For WPA Approved Competitions, where the height of the netting panels or draped netting is lower than 6m for the 3m nearest the front of the cage on each side, the LOC is responsible for ensuring that safety measures are in place during the discus and club throw events. Note (i): The arrangement of the rear panels/netting is not important provided the netting is a minimum of 3.00m away from the centre of the circle. Note (ii): Innovative designs that provide the same or better degree of protection and do not increase the danger zone compared with conventional designs may be World Athletic certified. Note (iii): The cage side particularly alongside the track may be lengthened and/or provided with (a) movable panel(s) and/or increased in height so as to provide greater protection to athletes competing on the adjoining track during a discus competition. 6. The netting for the cage can be made from suitable natural or synthetic fibre cord or, alternatively, from mild or high tensile steel wire. The measurement of the mesh cord centres shall be a maximum of 45mm for cord netting and 50mm for steel wire netting. Note: Further specifications for the netting and safety inspection procedures are set out in the World Athletics Track and Field Facilities Manual. 7. The maximum danger sector for discus throws from this cage is approximately 69°, when used by both right and left handed throwers in the same competition (calculated by assuming that the discus is released from a circumscribed circle of 1.5m radius). The position and alignment of the cage in the field of play is, therefore, critical for its safe use. Note: the method used to determine the danger zone is illustrated in Figure 18.	円盤が囲いの継手箇所や、パネルあるいは掛け網の下部を突き抜けるのを防止するような囲いの形状や構造を工夫しなければならない。 32.5.2. 囲いの口のどの高さであつたも、幅が同じになるようにネットや掛け網を固定しなければならない。パネルあるいは掛け網のもっとも低い部分の高さは 4 m 以上とし、囲いの前方に向かって徐々に高くなり、囲いの両側ともに開口部から 3 m の地点では高さ 6 m 以上とする。 32.5.3. W P A 承認大会では、パネルあるいは掛け網の最も低い部分の高さが囲いの両側ともに開口部から 3 m の地点で高さ 6 m 未満の場合は、組織委員会は円盤投げやこん棒投げ競技中に安全対策が講じられていることを確認する責任がある。 注意(i)：サークル後部については、中心から最低 3 m 離れてさえいれば、それがパネルであるか網目であるかは大きな問題ではない。 注意(ii)：従来の形状に比較して、同程度あるいはそれ以上の角度の防護機能を備え、危険区域が拡大していなければ、新式の形状が WA の承認を受けることができる。 注意(iii)：特にトラック側に面する側の囲いは、円盤投の競技中に、隣接したトラックで競技中の競技者をより確実に保護するために、長くしても可動パネルを設置しても、高くしてもよい。 32.6. 囲いの網目は適切な天然または合成繊維でつくられた紐、または柔軟で伸張力のある鋼製ワイヤーとする。網目の中心の大きさは、紐で作られた場合は最大 45 mm、鋼製ワイヤー場合は最大 50 mm とする。 注意：網目と安全検査手順の詳細は WA 陸上競技施設マニュアルに定められている。 32.7. この囲いからの円盤の投てきで、同一競技会に右投げ、左投げの競技者が参加している場合、危険な範囲は最大 69 度である（サークルを中心に、半径 1.5m の円の外側から円盤が投げられたと仮定して計算）。競技場内の囲いの設置位置及び取り付け調整は、安全確保のため、十分な配慮が必要である。 注意：危険領域を確定するために使われる方法は、図 18 に描かれている。
---	--




Figure 18 – Cage for Discus Throw only




Figure 19 – Cage for Discus Throw with concentric circles




Figure 20 – Cage for Discus Throw with separate circles

Rule 33: Javelin Throw Competition

1.

- a) The javelin shall be held at the grip with one hand only. It shall be thrown over the shoulder or upper part of the throwing arm and shall not be slung or hurled. Non-orthodox styles are not permitted;
- b) A throw shall be valid only if the metal head strikes the ground before any other part of the javelin;
- c) Until the javelin has been thrown, an athlete shall not at any time turn completely around, so that their back is towards the throwing arc.

第33条 やり投 競技会

33.1.

- a) やりは片手でグリップのところを握らなければならない。やりは肩または投げの方の腕の上で投げなければならない。振り返したりして投げてはならない。正常とは言えない投げ方は認められない。
- b) やり投は、やりの頭部が他のどの部分よりも先に地面に落下した場合のみ有効とする。
- c) 投げる用意をしてから、やりが空中に投げられるまでの間に、競技者はその背面がスターティングラインに向けるように完全に回転させることはできない。

COMMENT: Previous references in the Rules to the “tip” of the javelin have been removed and are replaced by a generic reference to the head. This acknowledges that the shape of the head varies greatly, making it harder to separately define the tip. It means that Judges in determining whether the javelin has landed correctly in terms of Rule 30.16 and Rule 33.1 (b) and the reference point for measurement in terms of Rule 30.20 (b) now have a bigger area with which to assess. But the principles remain as before and there must be some angle on landing, however small, for the throw to be valid. Flat or “tail-first” landings are still to be red flagged. 2. If the javelin breaks during a throw or while in the air, it shall not count as a failure, provided the trial was otherwise made in accordance with this Rule. Nor shall it count as a failure if an athlete thereby loses their balance and as a result contravenes any part of this Rule. In both cases the athlete shall be awarded a new trial. Javelin 3. The javelin shall consist of three main parts: a shaft, a head, and a cord grip. 4. The shaft may be solid or hollow and shall be constructed of metal or other suitable material so as to constitute a fixed and integrated whole. The surface of the shaft shall have no dimples or pimples, grooves or ridges, holes or roughness, and the finish shall be smooth and uniform throughout. 5. The shaft shall have fixed to it a metal head terminating in a sharp point. The head shall be constructed completely of metal. It may contain a reinforced tip of other metal alloy welded on to the front end of the head provided that the completed head is smooth and uniform along the whole of its surface. The angle of the tip shall not exceed 40 degrees. Note: The metal head up to 3mm from the tip may be disregarded for the angle of the point, when the construction of the tip is made with safety measures implemented. 6. The cord grip, which shall cover the centre of gravity, shall not exceed the average diameter of the shaft by more than 8mm. It may have a regular nonslip pattern surface but without thongs, notches or indentations of any kind. The grip shall be of uniform thickness. 7. The cross-section shall be regularly circular throughout (see Note (i)). The maximum diameter of the shaft shall be immediately in front of the grip. The central portion of the shaft, including the part under the grip, may be cylindrical or slightly tapered towards the rear but in no case may the reduction in diameter, from immediately in front of the grip to immediately behind, exceed 0.25mm. From the grip, the javelin shall taper regularly to the tip at the front and the tail at the rear. The longitudinal	コメント：以前の規則で使われていたやりの「先端」という表現は削除され、「頭部」という表記に一括して置き換えられている。これは、頭部の形状が製品により大きく異なることを認識し、「先端」と「頭部」とを別々に定義することが困難であるからである。これは、やりが正確に着地したかの規則 30.16 及びこの規則 33.1(b)、及び計測規準点についての規則 30.20(b)に関し、審判員が判断する際の範囲が広くなることを意味する。しかし、その原則は以前と同じままであり、投てきが有効であるためには、着地が有効となるためにある程度の角度が必要であり、フラットまたは「テール・ファースト(後部から)」の着地は依然として赤旗となる。 33.2. やりが投てき動作中あるいは空中で壊れた時は規則に従って投げられたものであれば 1 回の無効試技には数えない。この時競技者が身体の平衡を失って反則の動作をしたとしても無効試技とはせず、新試技が許される。 やり 33.3. やりは頭部、柄、グリップという 3 つの主要部分によって構成される。 33.4. 柄の部分は、中が詰まっても空洞でもよく、全体が固定され一体化されるような金属あるいは他の適した材質とする。柄の表面は、くぼみ、でこぼこ、みぞやうね、穴やざらざらがあってはならず、全体的に滑らかで均一な仕上がりでなければならない。 33.5. 柄は先端に向け尖った金属製の頭部とつながっていなければならない。頭部はすべて金属でなければならない。頭部の表面が全体的にすべらかであれば、頭部の端に別の合金で補強した先端部を取り付けてもよい。先端部の角度は 40 度を超えないものとする。 注意：先端に安全対策がなされた構造のやりの場合、先端から 3mm までの金属製頭部は、先端の角度を無視してもよい。 33.6. グリップは重心のまわりを巻き、その直径は柄の直径の平均より 8mm を超えてはならない。グリップはどのような種類であろうと一律に滑らない表面で、たれ下がり、きざみ目、くぼみのないようにする。グリップの厚さは均一でなければならない。 33.7. 切断面は、どこでも完全に円形でなければならない(注意(i)参照)。柄の最大直径はグリップの直前でなければならない。グリップの下の部分を含む柄の中央の部分は、筒状かやりの後方に向かって幾分細くなるようにするが、グリップの直前から直後までの直径の減少は 0.25mm を超えてはならない。やりはグリップから頭部先端と後部末尾に向かってだんだん細くなっていなければならない。グリップから頭部先端の先及び後部末尾に至る縦断面は、直線であるか、もしくは、わずかなふくらみがあってもよいが(注意(ii)参照)、頭部の直前の部分及	やり
---	--	-----------

profile from the grip to the front tip and to the tail shall be straight or slightly convex (see Note (ii)), and there shall be no abrupt alteration in the overall diameter, except immediately behind the head and at the front and rear of the grip, throughout the length of the javelin. At the rear of the head, the reduction in the diameter may not exceed 2.5mm.

Note (i): Whilst the cross section throughout should be circular, a maximum difference between the largest and the smallest diameter at cross section of 2% is permitted. The mean value of these two diameters, at any nominated cross section, shall meet the specifications of a circular javelin in the tables hereunder.

Note (ii): The shape of the longitudinal profile may be quickly and easily checked using a metal straight edge at least 500mm long and two feeler gauges 0.20mm and 1.25mm thick. For slightly convex sections of the profile, the straight edge will rock while being in firm contact with a short section of the javelin. For straight sections of the profile, with the straight edge held firmly against it, it must be impossible to insert the 0.20mm gauge between the javelin and the straight edge anywhere over the length of contact. This shall not apply immediately behind the joint between the head and the shaft. At this point it must be impossible to insert the 1.25mm gauge.

8. The javelin shall conform to the following specifications:

Javelin					
Minimum weight for admission to competition and acceptance of a Record (inclusive of the cord grip):					
	400g	500g	600g	700g	800g
Information for manufacturers: Range for supply of implement for competition					
	405g	505g	605g	705g	805g
	425g	525g	625g	725g	825g
Overall length (L0)					
Min.	1850mm	2000mm	2200mm	2400mm	2600mm
Max.	1950mm	2100mm	2300mm	2500mm	2700mm
Distance from tip of metal head to centre of gravity (L1)					
Min.	750mm	780mm	800mm	850mm	900mm
Max.	800mm	880mm	920mm	990mm	1060mm
Distance from tail to centre of gravity (L2)					
Min.	1050mm	1120mm	1280mm	1410mm	1540mm
Max.	1200mm	1320mm	1500mm	1650mm	1800mm
Length of metal head (L3)					
Min.	200mm	220mm	250mm	250mm	250mm
Max.	250mm	270mm	330mm	330mm	330mm
Width of cord grip (L4)					
Min.	130mm	135mm	140mm	150mm	150mm
Max.	140mm	145mm	150mm	160mm	160mm
Diameter of shaft at thickest point (in front of grip – D0)					
Min.	20mm	20mm	20mm	23mm	25mm
Max.	23mm	24mm	25mm	28mm	30mm

9. The javelin shall have no mobile parts or other apparatus, which during the throw could change its centre of gravity or throwing characteristics.

びグリップの直前、直後の部分を除き、やりの長さの全体を通して直径に急な変化をつけてはならない。やりの頭部の後ろの部分における直径の減少は、2.5mm 以下とする。

注意(i)：やりのどの部分でも切断面は円形であるべきであるが、どの切断面においても最大直径と最小直径の差が 2%まで許容される。最大直径と最小直径の平均値は、指定されたどの切断面においても、表に示す仕様が満たされなければならないものとする。

注意(ii)：やりの縦断面は、長さ 500mm の金属製直定規と 0.20mm と 1.25mm 厚のフィーラー・ゲージを使うことで迅速かつ容易にチェックできる。わずかにふくらんでいる場合は、直定規をふくらんでいない部分にしっかりと接触させようとする揺れ動くはずである。縦断面が直線となっている部分は、直定規をやりにしっかりと固定した際、やりと直定規の間に 0.20mm 厚のフィーラー・ゲージが入る隙間があってはならない。ただし、これは頭部と柄の接合部分については適用しない。この接合部分については 1.25mm 厚のフィーラー・ゲージが入る隙間があってはならない。

33.8. やりは下記の仕様に一致しなければならない。

33.9. やりに可動部分あるいは投てき中に重心や投てきに対する性能が変えられるような装置をつけてはならない。

10.The tapering of the javelin to the tip of the metal head shall be such that the angle of the point shall be not more than 40°. The diameter, at a point 150mm from the tip, shall not exceed 80% of the maximum diameter of the shaft. At the midpoint between the centre of gravity and the tip of the metal head, the diameter shall not exceed 90% of the maximum diameter of the shaft.

11.The tapering of the shaft to the tail at the rear shall be such that the diameter, at the midpoint between the centre of gravity and the tail, shall not be less than 90% of the maximum diameter of the shaft. At a point 0.15m from the tail, the diameter shall be not less than 40% of the maximum diameter of the shaft. The diameter of the shaft at the end of the tail shall not be less than 3.5mm.




Figure 21 – International Javelin

Lengths		Diameters		Maximum	Minimum
L0	Overall	D0	In front of grip	–	–
L1	Tip to C of G	D1	At rear of grip	D0	D0-0.25mm
1/2L1	Half L1	D2	150mm from tip	0.8 D0	–
L2	Tail to C of G	D3	At rear of head	–	–
1/2L2	Half L2	D4	Immediately behind head	–	D3-2.5mm
L3	Head	D5	Halfway tip to C of G	0.9 D0	–
L4	Grip	D6	Over grip	D0+8mm	–
		D7	Halfway tail to C of G	–	0.9 D0
		D8	150mm from tail	–	0.4 D0
C of G	Centre of Gravity	D9	At tail	–	3.5mm

Note: All measurements of diameters must be to at least 0.1 mm.

COMMENT: Team of Officials

For a Javelin Throw Event, it is recommended to allocate the available officials as follows:

- 1) The Chief Judge will watch over the whole of the event.
- 2) Two Judges checking whether the throw has been made correctly and measuring the trial. One must be provided with two flags – white to indicate if the trial is valid and red if it is a failure. When the throw has been measured, it is advised that the Judge stands on the runway holding the red flag, while the implement is returned, and the landing area is cleared. A cone may be placed on the runway instead. (In some competitions this position is assumed by the Chief Judge of the event.)
- 3) Where EDM is not in use the second Judge should pull through and hold the measuring tape in such a way that it passes through the 8m point marked on the runway.

33.10. 金属製穂先の角度は 40 度を超えてはならない。穂先の先端から 150mm のポイントでの直径は柄の一番太いところの 80%を超えてはならない。重心と金属製穂先の先端との中間点において、直径は柄の一番太いところの 90%を超えてはならない。

33.11. 末端に向かって細めるのは、重心と末端の中間点では柄の最大直径の 90%以上とする。やりの末端から 0.15m のところでは、柄の最大直径の 40%以上とする。やりの柄の末端の直径は 3.5mm 以上とする。

コメント：競技役員チーム

やり投の場合、以下のように競技役員を配置することが推奨される。

- 1) 審判員主任は、競技全体を監視する。
- 2) 投てきが正しくなされたかを確認し、試技を計測する 2 名の審判員。一名は 2 種類の旗を用意しなければならない。試技が有効であることを示す白旗と無効であることを示す赤旗。距離が計測されたら、審判員は、やり戻しと、落下域の準備ができるのを待つ間、助走路に立ち、赤旗を掲げる。赤旗の代わりに、助走路にコーンを置いてよい。（競技会によっては、この役目は、審判員主任の任務であると想定されている）。
- 3) EDM を使用しない場合、もう 1 名の審判員は、巻尺を引っ張り、スターティングラインから後方 8 m の助走路にあるポイントを通す。

4) one or two Judges immediately after the throw placing a marker indicating the point from which the trial is to be measured. If the implement lands outside the sector either this Judge or the one with the spike/prism (whichever is closer to the line) should indicate this by holding their arm outstretched. An appropriate indication is also required if these Judges determine that the implement has not landed "head first". It is recommended that some form of signal other than flags is used for this purpose. No indication is required for a valid trial. 5) Judge positioning the spike/prism at the point where the marker has been placed ensuring the tape is on the zero mark. 6) one or more Judges or assistants in charge of retrieving the implements and returning them to the implement stand or placing them in the return device. Where a tape is used for measurement, one of these Judges or assistants should ensure that the tape measure is taut in order to ensure a correct measurement. 7) Judge - a recorder scoring the results sheet and calling each athlete (and the one who is to follow). 8) Judge in charge of the scoreboard (trial-number-result). 9) Judge in charge of the clock indicating to the athletes that they have a certain time to take their trial. 10) Judge in charge of athletes. 11) Judge in charge of the implement stand. Note (i): This is the traditional setting-up of the officials. In major competitions, where a data system and electronic scoreboards are available, specialised personnel are certainly required. To be clear in these cases, the progress and scoring of a Field Event is followed by both the recorder and by the data system. Note (ii): Officials and equipment must be placed in such a way as not to obstruct the athlete's way nor impede the view of the spectators. Note (iii): A space must be reserved for a wind-sock to indicate the wind direction and strength. D. THROWING EVENTS FOR SEATED ATHLETES Rule 34: General Conditions COMMENT: Unless specific rule modifications exist within this Section D, the General Conditions and event specific rules contained within Section C – THROWING EVENTS FOR AMULANT ATHLETES equally apply to Seated Throws. Official Implements 1. The implements used (not otherwise unique to Para Athletics) shall comply with current World Athletics specifications. Only those implements	4) 落下域において、距離を計測のための痕跡を確認する審判員。もしやりが角度線の外に落下した場合、この審判員もしくはプリズムを持っている審判員（角度線に近い方のどちらか）は、その事実を、腕を外に向けてようなくさで伝える。やりが頭部から先に着地しなかったと判断した場合にも適切な合図が必要であり、旗以外の何らかの合図で伝えることを推奨する。有効試技の場合はこのような合図は不要である。 5) 落下域において距離計測のために痕跡にピン／プリズムを刺し、巻尺を0に位置をピンに合わせて持つ審判員。 6) やりを回収し、置き場に戻す、もしくは返送車に置く、1名以上の審判員もしくは補助員。巻尺を使用して計測する場合は、これらの審判員または補助員のうち1名は、正確な測定を確実に行うために巻尺がきちんと張っている状態を確認する。 7) 審判員－記録表を記入し、各競技者（及びさらにその次の競技者）を呼び出す記録者 8) スコアボード（試技回数-競技者のナンバー-結果）を担当する審判員 9) 試技の残り時間を競技者に示す時計を担当する審判員 10) 競技者を担当する審判員 11) 投てき物置き場担当の審判員 注意(i)：これは競技役員の伝統的な配置である。データシステムと電子スコアボードが利用可能な大規模な競技会では、専門の人材が必ず必要である。このような場合には、フィールド種目の進捗状況と結果は、記録者とデータシステムの双方で記録される。 注意(ii)：競技役員及び用具は、競技者を妨害したり、観客の視界を妨げたりしないように配置されなければならない。 注意(iii)：風の方向と強さを示すために、吹き流しのためのスペースを確保する必要がある。 D. 座位競技者投てき種目 第34条 総則 コメント：特定のルールの違いがない限り Section D-座位競技者の投てき競技に含まれる一般受験および本 Section C に含まれる特定の競技規則、立位投てきと座位投てきに等しく適用される。 公式用器具 34.1. 投てき用具（パラ陸上競技独特のものを除く）は最新のWAの規格に合致したものでなければならない。WPA 認可競技会（PART-B 規則 3.1.2	D. 座位競技者投てき種目 第34条 総則 公式用器具
---	---	---

which hold a current valid World Athletics Product Certificate of approval may be used at WPA Recognised Competitions (see Part B - 3.1.2). The Para Athletics Implement Weights lists are set out in Appendix 1. Note: In WPA Recognised Competitions under Part B - 3.1.2, athletes must only use the implement weights relevant to their Sport Class (as outlined in Appendix 1). 2. The weights of Implements listed in Appendix 1 and not otherwise identified by World Athletics specifications must be verified by the Technical Delegate to confirm the implement is compliant. Note: This refers to implements unique to Para Athletics that are not documented within World Athletics Rule 187 or related appendices. 3. Except as provided below, all such implements shall be provided by the LOC. The Technical Delegate(s) may, based on the relevant Technical Regulations of each competition, allow athletes to use their own implements or those provided by a supplier, provided that such implements are World Athletics certified or, those implements that are not on the World Athletics list of certifiable implements which must be measured, verified and marked as approved by the LOC and approved by the Technical Delegate(s) before being made available to all athletes for use in competition. Such implements will not be accepted if the same model is already on the list of those provided by the LOC. 4. No modification shall be made to any implements during the competition. Assistance. 5. The following shall be considered assistance and are therefore not allowed: a) The taping of two or more fingers together. If taping is used on the hands and fingers, it may be continuous provided that as a result no two or more fingers are taped together in such a way that the fingers cannot move individually. The taping should be shown to the Chief Judge before the event starts. b) The use of any device of any kind, including weights attached to the body, which in anyway provides assistance when making a trial; c) Use of gloves except for athletes in Classes F31-33 and F51-53 that is not in contravention Rule 34.6 (d); 6. The following shall not be considered assistance and are therefore allowed: a) The use by an athlete, in order to obtain a better grip, of a suitable substance on their hands only. Shot putters may use such substances on their neck; b) The placement by an athlete, in the Shot Put, Discus Throw and Club Throw, on the implement,	参照) では、有効な WA 認証がある用具のみ使用できる。 「パラ陸上競技用器具重量」の一覧表は、付録 1 に記載している。 注意) PART-B 規則 3.1.2 に記された WPA 認可競技会では、競技者は付録 1 に示されている通り、自身の競技クラス用の重量の用器具を使用しなくてはならない。 34.2. 付録 1 に記載され、WA 仕様であることが別途示されていない用器具は、所定の仕様を満たしていることが技術代表によって検証確認されなければならない。 注意：この一覧表には、WA 規則 187 または関連する付録に掲載されていないパラ陸上競技独特な用具も含まれる。 34.3. 以下に規定する場合を除き、用具はすべて大会組織委員会が用意するものとする。 技術代表は、各競技会の競技規定に基づき、競技者自身が用意した用具や供給業者より提供された用具を認めることができる。ただし、WA に承認されたものであること、事前 に大会組織委員会の検査を受けて承認済みであることが表示されていること、すべての競技者が使用できるようにすることを条件とする。大会組織委員会が提供する用具一覧に同一モデルが含まれている場合は、かかる用器具の使用は認められない。 34.4. 競技期間中、用器具の改造は一切行ってはならない。 助力 34.5. 以下に掲げるものは助力とみなされ、認められない。 a) 2 本またはそれ以上の指をテープで巻きついたり貼り合わせたりすること。テープを使用する場合は、2 本あるいはそれ以上の指にテープを巻き、それぞれの指が独立して動かせないような使用をしてはならない。手や指にテープを使用する場合、競技開始前に審判員主任に見せなければならない。 b) 試技を行う際に、身体に重りを装着する等、なんらかの形で助けとなる用具を使用すること。 c) グローブを着用すること。ただし、競技クラス F31-33 及び F51-53 の競技者によるグローブの着用で規則 34.6(d)の違反に該当しないものは除く。 34.6. 以下に掲げるものは助力とみなされず、認められる。 a) 握りをよくするために手だけに適切な物質をつけること。砲丸投の競技者は首にそのような物質をつけることが認められる。 b) 砲丸投、円盤投、こん棒投の競技者がチョーク等の物質を用具につけること。ただし、手のひらや用具	助力
--	--	------------------

of chalk or a similar substance. All substances used on the hands and on the implements shall be easily removable from the implement using a wet cloth and shall not leave any residue; COMMENT: It is important to note that this applies to Shot Put, Discus Throw and Club Throw only. A javelin thrower may not apply any substance to the implement. However, there is no provision which would restrict a javelin thrower from using any substance on their hands (but not the implement) that complies with Rule 34.6 (a). c) The use of taping on the hands and fingers that is not in contravention of Rule 34.5 (a); d) The use of gloves that is not in contravention of Rule 34.5 (c); Athletes in Sport Classes F31-33 and F51-53 (i.e., quadriplegic athletes) use strapping or a glove on their non-throwing hand and anchor/attach that hand to any part of the throwing frame within the vertical plane of the throwing circle. Throwing Circle 7. The rim of the circle shall be made of band iron, steel or other suitable material, the top of which shall be flush with the ground outside. The ground surrounding the circle may be concrete, synthetic, asphalt, wood or any other suitable material. The interior of the circle may be constructed of concrete, asphalt or some other firm but not slippery material. The surface of this interior shall be level and 2cm±6mm lower than the upper edge of the rim of the circle. In the Shot Put, a portable circle meeting these specifications is permissible. Surface of Tie-down Devices (Sport Classes F31-34 and F51-57) a) WPA Approved Tie-down Devices must be used to conduct seated throwing events at WPA Recognised Competitions (see Part B - 3.1.2); b) At the Paralympic Games and WPA Championships (see Part B - 3.1.2 (a) and (b)) the interior of the Throwing Circle should be constructed of concrete, asphalt or a similar non-slippery material; c) Where portable WPA Approved Tie-down Devices are being used the surface must provide similar grip to a concrete throwing surface (e.g., coated in gritty paint OR covered in "gritty tape"); d) Movable platforms can be used at the discretion of the Technical Delegate. The platform does not have to be a full circle, but in these circumstances the front arc or semi-circle must be designed to give the same effect of throwing from a circle, diameter 2.135m to 2.5m and not alter the angle of the sector.	についた物質は、ぬれた布で簡単に拭きとれ、後に残らないものでなければならない。 コメント：ここで重要なのは、本条項が適用されるのは砲丸投、円盤投及びこん棒投のみで、やり投には適用されない。やりの投てき者は用具に物質を使うことはできないが、（用具ではなく）手に物質を使用することを制限する規定はない。34.6(a)参照 c) 規則 34.5(a)の違反に該当しない手や指のテーピング。 d) 規則 34.5(c)の違反に該当しないグローブの着用。 競技クラス F31-33 及び F51-53 の競技者（四肢麻痺の競技者）が投てきをしない方の手をストラップまたはグローブで投てき台のサークル垂直面内に位置するいずれかの箇所にまたはホールディングバーに固定・付着させること。 投てきサークル 34.7. 投てきサークルの縁枠は帯鉄、鋼鉄、その他の適切な物質でできていなければならない。その上部は外側の地面と同一平面になっていなければならない。投てきサークルの周りの地面は、コンクリート、合成材、アスファルト、木材等の適切な物質を用いることができる。投てきサークルの内側は、コンクリート、アスファルト等の頑丈で滑りにくい物質を用いることができる。内側の表面は水平で、投てきサークルの縁枠の上端より 2cm±6mm 低くしなければならない。 砲丸投については、下記の仕様を満たす移動式サークルの使用が認められる。 固定装置の表面（競技クラス F31-34 及び F51-57） a) WPA 認可競技会（PART-B 規則 3.1.2 参照）における座位競技者投てき種目では、WPA が許可する固定装置を使用しなければならない。 b) パラリンピック競技会及び WPA 競技会 PART-B 規則 3.1.2(a)及び(b)参照）においては、投てきサークルの内側はコンクリート、アスファルト、その他の滑りにくい材質のものでできていることが望ましい。 c) WPA が許可する移動式固定装置を使用する場合、その表面はコンクリートの表面を同じように捉えることができるもの（ざらざら塗装またはざらざらのテープで覆われている等）のものでなければならない。 d) 可動式プラットフォームの使用は技術代表の裁量で認めることができる。プラットフォームは完全な円ではなくてもかまわないが、その場合、正面の円弧または半円は、直径 2.135m～2.5m の円から投てきするのと同じ効果を与えるものでなければならない。その部分の扇形の中心角の角度は変更してはならない。	投てきサークル
--	--	----------------

COMMENT: The throwing platforms are becoming more available and more widely used. It is most important to ensure that they are adequately secured to the ground so that even the largest and heaviest of athletes cannot dislodge them during the throwing action. 8. All Seated Throwing Events (Shot Put, Discus Throw, Javelin Throw and Club Throw) should be conducted from a circle with diameter of $2.135\text{m} \pm 0.005\text{m}$ or $2.50\text{m} \pm 0.005\text{m}$, using a 34.92 degree sector. The rim of the circle shall be at least 6mm thick and shall be white. The use of movable platforms meeting these specifications is permissible. Note (i): The circular ring should preferably be coloured other than white so that the white lines required by this Rule are clearly visible. Note (ii): Discus Throw and Club Throw shall be conducted from a cage. Trials and Measurement 9. In all Seated Throwing Events, it shall be a failure: a) if the shot, the discus, the club, or the head of the javelin in contacting the ground when it first lands touches the sector line, or the ground or any object (other than the cage) outside the sector line. Note: It will not be considered a failure if the discus strikes the near side of the cage (right side for a right-handed thrower when facing the landing sector or the left side for a left-handed thrower when facing the landing sector) after the release of the implement, then lands within the landing sector outside the limits of the cage, provided that no other Rule is infringed, including Rule 30.16. b) if an athlete touches any holding straps outside the vertical plane of the rim of the throwing circle. 10. In all Seated Throwing Events, distances shall be recorded to the nearest 0.01m, rounded down to the nearest 0.01m if the distance measured is not a whole centimetre. 11. The measurement of each throw shall be made immediately after each valid trial (or after an immediate oral protest made under Rule 50.5): a) from the nearest mark made by the fall of the shot or discus to the inside of the circumference of the circle along a line to the centre of the circle; b) from where the head of the javelin first struck the ground to the inside of the circumference of the circle along a line to the centre of the circle; c) from the first point of contact by any part of the club to the inside of the circumference of the	コメント：プラットフォームは、より入手しやすく、より広く使用されるようになってきている。最も重要なことは、最も大きくて重い競技者でも、投てき動作中にそれらが外れることがないように、それらが地面に適切に固定されていることを確認することである。 34.8. すべての座位競技者投てき種目（砲丸投、円盤投、やり投、こん棒投）は、直径 $2.135\text{m} \sim 2.50\text{m}$ の円形の中心角 34.92 度の扇形部分から投てきを行うべきである。投てきサークルの縁枠は厚さ 6mm 以上で白色でなければならない。可動式プラットフォームの使用は認められる。 注意(i)：円形リングは本規則で求められている白線がはっきり見えるよう、できれば白以外の色であることが望ましい。 注意(ii)：円盤投とこん棒投は囲いから実施する。 試技と計測 34.9. 座位の投てき種目では、次のことをした時は 1 回の無効試技とする。 a) 砲丸、円盤、こん棒、またはやりの頭部が最初に着地して残した痕跡が区画ラインや区画ラインの外側地面あるいは他の物体（囲いを除いて）に触れた場合。 注意：もし円盤を投げた後、囲いの近い側（右投げの場合は落下点に向かって右側、左投げの場合は落下点に向かって左側）にぶつかり、囲いの外のセクター内に落下した場合、規則 30.16 を含み他の規則に反していない限り、無効試技とはみなさない。 b) 競技者が、サークル外縁外側の空間にある固定用ストラップに触れたとき。 34.10. 座位の投てき種目において、その距離は、cm未滿の端数を切り捨てた 1 cm単位で記録しなければならない。 34.11. 投てきの計測は、有効試技終了後（または、規則 50.5 に定める口頭による即時抗議が行われた後）、直ちに以下のとおり行うものとする。 a) 砲丸または円盤の落下による痕跡のサークルにもっとも近い地点から、サークルの中心をつなぐ線上のサークルの内側まで。 b) やり投では、やりの頭部が最初に落下した痕跡から、スターティングラインの中心をつなぐ線上のスターティングラインの内側まで。 c) こん棒では、どの部分でも最初に落下した痕跡から、サークルの中心をつなぐ線上のサークルの内側ま	試技と計測
--	---	--------------

circle along a line to the centre of the circle. Rule 35: Seated Throwing Requirements (Sport Classes F31-34, F51-57) [Note to officials: for the purpose of interpreting this rule and other rules regarding the shape, dimensions, construction and other characteristic of competition equipment, the 'fundamental principles' set out in Part B – 7.1 regarding 'Technology and Equipment' should be observed.] 1. Throwing Frame Specifications: a) The maximum height of the seat surface, shall not exceed 75 cm including any cushioning, that must not exceed 5cm in thickness. b) Each throwing frame must have a seat which is square or rectangular in shape and each side at least 30 cm in length. The seat surface must be level or with the front higher than the back (i.e. inclined backwards). The cushioning, if any, must be the same size and shape as the seat. Note: The front is the plane furthest from the athlete's spine with the athlete in a seated position regardless of the direction of the athlete in relation to the landing area. c) The throwing frame may incorporate side, front and back rests for the purposes of safety and stability. They can either be made of non-elastic fabric (e.g., non-elastic canvas) or be a rigid construction that does not move (e.g., rigid steel or aluminium). The backrest may incorporate cushioning that must not exceed 5 cm in thickness. Note: The structure of the throwing frame /or backrest shall not impede the view of judges. d) The side, front and back rest should not incorporate springs or movable joints or any other feature that could assist with propulsion of the throwing implement; e) The throwing frame may have a rigid vertical bar. The vertical bar must be a single, straight piece of material without curves or bends, and with a uniform cross-sectional profile without any changes to the thickness or diameter that is circular or square, not oval or rectangular. It must not incorporate springs or movable joints or any other feature that could assist with propulsion of the throwing implement; Note (i): It is understood that most materials will flex and distort to some degree under pressure and it will not be practical or economically viable to engineer a solution whereby all flexing is totally eliminated. However, flexing must not be clear to the naked eye and in the opinion of the technical officials the spirit of these rules and Part B - 7 is being breached. Note (ii): The vertical bar may have layers of tape and/or any other suitable material to provide a better grip. The thickness of the tape or	で。 第 35 条 座位競技者投てき種目に関する要件 (競技クラス F31-34, F51-57) [役員留意事項：本規則ならびに競技用器具の形状、寸法、構造等の特徴に関するその他の規則を解釈するにあたり、「技術及び用器具」の規定、とりわけ PART-B 規則 7.1 の「基本原則」が留意されるべきである。] 35.1. 投てき台の仕様 a) 台座の表面の高さは、クッションがある場合はそれも含めて、75cm 以下でなければならない。クッションの厚さは、5cm を超えてはいけない。 b) 投てき台には、各辺 30cm 以上の正方形または長方形の台座が設けられていなければならない。台座の表面は水平または前方が後方より高い（後ろに傾く）構造になっていなければならない。クッションは、座面と同じ大きさ、形でなければならない。 注意：前方とは、着地エリアに対して競技者がどの方向を向いているかにかかわらず、着座した状態の競技者の背骨から一番遠い位置にある面のことをいう。 c) 台座は、安全性と安定性を確保するためにサイドレスト、フロントレスト、背もたれのあるものでもよい。サイドレストや背もたれは、伸縮性のない布（非伸縮性のキャンバス地製等）でできていても、動かない堅固な構造（鉄製、アルミニウム製等）であってもよい。背もたれはクッションがついていてもよいが、クッションの厚さは 5cm を超えないものとする。 注意：投てき台の構造/または背もたれは、審判員の視界を妨げてはならない。 d) サイドレスト、フロントレスト、背もたれは、バネ、可動接合部等、投てき動作の助けとなり得る構造を有しているべきではない。 e) 投てき台には堅固で垂直なホールディングバーを設置することができる。ホールディングバーは、湾曲や折れ曲がりがなく厚さや直径に変化のない1本の棒でなければならない。切断面の形状は円または正方形でなければならない。楕円や長方形のものは認められない。バネ、可動接合部等、投てき動作の助けとなり得る構造を有してはならない。 注意(i)：ほとんどの物質は、圧力がかかれば一定程度の湾曲や歪みを生じるものであり、湾曲を完全になくするのは現実性または経済的実現可能性に欠けることは認識している。しかし、湾曲は目視で明らかなのであってはならず、技術役員の判断において、上記規則及び PART-B 規則 7 の精神に反するものであってはならない。 注意(ii)：ホールディングバーは、握りを良くする目的でテープ及び／または適当な素材を巻いてもよい。テープ及び／または適当な素材の厚さは、競技者の本来の能力以上の不公正な利益を得る結果となつては	第 35 条 座位競技者投てき種目に関する要件
---	--	---

other alternative material must not result in any unfair advantage exceeding the athlete's physical prowess. Any tape on the vertical bar must be uniform except for incidental overlapping and must not result in any sudden change in diameter, such as the creation of any ring on the vertical bar. Only regular taping in accordance with the rule is allowed on the vertical bar – rings, loops and the like are not permitted.

Note (iii): For the avoidance of doubt, an athlete shall be entitled to hold on to any component of the throwing frame for stability.

COMMENT: There is no minimum or maximum length requirement for the vertical bar. The vertical bar must be smooth without any indentation, bulges or sudden change in diameter or thickness. The bar must be vertical however some deviation from "exactly perpendicular to the ground" may be permitted. Such deviation should not usually exceed 5 degrees from the vertical. An additional piece which acts as support to the vertical bar (similar to the example illustrated below) is permitted and strongly encouraged to mitigate against potential flexing of the vertical bar. The vertical bar, or any of its supports, may not protrude outside the throwing circle or platform.

The use of a plumb bob will assist in determining if any part of the throwing frame or vertical bar is not in conformity with this rule when placed in the throwing circle or platform.

It should also be noted that at the Paralympic Games and WPA Championships a courtesy precheck of throwing frames is conducted to enable athletes to make any necessary amendments prior to final check at the entry to the Call Room.




Figure 22 – Additional piece to mitigate the potential flexing of the vertical bar

f) No part of the throwing frame, including any vertical bar, shall move (save for incidental movement that cannot reasonably be eliminated)

ならない。ホールディングバーに巻いてあるテープは、偶発的な重なりを除いて均一である必要があり、バーにリングができるなど、突発の直径の変化が生じてはならない。バーには、ルールに従った通常のテーピングのみが許される。リングやループなどは認められない。

注意 (iii) : 誤解を避けるため、競技者は安定のために投てきフレームのどこをつかんでもよい。

コメント：ホールディングバーには長さの制約はない。ホールディングバーは、へこみ、膨らみまたは直径や厚みの急激な変化がなく、滑らかでなければならない。バーは垂直でなければならないが"地面から少しのずれもなく垂直"ということからは少し外れることもあり得るものとし、それは許容範囲とすることができる。このずれは垂直面から 5 度を超えてはならない。参考図にあるように、ホールディングバーが支え無しの状態で湾曲することを軽減するため、ホールディングバーを支える補助部品は許可され強く推奨される。ホールディングバー、あるいはいかなる補助部品も、投てきサークルあるいはプラットフォームから外へでてはならない。

プラム・ボブの使用は、投てきサークルやプラットフォームに置かれたときに、投てき台やバーの一部がこの規則に適合していないかどうかを判断するのに役立つ。

また、パラリンピック競技大会や WPA 競技会では、競技者が招集所への入場時に最終チェックを行う前に必要な修正を行うために、投てき台の礼儀的な事前チェックが行われることにも注意が必要である。

f) 投てき動作中に、ホールディングバーも含め投てき台のいかなる部分も動いてはならない（ただし、合理的な方法で防げない偶発的な動きは除く）。投てき台に、サイドレスト、フロントレスト、背もたれ、

during the throwing action. The corner(s) of, or notches in, the seat surface may be cut to accommodate side, front, back rests and/or a vertical bar into the main throwing frame. The size of these cuts shall not be appreciably more than the space needed to insert the rests or the vertical bar in them. The overall shape of the seat shall remain square or rectangular. g) Footplates, if used, are for support and stability only. <u>Existing Rule 35.1.h in force until 31 December 2026</u> h) A daily wheelchair that satisfies these criteria is acceptable (including the requirement that it must not move during the throwing action). <u>New Rule 35.1.h in force from 1 January 2027</u> h) Only athletes in Sports classes F31 and F51 may use a daily wheelchair as their throwing frame, which must not move during the throwing action. Note: Strapping across the upper thighs and or pelvis is encouraged. Strapping must be only to the daily wheelchair with non-elastic material. Such strapping shall be the responsibility of the athlete's assistant and included within the time permitted in Rule 35.5b) 2. Throwing Frame Measurement and Inspection Throwing Frames will be measured and inspected in the Call Room or at the competition area prior to the commencement of the event. Once it has been measured and inspected an athlete's Throwing Frame must not be taken from the competition area before the start of the event. Throwing Frames can be re-examined by the officials before, during or after the event. Note: Measurement will always take place without the athlete sitting in the frame. 3. Athlete's Responsibility for Throwing Frame Compliance It is the responsibility of the athlete to ensure that their Throwing Frame conforms to the requirements stipulated in Rule 35.1. No event shall be delayed while an athlete makes adjustments to their throwing Frame. If an athlete fails to comply with this Rule, then the athlete will not be permitted to start the event and shall be shown in the results as "DNS" in accordance with Rule 6.16. 4. Positioning of the Throwing Frame When positioning and securing the throwing frame inside the competition area all parts of the throwing frame, vertical bar and footplates must remain inside the vertical plane of the rim of the circle throughout the trial. Personal strapping securing the athlete to the throwing frame is not considered to be part of the throwing frame for	及び/またはホールディングバーを固定する目的で、台座の角を切ったり、削ったりしてもよい。こうした切り取りの範囲は、レストやホールディングバーを差し込むに必要な最小限とする。台座の形状の外観は、正方形または長方形のままでなくてはならない。 g) フットプレートを使用する場合は、専ら足を支え安定させる目的でのみ使用する。 <u>2026年12月31日まで既存規則 35.1h を適用</u> h) 普段使っている車いすは、上記要件（投てき動作中に動いてはならないという要件も含む）を満たしていれば、使用が認められる。 <u>2027年1月1日より新しい規則 35.1.h を適用</u> h) 競技クラス F31 及び F51 は、投てき動作中に動かなければ投てき台として生活用車いすを使用してもよい。 注意：大腿上部か骨盤あるいはその両方をベルトなどでしっかり固定することを推奨する。そのベルトは、伸縮性のないもので生活用車いすにのみ取り付けなければならない。そのような固定は競技者のアシスタントの責任の上なされ、規則 35.5b の規則に定められた時間内に行われなければならない。 35.2. 投てき台の計測と検査 投てき台の計測・検査は、競技開始前に招集所または競技区域で行う。計測・検査を済ませた投てき台は、競技開始前に競技区域から持ち出してはならない。競技開始前、競技中、または競技開始後に、競技役員が投てき台の再検査を行う場合がある。 注意：計測は常に競技者が着座していない状態で行う。 35.3. 投てき台の適合性に関する競技者の責任 競技者は責任を持って規則 35.1 の要件を満たす投てき台を準備しなければならない。競技者による投てき台の調整で競技の開始が遅れることがあってはならない。この規則に反する競技者はその後参加しようとする種目での試技を開始してはならず、その記録は規則 6.16.に従い"DNS"と記録される。 35.4. 投てき台の位置決め 競技区域内で投てき台の位置を決めて固定する際、試技中を通して、投てき台のすべての部分、ホールディングバー、フットプレートが投てきサークル内側の垂直延長面の内側におさまるようにしなければならない。ホールディングバーの先端は投てきサークルの縁を垂直に延長した面上の線の内側になければならない。この規則は、競技者を投てき台に固定する個人用ストラップは、投てき台の一部としてみなさない。
---	--

the purposes of this rule. 5. Time Allocation for Securing Frames A reasonable amount of time will be permitted for an athlete's throwing frame to be secured in the circle before the athlete attains a seated position on the throwing frame. The maximum time allowed is for athletes to secure themselves to the chair and have as many warm-up throws as time permits is: a) 4 minutes for Sports Classes F32-34 and F54-57, or b) 5 minutes for classes F31 and F51-53. Note (i): Timing should begin at the time the chair is oriented, secured to the throwing platform and made available to the athlete to secure themselves into position. COMMENT: Timing for securing the athlete into the throwing chair and conducting practice throws begins when the throwing frame is situated in the circle or throwing platform. If the time in this rule elapses prior to securing the athletes into the Throwing chair, the time for the first trial should commence as it would if the athlete was secured. If the athlete is using a day chair that meets the requirements for a throwing frame the time starts when the day chair is placed and strapped in the throwing circle or on the throwing platform. 6. Tie-down Device Failure (Sport Classes F31-34, F51-57) If a tie-down device should break or fail during the execution of a throw then the overseeing official should: a) If the athlete does not fail, offer the athlete the option of re-taking that trial (i.e., if the athlete is happy with the distance and they haven't failed then the athlete has the option of counting the affected trial), or; b) If the athlete fails, then the trial should not be counted and the athlete should be allowed to retake the affected trial. Rule 36: Seated Throwing Technique, Lifting and Failure 1. In Seated Throw Events, all athletes (Sport Classes F31-34, F51-57) shall throw implements from a Throwing Frame in a seated position. The seated position is defined as follows: a) The athlete must sit so that both legs are in contact with the seat surface from the back of the knee to the back of the buttock (Ischial tuberosity). For athletes with lower limb above and through knee amputation, the residual length of the leg(s)	35.5. 投てき台固定のための時間 競技者が投てき台の投てき位置につく前に、投てきサークル内に投てき台を設置するため適当な時間が与えられる。投てき台に固定後、以下の時間内で競技者を投てき台に固定し、練習投てきを時間が許す限り行うことができる。 a) 競技クラス F32-34 及び F54-57 は 4 分以内 b) 競技クラス F31 及び F51-53 は 5 分以内 注意(i)：カウントダウンの開始は、投てき台の位置が決まり、プラットフォームに固定され、競技者が投てき位置に移動する準備ができたときとする。 コメント：競技者を投てき台に固定して練習投てきを行うタイミングは、投てき台がサークルまたは投てき台に位置したときに開始される。この規則の時間が競技者を投てき台に固定する前に経過した場合、最初の試技の時間は、競技者を固定した場合と同様に開始されるべきである。 競技者が投てき台の要件を満たすデイ・チェア(生活用車いす)を使用している場合は、生活用車いすが投てきサークルか投てき台に置かれ、ストラップを付けられた時に開始される。 35.6. 固定装置・ホールディングバーの故障（競技クラス F31-34 及び F51-57） 投てき動作中に固定装置が壊れたり、故障したりした場合、担当役員は以下のとおり対処すべきである。 a) 試技が無効でない場合は、試技をやり直す選択肢を提供する（投てきが有効で、その結果に満足している場合は、競技者は当該試技を正式な結果として記録に残すことができる）。 b) 試技が無効であった場合は当該試技を記録せず、競技者に試技のやり直しを認めるべきである。 第 36 条 座位競技者投てき種目の技術、リフティング、無効 36.1. 座位競技者投てき種目においては、すべての競技者（競技クラス F31-34 及び F51-57）は投てき台から座位姿勢で投てきを行うものとする。座位姿勢の定義は以下のとおり。 a) 両脚が膝裏から臀部後方（坐骨結節）まで座面に接触するように座らなければならない。膝上切断の競技者は、大腿部すべてが臀部後方（坐骨結節）まで座面に接触していなくてはならない。	第 36 条 座位競技者投てき種目の技術 リフティング無効
---	--	---

must be in contact with the seat surface till the back of the buttock (Ischial tuberosity).

b) This sitting position must be maintained throughout the throwing action until the implement has landed. Strapping across the upper thighs, pelvis **and knees are recommended**. All strapping used to strap athlete whether it is attached to the frame or not must be made with non-elastic material.

Note (i): The intention of this rule is to minimise the contribution of the legs to the athlete's performance.

Note (ii): If an athlete presents with anatomical limitation that prevents adherence to the above requirements, then an assessment shall be made by WPA in advance of the event. WPA shall establish a process for such exception to be granted so that the athlete is throwing within the spirit of the rules.

Note (iii): For the purposes of this rule, the back of the buttock refers to the most posterior part of the buttock which remains in contact with the seat surface when the athlete is seated and bends as far forward as possible at the hips, so that chest goes towards the knees and the ischial tuberosities remain in contact with the seat surface.

Note (iv): It is not necessary for both knees to be in contact with the same plane of the vertical edge of the seat surface provided that all other requirements of this rule are satisfied to the effect that the athlete may "straddle" the corner of the vertical edge of the seat surface with one leg on adjacent planes.




Figure 23 Ischial tuberosities

2. An athlete shall commence their trial from a stationary seated position.

3. It shall be a failure if an athlete moves from the seated position from the time the athlete takes the implement into the starting position of the trial until the implement has landed.

Note: It is not a failure as long as any part of the back of the knee is in contact with the seat

b) 上記座位姿勢は、投てき動作の始めから投てきの着地点に印がつけられるまでの間ずっと維持しなければならない。大腿上部、骨盤あるいはその両方、**両膝をベルトなどでしっかり固定することを推奨する。そのベルトは、フレームに取り付ける場合でも、そうでない場合でも伸縮性のないものでなければならない。**

注意(i)：本規則は、脚力が競技者の競技に与える影響を最小限にすることを目的とする。

注意(ii)：身体構造上、上記の要件を満たすことができない競技者については、競技開始に先立ち、WPAが評価するものとする。WPAは、上記規則にのっとった投てきが行われるよう、かかる例外措置を認めるための手続きを確立しなければならない。

注意(iii)：本規則の解釈上、臀部後方とは、臀部の最も後方に位置し、着座した状態で坐骨結節点を座面から離すことなく胸を膝につけるように可能な限り前屈したときに座面に接触したままの部分のことをいう。

注意(iv)：この規則の他のすべての要件を満たしていれば、競技者の両膝がシート座面の同じ面に密着している必要はなく、片方の足が隣接したコーナーをまたいで座ってもよい。

36.2. 競技者は、座位姿勢で静止した状態で試技を始めるものとする。

3. 競技者が投てき物を構えてから投てき器具が落下するまでの間に座位姿勢から動いた場合は無効とする。

注意：投てき器具が落下するまでの投てき動作の間に、ひざ裏すべてが座面に接触している限りは、無効

during the throwing action until the implement has landed. COMMENT: It is important to note that if one or both knees slide forward and lose contact with the seat surface during the throwing action, it shall be considered a failure. Team of Officials For Seated Throw Events, it is recommended to allocate the available officials as follows: 1) The Chief Judge will watch over the whole of the event. 2) Judges checking whether the trial has been made correctly including: a) observing if the knee “slides forward” off the seat cushion; b) observing whether the seated position has been maintained throughout the trial in accordance with the Rules; and c) observing whether the vertical holding bar flexes and measuring the trial. One must be provided with two flags - white to indicate if the trial is valid and red if it is a failure. Where EDM is not in use the second judge should pull through and hold the measuring tape in such a way that it passes through the centre of the circle. 3) Judge immediately after the trial placing a marker indicating the point from which the trial is to be measured. 4) Judge positioning the spike/prism at the point where the marker has been placed ensuring the tape is on the zero mark. 5) Judge in charge of retrieving the implements and returning them to the implement stand or placing them in the return chute. 6) Judge - a recorder scoring the results sheet and calling each athlete (and the one who is to follow). 7) Judge in charge of the scoreboard (trial-number-result). 8) Judge in charge of the clock indicating to the athletes that they have a certain time to take their trial. 9) Judge in charge of athletes. 10) Judge in charge of the implement stand. Note (i): This is the traditional setting-up of the officials. In major competitions, where a data system and electronic scoreboards are available, specialised personnel are certainly required. To be clear in these cases, the progress and scoring of a Field Event is followed by both the recorder and by the data system.	試技ではない。 コメント：投てき動作の間に片方または両方の膝が前方にスライドして座面との接触を失った場合、それは失敗とみなされることに注意することが重要である。 競技役員チーム 座位投てき種目の場合、以下のように競技役員を配置することが推奨される。 1) 審判員主任は、競技全体を監視する。 2) 2名の審判員は、以下を含め試技が正しくなされたかを確認する。 a) 膝がシートやクッションを離れ、前方にスライドしているかどうか。 b) 規則に則り、試技の間、座位の姿勢が維持できているかどうか。 c) ホールディングバーがしなるかどうか、計測がなされているかどうか審判員の1名は、有効試技を示す白旗と無効試技を示す赤旗の2種類の旗を用意しなければならない。 EDMを使用しない場合、もう1名の審判員は、巻尺を引っ張り、サークル中央に通す。 3) 試技終了直後に試技を測定するための痕跡にマーカーを置く審判員。 4) 落下域において距離計測のために痕跡にピン／プリズムを刺し、巻尺を0に位置をピンに合わせて持つ審判員。 5) 投てき物を回収し、置き場に戻す、もしくは返送車に置く、審判員 6) 審判員—記録表を記入し、各競技者（及びさらにその次の競技者）を呼び出す記録者 7) スコアボード（試技回数-競技者のナンバー-結果）を担当する審判員 8) 試技の残り時間を競技者に示す時計を担当する審判員 9) 競技者を担当する審判員 10) 投てき物、置き場担当の審判員 注意(i)：これは競技役員の伝統的な配置である。データシステムと電子スコアボードが利用可能な大規模な競技会では、専門の人材が必ず必要である。このような場合には、フィールド種目の進捗状況と結果は、記録者とデータシステムの双方で記録される。	
---	--	--

Note (ii): Officials and equipment must be placed in such a way as not to obstruct the athlete's way nor impede the view of the spectators.

Note (iii): As a safety precaution it is recommended to delay handing the implement to the athlete until the landing area is clear.

Note (iv): The clock should be positioned such that the athlete can easily see it. It may therefore need to be moved for each athlete.

Rule 37: Club Throw The Competition

1. The club shall be held at its neck and/or head with one hand only. It may be thrown either from a position facing the landing sector or from a position facing backward and throwing overhead.

2. The use of sticky or adhesive substances (e.g. pine tar, tacky spray) is not permitted. Only substances that can be easily removed with a wet cloth such as chalk or non-residue sprays may be used.

The Club

3. Construction. The Club shall consist of four main parts: a head, a neck, a body and an end. The head, neck and body shall be solid and made of wood so as to constitute a fixed and integrated whole. The body shall have fixed it to a cylindrical end constructed of metal without indentations, projections or sharp edges.

4. The surface of the head, neck and body shall be smooth and have no dimples or pimples, grooves or ridges, holes or roughness.

5. The head shall be spherical or cylindrical in shape and immediately taper towards the neck. The diameter of the widest part of the body shall not exceed 60mm and may be cylindrical. The club shall taper regularly towards the neck and slightly towards the metal end.

6. The shape of the Club must be as shown in Figure 24. It shall conform to the following shape and specifications:




Figure 24 – Club

Figure 25- Examples of Club shapes not compliant
See APPENDIX2

注意(ii) : 競技役員及び用具は、競技者を妨害したり、観客の視界を妨げたりしないように配置されなければならない。

注意(iii) : 安全のため、落下地点が準備できてから投てき物を競技者に渡す。

注意(iv) : 時計は競技者が容易に見える位置に置く。そのため、必要に応じて位置を変える。

第37条 こん棒投 競技会

37.1. こん棒は首部と先端部またはそのいずれかで片手だけを使って支えるものとする。こん棒は着地エリアの方向を向いて投げて、後ろ向きの姿勢から頭上越えて投げてよい。

37.2. 粘着性または接着性のある物質（例：松ヤニ、粘着スプレー）の使用は認められない。チョークや非粘着性残留スプレーなど、ぬれた布で簡単に除去することができる物のみの使用が認められている。

こん棒

37.3. 構造：こん棒は、先端部（ヘッド）、首部（ネック）、胴体部（ボディ）、底部（エンド）の4つの部分からなるものとする。先端部、首部、胴体部は木製で、全体として固定され、一体化した頑丈なものでなければならない。胴体部は、金属製で刻み目や突起や鋭い縁のない円筒状の底部に固定されていなければならない。

37.4. 先端部、首部、胴体部の表面は、くぼみ、でこぼこ、溝、畝、穴、ざらつきがなく、滑らかなものでなければならない。

37.5. 先端部は球状または円筒状で、首部に向けてすぐに細くなる形状でなければならない。胴体部は、一番太い部分の直径が 60mm 以下でなければならない。形状は円筒状でもよい。こん棒は、首部に向けて均等に細くなり、金属製底部に向けて少しか細くなるものとする。

37.6. 以下の仕様に従うものとする。

図25（巻末）規則に準拠していない例参照

Club	
Minimum weight for admission to competition and acceptance of a Record	397g
Information for manufacturers	
Range for supply of implement for competition	402g 422g
Overall length (including metal end)	
Min.	350mm
Max.	390mm
Diameter of neck	
Min.	18mm
Max.	20mm
Diameter of widest part of the body	
Min.	50mm
Max.	60mm
Diameter of metal end	
Min.	38mm
Max.	39mm
Thickness of metal end	
Min.	12.5mm
Max.	13mm

COMMENT: The Club Throw is one of the more dangerous events for Officials and therefore special care must be taken to ensure the safety of all Officials, other athletes and their assistants as well as media and spectators. Announcing that the implement is being handed to the athlete may improve safety for all concerned. In addition, advising the athlete that it is now safe to throw will increase the safety for all concerned, as indicated in the commentary under Note (i) on Rule 24.17.

SECTION V – INDOOR COMPETITIONS

Rule 38: Applicability of Outdoor Rules to Indoor Competitions

With the exceptions stated in the following Rules of this Section V and the requirement for wind measurement set out in Rule 18 and Rule 27, the Rules of Sections I to IV for outdoor competitions shall apply to Indoor Competitions.

Rule 39: The Indoor Stadium

1. The stadium shall be completely enclosed and covered. Lighting, heating and ventilation shall be provided to give satisfactory conditions for competition.

2. The field of play should include an oval track; a straight track for sprints and runways and landing areas for jumping events. In addition, a circle and landing sector for the Shot Put should be

コメント：こん棒投は競技役員にとって最も危険な競技の一つであるため、すべての競技役員、他の競技者、その補助者、メディア、観客の安全を確保するために特別な注意が払われなければならない。器具が競技者に手渡されることをアナウンスすることで、関係者全員の安全性を高めることができる。さらに、規則 24.17 の注意(i)の解説で示されているように、競技者に投げても安全であることを伝えることは、関係者全員の安全性を高めることになる。

第5部 室内競技

第38条 屋外競技規則の室内競技への適用

第5部及び規則 18と規則 27に記されている風力を求められるルールを除いて、以下の競技規則で定められた内容以外は、屋外競技の第1部から第4部の競技規則が室内競技にも適用される。

第39条 室内競技場

39.1. 室内競技場は完全に壁で囲まれ、かつ屋根で覆われていなければならない。照明、暖房、換気設備は、競技会運営が満足のいく状態となるよう備え付けられていないと
はならない。

39.2. 室内競技場は周回トラック走路、短距離競走用の直走路、跳躍競技用の助走路と着地場所を含むべきである。さらに砲丸投用のサークル及び扇形の着地場所も、恒久的あるいは暫定的であれ用意さ

provided, whether permanently or temporarily. All the facilities should conform to the specifications in the World Athletics Track and Field Facilities Manual. 3. All the tracks, runways or take-off surface areas shall be covered with a synthetic material that should preferably be able to accept 6mm spikes in running shoes/prosthetic devices. The track manufacturer or the stadium operator may allow the use of spikes of up to 9mm. If the track manufacturer or the stadium operator mandates an alternate maximum or prohibits the use of certain shaped spikes, this shall be applied and the athletes notified of accordingly. WPA Indoor Championships should be held only on facilities that hold a current valid World Athletics Indoor Athletics Facility Certificate. It is recommended that other WPA Recognised competitions (see Part B - 3.1.2) should also be held on these facilities. 4. The foundation on which the synthetic surface of the tracks, runways and take-off areas is laid shall be either solid e.g., concrete or, if of suspended construction (such as wooden boards or plywood sheets mounted on joists), without any special sprung sections and, as far as technically possible, each runway shall have a uniform resilience throughout. This shall be checked, for the take-off area for the jumps, before each competition. Note (i): A “sprung section” is any deliberately engineered or constructed section designed to give extra assistance to an athlete. Note (ii): The World Athletics Track and Field Facilities Manual, which may be downloaded from the World Athletics website, contains more detailed and defined specifications for planning and construction of indoor stadia including diagrams for track measurement and marking. Note (iii): The current standard forms required to be used for the certification application and measurement report as well as the Certification System Procedures may be downloaded from the World Athletics website. COMMENT: Lack of suitable lighting is a common problem for Indoor Competitions. A covered stadium must have a lighting which allows a correct and fair delivery of the events and if there is television coverage the illumination level may need to be higher. The finish line area(s) may require additional lighting for the Fully Automatic Timing. Rule 40: The Straight Track 1. The lateral inclination of the track should not exceed 1:100 (1%) unless special circumstances exist which justify World Athletics providing an exemption and the inclination in the running direction shall not exceed 1:250 (0.4%) at any point and 1:1000 (0.1%) overall.	れるべきである。すべての施設は WA 陸上競技施設マニュアルの仕様に適合させるべきである。 39.3. すべてのトラック走路、助走路または踏切場所の表面は、合成物質で覆われていなければならない、その合成物質は長さ6mmのスパイクシューズ/義肢に対応できることが望ましい。トラック舗装材業者または競技場管理者は、最大9mmのスパイクの使用を認めることができる。トラック製造業者もしくは競技場管理者が、より小さい寸法の上限を設けている場合や、特定の形状のスパイクの使用を認めていない場合は、これを適用し、そのことが競技者に対して通知されなければならない。 WPA 室内選手権大会は、WA による室内競技施設認証を受けた施設で実施すべきである。 WPA 認可競技会(PART-B 規則 3.1.2 参照)もこのような施設で実施することが望ましい。 39.4. トラック走路、助走路、踏切区域に敷設されている合成舗装材の基礎は堅固なもの（たとえばコンクリートなどあるいは懸架構造（梁の上に木板や合板を取り付けたもの）の場合は、特に弾むような箇所がないようにし、技術的に可能である限り、すべての走路は全体を通して均一な弾性を持たなくてはならない。この弾性について競技会の前に跳躍競技用の踏切場所を点検しなければならない。 注意(i)：「弾むような箇所」とは競技者に特別な助力を与えるように意図的に設計ないしはデザインし建設された箇所である。 注意(ii)：WA 陸上競技施設マニュアルには、トラックの計測やマーキングのための図を含む室内競技場の構造や設計のための詳細や規定する仕様が含まれており、WA ウェブサイトからダウンロードにより入手可能である。 注意(iii)：WA の施設公認手続き方法をはじめ、申請のための標準書式や計測報告書書式は、WA ウェブサイトからダウンロードにより入手可能である。 コメント：適切な照明の不足は、室内競技会の共通の問題である。屋根で覆われたスタジアムは、競技の正確で公正な実施を可能にする照明を備えていなければならない、テレビの中継がある場合、照明レベルはより高くする必要がある。フィニッシュライン付近は、写真判定装置のために追加の照明を必要とすることがある。 第 40 条 フィールド内直走路 40.1. トラックの許容傾斜度は幅で 100 分の 1 (1%)、走る方向で個々の箇所では 250 分の 1 (0.4%)、全体では 1,000 分の 1 (0.1%) を超えてはならない。	第 40 条 フィールド内直走路
---	---	---

Lanes 2. The track should have a minimum of 6 and a maximum of 8 lanes separated and bounded on both sides by white lines 50mm wide. The lanes shall all be 1.22m ± 0.01m wide including the lane line on the right. Note: For all tracks constructed before 1 January 2004, the lanes may have a width of maximum 1.25m. However, when such a track is fully resurfaced, the lane width shall comply with this Rule. Start and Finish 3. There should be a clearance of at least 3m behind the start line free of any obstruction. There shall be a clearance of at least 10m beyond the finish line free of any obstruction with adequate provision beyond for an athlete to come to a halt without injury. Note: It is strongly recommended that the minimum clearance beyond the finish line should be 15m. COMMENT: The straight track can measure 50m or 60m. In major competitions, it is necessary that the events take place over a distance of 60m. If advice is sought, it is necessary to insist on the area which must be free at the start and at the finish. Experience has proved that in many situations, behind the starting line, the free zone cannot be more than 2 metres. This distance is sufficient to place the starting-blocks with false start apparatus and the lane boxes indicating the lanes. Rule 41: The Oval Track and Lanes 1. The nominal length should preferably be 200m. It shall consist of two parallel straights and two bends, which may be banked, whose radii should be equal. The inside of the track shall be bordered either with a kerb of suitable material, approximately 50mm in height and width, or with a white line 50mm wide. The outside edge of this kerb or line forms the inside of lane 1. The inside edge of the line or kerb shall be horizontal throughout the length of the track. However, this kerb or line may be located on the banking slope such that the pivot line of the banking shall be horizontal throughout the length of the banking. The kerb on the two straights may be omitted, and a white line 50mm wide substituted. Note: All measurements shall be taken as indicated in Rule 15.2 Lanes 2. The track should have a minimum of four and a maximum of six lanes The nominal width of the lanes shall be between 0.90m and 1.10m including the lane line on the	レーン 40.2. トラックは 6 レーン～8 レーンとし、幅 50mm の白線で両側が区分されていなければならない。レーンの幅は 1m220 (±10mm) とし、右側のレーンラインを含む。 注意:2004 年 1 月 1 日以前に作られたトラックについては、レーンは最大 1m250 の幅でもよい。しかしトラック舗装材の完全なる張り直しを実施したならレーンの幅は本規則に合致しなくてはならない。 スタートとフィニッシュ 40.3. スタートライン後方の少なくとも 3m はどのような障害物も置かない。フィニッシュライン前方の少なくとも 10m はどのような障害物も置かず、その先に競技者が怪我なく停止できるようなものを置く。 注意：フィニッシュライン前方については、15m 以上を確保することを強く推奨する。 コメント：直走路は 50m または 60m とすることができる。主要な競技会では、60m 以上の距離で行われることが必要である。 もしアドバイスを求められた場合は、スタート時とフィニッシュ時にフリーでなければならないエリアを主張することが必要である。 経験上、多くの状況では、スタートラインの後ろのフリーゾーンは 2m を超えてはならないことが証明されている。この距離は、偽のスタート装置とレーンを示すレーンボックスを備えたスタートブロックを配置するのに十分な距離である。 第 41 条 周回トラック及びレーン 41.1. トラック 1 週の通常の長さは、200m が望ましい。トラックは、平行である二つの直走路と、同じ半径でかつ傾斜（バンク）してもよい二つの曲走路から構成される。トラックの内側は高さ及び幅 50mm の適切な材質の縁石または幅 50mm の白線で区分される。この縁石または白線の外側（右側）の端は、第 1 レーンの内側の端となる。縁石または白線の内側の端はトラック全体を通して水平でなければならない。この縁石または白線は、トラックの傾斜部分の長さ全体にわたって、傾斜や勾配を考慮し、傾斜面に沿って配置する。二つの直走路の縁石を取り除き、50mm 幅の白線で代用しても良い。 注意：すべての距離計測は規則 15.2 に記載の通りされなくてはならない。 レーン 41.2. トラックは 4 レーン～6 レーンとする。 レーンの幅は右側のラインを含めて 900mm～1m100 とする。どのレーンも同じ幅でなければならない。所定の幅との誤差は±10mm までとする。各レーン	レーン スタートとフィニッシュ 第 41 条 周回トラック及びレーン レーン
--	--	---

right. All lanes shall be of the same nominal width with a tolerance of $\pm 0.01\text{m}$ to the selected width. The lanes shall be separated by white lines 50mm wide. COMMENT: Despite the oftentimes narrowness of the width of the lanes for indoor competitions, athletes must still start (e.g. Have their hands completely within) inside their lanes. This does not mean that part of their starting blocks cannot be outside their lanes providing they do not interfere with another athlete, (see Rule 16.2 (e)). Banking 3. The angle of banking in all the lanes should be the same at any cross section of the track. The straight may be flat or have a maximum lateral inclination of 1:100 (1%) towards the inside lane. In order to ease the change from the straight to the banked bend, the change may be made with a smooth gradual horizontal transition which may be extended into the straight. In addition, there should be a vertical transition. Marking of the Inside Edge. 4. Where the inside edge of the track is bordered with a white line, it shall be marked additionally with cones or flags on the bends and optionally on the straights. The cones shall be at least 0.15m high. The flags shall be approximately 0.25m x 0.20m in size, at least 0.45m high and set at an angle of 60° with the ground away from the track. The cones or flags shall be placed on the white line so that the edge of the base of the cone or flag pole coincides with the edge of the white line closest to the track. The cones or flags shall be placed at distances not exceeding 1.5m on the bends and 10m on the straights. Note: the use of an inside kerb is strongly recommended. COMMENT: An Oval Track may be longer than 200m but any records for 200m or longer races would not be ratified. The development of a 200m track is more advantageous than those of a shorter distance. To organise top level competitions, it will be useful to have a 6-lane track. The ideal width of the lanes of an Oval Track should be 1m. Cones must be placed not only along the bends, but along the whole of the oval track. When positioning the flags or cones it must be taken into account that the white line on the inside edge of lane 1 does not belong to the runner drawn in that lane. Cones are preferred and recommended for Indoor Competitions Rule 42: Start and Finish on the Oval Track 1. Technical information on the construction and marking of a 200m banked indoor track are given in detail in the World Athletics Track and Field Facilities Manual. The basic principles to be adopted are given hereunder.	ンは幅 50mm の白線で区切る。 コメント：室内競技会ではレーンの幅が狭くなることがよくあるが、競技者はレーン内でスタートしなければならない（例：手を完全にレーン内に入れなければならない）。これは、他の競技者の邪魔にならないければ、スタートブロックの一部をレーンの外に出してはならないという意味ではない（規則 16.2 (e)を参照）。 バンク 41.3. すべてのレーンの傾斜度は、トラックのどの断面でも同じでなければならない。直走路は平坦あるいは内側のレーンに向かって最大 100 分の 1 (1%) の傾斜があってもよい。 直走路から傾斜した曲走路への水平移行を容易にするために、その場所は直走路の終わりからならかな勾配にし、直走路方向に伸ばすことができる。加えて垂直方向へ変化も考慮されるべきである。 41.4. トラックの内側を白線で区分する時は、曲走路には必ず直走路には必要があればコーンまたは旗を置く。コーンの高さは少なくとも 150mm とする。旗の大きさは 250mm x 200mm で、高さは少なくとも 450mm とし、フィールドに 60 度の角度に倒すように立てる。コーンまたは旗は、その底の縁がトラックに最も近い白線の端になるように設置する。その間隔が曲走路では 1m500、直走路で 10m を超えないように配置する。 注意:内側の縁石の使用を特に推奨する。 コメント：周回トラックは 200m を超える場合があるが、200m 以上の距離のレースの記録は公認されない。200m トラックのほうが、それより短い距離のトラックよりも有利である。トップレベルの競技会を開催するには、6 レーンあるほうが使い勝手がよい。周回トラックの理想的な幅は 1m である。 （縁石ではなく）コーンを置く場合、曲走路に沿ってだけでなく、周回全体に沿って配置する必要がある。旗またはコーンを置くときは、第 1 レーンの内側にある白線がそのレーンに含まれないということを考慮する必要がある（つまり白線の上に置くべき）。（縁石でなく）コーンの使用は、室内競技会では推奨される。 第 42 条 周回トラックのスタート及びフィニッシュ 42.1. 200mの傾斜した室内トラックの構造とマーキングに関する詳細は、WA 陸上競技施設マニュアルに記載されている。その中の基本的原則を以下に示す。	バンク 第 42 条 周回トラックのスタート及びフィニッシュ
---	---	---

Basic Requirements 2. The start and finish of a race shall be denoted by white lines 50mm wide, at right angles to the lane lines for straight parts of the track and along a radius line for curved parts of the track. 3. The requirements for the finish line are that, if at all possible there should be only one for all the different lengths of race; that it shall be on a straight part of the track and that as much of that straight as possible should be before the finish. 4. The essential requirement for all start lines, straight, staggered or curved, is that the distance for every athlete, when taking the shortest permitted route, shall be the same. 5. As far as possible, start lines (and take-over zone lines for relay races) should not be on the steepest part of the banking. Conduct of the Races 6. a) Races of up to, and including, 300m shall be run entirely in lanes. b) Races over 300m, and less than 800m shall start and continue in lanes until the breakline marked at the end of the second bend c) For the start of races of 800m, each athlete may be assigned a separate lane, or up to two athletes may be assigned per lane, or a group start, preferably commencing in lanes 1 and 4, may be used. In these cases, athletes may leave their lane, or those running in the outer group may join the inner group, only after the breakline marked at the end of the first bend, or if the race is run with two bends in lanes, end of the second bend. d) Races longer than 800m shall be run without lanes using an arced start line or group starts. If a group start is used, the breakline shall be at the end of either the first or second bend. If an athlete does not follow this Rule, they shall be disqualified. The breakline shall be an arced line marked after each bend, 50mm wide, across all lanes other than lane 1. To assist athletes identify the breakline, small cones or prisms, 5cm 50mm × 50mm and no more than 0.15m high, preferably of different colour from the breakline and the lane lines, shall be placed on the lane lines immediately before the intersection of the lane lines and the breakline. Note (i): In competitions other than the Paralympic Games and WPA Championships (see Part B - 3.1.2 (a) and (b)) the NPCs concerned may agree not to use lanes for the 800m event. Note (ii): On tracks with less than six lanes, a group start may be used to allow six athletes to compete. This doesn't apply for athletes in class 11 and class 12 if accompanied by a guide-runner.	基本条件 42.2. レースのスタートライン及びフィニッシュラインは、直走路ではレーンラインに直角に、また曲走路では半円上に、幅 50mm の白線で示す。 42.3. フィニッシュラインの設定条件は、距離の異なる種目であってもできる限り 1 カ所のみとし周回の直線部分におき、可能な限りフィニッシュ前の直線部分が長くなるようにする。 42.4. すべてのスタートライン（直線、階段式、弧形）の最も基本となる設定条件は競技者が許される中での最短距離を取った時に、誰にとっても距離が同じということである。 42.5. スタートライン（リレー競走のテイクオーバーゾーンを含む）は、できる限り、もっとも大きな斜度の場合所に設置しないようにする。 競走種目の実施 42.6. a) 300m までのレースは最後までレーンを走る。 b) 300m を超え 800m 未満の競走は、レーンを使用してスタートし、第 2 曲走路の終わりに引かれたブレイクラインまではそのレーンを走る。 c) 800m の競走のスタートは各競技者が各レーンに一人ずつ、またはレーンに最大二人を割り振って行うか、第 1 レーンと第 4 レーンを用いたグループスタートで行う。このような場合、各競技者が自分のレーンを離れたり、グループスタートの外側を走る競技者が内側のグループに合流したり出来るのは、第 1 曲走路の終わりのブレイクラインを過ぎた後とするが、もし 2 つの曲走路を自分のレーンで走るのであれば、第 2 曲走路終わりのブレイクラインを過ぎた後である。 d) 800m を超える競走は、レーンを用いず、円弧スタートまたはグループスタートによって行わなければならない。もしグループスタートを用いるなら、ブレイクラインは第 1 または第 2 曲走路の終わりに引かなければならない。もし競技者がこのルールに従わない場合は失格となる。ブレイクラインは、各曲走路が終わる地点に弧を描くように引かれた幅 50mm のラインで、第 1 レーンを除く全レーンにまたがるように引く。競技者がブレイクラインを認識しやすいように、各レーンラインとブレイクラインが交差するすぐ手前のレーンライン上に、50mm 四方で高さ 150mm 以下のコーンか角柱、その他適当な目印を置く。コーンや角柱の色はブレイクラインやレーンラインの色と異なるものにするのが望ましい。 注意(i)：パラリンピック競技大会及び WPA 競技会以外の競技会(PART-B 規則 3.1.2 (a)及び(b)参照)では、800mについては参加 NPC の合意によりレーンを使用しないで行うことができる。 注意(ii)：6 レーン未満のトラックでは、6 人での競走を可能とするためにグループスタートを用いてもよい。しかし競技クラス 11 と 12 でガイドランナーと一緒に走る場合には本条項は適用しない。	基本条件 競走種目の実施
--	---	--

Note (iii) For races running in lanes, athletes in Sport Classes 11 and 12, shall have two lanes available. Start Line and Finish Line for a Track of 200m Nominal Length 7. The start line in lane 1 should be on the principal straight. Its position shall be determined so that the most advanced staggered start line in the outside lane (400m races) should be in a position where the angle of banking should not be more than 12 degrees. The finish line for all races on the oval track shall be an extension of the start line in lane 1, right across the track and at right angles to the lane lines. COMMENT: Colours to use for marking the track are indicated on the Track Marking Plan included in the World Athletics Track and Field Facilities Manual. Rule 43: Seeding, Draws and Qualification in Track Event Rounds and Heats 1. In indoor competitions, the following tables shall, in the absence of extraordinary circumstances, be used to determine the number of rounds and the number of heats in each round to be held and the qualification procedure, i.e., those to advance by place (P) and time (T), for each round of Track Events: Note: The applicable regulations may specify, following consultation with the Technical Delegate(s) where appointed, how vacant positions due to withdrawals in semi-finals and finals may be filled by the next ranked athlete(s) following the previous round after those qualified. 60m <table><tr><th>Declared Entries</th><th>First Round Heats</th><th>First Round Place</th><th>First Round Time</th><th>Second Round Heats</th><th>Second Round Place</th><th>Second Round Time</th><th>Semi-Finals Heats</th></tr><tr><td>9-16</td><td>2</td><td>3</td><td>2</td><td></td><td></td><td></td><td></td></tr><tr><td>17-24</td><td>3</td><td>2</td><td>2</td><td></td><td></td><td></td><td></td></tr><tr><td>25-32</td><td>4</td><td>3</td><td>4</td><td></td><td>2</td><td>4</td><td></td></tr><tr><td>33-40</td><td>5</td><td>4</td><td>4</td><td></td><td>3</td><td>2</td><td>2</td></tr><tr><td>41-48</td><td>6</td><td>3</td><td>6</td><td></td><td>3</td><td>2</td><td>2</td></tr><tr><td>49-56</td><td>7</td><td>3</td><td>3</td><td></td><td>3</td><td>2</td><td>2</td></tr><tr><td>57-64</td><td>8</td><td>2</td><td>8</td><td></td><td>3</td><td>2</td><td>2</td></tr><tr><td>65-72</td><td>9</td><td>2</td><td>6</td><td></td><td>3</td><td>2</td><td>2</td></tr><tr><td>73-80</td><td>10</td><td>2</td><td>4</td><td></td><td>3</td><td>2</td><td>2</td></tr></table>	Declared Entries	First Round Heats	First Round Place	First Round Time	Second Round Heats	Second Round Place	Second Round Time	Semi-Finals Heats	9-16	2	3	2					17-24	3	2	2					25-32	4	3	4		2	4		33-40	5	4	4		3	2	2	41-48	6	3	6		3	2	2	49-56	7	3	3		3	2	2	57-64	8	2	8		3	2	2	65-72	9	2	6		3	2	2	73-80	10	2	4		3	2	2	注意(iii)：レーンを走る種目で、競技クラス 11 と 12 でガイドランナーと一緒に走る場合には、競技者に 2 レーンが与えられる。 200mトラックのスタートラインとフィニッシュライン 42.7. 第 1 レーンのスタートラインは原則として直線上におくものとする。そのスタートラインの位置は、もっとも外側のレーンのスタートライン（400m のレース）がバンク傾斜度 12 度以下の場所としたうえで確定する。 周回トラックにおけるすべてのレースのフィニッシュラインは、第 1 レーンに設けたスタートラインを延長し、各レーンラインに直角に引く。 コメント：トラックのマーキングに使用する色は、WA 陸上競技施設マニュアルに含まれるトラックマーキングプランに示される。 第 43 条 トラック競技におけるレーンの抽選予選 43.1. 室内競技会のラウンド数、各ラウンドにおける組数、各ラウンドの予選通過者の決め方は、特別な事情がない限り、次の表を使用する。トラック競技で次のラウンドへの進出は、順位(P)及び記録(T)と表示される。 注意：準決勝および決勝において棄権により空いたレーンについて、前ラウンドで当該ラウンドに進出する資格を獲得した競技者の次にランク付けされた者で補充することを、適用する規則で定めることができる。	200mトラックのスタートラインとフィニッシュライン 第 43 条 トラック競技におけるレーンの抽選予選
Declared Entries	First Round Heats	First Round Place	First Round Time	Second Round Heats	Second Round Place	Second Round Time	Semi-Finals Heats																																																																											
9-16	2	3	2																																																																															
17-24	3	2	2																																																																															
25-32	4	3	4		2	4																																																																												
33-40	5	4	4		3	2	2																																																																											
41-48	6	3	6		3	2	2																																																																											
49-56	7	3	3		3	2	2																																																																											
57-64	8	2	8		3	2	2																																																																											
65-72	9	2	6		3	2	2																																																																											
73-80	10	2	4		3	2	2																																																																											

200m, 400m, 800m, 4x200m, 4x400m

Declared	First Round			Second Round			Semi-Finals		
Entries	Heats	Place	Time	Heats	Place	Time	Heats	Place	Time
7-12	2	2	2						
13-18	3	3	3				2	3	
19-24	4	2	4				2	3	
25-30	5	2	2				2	3	
31-36	6	2	6				3	2	
37-42	7	2	4				3	2	
43-48	8	2	2				3	2	
49-54	9	2	6	4	3		2	3	
55-60	10	2	4	4	3		2	3	

1500m

Declared	First Round			Second Round			Semi-Finals		
Entries	Heats	Place	Time	Heats	Place	Time	Heats	Place	Time
12-18	2	3	3						
19-27	3	2	3						
28-36	4	2	1						
37-45	5	3	3				2	3	3
46-54	6	2	6				2	3	3
55-63	7	2	4				2	3	3

The following alternative tables shall be used for the specific class or class combination as denoted in the respective table. For class combination not entirely covered by the below tables, the above regular tables shall normally be applied, otherwise an appropriate table shall be determined by the Technical Delegate.

60m (T11-12) – 8 Lanes

Declared	First Round			Second Round			Semi-Finals		
Entries	Heats	Place	Time	Heats	Place	Time	Heats	Place	Time
5-8	2	1	2						
9-12	3	1	1						
13-16	4	1	4				2	1	2
17-20	5	1	7				3	1	1
21-24	6	1	6				3	1	1
25-28	7	1	5				3	1	1
29-32	8	1	8	4	1	4	2	1	2

200m, 400m, 800m (T11-12) – 6 Lanes

Declared	First Round			Second Round			Semi-Finals		
Entries	Heats	Place	Time	Heats	Place	Time	Heats	Place	Time
4-6	2	1	1						
7-9	3	1	0						
10-12	4	1	2				2	1	2
13-15	5	1	1				2	1	2
16-18	6	1	0				2	1	2

1500m (T11-12) – 6 Lanes

Declared	First Round			Second Round			Semi-Finals		
Entries	Heats	Place	Time	Heats	Place	Time	Heats	Place	Time
6-10	2	1	3						
11-15	3	1	2						
16-20	4	1	6				2	1	3

Note: The above qualifying procedures are only valid for 6 lanes oval tracks and/or 8 lanes straight tracks.

COMMENT: For an outdoor competition with a track having only 6 lanes this rule could be used for seeding and progressions.

次の代替表は、それぞれの表に示されている特定のクラスまたはクラスの組み合わせに使用される。以下の表で完全にカバーされていないクラスの組み合わせについては、通常、上記の通常の表が適用される。それ以外の場合、適切な表は技術代表によって決定される。

注意：上記の予選通過者の決め方は、6レーンの楕円トラック及び／または 8レーンのストレートトラックのみ有効である。

コメント：6レーンしかないトラックを持つ屋外競技会では、このルールはシードと予選通過条件に使用することができる。

Draw for Lanes 2. For all events run wholly or partly in lanes around a bend, where there are successive rounds of a race, three draws for lanes will be made: a) One for the two highest ranked athletes or teams to determine placings in the outer two lanes; b) Another for the third and fourth ranked athletes or teams to determine placings in the next two lanes; c) Another for the other athletes or teams to determine placings in any remaining inner lanes; d) The ranking referred to shall be determined as follows: e) For the first round, from the relevant list of valid performances achieved during the predetermined period; f) After the first round, in accordance with the procedures identified in Rule 21.3 (a) or in the case of 800m, Rule 21.3 (b). 3. For all other races, the lane order shall be drawn in accordance with Rules 21.4 and 21.5. COMMENT: Where tracks have a different configuration of lanes, then the tables to be used should be adapted either in the specific Technical Regulations for the competition or if not by the Technical Delegate(s) or the LOC Rule 44: Spike Length When a competition is conducted on a synthetic surface, that part of each spike which projects from the sole or the heel shall not exceed 6mm (or as required by the LOC) subject always to the maxima provided in Rule 6.4. Rule 45: Relay Races Conduct of the Races 1. In the 4x200m relay race all the first leg and the first bend of the second leg up to the nearer edge of the breakline described in Rule 42.6 shall be run in lanes. Each takeover zone shall be 20m long and the second, third and fourth athletes shall start within this zone. 2. The 4x400m relay race shall be run according to Rule 42.6 (b). 3. The 4x800m relay race shall be run according to Rule 42.6 (c). 4. In relay races where athletes are permitted to leave their respective lanes on entering the straight after running two or three bends in lanes, the layout for the echelon start is described in Rule 42. 5. The waiting athletes in the third and fourth legs of the 4x200m relay race, in the second, third and fourth legs of the 4x400m and the 4x800m relay race shall, under the direction of a	レーンの抽選 43.2. 一つの曲走路を全面的にあるいは部分的にレーンを用いる全ての種目で複数のラウンドが行われる場合、次の3つのレーン分けが行われる。 a) ランキングの上位2人の競技者または2チームが一番外側の2レーン。 b) 3番目と4番目のランクの競技者またはチームが次の2レーン。 c) 残りの競技者またはチームが内側に残ったレーン。 d) ここで使われるランキングは次のように決定される。 e) 予選ラウンドの場合、決められた期間中に達成した自己記録のリストを利用する。 f) 最初のラウンド後は、規則 21.3(a)の手続きで、800m 競走では規則 21.3(b)の手続きにより行う。 43.3. その他の種目の場合、レーン順は規則 21.4 及び 21.5 に従って決定をする。 コメント：トラックのレーン構成が異なる場合、使用するテーブルは、競技会の特定の技術規定に適合するか、技術代表または主催者によって適合される必要がある。 第44条 スパイクの長さ 競技場が合成物質で覆われている場合は、競技用靴の靴底または踵の各スパイクの長さは 6mm（あるいは競技会の主催者が要求した長さ）を超えてはならず、規則 6.4 に定める寸法の上限に従う。 第45条 リレー競走 リレー競走の実施 45.1. 4x200m リレーの場合、すべての第1走者と第2走者の第1曲走路において規則 42.6 に述べたブレイクラインの手前までは、各自のレーンを走る。第2、第3、第4走者は、テイクオーバーゾーンは20mであり、ゾーンの中からスタートしなければならない。 45.2. 4x400mリレーの場合、規則 42.6(b)に従う。 45.3. 4x800mリレーの場合、規則 42.6(c)に従う。 45.4. リレーにおいて、競技者がレーン内で2つまたは3つの曲走路を走った後、ストレートに入った時点で各レーンを離れることが許されている場合、階段状スタートのレイアウトは、規則 42 に記載されている。 45.5. 4x200mリレーの第3・第4走者、4x400mリレー及び4x800mリレーの第2・第3・第4走者として待機している競技者は、担当役員の指示のもと、各自のチームが直近の曲走路に進出したのと同	レーンの抽選 第44条 スパイクの長さ 第45条 リレー競走 リレー競走の実施
---	--	---

designated official, place themselves in their waiting position in the same order (inside to out) as the order of their respective team members as they enter the last bend. Once the incoming athletes have passed this point, the waiting athletes shall maintain their order, and shall not exchange positions at the beginning of the take-over zone. If an athlete does not follow this Rule, their team shall be disqualified. Note: Owing to the narrow lanes, indoor relay races are much more liable to collisions and unintended obstruction than outdoor relay races. It is, therefore, recommended that, when possible, a spare lane should be left between each team. Rule 46: High Jump Runway and Take-Off Area 1. If portable mats are used, all references in the Rules to the level of the take-off area must be constructed as referring to the level of the top surface of the mat. 2. An athlete may start their approach on the banking of the oval track provided that the last 15m of their run up is on a runway complying with Rules 26.3, Rule 26.4 and Rule 26.5. Rule 47: Horizontal Jumps Runway An athlete may start their approach on the banking of the oval track provided that the last 40m of their run up is on a runway complying with Rules 27.1 and Rule 27.2. Rule 48: Shot Put Landing Sector 1. The landing sector shall consist of some suitable material on which the shot will make an imprint, but which will minimise any bounce. 2. The landing sector shall be enclosed at the far end and on the two sides, as close to the circle as may be necessary for safety of the other athletes and officials, by a stop barrier and protective netting of approximately 4m height which should stop a shot whether in flight or bouncing from the landing surface. 3. In view of the limited space inside an indoor field of play, the area enclosed by the stop barrier may not be large enough to include a full 34.92° sector. The following conditions shall apply to any such restriction: a) The stop barrier at the far end shall be at least 0.50m beyond the current World Record in Shot Put for men or women; b) The sector lines on either side shall be symmetrical about the centre line of the 34.92° sector; c) The sector lines may either run radially from the centre of the Shot Put circle at an angle of 34.92° until the sector has a width of at least 9m. From there on they run parallel to the centre	じ順番で（内側から外側へ）待機する。接近する競技者がこの地点を通過したならば、待機順を維持しなければならず、テイクオーバーゾーンの起点において待機順を交換してはいけない。この規則に従わなければ、当該チームは失格とする。 注意：室内のリレー競走は、狭いレーンのために、屋外のリレー競走よりも衝突や非意図的妨害が非常に生じやすい。それゆえ、可能ならば空きのレーンが各チームの間にあることが望ましい。 第 46 条 走高跳 助走路及び踏切場所 46.1. 移動式の助走用マットを使用する場合は、踏切場所の水平に関する規則の内容はマットの上部表面をして水平かどうか解釈する。 46.2. 助走路の最後の 15m が規則 26.3、26.4 及び 26.5 に適合していれば、競技者は周回トラックのバンクから助走を開始してもよい。 第 47 条 長さの跳躍 助走路 助走路の最後の 40m が規則 27.1 及び 27.2 に適合していれば、競技者は周回トラックのバンクから助走を開始してもよい。 第 48 条 砲丸投 着地場所 48.1. 着地場所は、砲丸の痕跡がつき、一方でそのはずみが最小となるような材質とする。 48.2. 観客、競技役員、競技者の安全を確保するために、必要に応じてサークルの直近から、着地区域の遠位端と両側は防止柵あるいは防護ネットで囲われていなければならない。飛来する砲丸や着地場所でバウンドした砲丸を止めるために十分なネットの最低高は 4m であるべきである。 48.3. 室内競技場の限られた空間を考慮して、防止柵によって囲まれた場所は 34.92 度の扇形全部を含む広さでなくてもよい。次の条件はそのような制限に適用する。 a) サークルから投げる方向の側の防止柵は、男女の世界記録より 500mm 離れていればよい。 b) 両側の扇形ラインは、34.92 度の扇形の中心線と左右対称にする。 c) 砲丸投げのサークルの扇型ラインはサークル中心から 34.92°の角度で放射状に、着地場所の幅が少なくとも 9 m になるまで引く。そこからは着地場所の中心線と並行になるようにひく。	第 46 条 走高跳 第 47 条 長さの跳躍 助走路 第 48 条 砲丸投 着地場所
---	---	---

line of the landing sector.

COMMENT: It is recommended that the stop barrier / protective netting on either side should be extended towards the circle so that it starts within 8m of it and that for the length of these extensions, the height of the netting should be at least 5m.

4. For Seated Throw Shot Put Events, a stop board is not necessary. For these classes, the use of a movable platform at a suitable place in the indoor area is allowed.

Construction of the Shot

5. Depending on the type of landing area (see Rule 48.1), the shot shall be either solid metal or metal cased or, alternatively, soft plastic or rubber casing with a suitable filling. Both types of shot may not be used in the same competition.

6. These shall comply with Rule 31.4 and Rule 31.5, for the Shot Put outdoors.

Plastic or Rubber Cased Shot

7. The shot shall have a soft plastic or rubber case with a suitable filling such that no damage shall be caused when landing on a normal sports hall floor. It shall be spherical in shape and its surface finish shall be smooth.

Information for manufacturers: to be smooth, the surface average height must be less than or equal to 1.6µm, i.e., a roughness number N7 or less.

8. The shot shall conform to the following specifications:

Shot						
Minimum weight for admission to competition and acceptance of a						
Record	2.000kg	3.000kg	4.000kg	5.000kg	6.000kg	7.260kg
Information for manufacturers						
Range for supply of implement for competition	2.005kg	3.005kg	4.005kg	5.005kg	6.005kg	7.265kg
	2.025kg	3.025kg	4.025kg	5.025kg	6.025kg	7.285kg
Minimum Diameter	80mm	85mm	95mm	100mm	105mm	110mm
Maximum Diameter	110mm	120mm	130mm	135mm	140mm	145mm

SECTION VI - ROAD RACES

Rule 49: Road Races

Preamble

In the case of mass participation events held outside the stadium, these rules should normally only be applied in full to those athletes, if any, who are designated as taking part in the elite or other defined section of the races such as age group categories for which there are placings for awards or prizes. Race organisers should outline in the information provided to other athletes which other rules will apply to their participation, particularly those pertaining to their safety.

Distances

1. The standard distances for men and women

コメント：両側の停止障壁/保護ネットは、サークルから 8m 以内に始まるようにサークルに向かって延長し、これらの延長の長さについては、ネットの高さを少なくとも 5m にすることが推奨されている。

48.4. 座位砲丸投競技の場合は、ストップボードは必要ない。これらのクラスでは、屋内の適当な場所に可動式の台を使用することを認める。

砲丸の構造

48.5. 着地場所（規則 48.1 参照）の構造によって、砲丸は硬い金属か、金属をかぶせたもの、あるいは適切な詰め物をした軟らかいプラスチックまたはラバーで覆ったものとする。両タイプの砲丸を同一の競技会で使用することは認められない。

48.6. これらの砲丸は、屋外の砲丸投に関する規則 31.4、31.5 の仕様と同一とする。

プラスチックまたはラバーで覆った砲丸

48.7. 砲丸は、通常のスポーツホールの床に着地しても破損しないように、軟質のプラスチックまたはゴム製のケースに適当な充填物を入れたものでなければならない。形状は球形で、表面の仕上げは滑らかでなければならない。

製造者向け情報：平滑であるためには、表面の平均高さが 1.6µm 以下、すなわち粗さ番号 N7 以下であること。砲丸は以下の仕様に適合するものとする。

48.8. 砲丸は以下の規格による。

第6部 道路競走

第49条 道路競走

前文


競技場の外で行われる大量参加型競技の場合、これらの規則は、通常、エリートまたはその他の定義されたセクションのレースに参加すると指定されている競技者、例えば、賞や賞金のための順位が設定されている年齢別カテゴリーなどに参加する競技者にのみ、完全に適用されるべきである。レース組織委員会(LOC)は、他の競技者に提供される情報の中で、他のルールが競技者の参加に適用されるもの、特に競技者の安全に関するものを概説しなければならない。

距離

49.1. 男女の標準となる距離は 10km、ハーフマラ

shall be 10km, Half-Marathon, Marathon (42.195km). Course 2. The races shall be conducted on made-up roads. However, when traffic or similar circumstances make it unsuitable, the course, duly marked, may be on a bicycle path or footpath alongside the road, but not on soft ground such as grass verges or the like. The start and finish may be within an athletic field of play. Note (i): It is recommended that, for road races staged over standard distances, the start and finish points, measured along a theoretical straight line between them should not be further apart than 50% of the race distance. Note (ii): It is acceptable for the start, finish and other segments of the race, except for the wheelchair events, to be conducted on grass or other non-paved surfaces. These segments shall be kept to a minimum. 3. The course shall be measured along the shortest possible route that an athlete could follow within the section of the road permitted for use in the race. In all the Paralympic Games and WPA Championships (see Part B - 3.1.2 (a) and (b)) the measurement line should be marked along the course in a distinctive colour that cannot be mistaken for other markings. The length of the course shall not be less than the official distance for the event. At the Paralympic Games and WPA Championships (see Part B - 3.1.2 (a) and (b)), the uncertainty in the measurement shall not exceed 0.1% (i.e., 42m for the Marathon) and the length of the course should have been certified in advance by a World Athletics approved course measurer. Note (i): For measurement, the "Calibrated Bicycle Method" shall be used. Note (ii): To prevent a course from being found to be shorter than the official race distance on future re-measurement, it is recommended that a "short course prevention factor" be built in when laying out the course. For bicycle measurements this factor should be 0.1% which means that each km on the course will have a "measured length" of 1001m. Note (iii): If it is intended that parts of the course on race day will be defined by the use of non-permanent equipment such as cones, barricades, etc. their positioning shall be decided not later than the time of the measurement and the documentation of such decisions shall be included in the measurement report. Note (iv): It is recommended that for Road Races staged over standard distances, the overall decrease in elevation between the start and finish should not exceed 1:1000, i.e., 1m per km (0.1%).	ソン及びマラソン (42.195km) とする。 コース 49.2. 道路競走は公認長距離競走路を走る。交通量やそれと同じような事情で不適当な時は、走路を正しく表示して外側に沿う自転車道や歩道を走ってもよいが、芝生地やそれに類する柔らかい土ではない。スタートとフィニッシュ地点は競技場内に置くことができる。 注意(i)：標準距離の道路競走においては、スタートとフィニッシュの 2 点間の直線の距離は、そのレースの全距離の 50%以下とする。 注意(ii)1：レースのスタート、フィニッシュ、その他のいかなる区間も、芝その他の未舗装路で行うことができる。ただし、こうした区間は最小限にとどめる。 49.3. コースは競技者の使用が許される道路として区分されている場所の最短距離を測定する。パラリンピック競技大会及び WPA 競技会(PART-B 規則 3.1.2(a)及び(b)参照)においては、測定線を他のマーキングと間違えないように特有の色でコースに沿ってマークされているべきである。コースの長さは種目の公式距離より短くしてはいけない。パラリンピック競技大会及び WPA 競技会(PART-B 規則 3.1.2(a)及び(b)参照)における測定誤差許容範囲は、全長の 0.1% (すなわち、マラソンは 42m) より長くなってはならず、コースの長さは、WA 公認コース計測員によって事前に確認されているべきである。 注意(i)：測定は「自転車の回転測定器」によって行わなければならない。 注意(ii)：後日再計測した際にコースの公式距離より短かったということのないようにするため「コース短小防止ファクター」をとり入れて測定することが望ましい。自転車による計測の場合、このファクターは 0.1%とし、各 1km の計測を 1001m として測定する。 注意(iii)：レース当日にコースの一部をセーフティコーンやバリケードなどによって区分する場合、それらの設置場所については、測定が行われる時期までに決定し、その決定を書面にして、測定報告書に記載しなければならない。 注意(iv)：標準距離の道路競走においては、スタートとフィニッシュ地点の 2 点間の標高の減少は全体として 1000 分の 1km を超えないことが望ましい (すなわち 1km あたり 1m (0.1%))。	コース
---	--	------------

Note (v): A course measurement certificate is valid for five years, after which the course shall be re-measured even when there are no obvious changes to it. 4. The distance in kilometres on the route shall be displayed to all athletes. The distance in miles may also be displayed in addition to the distance in kilometres. Where wheelchair athletes are competing in a race, the maximum height of the intermediate distance signs shall not exceed 1 metre. Start 5. The races shall be started by the firing of a gun, cannon, air horn or like device. The commands and procedure for races longer than 400m shall be used. In races which include a large number of athletes, five-minute, three-minute and one-minute warnings before the start of the race should be given. On the command "On your marks", the athletes shall assemble on the start line in the manner determined by the LOC. The Starter shall ensure that no athlete has their foot (or any part of their body) or the front wheel (classes T33-34 and T51-54) touching the start line or the ground in front of it, and shall then start the race. COMMENT: As for middle and long distance Track Events, it is emphasised for events held outside the stadium that Starters and Referees should avoid being over-zealous in the application of the false start Rules to such events. Recalling starts in road races and other outside events can be difficult, and in large fields impractical, in any case. However, where there is a clear and wilful breach, the Referee should not hesitate to consider appropriate action in respect of an individual either during or after the race. However, in major events, where the start mechanism malfunctions, and it is clear or possible that the timing system may not have started a recall where practical might be the best option. Note (i): In Road races, ambulant athletes may start together, but will be ranked by the finishing time according to the eligible sport class(es) of each event. Note (ii): In Road races, wheelchair athletes will start according to the decision of the Technical Delegate for the event but will be ranked by the finishing time according to the eligible sport class(es) of each event. Note (iii): Seeding for Wheelchair Road Races should be by Sports Class, Seed Time and Gender (i.e., T54/34 Males should be seeded in the front row/s, then T54/34 Females, then T52/33/51 Males and then the T52/33/51 Females). The start of each Sports Class event/division should be separated by intervals of a minimum 30 seconds. Note (iv): The seeding grid for each Sports Class event/division should position the #1 seeded	注意(v) : コースの測定証明書は 5 年間有効で、その後はコースに変更がなくても再計測しなければならない。 49.4. 走路の途中距離は、kmで競技者に表示しなければならない。マイル表示は、km表示とともに表示することができる。車いすの競技者が競技会に参加している場合は、距離表示板の高さは 1m を超えてはならない。 スタート 49.5. レースは信号器、大砲・エアホーン、その他類似の機器の発射で開始する。その合図は 400m を超える競走で用いる方法で行う。参加者の多いレースでは、スタート 5 分前、3 分前、1 分前の合図をすべきである。「位置について (On your marks)」の合図で、競技者は組織委員会(LOC)が定めた方法でスタートラインに集合しなければならない。スターターは競技者の足や体の一部または前輪 (クラス T33-34、T51-54) がスタートラインやその前の地面に触れていないことを確認したうえで、レースをスタートさせなければならない。 コメント : 中・長距離のトラック種目同様に、競技場外種目でも、スターター及び審判長は、スタート規則の不正スタートの適用にあたり、過剰にならう強調される。道路競走やその他の競技場外種目で、スタートの呼び戻しは困難であり、どんな場合でも大規模な参加者に対しては実用的ではない。しかし、明確かつ故意の違反がある場合、審判長は、レース中またはレース後に個人に関する適切な措置を検討することを躊躇してはならない。しかし、主要競技会で、スタート・メカニズムが誤動作し、タイミングシステムがスタートしなかった場合、呼び戻しが最良の選択肢となる可能性もある。 注意(i) : 道路競技では、立位競技者は一緒にスタートをきることができるが、着順は各種目の競技クラス毎の記録に従い決定する。 注意(ii) : 道路競技では、車いす競技者は技術代表がその種目で決定した方法に従いスタートするが、着順は各種目の競技クラス毎の記録に従い決定する。 注意(iii) : 車椅子道路競技のシードは競技クラス、シードタイム、性別によるものとする(すなわち、T54/34 の男性は最前列、T54/34 の女性、T52/33/51 の男性、T52/33/51 の女性の順にシードされるべきである)。各競技クラスの種目・区分のスタートは最低でも 30 秒の間隔をあけるものとする。 注意(iv) : 各競技クラスの競技会/区分のシード・グリッドは、1 番目のシード競技者をグリッドの最前列の	スタート
--	--	-------------

athlete at the centre position in the front row of the grid with #2 and #3 placed on their immediate right and left respectively, and #5 and #4 on their outside right and left respectively and so on (See Figure 25). Note (v): In the case of events starting outside the stadium, the start line may be up to 0.3m in width and made of any colour contrasting distinctively with the surface of the start area. COMMENT: For the Paralympic Games and WPA Championships and WPA Sanctioned Competitions (3.12 (a) – (c)), at least, the basis of seeding should be by the best valid time achieved by each athlete during the pre-determined period. This period will be specified in the Technical Regulations or in the document setting out the entry conditions and standards for the competition. Where there is no such specification, then the Technical Delegate(s) together with the LOC should decide the basis on which the seeding will be determined. For World Para Athletics Approved Competitions (3.1.2 (d)) the seeding and seeding grid shall be agreed between the Technical Delegate (if appointed) and the LOC.  Figure 25 – Example of Seeding Grid for Wheelchair Road Races COMMENT: Establishing the starting positions is not as important tactically for a half-marathon or marathon, or any mass road race in reality, however it is important to the athletes that proper recognition be given. The above is an example only, but the importance of the first two rows is paramount. The Finish 6. In the case of events finishing outside the stadium: a) the finish line may be up to 0.30m in width and may be of any colour contrasting distinctively with the surface of the finish area. The race organisers must ensure that the entire finish line is clearly defined, so that there can be no confusion as to when the athlete has reached the finish line. b) In races for athletes in Sports Classes T11 and T12 competing with a guide-runner the athlete must cross the finish line in front of the guide-runner or the athlete will be disqualified.	中央に置き、2 番目と 3 番目を 1 番目のすぐ右と左に、5 番目と 4 番目を 2 番目、3 番目それぞれの外側の右と左に配置する。(図 2 5 参照) 注意(v)：競技場外でスタートする種目の場合、スタートラインの幅は 0.3m までで、その色はスタートエリアの道路面とはっきり区別できる色ならば何でもよい。 コメント パラリンピック競技大会と WPA 競技会及び WPA 認定競技会(3.12(a) -(c))では、少なくとも事前に決められた期間において競技者が達成した最高有効記録を元にシーディングを行うべきである。この期間は、競技会規則やエントリー条件や基準を定めた文書に明記されるものとする。このような定められたものがない場合、技術代表と組織委員会が協議の上、シード方法を決定する。WPA 承認競技会(3.1.2(d))で、(任命されている場合)技術代表と主催者がシード方法に合意されなければならない。 コメント：ハーフマラソンやマラソン、実際にはどんなマースロードレースでも、スタート位置を決めることは戦術的にはそれほど重要ではないが、競技者にとっては適切な認識が与えられることが重要である。上記は一例であるが、最初の 2 列の重要性が最も重要である。 フィニッシュ 49.6. 競技場外でフィニッシュする競技では、 a) フィニッシュラインの幅は最大 0.3m で、その色はフィニッシュエリアの道路面とはっきり区別できる色ならば何でもよい。レース主催者は、競技者がフィニッシュラインに到着したタイミングについて混乱が生じないようにフィニッシュライン全体が明確に明示されていることを確認しなければならない。 b) 競技クラス T11、T12 の競技者がガイドランナーと競うレースでは、競技者はガイドランナーの前でフィニッシュラインを通過しなければならない、そうでない場合は失格となる。	フィニッシュ
--	---	---------------

Safety 7. The LOC of Road Races shall ensure the safety of athletes and officials. At the Paralympic Games and WPA Championships (see Part B - 3.1.2 (a) and (b)), the LOC shall ensure that the roads used for the competition are closed to motorised traffic in all directions; Drinking / Sponging and Refreshment Stations 8. Except for wheelchair events: a) Water and other suitable refreshments shall be available at the start and finish of all races; b) For all events, water shall be available at suitable intervals of approximately 5km. For events longer than 10km, refreshments other than water may be made available at these points; Note (i): Where conditions warrant, taking into account the nature of the event, the weather conditions and the state of fitness of the majority of the competitors, water and/or refreshments may be placed at more regular intervals along the route. Note (ii): Mist stations may also be arranged, when considered appropriate under certain organisational and/or climatic conditions. COMMENT: If mist stations are in place, they shall not span over the entire width of the course. This is to allow for some athletes to run or wheel without getting wet. It is very important to note that many wheelchair racers typically do not like mist stations because push rims and gloves might get wet and therefore hamper propulsion. c) Refreshments may include drinks, energy supplements, foodstuffs or any other item other than water. The LOC will determine which refreshments it will provide based on prevailing conditions; d) Refreshments will normally be provided by the LOC, but it may permit athletes (and their guide-runners) to provide their own refreshments, in which case the athlete shall nominate at which stations they shall be made available to the athlete. Refreshments provided by the athletes (and their guide-runners) shall be kept under the supervision of officials designated by the LOC from the time that the refreshments are lodged by the athletes or their representatives. Those officials shall ensure that the refreshments are not altered or tampered with in any way; e) The LOC shall delineate, by barriers, tables or markings on the ground, the area from which refreshments can be received or collected. It should not be directly in the line of the measured route. Refreshments shall be placed so that they are easily accessible to, or may be put by authorised persons into the hands of, the athletes (and/or their guide-runner). Such persons shall	安全 49.7. 道路競走の組織委員会(LOC)は、競技者及び競技役員の安全を確保しなければならない。パラリンピック競技大会及び WPA 競技会(PART-B 規則 3.1.2 (a) 及び (b)参照)に該当する競技会では、LOC は道路を全面車両通行止にして、自動車の通行を遮断しなければならない。 水・スポンジ及び飲食物供給所 49.8. 車いす種目を除き a) 水その他の飲食物はスタートとフィニッシュ地点に用意しなければならない。 b) 全ての種目において、約 5 km間隔で給水所を設けるものとする。10 kmを超える種目の場合、水以外の飲食物も給水所で提供することができる。 注意(i)：種目の特性、気象条件、大多数の競技者の健康状況を踏まえ必要性が認められる場合、競技ルート沿いに一定間隔でより多くの水・飲食物供給所を設けることができる。 注意(ii)：気象状況によっては体勢が整えられる場合に、ミストステーションも用意して良い。 コメント：ミストステーションを設置する場合、濡れずに走りたい競技者もいるため、コースの幅全体を覆わないようにする。多くの車いす競技者は、ハンドリムやグローブが濡れることで推進力を妨げることを防ぐために、ミストステーションで濡れることを好まないことに注意が必要である。 c) 飲食物には、飲料、エネルギーサプリメント、食品、その他の水以外のものを含めることができる。組織委員会(LOC)は、状況に基づいてどの飲食物を提供するかを決定する。 d) 飲食物は通常、組織委員会(LOC)が提供するが、組織委員会(LOC)は競技者が自分で飲食物を用意することを認めることができる。その場合、競技者は、どの供給所で自分の用意した飲食物を受け取るか指定しなければならない。競技者が用意した飲食物は、その競技者または代理人によって預けられた時から組織委員会(LOC)によって任命された役員監視の下で管理しなければならない。これらの役員は、預けられた飲食物が取り替えられたり、何らかの異物が混入されたりすることのないよう管理しなければならない。 e) 組織委員会(LOC)は、柵やテーブルを置いて、または地面に印をつけることによって、飲食物を受け取れる区域を示さなければならない。その区域はコースの計測線に直接かかるべきではない。飲食物は、競技者が手に取りやすい場所、あるいは、許可された者が競技者に簡単に手渡せる場所に置くものとする。競技者に手渡す者は所定の区域内にとどまるものとし、コースに入ったり、競技者を妨害したりしてはならない。	安全 水・スポンジ及び飲食物供給所
---	---	--

remain inside the designated area and not enter the course nor obstruct any athlete. No officials shall, under any circumstances, move beside an athlete while they are taking refreshment or water; f) In the Paralympic Games and WPA Championships (see Part B - 3.1.2 (a) and (b)), a maximum of two officials per Country may be stationed behind the area designated for their country at any one time; Note: For an event in which a Country may be represented by more than three athletes, the Technical Regulations may allow additional officials at the refreshment tables. COMMENT: The revisions to Rule 49 adopted in 2011 included a harmonisation of the provisions within the rules pertaining to outside events, where this was logical and in accordance with practice. As a result, specific provision was made for the first time in this rule to cover team officials and refreshment tables. g) An athlete and/or guide-runner may carry water, refreshments or sponges by hand or attached to their body provided such items are (i) carried from the start of the race; or(ii) collected from an official station during the race. Such items may be exchanged between an athlete and their guide-runner (or vice versa) at any time during the race. In addition, such items may be provided to athletes and/or guide runners for medical reasons, either from an official medical staff member appointed by WPA and/or LOC or at the direction of race officials. h) The carrying, collection or exchanging of water, refreshments or sponges during the race other than as permitted above in Rule 49.8(g) is prohibited. An athlete and/or guide runner who breaches this Rule shall, for a first such offence, be warned by the Referee, normally by showing a yellow card. For a second offence, the Referee shall disqualify the athlete and/or guide runner, normally by showing a red card. Wheelchair athletes (Sport Classes T33-34, T51-54) may carry their own refreshments. Note: The LOC must ensure that officials are aware of the specific problems of safety presented in providing drinks to athletes with vision impairment (Classes T11-13) or upper limb impairment (Classes T45-46), and that adequate training is given to all assistants involved. Race Conduct 9. In Road Races, an athlete may leave the marked course with the permission and under the supervision of an official, provided that by going off course they do not lessen the distance to be covered. 10.If the Referee is satisfied on the report of a Judge or Umpire or otherwise that an athlete has left the marked course thereby shortening the	いかなる状況にあっても、飲食物や水を摂る際、競技役員や承認された者であっても競技者と並んで移動してはならない。 f) パラリンピック競技大会及び WPA 競技会 (PART-B 規則 3.1.2(a)及び(b)参照)においては、各国（チーム）最大 2 名の役員が所定区域で同時に待機できる。 注意：一つの国から 4 人以上の競技者が参加する種目では、技術要件で、その各国（チーム）の飲食物供給所に役員を追加することを認めてもよい。 コメント：2011 年に採択された規則 49 の改正には、論理的で実務に沿った場外競技に関する規則内の規定の調和が含まれていた。その結果、この規則では初めてチーム役員とリフレッシュメントテーブルを対象とした具体的な規定が設けられた。 g) 競技者および/またはガイドランナーは水、飲食物またはスポンジ例えば、(i)レースのスタートから持っているものまたは、(ii)レース中に公式供給所で受け取ったものを手に持ったり身体につけたりしてもよい。それらの物をレース中に競技者とそのガイドランナー（またはその逆）の間でいつでも交換できる。さらにそのような物は、大会役員や WPA 又は/及び LOC が任命した公式の医療スタッフの指示により競技者およびガイドランナーに医療的理由で提供される事もある。 h)規則 49.8(g)で許可されている場合を除き、レース中に水、飲食物、スポンジを持ち運んだり、受け取ったり、交換したりすることは禁止されている。この規則に違反した競技者および/またはガイドランナーに対して審判長は、それが 1 回目の違反であれば警告とし、通常はイエローカードの提示によりこれを知らせる。2 回目の違反があった競技者又は/及びガイドランナーは失格させる。通常レッドカードを提示する。 車いすの競技者（競技クラス T33-34、T51-54）は、リフレッシュメントを持参してもよい。 注意：組織委員会(LOC) は、視覚障害のある競技者（クラス T11～13）や上肢障害のある競技者（クラス T45～46）に飲み物を提供する際に、安全上の問題があることを役員が認識していることを確認し、関係するすべての補助員等に適切なトレーニングが行われていることを確認しなければならない。 レース管理 49.9. 道路競走で競技者は競技役員の許可を得て、かつその監督下にある場合は、コースを離れたことにより走行距離が短くならないことを条件に示されたコースを離れることができる。 49.10. 審判長が監察員や他の審判員、またはそれ以外の大会関係者の報告により競技者がコースをはずれ距離を短くしたと判定した場合、競技者は失	レース管理
--	--	--------------

distance to be covered, they shall be disqualified. COMMENT: The finish area shall be wide enough to enable several runners to sprint side by side and long enough to separate them at the finish. Unless a Transponder Timing System is being used together with a backup system (such as a video recording) to check finishing orders, finish lanes ("funnels") should be set up some 8 to 10 metres after the finish line with a maximum width of 0.70-0.80m. Once in the funnels, the athletes must not be able to overtake one another. The funnels should be 35-40m long into which the athletes will be directed as they cross the finish line. At the end of each funnel, officials will note the athletes' numbers/names and if applicable recover their transponder timing chips. The funnels should have moveable ropes at the end at which the athletes enter, so that when one lane is full, the next rope can be drawn across behind the last athlete, to enable the next finisher to enter the new finish lane, and so on. Judges and Timekeepers will additionally be placed on either side of the finish line and it is recommended that, in order to follow up any appeal relative to the finishing order, an official with video recording equipment (if possible with a timing clock in sight) shall be assigned and placed a few metres after the finish line in order to record the order in which the athletes cross the line. Where a Road Race finishes on a running track the provisions of Rule 18.5 (Lane Infringement) do not apply and, in the event that an athlete steps inside the track at the end of a Road Race the Referee shall apply this Rule 49.10 in determining whether an athlete has left the marked course thereby shortening the distance to be covered having regard to all the circumstances. 11. Umpires should be placed at regular intervals and at each key point. Other umpires should move along the course during the race. COMMENT: It is acknowledged that following the practice of first giving a warning when applying relevant aspects of Rule 49 and where applicable Rule 7.2 and Rule 7.3 will create difficulties in implementation but where the opportunity arises, the Referee should do so. It is suggested that one option might be that course or refreshment station umpires be designated as assistant Referees and that they be in communication with the Referee and each other to ensure the effective co-ordination of warnings and disqualifications. But there remains the possibility as per the Note to Rule 7.2 that in some circumstances disqualification can, and should, occur without a warning being given. When a Transponder Timing System is not in use, or where an additional back-up recording system is desired, it is recommended that a funnel system such as that described in the commentary	格となる。 コメント：フィニッシュエリアは、複数のランナーが並んで走れるように十分広く、フィニッシュでランナーを分けるのに十分な長さでなければならない。トランスポンダータイミングシステムをバックアップシステム（ビデオ録画など）と一緒に使用してフィニッシュ順を確認しない限り、フィニッシュレーン（ファンネル）は、最大幅のフィニッシュラインの約 8～10m 後で幅は 0.70-0.80m に設定する必要がある。ファンネル入るとアスリートは互いに追い越し禁止とする。ファンネルは 35-40m の長さにして、アスリートがフィニッシュラインを通過するときにそこに入るようにする。各ファンネルの最後に、役員は競技者の番号/名前を記録し、該当する場合はトランスポンダーのタイミングチップを回収する。 ファンネルには、競技者が入る端に移動可能なロープが必要である。これにより、1 つのレーンが満杯になったときに、次のフィニッシャーが新しいフィニッシュレーンに入ることができるように、次のロープを最後の競技者の後ろに引くようにする。 決勝審判員と計時員はさらにフィニッシュラインのどちらかの側に配置され、着順に関連する抗議をフォローアップするために、ビデオ記録装置を備えた審判員（可能な場合はタイミングクロックが見えるところ）を競技者がフィニッシュラインを通過する順序を記録するために、フィニッシュラインの数 m 後に割り当てて配置する。 トラックでフィニッシュする道路競技では、規則 18.5（レーン侵害）は適用されず、もし競技者が道路競技の終盤でトラックの内側を踏んだ場合、規則 49.10 を適用し、すべての状況を勘案したうえで競技者が走路を離れ距離が短くなったかどうかを判断する。 49.11. 監察員は等間隔で配置し、重要な場所にも配置しなければならない。その他の監察員はレース中コースに沿って移動し、監察を行う。 コメント：規則 49 の関連する側面を適用するときに最初に警告を発する慣行に従い、該当する場合、規則 7.2 と 7.3 は実行に困難をもたらすが、機会が生じた場合、審判長はそうする必要がある。コースまたは飲食物供給所の審判員が審判長補佐として指定されていること、及び警告と失格の効果的な調整を確実にするために審判長と相互に連絡していることが 1 つの選択肢である可能性がある。ただし、規則 7.2 の注記に従って、警告が出されずに失格が発生する可能性がある。 トランスポンダータイミングシステムを使用していない場合、または追加のバックアップ記録システムが必要な場合は、規則 49.10 の解説に記載されているようなファンネルシステムを使用することを推奨する。
--	--

on Rule 49.10 be used. 12.The LOC shall provide numbered bibs that distinguish between athletes of each Sport Class. 49.13.1. During road races athletes in Sport Classes T11-12 are allowed to use a maximum of two (2) guide-runners. 49.13.2 Any interchanges must take place without any hindrance to other athletes, and may take place at either the 10km, 20km, or 21.1km (half-way); or 30km marks for marathon races, at the 10km mark for half-marathon races and 5km mark for 10km races. 49.13.3. If there is an interchange of guide-runners, the athlete and the substituting guide-runner must both finish the event for the performance to be recognised. 49.13.4. The exchange zone for the interchange of guide-runners must be notified to athletes in advance of race. The interchange of guide-runners must only be completed within this exchange zone, with the athlete and substituting guide-runner exiting the exchange zone with the tether correctly attached as set out in these Rules. Note (i): It is strongly recommended that the LOC ensures that the race takes place in its entirety in good daylight conditions. Note(ii): The exchange zone should be 50m in length and clearly indicated by 50mm wide lines to denote the start and end of the exchange zone(s). Where conditions permit, the exchange zone should be located within a designated 'lane' alongside the course, so as not to impede other athletes during the exchange. Note (iii): Depending on the set up of the course, the interchange may take place at an alternative mark as determined by the Technical Delegate(s) together with the LOC. COMMENT: in order to clearly define the exchange zone, it is recommended to use cones, tape or flags. 14.The intention to interchange guide-runners must be notified in advance to the Referee and Technical Delegate. The technical officials will determine the conditions of the interchange and will communicate these in advance to the athletes. Note: If the interchange does not take place after the technical arrangement being made, the athlete shall be disqualified from the race. Drafting (Sport Classes T33-34, T51-54) 15. In WPA Recognised Competitions under Part B - 3.1.2, for Road Race Events where Sport Classes T33-34, T51-54 compete together,	49.12. LOC は、各競技クラスの競技者を区別する番号付きビブスを提供するものとする。 49.13.1. 道路競走に参加する競技クラスT11-12の競技者は、2 名までガイドランナーを付けることができる。 49.13.2 ガイドランナーの交代は、他の競技者の邪魔にならないようにしなければならず、マラソンでは、10km、20km、または 21.1km(中間地点) 、30km 地点、ハーフマラソンでは、10km 地点、10kmレースでは5km地点のいずれかで行ってよい。 49.13.3. ガイドランナーの交代があった場合、成績が認定されるためには、競技者と交代したガイドランナーの双方が競技を終了する必要がある。 49.13.4. ガイド交代ゾーンは、競技者にレース前に示さなければならない。ガイドランナーの交代はこの交代ゾーン内で完結しなければならない。競技者と交代するガイドランナーは本規則に定められた通りにテザーで正しくつながって交代ゾーンを出なければならない。 注意(i)：組織委員会(LOC)により、レースが全体的に日中の良い状態で行われるようにすることを強く推奨する。 注意(ii)：ガイド交代ゾーンは、長さ 50m とし交代ゾーンの開始と終了を示すために幅 5 0 mm のラインで明確に表示する必要がある。状況が許す限り、交代ゾーンはコース沿いの指定された「レーン」内に設置し、交代中に他の競技者の妨げにならないようにする。 注意(iii)：コース設定次第では、技術代表と組織委員会(LOC)が決定すれば別の地点で交代を行ってもよい。 コメント：交代ゾーンを明確に区切るためにコーン、テープ、または旗を使用することを推奨する。 49.14. ガイドランナーの交代の意向は、事前に審判長及び技術代表に通知すること。競技役員は、交代の条件を決定し、それを事前に競技者に伝える。 注意：技術的な取り決めが行われた後に交代が行われなかった場合、その競技者はレースから失格とする。 ドラフティング (競技クラス T33-34, T51-54) 49.15. PART-B 規則 3.1.2 における WPA 認可競技会で、競技クラス T33-34、T51-55 が一緒に競技を行う場合、異なる競技クラスまたは性別の競	ドラフティング
--	--	--

drafting behind an athlete from another Sports Class or gender is prohibited. Athletes are also prohibited from drafting behind motorised vehicles or bicycles. In violation of this Rule, the athlete concerned shall be disqualified. Note (i): Drafting is defined as seeking a performance advantage by following another athlete within a distance of less than 5m for one minute. Note (ii): In Road races, Sport Class T53 and T54 are considered as one class. The Rule 49.15 does not apply. Obstruction 16.The provisions of Rules 18.1, 18.3 and 18.4 shall apply to Road Races. SECTION VII - PROTESTS AND APPEALS Rule 50: Protests and Appeals These Protest Regulations do not cover Classification or Anti-Doping issues which will be dealt with exclusively under the World Anti-Doping Code and the WPA Classification Rules and Regulations respectively. Protests 1. Protests concerning the status of an athlete to participate in a competition (other than relating to Classification and Anti-Doping) must be made to the Technical Delegate(s) prior to the commencement of the competition. Once the Technical Delegate(s) make(s) a decision, there shall be a right of appeal to the Jury of Appeal. If the matter cannot be resolved prior to the competition, the athlete shall be allowed to compete "under protest" and the matter shall be referred to the IPC. In such cases WPA will be entitled to rule conclusively on an athlete's status after the event has been completed and the results may then be adjusted retrospectively. 2. Protests concerning the result or conduct of (a round of) an event shall be made within 30 minutes of the official announcement of the result of that (round of the) event. The LOC of the competition shall be responsible for ensuring that the time of the announcement of all results is recorded. COMMENT: Normally this means that the 30 minutes start when the results are posted (with the time noted on the posted results sheet) at the TIC or as indicated in the Technical Regulations for the competition. The Secretary to the Jury of Appeal is the person who "manages" the process. If there isn't one, then someone in the TIC would manage it. That is, ensuring the time limits are being followed, arranging for discussions with the appropriate Referee, etc. 3. Any protest shall, in the first instance, be made orally to the Referee by an athlete or by someone acting on their behalf or by an official representative of a team. Such person or team	技者の後ろについてドラフティングすることは禁止されている。競技者は、エンジンのついた車両あるいは自転車の後ろを走行しドラフティングすることも禁止されている。本規則に違反した場合、関係する競技者は失格となる。 注意(i)：ドラフティングとは、5m 以内の距離で他の競技者を 1 分間追いかけて、パフォーマンスの優位性を求めることと定義される。 注意(ii)：道路競技では競技クラス T53 と T54 を 1 つのクラスとみなす。規則 49.15 は適用されない。 妨害行為 49.16. 規則 18.1、18.3 及び 18.4 は道路競技にも適用される。 第 7 部 抗議と上訴 第 50 条 抗議と上訴 本章に定める抗議及び上訴に関する規定は、クラス分けやドーピング防止に関する問題には適用されない。かかる問題はそれぞれ世界アンチドーピング規定及び WPA クラス分け規則及び規程に基づいて取り扱う。 抗議 50.1. 競技会に参加する競技者の資格に関する抗議は、競技会の開始前に技術代表になされなければならない。技術代表の決定に対し、 Jury に上訴できる。競技会が始まるまでに解決しない場合は、その競技者は「抗議中」の状態で競技に参加することが許され、その抗議は、IPC に付託しなければならない。そのような場合、WPA は、競技が終了した後、競技者の立場を最終的に決定する権利があり、結果は遡及的に調整される場合がある。 50.2. 競技（ラウンド）の結果または競技実施に関する抗議は、その競技（ラウンド）の結果の正式発表後 30 分以内に行わなければならない。主催者は記録発表の時刻を記録しておかなければならない。 主催者は記録発表を行った時刻を記録しておかなければならない。 コメント：通常、これは TIC で、または競技規則に示されているように、結果が（公表された結果シートに記載された時間で）公表されたときに 30 分が始まることを意味する。 Jury 秘書は、プロセスを「管理」する。いない場合は TIC の誰かが管理する。つまり時間制限が守られていることの確認、該当審判長との話し合いの手配などである。 50.3. 競技の結果または行為に関するいかなる抗議も、競技者自身または代理人あるいはチームを公式に代表する者から審判長に対して口頭でなされなくてはならない。抗議に関連する種目の同じラウンドで	妨害行為 第 7 部 抗議と上訴 第 50 条 抗議と上訴 抗議
--	--	--

may only protest if they are competing in the same round of the event to which the protest (or subsequent appeal) relates (or are competing in a competition in which a team points score is being conducted). To arrive at a fair decision, the Referee should consider any available relevant evidence. The Referee may decide on the protest or may refer the matter to the Jury of Appeal. If the Referee makes a decision, there shall be a right of appeal to the Jury. Where the Referee is not available, the protest should be made to them through the Technical Information Centre (TIC) or other administrative base where official competition administration is being carried out. Note: The International Photo Finish Judge, where appointed, should act on behalf of the Road Race Event Referee regarding protests about the placing of athletes. 4. In a Track Event a) if an athlete makes an immediate oral protest against having been charged with a false start, the Start Referee (or if one is not appointed, the relevant Track Referee) may, if they are in any doubt, allow the athlete to compete "under protest" in order to preserve the rights of all concerned. Competing "under protest" shall not (subject to the Comment below) be allowed if the false start was detected by a World Athletics approved Start Information System; unless for any reason the Referee determines that the information provided by the system is obviously inaccurate. If an athlete is allowed to compete under protest, a red and white (diagonally halved) card shall be raised in front of the athlete. b) a protest may be based on the failure of the Starter to recall a false start or, under Rule 17.5 to abort a start. The protest may be made only by, or on behalf of, an athlete who should normally have completed the race with bona fide effort. If such a protest is upheld, any athlete who committed the false start or whose conduct should have led to the start being aborted, and who was subject to warning or disqualification according to Rule 17.5 or Rule 17.7 and Rule 17.8, shall be warned or disqualified. Whether or not there may be any warning or disqualification, the Referee shall have the authority to declare the event or part of the event void and that it or part of it shall be held again if in their opinion justice demands it. Note: The right of protest and appeal in Rule 50.4 (b) shall apply whether or not a Start Information System is used. c) If a protest or appeal is based on an athlete's incorrect exclusion from an event due to a false start and it is upheld after the completion of the race, then the athlete should be afforded the opportunity to run on their own to record a time in the event and consequently, if applicable, to be advanced to subsequent rounds. No athlete should be advanced to a subsequent round without competing in all rounds unless the	競技している（チーム得点対抗の競技会で競技している）チームに限り抗議（または上訴）することができる。公正な判定を下すために、審判長は自身が必要と考える利用可能な証拠を考慮すべきである。審判長は、その抗議に結論を下すことも、 Jury に付託することもできる。もし審判長が結論を下したとしても Jury に上訴することができる。審判長がその場にいらないあるいは参加できない場合の抗議は、テクニカルインフォメーションセンター（TIC）あるいは公式の競技会管理が行われている管理基盤を通して行うべきである。 注意：国際写真判定員が任命されている場合、競技者の順位に関する抗議に関しては、トラック審判長に代わって対応する必要がある。 50.4. トラック競技で： a) 不正スタートを告げられたことに対して直ちに口頭で抗議をした場合、スタート審判長（または任命されていない場合はトラック審判長）は、不正スタートであったと少しでも確信が持てないとき、その権利を留保するために、抗議中として競技者が競技することを許可できる。WA が承認したスタートインフォメーションシステムにより不正スタートの判定が下された場合、当該競技者は競技を継続することはできない。ただし、スタートインフォメーションシステムが明らかに不正確であると審判長が判断した場合（下記コメントが対象となる）は、この限りではない。抗議中として競技することを認めた場合、競技者に対して、赤白（斜め半分形）カードを示す。 b) レース後の抗議は、スターターが不正スタートであったにもかかわらずリコール（呼び戻し）できなかった場合、または規則 17.5 の行為があったにもかかわらずスタートの中止ができなかったことを理由に行われる。その抗議は通常、誠実に力を尽くしてそのレースを走り終えた競技者本人、またはその競技者の代理者からのみ行うことができる。抗議が認められる場合、当該不正スタートまたは本来スタート中止を招くはずだった行為を行い、規則 17.5、17.7、17.8 の警告または失格の対象となった競技者は、警告または失格処分を受ける。警告または失格処分の可能性のあるなしにかかわらず、審判長は、当該種目の全部または一部の競技を無効とする権限を有し、全部または一部の競技をやり直すが公正であると判断した場合は再レースを行う。 注意：規則 50.4(b)における抗議及び上訴の権利は、スタートインフォメーションシステムが使われている、いないに拘わらず適用される。 c)不正スタートとして誤って競技から除外された競技者による抗議や上訴がレースの後に認められた場合、記録を残すために走る機会が与えられる。その結果によっては、次のラウンドに進むことができる。審判長が Jury の何らかの決定が特別な状況（例：次ラウンドまでの時間が短すぎたり、競技の距離が短すぎるような場合）でない限り、いかなる競技者もそれまでに行われる全ラウンドで競技をしないで次のラウンドに進むことはできない。
---	---

Referee or Jury of Appeal determines otherwise in the particular circumstances of the case, e.g. the shortness of time before the next round or the length of the race. Note: This Rule may also be applied by the Referee, the Jury of Appeal in other circumstances where it is deemed appropriate (see Rule 18.1). d) When a protest is made by or on behalf of an athlete or team which did not finish a race, the Referee must first ascertain whether the athlete or team was or should have been disqualified for a breach of the Rules unrelated to the matter raised in the protest. Should that be the case the protest shall be dismissed. COMMENT: When the Start Referee decides on an immediate oral protest made by an athlete for being charged with a false start, they have to consider all the available data and in case of only a reasonable possibility that the athlete's protest may be valid, they should allow the athlete to compete under protest. After the race, a final decision must be taken by the Referee, a decision that may be subject of an appeal to the Jury. The Referee should not normally allow an athlete to compete under protest if the false start has been detected by a Start Information System that appears to be working properly or in cases where it is very clear by visual observation that the athlete has committed a false start and there is no valid reason to allow the protest. However, it is acknowledged that when the reaction time is close to the allowed limit, any movement could be hardly visible. In this case if, in the opinion of the Start Referee, it would require further study of the technological evidence, the Start Referee may decide to allow the athlete to run under protest to preserve the rights of all concerned. These Rules not only apply where a Starter failed to recall a false start but where also a Starter failed to correctly "abort" a start. In both cases the Referee must consider all factors involved in the particular case and must decide if the race (or part of it) has to be re-held. Giving two examples of extreme situations, it will not be logical or necessary to re-run a Marathon race in a case where an athlete who finishes was responsible for a non-recalled false start. But the same will probably not be the case in a sprint event where an athlete was responsible for a nonrecalled false start as this may have affected the start and subsequent race of other athletes. On the other hand, if for example in a Qualification Round it was clear that only one or some athletes were disadvantaged by a failure to recall a false start or to abort a start, a Referee could decide that only those athletes be given the opportunity to run again – and if so under what conditions. Rule 50.4 (c) covers the situation in which an athlete is wrongly given a false start and excluded from a race.	注意：この規則は審判長やジュリーが適用するのがふさわしいと考えた時に適用することができる。(参照規則 18.1 参照) d) レースを終了しなかった競技者またはチームによって、あるいはそれらに代わって関係者から抗議がなされた場合、審判長は最初に、当該競技者またはチームがその競技会で当該抗議以外の他の事由によって失格となっていないか確認しなければならない。失格となっている場合は、その抗議は却下されなければならない。 コメント：スタート審判長が、不正スタートを課せられた競技者による現地での口頭抗議を裁定するときは、利用可能なすべてのデータを考慮しなければならない。競技者の抗議が妥当である可能性がある場合に限り、競技者は抗議中（UnderProtest）の立場で競技することが許される。そのレース後、通常審判長により最終決定がなされなくてはならないが、その決定に対し競技者がジュリーに上訴することが可能である。不正スタートが、正常に動作している SIS によって感知された場合、及びその競技者に不正スタートの責任があることが視覚的に明らかであり、抗議を認める理由がない場合には、抗議中の立場で競技することを認めてはならない。但し、反応時間が許容限界に近づく、動きがほとんど見えなくなる可能性があることが認識されている。このような場合、スタート審判長が技術的証拠のさらなる分析が必要であると判断したら、関係者全員の権利を守りために、スタート審判長は、抗議中の立場で競技者が競技することを許可することができる。 これらの規則は、スターターが不正スタートを呼び戻せず走らせてしまった場合だけでなく、スターターが（不適切行為等があったにもかかわらず）適切にスタートを中止できず走らせてしまった場合にも適用される。どちらの場合も、審判長は、それぞれの事案に関わるすべての要素を考慮し、レース（全員またはその一部人数で）を再度実施する必要があるかどうかを判断する必要がある。極端な状況の2つの例を挙げると、フィニッシュした競技者が、不正スタートしたにもかかわらずリコール（呼び戻し）がなかったとしても、マラソンでは再レースは論理的ではないし、不要である。しかし、短距離種目で不正スタートしたにもかかわらずリコール（呼び戻し）がなかったことで他の競技者のスタートやレースに影響を与えた場合は、再レースを不要とは言えない。 一方、予選において、スターターが不正スタートを呼び戻せず走らせてしまったか、スターターが（不適切行為等があったにもかかわらず）適切にスタートを中止できず走らせてしまったことで、1人もしくはそれ以上の競技者が不利益を被ったことが明らかな場合、審判長は、被害を被った競技者だけに再レースの機会を与えるという決定をすることができる。その場合、進出条件も決定できる。 規則 50.4(c)は、競技者が間違って不正スタートを課せられ、レースから除外されてしまった状況を想定している。	
---	---	--

5. In a Field Event, if an athlete makes an immediate oral protest against having a trial judged as a failure, the Referee of the event may, at their discretion, order that the trial be measured and the result recorded, in order to preserve the rights of all concerned. If the protested trial occurred: a) During the first three rounds of trials of a horizontal Field Event in which more than eight athletes are competing, and the athlete would advance to any subsequent rounds of trials only if the protest or subsequent appeal was upheld, or; b) In a vertical Field Event, where the athlete would advance to a higher height only if the protest or subsequent appeal is upheld, the Referee may, if they are in any doubt, allow the athlete to continue competing under protest to preserve the rights of all concerned. COMMENT: In cases where the Referee is sure that the decision of the Judges is correct, particularly by their own observation or advice received from a Video Referee, the athlete should not be allowed to continue. But when considering whether to order the measurement of a trial which is the subject of an immediate oral protest the Referee should: (a) not do so in cases where there was a clear breach of the Rules, for example in the long jump a clear mark made in the plasticine by the athlete in question or in a throwing event where the implement has clearly landed outside the sector; (b) always do so (and immediately so as to not delay the competition) in cases where there is any doubt. The good operation of this Rule means that the Judge with the spike or prism should always mark the point of landing (except in throwing events where the implement clearly lands outside the sector) even when they see a red flag. Apart from the possibility that the athlete may make an immediate oral protest, it is also possible that the Judge with the flags may have incorrectly or accidentally raised the wrong one. 6. The protested performance of the athlete and any other performance achieved while competing under protest will become valid only if the athlete is subsequently found to have competed within the rules such that the trial is no longer judged a failure. In Field Events, where, as a result of an athlete competing “under protest”, another athlete is allowed to continue in the competition when they would otherwise not have done so, such athlete’s performances and eventual results will remain valid irrespective of whether the “under protest” athlete’s immediate oral protest is successful.	50.5. フィールド種目で、もし競技者が無効試技と判定されたことに対し、ただちに口頭の抗議を行った場合、審判長は疑義があると考えたら、該当する事項を保全するためにその試技を計測、記録させることができる。 (a) 距離を競う競技種目において、もし抗議に該当する試技が、8 人を超える競技者が競技する前半の 3 ラウンドで発生した場合で、抗議あるいはそれに続く上訴が支持された場合に限り、その競技者はそれ以降のいかなるラウンドへ進むことができる。 (b) 高さを競う競技においては、その抗議あるいはそれに続く上訴が支持された場合に限り、次の高さに進むことができる。審判長は、無効試技の判定に少しでも確信が持てないとき、関連するすべての権利を保全するため、抗議中として競技者に競技継続を認めても良い。 コメント：審判長が、自身の肉眼による監察、またはビデオ審判長から受け取った助言により、審判員の判定が正しいと確信している場合、競技者が抗議中として競技を継続することを許されない。 しかし、現場での口頭抗議の対象である試技の測定（距離の保全）を命じるかどうかを検討するにあたり： (a) 審判長は、ルールの明確な違反があった場合、例えば、走幅跳で、問題の競技者が粘土板に明瞭な痕跡を残していたり、投てき種目で、投てき物が角度線の明らかに外側に落下した場合には、記録の保全をすべきではない。 (b) 審判長は、多少でも判定に疑念がある場合には常に（競技会の進行を遅らせることなく直ちに）記録の保全を行うべきである。 ピンまたはプリズムを持った落下域担当の審判員が、（投てき種目で投てき物が完全に角度線外に落下した場合を除き）旗を持った審判員が赤旗を上げるのを見たとしても、着地地点の痕跡をどんな時でも（記録の保全に備えて）常にマークしているとき、この規則が十分に理解されているといえる。競技者による現場での口頭抗議だけでなく、旗を持った審判員が誤って、または偶発的に、間違えた色の旗を上げてしまう可能性もある。 6. 抗議対象となった競技の成績や当該競技者が抗議中として競技した結果得られた成績は、審判長がこれを有効と認める判断を下すか、上訴が行われ Jury がその主張を認めた場合に限り、有効となる。 フィールド競技において、口頭抗議が認められるか認められないにかかわらず、抗議中として競技を行なった競技者がいて、抗議が認められれば競技を続けることができないはずの別の競技者も競技を続けることが認められた場合、抗議中扱いの競技者の記録が裁定によって有効になったとしても、競技継続が認められた競技者の記録や最終成績は有効となる。
---	--

Protest Appeals 7. An appeal against a Protest decision is possible and such appeal must be made to the Jury of Appeal within 30 minutes: a) Of the official announcement of the amended result of an event arising from the decision made by the Referee, or; b) Of the advice being given by or on behalf of the Referee to those making the protest, where there is no amendment of any result. The Appeal shall be in writing, signed by a responsible NPC official on behalf of the athlete or team, and shall be accompanied by an appeal fee of €200 or its equivalent in the currency of the country where the competition is being held. The appeal fee will be forfeited if the appeal is not allowed. Such athlete or team may appeal only if they are competing in the same round of the event to which the appeal relates (or are competing in a competition on which a team points score is being conducted). Note: The relevant Referee shall, after their decision on a protest, immediately inform the TIC of the time of the communication of the decision. If the Referee was unable to communicate the decision orally to the relevant team(s)/athlete(s), the official time of the announcement will be that of posting of the amended results or of the decision at the TIC. 8. The Jury of Appeal shall consult all relevant persons, including the relevant Referee (except when their decision is to be fully maintained by the Jury of Appeal). If the Jury of Appeal is in doubt, other available evidence may be considered. If such evidence, including any available video evidence, is not conclusive, the decision of the Referee shall be upheld. 9. The Jury of Appeal may reconsider a decision if new conclusive evidence is presented, provided the new decision is still applicable. Normally such reconsideration may be undertaken only prior to the Victory Ceremony for the applicable event, unless the relevant governing body determines that circumstances justify otherwise. COMMENT: In certain circumstances the Judges (Rule 2.14.2), the Referee (Rule 2.13.6) and the Jury (Rule 50.9) can each reconsider a decision made by them – if it is still applicable and practical to do so. 10. Decisions involving points that are not covered by these Rules shall be reported subsequently by the Chairman of the Jury of Appeal to WPA appointed representative. 11. Decisions of the Referee (subject to appeal under these Regulations) and of the Jury of Appeal shall be final and there shall be no further right of appeal to any other body, including to CAS.	プロテストアピール(抗議結果への上訴) 50.7. ジュリーに上訴する場合は次のいずれかの時点から 30 分以内とする。 a) 審判長の裁定により当該種目の結果が変更された場合は、その結果が公式に発表されたとき。 b) 結果が変更されなかった場合は、抗議者に対して審判長あるいはその代理人からその旨の通知が行われたとき。 上訴は競技者、競技者の代理人、または責任ある NPC 役員によって署名された文書で、預託金 200 ユーロまたは競技会開催地域の現地通貨相当額を添えなければならない。この預託金は、上訴が受け入れられなかった場合は没収される。上訴に関連する種目の同じラウンドで競技している競技者またはチーム（または、チーム得点対抗の競技会で競技しているチーム）に限り上訴することができる。 注意：当該審判長は抗議に対する裁定を下した後、直ちに TIC に対して裁定結果を申立者に伝達した時刻を通知しなければならない。審判長が当該チーム・競技者に対して口頭で裁定を知らせることができなかった場合は、T I C で訂正された結果もしくは裁定結果を掲示した時刻をもって、公式発表が行われた時刻とする。 50.8. ジュリーは、審判長の決定をジュリーが十分に支持している場合を除き、当該審判長やすべての関係者から聞き取りをしなければならない。もしジュリーが納得できない場合は、他の証拠についても考慮する。もし、入手可能なあらゆるビデオ記録を含む証拠でも結論が出ない場合は、審判長の裁定が支持される。 50.9. ジュリーは、新たに決定的な証拠が提示された場合、新たな決定に変更可能な状況であれば決定を再考しても良い。決定の再考は通常その種目の表彰の前までに行われるものとする。ただし、統括団体が、その後であっても状況が許されると判断する場合はその限りではない。 コメント：ある特定の状況において、審判員（規則 2.14.2）、審判長（規則 2.13.6）及びジュリー（規則 50.9）は、そうすることが依然として適用可能で実用的であるなら、それぞれが、決定を再考できる。 50.10. 競技規則でカバーできない点に関する決定は、ジュリーの議長から WPA 代表者へ報告しなければならない。 50.11. 審判長の決定（本規則に基づいて上訴可能）ジュリーの決定が最終のものであり、CAS スポーツ仲裁裁判所に対するものを含めて、さらなる上訴の権利はない。	プロテストアピール
---	---	-------------------------

COMMENT: Where an appeal is presented, the payment of the funds (€200 or equivalent local currency) will be retained until after the Victory Ceremony. This will ensure that where the Jury of Appeal reconsiders its decision that the rights of all parties in the dispute are respected and where the decision to change an original decision, there is no question of having to request the appeal funds to be returned to the Jury of Appeal after they may have been returned via an earlier decision of the Jury of Appeal. Dispute Procedures at WPA Recognised Competitions As part of the WPA Competition Approval Process the LOC in consultation with the WPA appointed representative may stipulate specific dispute resolution procedures for disputes falling outside the Protest and Protest appeal procedures at WPA Recognised Competitions (see Part B - 3.1.2). For information regarding the dispute procedures for a specific competition please liaise with the respective Competition Manager and/or the WPA Technical Delegate. SECTION VIII - WORLD AND REGIONAL RECORDS Rule 51: World and Regional Records For detailed information regarding the procedures for Claiming WPA World and Regional Records refer to the WPA: https://www.paralympic.org/athletics/records COMMENT: Included on the website are the current application forms for records. Submission and Ratification 1. WPA World and Regional Records can only be achieved at WPA Recognised Competitions by an eligible athlete (or eligible athletes in the case of a relay event) as defined in Part B - 4 holding a: a) Sports Class Status of Confirmed (C), or; b) Sports Class Status of Review (R) with a Fixed Review Date which is after the date when the record was achieved. 2. Except for Field Events conducted as provided in Rule 4.7 and Rule 4.8 and Competitions held outside the stadium under Rule 49 no performance set by an athlete will be ratified if it has been accomplished during a mixed competition. Note: Women only Road Race records are subject to the conditions set out in Rule 51.22. 3. The following categories of Records are accepted by WPA: World Outdoor Records and Regional Outdoor Records. 4. An athlete (or athletes in case of a relay event) who sets a Record must have been eligible	コメント： 上訴があった場合、預託金（€200 または同等の現地通貨）は、表彰式の後まで保管される。これにより、 Jury が抗議者の権利が尊重されるという決定を再検討する場合、及び元の決定を変更する決定が行われた場合、預託金を Jury に返還するよう要求する必要があることに何の疑問も生じないことが保証される。 WPA 認可競技会での紛争手続き WPA 競技会承認プロセスの一環として、LOC は WPA の指名された代表者と協議して、WPA 認可競技会（PART-B 規則 3.1.2 参照）での抗議及び抗議の異議申し立ての手順に該当しない紛争の具体的な紛争解決手順を規定することができる。 特定の競技会の紛争手続きに関する情報については、それぞれの競技会マネージャー(総務)や WPA 技術代表に連絡する。 第 8 部 世界記録とエリア記録 第 51 条 世界記録とエリア記録 WPA 世界記録及びエリア記録の申請手続きに関する詳細は WPA ウェブサイト参照のこと。 www.worldparaathletics.org コメント： ウェブサイトには、記録の現在の申請書が含まれている。 提出と承認 51.1. WPA 世界記録及びエリア記録は、WPA 認可競技会で Part B 規則 4 で定義された有資格競技者(リレーの場合は全競技者)によって達成された場合にのみ認められる。 a)ステータスが確定(ステータス C)の競技者 b)ステータスが再審査扱い(ステータス R)記録を達成した日よりもあとに固定された再審査結果のある競技者 51.2. 規則 4.7、4.8 の条件下で行われたフィールド種目と規則 49 の条件下で競技場外実施された競技会を除いて、競技者の記録は、男女混合の競技で樹立されたものは承認されない。 注意： 女性のみの道路競技の記録は、規則 51.22 に規定された条件を必要とする。 51.3. 屋外世界記録及び屋外エリア記録が WPA により承認される。 51.4. 記録を樹立した競技者（またはリレー競技の競技者）は、本規則のもとで競技に参加する資格を有し、IPC 加盟団体によって当該競技会にエントリー	WPA 認可競技会での紛争手続き 第 8 部 世界記録とエリア記録 第 51 条 世界記録とエリア記録 提出と承認
--	---	---

to compete under these Rules, must have been entered into the relevant Competition by a member of the IPC; and all provisions of these Rules must have been duly observed at the relevant Competition. 5. The WPA Technical Delegate, if appointed to the relevant WPA Recognised Competitions (see Part B - 3.1.2), shall be responsible for ensuring all of the procedural requirements outline in this Rule are fulfilled. 6. When a performance equals or betters an existing Record, the national governing body where the performance was set shall collect, without delay, all the information required for the ratification of the Record by WPA. No performance shall be regarded as a Record until it has been ratified by WPA. The national governing body should immediately inform WPA of its intention to submit a performance. Note: The national governing body herein these Rules refers to the authorized body responsible for sending the Athletes to the respective event. This could be a National Paralympic Committee or the NF or the body responsible for Para Athletics in the country. 7. The submitted performance shall be better than or equal to the existing Record for that Event as accepted by WPA. If a Record is equalled, it shall have the same status as the existing Record. 8. The WPA Record Application Form shall be completed and dispatched to the WPA Office within thirty (30) days of a record being achieved. The WPA Record Application Forms are available, on request, from the WPA Office, or may be downloaded from the WPA website at: https://www.paralympic.org/athletics/technical-information Note: The WPA Record Application Form is required for performances achieved at WPA Approved Competition (see Part B - 3.1.2 (d)). 9. The national governing body where the performance was set shall send, with the WPA Record Application Form: a) The printed programme of the Competition (or electronic equivalent); b) The official result of the Event, including all information required under this regulation; c) In the case of a Track Record where Fully Automated Timing was in operation, the photo finish image of the event and zero control test image for track events up to and including 800m and 4x400m relays; and d) Any other information required to be submitted by this regulation, where such information is or should be in its possession.	され、当該競技会において本規則のすべての規定が適切に尊守されている必要がある。 51.5. WPA 認可競技会(PART-B -規則 3.1.2 参照)を担当する任命された WPA 技術代表は、以下についてあらゆる手続き要件が満たされていることを承認する。 51.6. 記録が新記録あるいはタイ記録だった場合、結果を集約している国内統括団体が遅滞なく、記録公認に必要なすべての情報を WPA に提出しなければならない。WPA が認定するまで、その記録は新記録あるいはタイ記録とはならない。主催団体は直ちに WPA に対して記録申請する意思があることを伝える。 注意：国内統括団体は規則上、該当種目に参加した競技者の所属する認定された団体にこのことを指す。これは NPC、NF あるいは国内のパラ競技の団体のことを言う。 51.7. 記録は、その種目の既存の記録よりもよいか、同じでなければならない。もし記録が等しいならば、その記録は従前の記録と同等の位置づけとして扱われる。 51.8. WPA への WPA 記録申請書は 30 日以内に、記入し WPA オフィスに送付する。申請用紙は WPA オフィスに申し込めば入手可能であるが、WPA のウェブサイトからもダウンロードすることができる。 注意：WPA 記録申請書は WPA 承認競技会 (PART-B 規則 3.1.2(d)参照)で達成された記録にも必要である。 51.9. 記録が樹立された国の国内統括団体は、WPA 記録申請書に次のものを添付しなければならない。 a) 大会のプログラム(またはデータ) b) 当該種目の全記録 c) トラック競技で写真判定が行われた場合は、その記録の判定写真およびゼロコントロールテストの写真 (800m までのトラック種目と 4x400m を含む) また d) この規則により提出が義務付けられているその他の情報であって、当該情報がすでに保有されているか、または保有されているべきものである場合。
--	--

10. WPA World and Regional Records will only be ratified if they are achieved at: a) Paralympic Games, WPA Championships or WPA Sanctioned Competitions (see Part B 3.1.2 (a) to (c)) conducted in accordance with the IPC Anti-Doping Code, or; b) WPA Approved Competitions conducted in accordance with the anti-doping rules of the relevant governing body and the WADC the International Standards at which random in-competition testing (urine only or urine and blood) was also conducted. Note (i): For the purpose of record ratification, all World and Regional Outdoor Records achieved by athletes in Sport Classes T61-62 shall undergo a measurement of their MASH which shall be conducted at the Call Room. Note (ii): WPA World and Regional Records will be ratified even though the athlete who sets the record performance may not have been tested at the Competition. 11.Records made in qualification rounds, in deciding ties, in any Event which is subsequently decreed void, may be required to be submitted for ratification. 12.WPA Management Team is responsible for ratifying Records. 13.When a Record has been ratified, WPA will supply the official Record certificate, for presentation to Record holders and the performance will be updated and available on the official WPA website. 14.WPA shall update the official List of Records every time a new Record has been ratified. This list shall represent the performances regarded by WPA as being, from the date of the list, the best performances yet set by an athlete or team of athletes in each of the recognised Events. 15.If the performance is not ratified, WPA will provide the reasons as to why this is the case. Specific Conditions 16.Except in Road Events: a) The performance shall be made in a certified athletics facility, which conforms to Rule 3; b) For any performance at any distance of 200m or more to be recognised, the track on which it was made shall not exceed 402.3m (440 yards) and the race shall have started on some part of the perimeter; c) A performance in an oval Track Event shall be made in a lane where, the running line radius does not exceed 50m, except where the bend is formed with two different radii, in which case the	51.10. WPA 世界記録及びエリア記録は、以下の競技会で達成された場合に承認される。 a) IPC アンチドーピング規程に従って開催されるパラリンピック競技大会、WPA 世界選手権大会及び WPA 認定競技会 (PART-B 規則 3.1.2 (a) - (c)参照) b) WPA 承認競技会のうち、当該国内統括団体及び WADA のドーピング防止規定に従って無作為の競技場外検査 (尿だけあるいは尿と血液による) が行われている競技会 注意(i) : T/F61-62 の競技者が屋外競技会で世界記録及びエリア記録を出した場合、承認のために招集所で MASH 再計測が行われなければならない。 注意(ii) : WPA 世界記録及びエリア記録は、記録を達成した競技者がその時点でドーピングテストを受けていない場合でも、承認される。 51.11. 記録は、予選、同記録を解決するための追加試技、結果的に無効とされた競技もしくはその一部であっても、申請することができる。 51.12. WPA 実務部門が世界記録及びエリア記録の承認を担当する。 51.13. 記録が公認されたら、WPA は記録保持者に対して公式記録証明を授与する。最新の世界記録は、WPA の公式サイトに公表される。 51.14. WPA は新しい記録が公認されるたびに、記録の公認リストを更新する。このリストには、公認種目において、競技者またはチームが達成したもっともよい成績が記載され、発表の日から記録としてみなされる。 51.15. もし記録が承認されなければ、WPA はその理由を明らかにする。 細則 51.16. 道路種目を除いて a) 世界記録及び地域記録は規則 3 に適合した陸上競技施設でつくられなければならない。 b) 200m 以上(200m を含む)のレースの記録は、1 周が 402.3m(440 ヤード)を超えないトラックでつくられ、またその競走が、曲走路のいずれかの部分からスタートした場合にのみ公認される。 c) 周回トラックで行われた種目の記録はレーンの距離計測部分の半径が 50m を超えないトラックで達成されたものでなければならない。ただし、曲走路が 2 つの円弧のうちの長い方が 180 度の回転のうち 60 度を超えないことを除く。	細則 51.16. 道路種目を除いて
---	---	--

longer of the two arcs should not account for more than 60° of the 180° turn. d) A performance made in a Track Event outdoors may be made only on a track which conforms to Rule 15. 17.For Records in Track (Running and Wheelchair Racing) Events a) The performance shall be timed by official Timekeepers, by an approved Fully Automatic Photo Finish System (for which a zero control test has been undertaken with Rule 20.20) or a Transponder System used (see Rule 20.25); b) For races up to and including 800m (including 4x400m), only performances timed by an approved Fully Automatic Timing Photo Finish System shall be ratified c) For all performance made outdoors up to and including 200m, information concerning wind velocity, measured as indicated in these Rules, shall be submitted. If the wind velocity, measured in the direction of running, averages more than 2 metres per second during the race, the performance will not be ratified. d) No performance will be ratified where the athlete has infringed Rule 18.5 except, (i) in cases covered in Rule 18.5(b), or (ii) in cases covered in Rules 18.5(c) and 18.5(d) if it is the first infringement in the event. COMMENT: The amendment to Rule 18.5 means for World Record ratification that if an athlete or relay team achieves a record time and, in that race, that athlete (or any athlete in the relay team) made a single infringement under Rules 18.5(c) or 18.5(d), and in the case of an event with more than one round, it was the first infringement in the event, the record may stand. If the athlete or relay team achieves a record time and, in that race, an infringement occurred more than once or the athlete or relay team carried over such infringement from a previous round of the same event, the record cannot be ratified. e) For all Records up to and including 400m (including 4x400m), where available starting blocks linked to a World Athletics approved Start Information System shall have been used and must have functioned correctly so that reaction times were obtained and are shown on the results of the Event. 18.For Records in Relay Events The time set by the first athlete in a relay team may not be submitted for ratification as Record. 19.For Records in Field Events a) The performances shall be measured either by three Field Judges using a calibrated and certified	d) 屋外記録は規則 15 に適合したトラックでつくられたもののみが認められる。 51.17. トラック(競走競技及び車いすレース)競技の記録 a) レースの記録は、計時員によって計時されるか、承認済みの写真判定システム(規則 20.20 にあるゼロコントロールテストを実施する)あるいはトランスポンダー計時システム(規則 20.25 参照)によって記録されなければならない。 b) 800m(4×400m リレーを含む)までの種目の世界記録及び地域記録は、承認済みの写真判定システムによって記録された時間だけが公認される。 c) 200m までの屋外記録は、規則に示される方法で測定された風速の報告が必要である。平均秒速 2m を超える風力が走る方向に吹いていたと測定された場合、記録は公認されない。 d) 以下の場合を除き、規則 18.5 に違反した場合その記録は、認められない。 (i) 規則 18.5(b)に該当する場合、または、 (ii) 規則 18.5(c)及び 18.5(d)が適用される場合、当該種目で最初の違反である場合 コメント：規則 18.5 の改正は、競技者またはリレーチームが記録を達成した際、そのレースで競技者（またはリレーチームの各走者）が規則 18.5 (c)または 18.5(d)に定められている規則に 1 回だけ違反した場合、あるいは当該種目の複数行われるラウンドの中で最初の違反であった場合には、その記録を認めるというものである。競技者またはリレーチームが記録を達成したとしても、違反が同一ラウンドで複数回あった場合や、同じ種目の前のラウンドで規則違反があり、再び違反した場合には失格となり、記録は認められない。 e)400m までのすべての世界記録及び地域記録の公認は、WA 認可のスタートインフォメーションシステムを組み込んだスターティングブロックを使用し、反応時間が得られるように正確に機能させなくてはならず、リザルトに記載されなければならない。 51.18. リレー競走の世界記録 リレー競技で第 1 走者が達成した記録は世界記録として申請することができない。 51.19. フィールド競技の記録 a) 記録は、3 名のフィールド競技審判員が検査済の鋼鉄製巻尺または高度計を使って、またはその他の	51.17. トラック（競走競技及び車いすレース） 競技の記録 51.18. リレー競走の世界記録 51.19. フィールド競技の記録
---	---	---

steel tape or bar or by an approved scientific measuring apparatus, the accuracy of which has been confirmed by a qualified Measurement Judge in accordance with Rule 10; b) In the Long Jump and Triple Jump, information concerning wind velocity, measured as indicated in these rules shall be submitted. If the wind velocity, measured in the direction of jumping, averages more than 2 metres per second, the performance will not be ratified; c) Records may be credited for more than one performance in a competition, provided that each Record so ratified shall have been equal or superior to the best previous performance at that moment; d) In Throwing Events, the implement used shall have been checked prior to the Competition in accordance with Rule 2.11. If the Referee becomes aware during an Event that a Record has been equalled or bettered, they shall immediately mark the implement used and undertake a check to ascertain whether it still complies with the Rules or if there has been any change in characteristics. Normally, such implement shall be checked again after the Event in accordance with Rule 2.11. 20. For Records in Road (Running and Wheelchair Racing) Events a) The course must be measured by an "A" or "B" grade World Athletics /AIMS approved measurer who shall ensure that the relevant measurement report and any other information required by this Rule is available to WPA upon request; b) The start and finish points of a course, measured along a theoretical straight line between them, shall not be further apart than 50% of the race distance; c) The overall decrease in elevation between the start and finish shall not exceed 1:1000 i.e., 1m per km (0.1%); d) Any course measurer who originally measured the course or other suitably qualified official designated by the measurer (after consulting the relevant body) with a copy of the documentation detailing the officially measured course shall in advance of the race check that the course is laid out in conformity with the course measured and documented by the Official course measurer. They shall then ride in the lead vehicle during the competition or otherwise validate that the same course is run by the athletes; e) The course must be verified (i.e., re-measured) as late as possible before the race, on the day of the race or as soon as practical after the race, by a different "A" grade measurer from the one that did the original measurement; Note: If the course was originally measured by at least two "A" grade or one "A" and one	科学的計測器を使って計測されたものでなければならない。使用する計測器は規則 10 の規定に基づき、正確性が確認されたものでなければならない。 b) 走幅跳及び三段跳の記録は、規則に示される方法で測定された風速の報告が必要である。平均秒速 2mを超える風が跳躍方向へ吹いていたと測定された場合、記録は公認されない。 c) 記録は、もし樹立された記録が、その時点でそれまでの記録と同じか上回る場合、1 競技会で複数の記録が認められる。 d) 投てき種目においては、使用された用具は規則 2.11 の規定に基づき事前に検査されたものでなければならない。種目競技中に記録と同等かそれを上回る記録が達成された場合、審判長は直ちに使用された用具に印をつけ、その用具が本規則の規定に合致しているか、あるいは特性面で何らかの変更がなされていないか確認すべく検査しなければならない。通常、そのような用具は種目終了後に、規則 2.11 に基づく検査を再度実施しなければならない。 51.20. 道路競走(ランニング及び車いすレース)における記録 a) コースは WA/AIMS 認定の A 級もしくは B 級の計測員によって計測されたものでなければならない。かかる計測員は、WPA の要請に応じて、計測報告書及び本条に定めるその他の必要な情報を確実に提供できるようにしなければならない。 b) スタートとフィニッシュの 2 点間の理論上の直線距離は、そのレースの全距離の 50%以下とする。 c) スタート地点とフィニッシュ地点間全体の標高の減少は 1000 分の 1(0.1%)、即ち 1km あたり 1m を超えてはならない。 d) 当初のコース計測を行った計測員、またはその計測員に指名され、正式に計測されたコースの詳細を記載した書類の写しを持つ、しかるべき資格を有すると主催者と協議して決めた役員は、競技に先立ち、正式に計測され記録されたとおりのコースであることを確認しなければならない。競技中は先導車に同乗するかほかの方法で、競技者が同じコースを走っていることを確認しなければならない。 e) コースは、レース当日のできる限り直前か、あるいはレース後ただちに、できるだけ最初の計測を行った計測員とは異なる A 級の WA/AIMS 自転車計測員が再確認（再計測）しなければならない。 注意: 当初の計測が少なくとも 2 人の A 級計測員、または A 級計測員 1 人と B 級計測員 1 人によって行われた場合、本規則で定める確認（再計測）は	51.20. 道路競走（ランニング及び車いすレース）における記録
---	---	--

"B" grade measurers, no verification (re-measurement) under this Rule will be required. f) Records in Road Events set at intermediate distances within a race must comply with the conditions set under these Rules. The intermediate distances must have been measured, recorded and subsequently marked as part of the course measurement and must have been verified in accordance of these Rules. 21. Other Records a) Games, championships, meeting and other similar records may be established by the relevant body having control over the Competition or by the LOC. b) The record should recognise the best performance achieved at any edition of the applicable Competition in accordance with the Rules, with the exception that wind velocity readings may be ignored, if so stated in the applicable Regulations for the Competition. 22. Events for which Records are Recognised Fully Automatically Timed performances (F.A.T.) Hand Timed performances (H.T.) Transponder Timed performances (T.T.) Men F.A.T. only: 100m; 200m; 400m; 800m; 4x100m Relay; 4x400m Relay; F.A.T. or H.T.: 1500m; 5000m; 10,000m; Road Races F.A.T. or H.T. or T.T.: 5km, 10km; Half Marathon; Marathon Jumps: High Jump; Long Jump; Triple Jump Throws: Shot Put; Discus Throw; Javelin Throw, Club Throw Women F.A.T. only: 100m; 200m; 400m; 800m; 4x100m Relay; 4x400m Relay; F.A.T. or H.T.: 1500m; 5000m; 10,000m; Road Races F.A.T. or H.T. or T.T.: 5km, 10km; Half Marathon; Marathon Jumps: High Jump; Long Jump; Triple Jump Throws: Shot Put; Discus Throw; Javelin Throw; Club Throw Universal F.A.T. only: 4x100m Universal Relay Note: A women only road race can be staged by having separate women's and men's start times. The time differential should be chosen to prevent any possibility of assistance, pacing, drafting or interference, especially on courses involving more than one lap of the same section of the course. SECTION IX - AWARDING MEDALS AND DIPLOMAS Rule 52: Awarding Medals and Diplomas 1. At WPA Recognised Competitions only finalists are eligible for medals. In relay events, the four (4) athletes and guide-runner(s) of each team entitled to a medal who	必要ない。 f) レース中の途中距離で達成された道路競走の記録は、本規則に定める条件に合致していなくてはならない。その途中距離は、コース計測実施の際に測られ、マークされていたものでなければならず、本規則に則った確認がなされなければならない。 51.21. その他の記録 a) ゲームズ(総合競技大会)、選手権大会、一般競技会等、競技会毎の大会記録は、その競技会を統括する団体や大会組織委員会により定められる。 b) 当該競技会で風の条件を考慮しないとの規定がある場合を除き、本競技規則を適用して行われたそれまでの大会の最高記録が大会記録として認められるべきである。 51.22. 記録が公認される種目 全自動写真判定 (F.A.T.) 手動計時 (H.T.) トランスポンダー計時 (T.T.) 男子 F.A.T.のみ：100m、200m、400m、800m、4x100m リレー、4x400m リレー F.A.T. または H.T.：1500m、5000m、10000m ロードレース(F.A.T.または H.T.、T.T.): 5km、10km、ハーフマラソン、マラソン 跳躍種目：走高跳、走幅跳、三段跳 投てき種目：砲丸投、円盤投、やり投、こん棒投 女子 F.A.T.のみ：100m、200m、400m、800m、4x100m リレー、4x400m リレー F.A.T.または H.T.：1500m、5000m、10000m ロードレース(F.A.T.または H.T.、T.T.): 5km、10km、ハーフマラソン、マラソン 跳躍種目：走高跳、走幅跳、三段跳 投てき種目：砲丸投、円盤投、やり投、こん棒投 ユニバーサル F.A.T.のみ：4x100m ユニバーサルリレー 注意(i): 女子単独の道路競走は、男女異なるスタート時間を設けることで実施できる。その際、特にコースが同じ箇所を複数回通過するように設定されている場合は、助力、ペース調整、妨害の可能性を防ぐべく適切な時間差が設定されるべきである。 第 9 部 メダルと賞状の授与 第 52 条 メダルと賞状の授与 52.1. WPA 認可競技会においては、決勝進出者のみがメダルを受賞することができる。 リレー競技の表彰においては、各チームのメンバーのうち決勝戦で競技した 4 名とガイドランナーが表彰台に登壇するものとする。規則 23.10 に従い、当該競技	51.21. その他の記録 51.22. 記録が公認される種目 第 9 部 メダルと賞状の授与 第 52 条 メダルと賞状の授与
---	--	--

competed in the final shall mount the Victory Ceremony podium. Other athletes and guide-runner(s) in accordance with Rule 23.10 who competed for any of these teams in the competition may either receive their medals on the Victory Ceremony podium or subsequently, at the discretion of WPA and the relevant LOC. 2. Athletes shall nominate the guide-runner(s) on the final entries. Only those guide-runners who meet the following criteria shall be eligible to receive a medal alongside the medal winning athletes. a) In individual events where athletes with vision impairment are allowed to compete using multiple guide-runners, only those guides who have completed the full event (from the first round to finals) with the athlete shall be eligible to receive the medal alongside the athlete. Note (i): Assistants in field events are not eligible to receive a medal. Note (ii): Should the athlete declare to use more than one guide-runner in an event, then these guide-runners will not be eligible to receive a medal. b) in relay events, the guide-runner(s) accompanying the medal winning athlete(s) in the final shall mount the Victory Ceremony podium and receive a medal. Note: The athletes and guide-runners of the winning teams, who competed in any previous rounds of the competition, may receive their medals on the Victory Ceremony podium or subsequently, at the discretion of WPA and the relevant LOC. 3. In individual events where athletes with vision impairment are allowed to compete using multiple guide-runners, all guide-runners in track and road events (including events in which multiple guide-runners have competed), are eligible to receive diplomas according to the diploma policy as stipulated in the relevant Protocol Guide applicable to the competition. 4. Sport Class changes in competition may affect an athlete's result(s), placing and record(s) and the impact varies in Track and Field events. Re-entry after Changes in Sport Class is subject to the Technical Delegate's approval in accordance with Rule 5.3 of these Rules. Track Events If the revised Sport Class is still within the eligible Sport Classes of that event, re-entry of that event is not required. Result, placing and prize won by the athlete shall stand. If the revised Sports Class is outside the eligible Sport Classes of that event, the performance(s) achieved by the athlete shall stand but the placing and prize won by the athlete shall be void.	会においてメダル獲得チームのメンバーとして競技したその他の競技者とガイドランナーには、表彰式の表彰台にて、またはその後にメダルが授与される。WPA および関連する組織委員会の裁量により決定される。 52.2. 競技者は最終エントリー時にガイドランナーを申告するものとする。正式に指名されたガイドランナーで以下の基準を満たす者のみ、競技者がメダルを獲得した場合と一緒にメダルを受け取ることができるものとする。 a) 視覚障害のある競技者が複数のガイドランナーを指名できる種目においては、ガイドランナーは、種目全体(予選から決勝まで)を通して伴走を務めた場合のみ、競技者とともにメダルを受け取ることができるものとする。 注意(i)：フィールド競技種目におけるアシスタントはメダルを受け取ることはできない。 注意(ii)：競技者が複数のガイドランナーの利用を申告した場合、これらのガイドランナーはメダルを受け取ることができない。 b) リレー競技の表彰においては、決勝でメダル獲得走者の伴走を務めたガイドランナーが表彰台に登壇し、メダルが授与される。 注意：当該競技会において、優勝チームのメンバーとして決勝までのラウンドで競技した競技者と伴走を務めたガイドランナーには、表彰式の表彰台にて、または、終了後にメダルが授与される。WPA および関連する組織委員会の裁量により決定される。 52.3. 視覚障害のある競技者が複数のガイドランナーを申告できる個人種目においては、トラック競技と道路競技で伴走を務めたすべてのガイドランナー（複数のガイドランナーがいる場合も含む）は、競技会におけるプロトコルガイドに定める表彰方針に従って、賞状を受け取ることができる。 52.4. 競技会での競技クラスの変更は、競技者の競技結果、順位、記録に影響を与える可能性があり、その影響は種目によって異なる。競技クラスの変更後の再エントリーは、規則 5.3 に従って技術代表の承認が必要である。 トラック種目 変更になった競技クラスが、なお出場種目のエリジブル(出場資格のある)クラスに含まれる場合、その種目への再エントリーは必要ない。リザルト、順位、獲得した賞は有効となる。 変更になった競技クラスが、出場種目のエリジブルクラスに含まれない場合、達成した記録は認められるが、順位と獲得した賞は無効になる。	トラック種目
---	---	---------------

Field Events If the revised Sport Class is still within the eligible Sport Classes of that event, re-entry of that event is not required. If the Points System is being used, the points which determine the placing and prize shall be recalculated against their revised Sport Class. The performance(s) achieved by the athlete may stand provided the same competition rules apply in their revised Sport Class. If the revised Sport Class is outside the eligible Sport Classes of that event, the performance(s) achieved by the athlete may stand provided the same competition rules apply in their revised Sport Class, but the placing and prize won by the athlete shall be void.	フィールド種目 変更になった競技クラスが、なお出場種目のエリジブルクラスに含まれる場合、その種目への再エントリーは必要ない。ポイントシステムが使用されている場合、順位と賞を決定するポイントは、変更になった競技クラスをもとに再計算される。達成した記録は、変更になった競技クラスと同じ競技規則が適用される場合に限り有効となる。 変更になった競技クラスが、出場種目のエリジブルクラスに含まれない場合、同じ競技規則が変更になった競技クラスに適用されていれば、達成した記録は認められるが、順位と獲得した賞は無効になる。	フ ィ ー ル ド 種 目
---	--	---

APPENDIX 1

WORLD PARA ATHLETICS IMPLEMENT WEIGHTS FOR SPORT CLASSES

Sport Classes F11-13

Age Group	Classes	Discus Male	Discus Female	Javelin Male	Javelin Female	Shot Put Male	Shot Put Female
Open	F11-13	2.00kg	1.00kg	800gr	600gr	7.26kg	4.00kg
U/20	F11-13	1.75kg	1.00kg	800gr	600gr	6.00kg	4.00kg
U/17	F11-13	1.50kg	1.00kg	700gr	500gr	5.00kg	3.00kg

Sport Class F20

Age Group	Classes	Discus Male	Discus Female	Javelin Male	Javelin Female	Shot Put Male	Shot Put Female
Open	F20	2.00kg	1.00kg	800gr	600gr	7.26kg	4.00kg
U/20	F20	1.75kg	1.00kg	800gr	600gr	6.00kg	4.00kg
U/17	F20	1.50kg	1.00kg	700gr	500gr	5.00kg	3.00kg

Sports Classes F31-38

Age Group	Classes	Discus Male	Discus Female	Javelin Male	Javelin Female	Shot Put Male	Shot Put Female	Club Male & Female
Open And U/20	F31	NE	NE	NE	NE	NE	NE	397gr
	F32	1.00kg	1.00kg	NE	NE	2.00kg	2.00kg	397gr
	F33	1.00kg	1.00kg	600gr	600gr	3.00kg	3.00kg	NE
	F34	1.00kg	1.00kg	600gr	600gr	4.00kg	3.00kg	NE
	F35	1.00kg	1.00kg	600gr	600gr	4.00kg	3.00kg	NE
	F36	1.00kg	1.00kg	600gr	600gr	4.00kg	3.00kg	NE
	F37	1.00kg	1.00kg	600gr	600gr	5.00kg	3.00kg	NE
	F38	1.50kg	1.00kg	800gr	600gr	5.00kg	3.00kg	NE
U/17	F31	NE	NE	NE	NE	NE	NE	397gr
	F32	750gr	750gr	NE	NE	1.00kg	1.00kg	397gr
	F33	750gr	750gr	500gr	500gr	2.00kg	2.00kg	NE
	F34	750gr	750gr	500gr	500gr	3.00kg	2.00kg	NE
	F35	750gr	750gr	500gr	500gr	3.00kg	2.00kg	NE
	F36	750gr	750gr	500gr	500gr	3.00kg	2.00kg	NE
	F37	750gr	750gr	500gr	500gr	4.00kg	2.00kg	NE
	F38	1.00kg	750gr	600gr	500gr	4.00kg	2.00kg	NE

Sport Classes F40-46

Age Group	Classes	Discus Male	Discus Female	Javelin Male	Javelin Female	Shot Put Male	Shot Put Female
Open and U/20	F40,F41	1.00kg	750gr	600gr	400gr	4.00kg	3.00kg
	F42	1.50kg	1.00kg	800gr	600gr	6.00kg	4.00kg
	F43,F44	1.50kg	1.00kg	800gr	600gr	6.00kg	4.00kg
	F45,F46	1.50kg	1.00kg	800gr	600gr	6.00kg	4.00kg
U/17	F40,F41	1.00kg	750gr	500gr	400gr	3.00kg	2.00kg
	F42,	1.00kg	1.00kg	700gr	500gr	5.00kg	3.00kg
	F43, F44	1.00kg	1.00kg	700gr	500gr	5.00kg	3.00kg
	F45,F46	1.00kg	1.00kg	700gr	500gr	5.00kg	3.00kg

Sport Classes F51- 57

Age Group	Classes	Discus Male	Discus Female	Javelin Male	Javelin Female	Shot Put Male	Shot Put Female	Club Male & Female
Open and U/20	F51	1.00kg	1.00kg	NE	NE	NE	NE	397gr
	F52	1.00kg	1.00kg	600gr	600gr	2.00kg	2.00kg	NE
	F53	1.00kg	1.00kg	600gr	600gr	3.00kg	3.00kg	NE
	F54	1.00kg	1.00kg	600gr	600gr	4.00kg	3.00kg	NE
	F55	1.00kg	1.00kg	600gr	600gr	4.00kg	3.00kg	NE
	F56	1.00kg	1.00kg	600gr	600gr	4.00kg	3.00kg	NE
	F57	1.00kg	1.00kg	600gr	600gr	4.00kg	3.00kg	NE
U/17	F51	750gr	750gr	NE	NE	NE	NE	397gr
	F52	750gr	750gr	500gr	500gr	2.00kg	2.00kg	NE
	F53	750gr	750gr	500gr	500gr	2.00kg	2.00kg	NE
	F54	750gr	750gr	500gr	500gr	3.00kg	2.00kg	NE
	F55	750gr	750gr	500gr	500gr	3.00kg	2.00kg	NE
	F56	750gr	750gr	500gr	500gr	3.00kg	2.00kg	NE
	F57	1.00kg	750gr	500gr	500gr	3.00kg	2.00kg	NE

Sport Classes F61- 64

Age Group	Classes	Discus Male	Discus Female	Javelin Male	Javelin Female	Shot Put Male	Shot Put Female
Open and U/20	F61,F63	1.50kg	1.00kg	800gr	600gr	6.00kg	4.00kg
	F62,F64	1.50kg	1.00kg	800gr	600gr	6.00kg	4.00kg
U/17	F61,F63	1.00kg	1.00kg	700gr	500gr	5.00kg	3.00kg
	F62, F64	1.00kg	1.00kg	700gr	500gr	5.00kg	3.00kg

Appendix 2 – Examples of Club shapes not compliant with WPA Rule 37.



Figure 25 – Examples of Club shapes not compliant

Note: The above shapes deviate from the shape permitted under Rule 37 (see figure 24).

APPENDIX 2

Classification Hierarchy Table 1 – Paralympic Games and World Championships

Class	100m	200m	400m	800m	1500m	5000m	10000m	Marathon	High Jump	Triple Jump	Long Jump	Discus	Shot Put	Javelin	Club	Class
11																11
12																12
13																13
20																20
31																31
32																32
33																33
34																34
35																35
36																36
37																37
38																38
40																40
41																41
61																61
42																42
63																63
43																43
62																62
44																44
64																64
45																45
46																46
47																47
51																51
52																52
53																53
54																54
55																55
56																56
57																57
71																71
72																72

Grouping classes on basis of Classification Hierarchy and/or technical rules.
Non existing class/event combination (2026).

- a. Class 11 can compete with Class 12. Class 12 can compete with Class 13. However, Class 11 should not compete with Class 13.
- b. Possible combinations: T51-53 or T52-54.
- c. T53 and T54 compete as a combined event.
- d. Possible combinations: any grouping of up to three consecutive classes.
- e. Possible combinations: any grouping of up to three consecutive classes within 53-57 (females) or 54-57 (males).

APPENDIX 2

Classification Hierarchy Table 2 – Regional Championships and Regional Games

Class	100m	200m	400m	800m	1500m	5000m	10000m	Marathon	High Jump	Triple Jump	Long Jump	Discus	Shot Put	Javelin	Club	Class
11																11
12																12
13																13
20																20
31																31
32																32
33																33
34																34
35																35
36																36
37																37
38																38
40																40
41																41
61																61
42																42
63																63
43																43
62																62
44																44
64																64
45																45
46																46
47																47
51																51
52																52
53																53
54																54
55																55
56																56
57																57
71																71
72																72

Grouping classes on basis of Classification Hierarchy and/or technical rules.
Non existing class/event combination (2026).

- a. Class 11 can compete with Class 12. Class 12 can compete with Class 13. However, Class 11 should not compete with Class 13.
- b. Possible combinations: T51-53 or T52-54.
- c. T53 and T54 compete as a combined event.
- d. Possible combinations: any grouping of up to three consecutive classes.
- e. Possible combinations: any grouping of up to three consecutive classes within 53-57 (females) or 54-57 (males).